Nitsch Engineering

September 29, 2022

# STORMWATER REPORT

For:

**STOUGHTON FIRE STATION NO.1**
400 Prospect Street
Stoughton, MA 02072

Prepared for:

**Dore+Whittier Architects**
260 Merrimac Street Building 7,2nd Floor
Newburyport, MA 01950

Prepared by:

**NITSCH ENGINEERING, INC.**
2 Center Plaza, Suite 430
Boston, MA 02108

Nitsch Project #13743

## TABLE OF CONTENTS


**1.0 INTRODUCTION ..... 3**

**2.0 EXISTING CONDITIONS ..... 3**

2.1 Existing Drainage Infrastructure ..... 3

2.2 NRSC Soil Designations ..... 3

2.3 On-Site Soil Investigations ..... 4

2.4 Wetland Resource Areas ..... 4

2.5 Total Maximum Daily Load (TMDL) ..... 5

**3.0 PROPOSED CONDITIONS ..... 5**

3.1 Project Description ..... 5

3.2 Stormwater Management System ..... 6

3.3 Stormwater Management During Construction ..... 7

**4.0 STORMWATER MANAGEMENT ANALYSIS ..... 7**

4.1 Methodology ..... 7

4.2 HydroCAD Version 10.00 ..... 8

4.3 Existing Hydrologic Conditions ..... 8

4.4 Proposed Hydrologic Conditions ..... 8

4.5 Peak Flow Rates ..... 8

**5.0 MASSDEP STORMWATER MANAGEMENT STANDARDS ..... 9**

Standard 1: No New Untreated Discharges ..... 9

Standard 2: Peak Rate Attenuation ..... 9

Standard 3: Groundwater Recharge ..... 9

Standard 4: Water Quality Treatment ..... 10

Standard 5: Land Uses with Higher Potential Pollutant Loads ..... 11

Standard 6: Critical Areas ..... 11

Standard 7: Redevelopments ..... 11

Standard 8: Construction Period Pollution Prevention and Sedimentation Control ..... 11

Standard 9: Operation and Maintenance Plan ..... 11

Standard 10: Prohibition of Illicit Discharges ..... 11

**6.0 CLOSED DRAINAGE SYSTEM DESIGN ..... 12**

**7.0 CONCLUSION ..... 12**

**FIGURES**

DR-1 Existing Watershed Areas
DR-2 Proposed Watershed Areas
DR-3 Proposed Structures Drainage Map

**APPENDICES**

**Appendix A Stormwater Management Standards Documentation**
MassDEP Checklist for Stormwater Report
Standard 3: 72-HR Drawdown Calculations
Standard 4: TSS Removal Calculations
Standard 4: Proprietary Water Quality Structure Calculations
Standard 10: Illicit Discharge Compliance Statement

**Appendix B Existing Conditions – HydroCAD Calculations**

**Appendix C Proposed Conditions – HydroCAD Calculations**

**Appendix D Closed Drainage System Design**

**Appendix E Long-Term Pollution Prevention and Stormwater Operation and Maintenance Plan**

**Appendix F DRAFT Stormwater Pollution Prevention Plan (SWPPP)**

**Appendix G Soil Investigations**
NRCS Soil Maps and Descriptions
Compiled Test Pit Information

**Appendix H Existing Culvert Sizing**

## 1.0 INTRODUCTION

Nitsch Engineering has prepared this Stormwater Report to support the Notice of Intent application to Stoughton Conservation Commission for the Stoughton Fire Station NO.1. The Project site is located at 400 Prospect Street Stoughton, Massachusetts (subsequently referred to as the "Site").

The Town of Stoughton is proposing to construct a new fire station in Stoughton, Massachusetts. Nitsch Engineering has reviewed existing site documentation, Mass GIS information, and performed a site visit to observe the existing site. This narrative outlines the anticipated environmental permitting and other approvals that will likely be needed to redevelop the project site.

The site improvements include the following:

1. Demolition of the existing building, existing access road, existing pavement & site utilities;
2. Construction of parking facilitates and pedestrian walkways;
3. Construction of a new fire station building;
4. Construction of new access road;
5. Installation of new utilities to support the proposed building; and
6. Construction of a new stormwater management system.

The proposed stormwater management system has been designed to comply with the requirements of the Stoughton Wetlands Protection Bylaw and Stormwater Management Bylaw and the Massachusetts Department of Environmental Protection (DEP) Stormwater Management Standards.

## 2.0 EXISTING CONDITIONS

The Site is located at 400 Prospect Street Stoughton, Currently the site is mostly undeveloped and wooded with wetlands located along the western side of the property. The existing 400 Prospect Street property contains a 3,700± square-foot abandoned two-story wood framed building and associated driveways, parking, and utilities. Access to the existing building is provided by an existing access road along the southside extending from prospect street. The site is bound residential houses to the south and west and wooded areas to the north and east.

### 2.1 Existing Drainage Infrastructure

The site topography generally slopes from the existing site and building to the surrounding wetland and wooded area. An existing 36" corrugated metal storm drainage culvert and an existing 15" culvert connect the two bordering vegetated wetland areas.

Stormwater runoff from the parking lot, access road, and existing building sheet flows untreated to the wetland areas. No stormwater Best Management Practices (BMPs) or mitigation practices were included on the existing conditions survey or noticed during Nitsch's site observations.

### 2.2 NRSC Soil Designations

The Soil Classification Summary (Table 1) outlines the Natural Resources Conservation Services (NRCS) designation of the soil series at the Site. The majority of soils are classified as Canton fine sandy loam with a hydrologic soil group (HSG) rating of A, indicating that the soils have a high

infiltrative capacity (refer to the NRCS Soil Maps and Descriptions in Appendix G). The Ridgebury fine sandy loam series and Canton fine sandy loam series are located on the western and southern portion of the site and are HSG B & D respectively (moderate to slow infiltration).

**Table 1. NRCS Soil Classification Summary**

| Soil Unit | Soil Series | Hydrologic Soil Group |
|---|---|---|
| **71B** | Ridgebury fine sandy loam, 3 to 8 percent slopes, extremely ston | D |
| **422B** | Canton fine sandy loam, 0 to 8 percent slopes, extremely stony | B |
| **424C** | Canton fine sandy loam, 8 to 15 percent slopes, extremely bouldery | A |
| **654** | Udorthents, loamy | A |

## 2.3 On-Site Soil Investigations

Test pits were performed on the Stoughton Fire Station Site by Riverhawk in November 2021, PES Associates in May 2022 and Nitsch Engineering in September 2022.

As part of an Environmental Site Assessment, Riverhawk excavated 11 test pits to depth between 43 and 82 inches below grade over the entire site including 3 test pits within or in close proximity of the proposed fire station location, TP-3, -4 and -6, and TP-5, -9, -10 and -110 in proposed paved areas. Riverhawk test pits encountered groundwater at 56 and 67 inches below ground surface in TP-4 and 6, respectively or about el. 255.5.

Nitsch Engineering conducted four test pits in September 2022 including one in the area of the proposed subsurface infiltration system. Groundwater was not observed in the area of the proposed infiltration system. Ledge was encountered in the three additional test pits located on the eastern side of the site.

The proposed infiltration area (subsurface infiltration systems) was designed to maintain a four-foot offset to estimated seasonal high groundwater. See **Appendix G** for test pit logs and map.

## 2.4 Wetland Resource Areas

There is an intermittent stream running through the center of the site and under the existing driveway with adjacent Bordering Vegetated Wetlands (BVW). The site also contains Bordering Land Subject to Flooding (BLSF). The project is within a FEMA mapped zone A therefore there is no base flood elevation on the mapping. Maguire and Associates performed a hydrologic study for the Town analyzing the existing drainage facilities. The study, which is consistent with the Town's Flood Hazard

Area Maps, establishes an elevation of 249.0. Please see Notice of Intent Report (under separate cover) for additional information.

### 2.5 Total Maximum Daily Load (TMDL)

The Site ultimately discharges into Dorchester Brook, which flows south to the Hockomock River in Easton. The Site is located within the Taunton Watershed and will potentially be subject to a Draft Pathogen Total Maximum Daily Load (TMDL) if it is finalized by MassDEP. The Project has been designed to minimize stormwater discharge and associated pathogen pollutants through extensive infiltration practices to meet the intent of the TMDL.

## 3.0 PROPOSED CONDITIONS

### 3.1 Project Description

The proposed Project includes the construction of new fire station building and associated utilities. The building will include a total area of approximately 17,450 SF, A new parking areas are planned at the location of the existing site following demolition. The proposed site improvements include the following:

1. Demolition of the existing building, existing access road, existing pavement & site utilities;
2. Construction of parking facilitates and pedestrian walkways;
3. Construction of a new fire station building;
4. Construction of new access road;
5. Installation of new utilities to support the proposed building; and
6. Construction of a new stormwater management system.

The Project is classified as a new development, under the MassDEP stormwater regulations. A portion of the site has been previously developed and cleared.

The Project is anticipated to increase the overall impervious area for the Project by approximately 0.94 acres. Refer to Table 2 for a comparison of the existing and proposed land use for the Site.

**Table 2. Proposed land use for Stoughton Fire Station Limit of Work (in acres)**

| Land Use | Existing Site (acres) | Proposed Site (acres) | Change |
|---|---|---|---|
| **Buildings** | 0.09 | 0.40 | +0.31 |
| **Site Pavement** | 0.65 | 1.20 | +0.55 |
| **Grass Areas** | 0.82 | 1.48 | +0.66 |
| **Wood Areas** | 1.60 | 0.08 | -1.52 |

| | | | |
|---|---|---|---|
| Total | 3.16 | 3.16 | --- |

### 3.2 Stormwater Management System

The Site will include the installation of a stormwater management system that is being designed to meet the MassDEP Stormwater Management Standards and the Town of Stoughton Stormwater management regulations. As a new development, the Project is required to provide peak flow and volume mitigation, water quality treatment, and groundwater recharge per the Town of Stoughton and MassDEP regulations.

The Project has been designed using environmentally sensitive site design including directing runoff to subsurface infiltration systems. This design prevents the generation of stormwater and non-point source pollution by disconnecting flow paths, treating and infiltrating stormwater at its source, and protecting natural processes. Stormwater systems have been designed to model natural hydrologic features, including promoting infiltration throughout the site.

The proposed stormwater management system for the Project will include, deep sump and hooded catch basins, subsurface infiltration systems, and proprietary water quality structures. Overflow from the proposed subsurface infiltration systems will be piped to the existing 15” culvert.

Deep Sump and Hooded Catch Basins

Deep sump and hooded catch basins are proposed to provide pretreatment in the impervious areas of the walkways and access road. Stormwater captured in the catch basins will be directed to another treatment or infiltration BMP prior to discharging from the Site.

Subsurface Infiltration/Detention Systems

Stormwater will be collected and infiltrated using a subsurface infiltration system. Subsurface Infiltration Systems are proposed to collect and infiltrate runoff from the proposed building, sidewalks, and immediately adjacent impervious and landscaped site area.

The systems consist of StormTech SC-740 chambers enveloped by crushed stone. The combination of native soils on site having a high infiltrative capacity (refer to the NRCS Soil Maps and Descriptions in Appendix G) and lack of groundwater encountered during geotechnical explorations will allow the subsurface systems to infiltrate at a high rate. The systems were designed and sized to reduce the peak rate and runoff volumes in the 2-, 10-, 25-, and 100-year design storms as well as provide groundwater recharge and water quality volume. Overflow from these systems will be discharged to outlet control structures, which will reduce the flow before discharging to an outlet.

Underground Infiltration System #1 is located under the existing landscape areas/driveway of the of the proposed building and collects runoff from the proposed building, sidewalks and paved parking areas.

Site impervious area that is tributary to these systems will be pretreated using deep sump and hooded catch basins and proprietary water quality units to meet the 44% TSS removal requirement set forth by the MassDEP Stormwater Standards for discharge to highly permeable soils.

Water Quality Structures
3 proprietary water quality structures & 1 water quality inlet are proposed for water quality pretreatment in areas of the Site where space is limited or additional pretreatment is required prior to infiltration. These BMPs have been designed to provide at minimum 80% TSS removal. Sizing calculations are provided in Appendix A.

### 3.3 Stormwater Management During Construction

The Site Contractor will be responsible for stormwater management of the active construction site and is required to adhere to the conditions of the 2022 Construction General Permit under the Environmental Protection Agency through the preparation and implementation of a Stormwater Pollution Prevention Plan (SWPPP). A draft SWPPP has been prepared in accordance with the MassDEP Stormwater Management Standards and the 2022 Construction General Permit (Appendix F).

## 4.0 STORMWATER MANAGEMENT ANALYSIS

### 4.1 Methodology

Nitsch Engineering completed a hydrologic analysis of the existing project site utilizing Soil Conservation Service (SCS) Runoff Curve Number (CN) methodology. The SCS method calculates the rate at which the runoff reaches the design point considering several factors: the slope and flow lengths of the subcatchment area, the soil type of the subcatchment area, and the type of surface cover in the subcatchment area. HydroCAD Version 10.00 computer modeling software was used in conjunction with the SCS method to determine the peak runoff rates and runoff volumes for the 2-, 10-, 25-, and 100-year, 24-hour storm events. The proposed project site is being analyzed with the same methodology.

The Site was divided into multiple drainage areas, or subcatchments, which drain to a design point. For each subcatchment area, SCS Runoff Curve Numbers (CNs) were selected by using the cover type and hydrologic soil group of each area. The peak runoff rates and runoff volumes for the 2-, 10-, 25- and 100-year 24-hour storm events were then determined by inputting the drainage areas, CNs, and time of concentration ($T_c$) paths into the HydroCAD model.

The National Oceanic and Atmospheric Administration Atlas 14 precipitation frequency estimates were used to calculate the 2-, 10-, 25-, and 100- year 24-hour storm events in HydroCAD, as these were noted to be more conservative than the precipitation frequency estimates generated by the National Resources Conservation Service Precipitation Frequency Analysis for New York and the New England States, or by the Atlas of Precipitation Extremes for the Northeastern United States and Southeastern Canada. Refer to the HydroCAD calculations in Appendix B and C for rainfall information.

### 4.2 HydroCAD Version 10.00

The HydroCAD computer program uses SCS and TR-20 methods to model drainage systems. TR-20 (Technical Release 20) was developed by the Soil Conservation Service to estimate runoff and peak discharges in small watersheds. TR-20 is generally accepted by engineers and reviewing authorities as the standard method for estimating runoff and peak discharges.

HydroCAD Version 10.00 uses up to four types of components to analyze the hydrology of a given site: subcatchments, reaches, basins, and links. Subcatchments are areas of land that produce surface runoff. The area, weighted CN, and $T_c$ characterize each individual subcatchment area. Reaches are generally uniform streams, channels, or pipes that convey water from one point to another. A basin is any impoundment that fills with water from one or more sources and empties via an outlet structure. Links are used to introduce hydrographs into a project from another source or to provide a junction for more than one hydrograph within a project. The time span for the model was set for 0-72 hours in order to prevent truncation of the hydrograph.

### 4.3 Existing Hydrologic Conditions

As summarized in Section 2.1, Nitsch Engineering delineated the project site into four (4) on-site subcatchment (watershed) areas discharging to one (1) design point utilizing an existing conditions survey and on-site observations (See Figure EX-DA). The design point (DP) is defined as the Bordering Vegetated Wetland located in the center of the site (DP-1). The HydroCAD model for existing conditions is provided in Appendix B and results from the HydroCAD calculations are summarized below in Table 3.

### 4.4 Proposed Hydrologic Conditions

The proposed project has been designed to mitigate the change in stormwater runoff at the design point as required by the DEP Stormwater Management Standards and the Town of Stoughton Rules and Regulations. The existing watershed boundary was modified to reflect the topography, storm drainage structures and BMPs, and roof areas of the proposed site. (See Figure PR-DA). The HydroCAD model for proposed conditions is provided in Appendix C and results from the calculations are summarized in Table 3.

### 4.5 Peak Flow Rates

The proposed stormwater management system is expected to reduce the proposed peak runoff rates below the existing peak runoff rates for Design Point DP-1 as required by the DEP Stormwater Management Standards and the Stoughton Stormwater Management By-Laws. Table 3 below summarizes the existing and proposed hydrologic analyses for the site at the design point.

**Table 3 – Peak Rates of Runoff in Cubic Feet per Second (cfs)**

| | Storm Event | 2-year | 10-year | 25-year | 100-year |
|---|---|---|---|---|---|
| **DP-1** | Existing | 0.29 | 1.76 | 3.48 | 6.63 |
| | Proposed | 0.11 | 1.26 | 2.43 | 6.26 |

## 5.0 MassDEP Stormwater Management Standards

The Project is considered a ***new development*** under the Town of Stoughton Stormwater Management and Erosion Control Bylaw and MassDEP Stormwater Management Standards. The Site will be designed to meet and exceed the MassDEP Stormwater Management Standards as summarized below:

### Standard 1: No New Untreated Discharges

The Project will not discharge any untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth. Stormwater from the Site will be collected and treated in accordance with the MassDEP Stormwater Management Standards and stormwater outfalls will be stabilized to prevent erosion.

### Standard 2: Peak Rate Attenuation

The proposed stormwater management system will be designed so that the post-development peak discharge rates do not exceed pre-development peak discharge rates. To prevent storm damage and downstream flooding, the proposed stormwater management practices will mitigate peak runoff rates for the 2-, 10-, 25- and 100-year, 24 hour storm events. Refer to Table 3 for a pre- and post-development peak runoff rate comparison.

### Standard 3: Groundwater Recharge

The Site was designed using stormwater BMP treatment trains to minimize the loss of annual recharge to groundwater. The annual recharge from the post-development site will approximate the annual recharge from pre-development conditions based on soil type using the guidelines provided in the MassDEP Stormwater Management Handbook.

Impervious Area in HSG A = 69,721 square feet
Rv (Recharge Volume) = 69,721 x 0.6 in. / (12 inches/ft)
= 3,486 cubic feet

The infiltration BMPs are sized to exceed the recharge volume required under the MassDEP Stormwater Management Standards (Table 5).

**Table 5 – Proposed Recharge Volumes for Stormwater BMPs**

| Infiltration BMP | Recharge Volume (cf) |
|---|---|
| Underground Infiltration Basin 1 | 3,922 |
| **Total** | **3,922** |

The HydroCAD reports provided in Appendix C indicate that all proposed infiltration BMPs will drain within 72 hours for the 2-, 10-, 25-, and 100-year storm events, meeting the 72-hour MassDEP drawdown requirement. 72-hour draw down calculations have been provided in Appendix A.

A minimum 4 feet of separation has been maintained between the bottom of the infiltration system and seasonal high groundwater.

The proposed site is underlain by high infiltration soils (> 2.4 inches per hour) and as such, the site is subject to the 44% TSS removal prior to discharge into an infiltration BMP requirement. Refer to Appendix A for TSS removal calculations.

**Standard 4: Water Quality Treatment**

The proposed stormwater management system will be designed to remove greater than 80% of the average annual post-construction load of Total Suspended Solids (TSS). Structural stormwater BMPs including deep sump and hooded catch basins, subsurface infiltration systems and water quality units are sized to capture the required water quality volume 1 inch over the total impervious area and remove a minimum of 80% of total suspended solids.

**Table 6. Proposed Treatment Train Summary**

| Treatment Train | Impervious Area | Final TSS Removal |
|---|---|---|
| **A** | 36,493 | 81% |
| **B** | 15,756 | 80% |

The proposed water quality treatment BMPs are subject to the 44% TSS removal pretreatment requirement and the 1-inch rule for calculating water quality volumes because the site contains soils with a rapid infiltration rate (greater than 2.4 inches per hour).

Pretreatment for most infiltration BMPs will generally meet or exceed the 44% TSS removal requirement, without considering any pretreatment for street sweeping practices. Pretreatment will be provided using combinations of deep sump and hooded catch basins and water quality units that have been sized using the flow rate associated with the water quality volume.

TSS removal calculation spreadsheets and water quality structure sizing calculations are provided in Appendix A.

Source control and pollution prevention measures, such as vacuum cleaning, street sweeping, proper snow management, and stabilization of eroded surfaces, are included in the Long-Term Pollution Prevention Plan and Operation and Maintenance Plan (Appendix E).

**Standard 5: Land Uses with Higher Potential Pollutant Loads**

The project is not considered a LUHPPL and therefore, this standard is not applicable.

**Standard 6: Critical Areas**

The Project is not located within any critical areas. Therefore, this standard is not applicable. this standard is not applicable.

**Standard 7: Redevelopments**

The Project is not considered a redevelopment under the Town of Stoughton regulations. Therefore, this standard is not applicable.

**Standard 8: Construction Period Pollution Prevention and Sedimentation Control**

A plan to control construction-related impacts, including erosion, sedimentation, and other pollutant sources during construction and land disturbance activities (construction period erosion, sedimentation, and pollution prevention plan) will be developed and implemented during the Notice of Intent permitting process.

Because the Project will disturb more than one (1) acre of land, a Notice of Intent will be submitted to the Environmental Protection Agency (EPA) for coverage under the National Pollution Discharge Elimination System (NPDES) Construction General Permit. As part of this application the Applicant is required to prepare a Stormwater Pollution Prevention Plan (SWPPP) and implement the measures in the SWPPP. The SWPPP, which is to be kept on site, includes erosion and sediment controls (stabilization practices and structural practices), temporary and permanent stormwater management measures, Contractor inspection schedules and reporting of all SWPPP features, materials management, waste disposal, off-site vehicle tracking, spill prevention and response, sanitation, and non-stormwater discharges. A draft SWPPP is provided in Appendix F (separately attached).

**Standard 9: Operation and Maintenance Plan**

A post-construction operation and maintenance plan has been prepared and will be implemented to ensure that stormwater management systems function as designed. Source control and stormwater BMP operation requirements for the site are summarized in the Long-Term Pollution Prevention Plan and Operation and Maintenance Plan provided in Appendix E.

**Standard 10: Prohibition of Illicit Discharges**

There will be no illicit discharges to the stormwater management system associated with the Project. An Illicit Discharge Compliance Statement is provided in Appendix A.

## 6.0 CLOSED DRAINAGE SYSTEM DESIGN

The proposed closed drainage system consists of deep sump and hooded catch basins, drainage manholes, and proprietary water quality treatment units connected with corrugated polyethylene pipe. The closed drainage system was designed to convey the 25-year storm event using the Rational method, as required by the Town of Stoughton. Refer to Appendix D for more information.

## 7.0 CONCLUSION

In conclusion, the Project's stormwater management system will reduce or maintain peak runoff rates and volumes through the widespread use of infiltration BMPs and improve the water quality of stormwater being discharged from the Site. Environmentally sensitive site design and low impact development techniques will be implemented throughout the Site. The Project is being designed to meet and exceed the MassDEP Stormwater Management Standards and the Town of Stoughton Stormwater Management Regulation.

## FIGURES

DR-1 Existing Watershed Areas

DR-2 Proposed Watershed Areas

DR-3 Proposed Structures Drainage Map

LEGEND:

- TREES
- IMPERVIOUS
- BUILDING
- PERVIOUS
- EXISTING DRAINAGE DIVIDE
- LIMIT OF WORK
- EXISTING TIME OF CONCENTRATION

EX-1
EX-2
EX-3
EX-4
DP-1

SCALE:
1" = 30'
30 15 0 30 60

NITSCH PROJECT NO. 13743


DORE + WHITTIER
MASSACHUSETTS
260 MERRIMAC STREET BUILDING 7, 2ND FLOOR
NEWBURYPORT, MA 01950
P: (978) 499-2999

VERMONT
212 BATTERY STREET
BURLINGTON, VT 05401
P: (802) 863-1428


# STOUGHTON FIRE STATION No. 1

400 PROSPECT STREET
STOUGHTON, MA 02072

PROJECT NUMBER: 19-0796

SEAL AND SIGNATURE:

REVISIONS:

| NO. | DATE | TITLE |
|---|---|---|

ISSUE TITLE AND DATE:

NOTICE OF INTENT
09/29/2022


COPYRIGHT © 2020 by Dore & Whittier Architects, Inc. (D+W). These documents are D+W's instruments of service and are protected by all applicable copyright and statutory rights. Use of these documents without D+W's express written permission will result in copyright infringement.


KEY PLAN

ORIENTATION AND SCALE:

N TRUE NORTH

PROJECT NORTH

SCALE: AS INDICATED

SHEET TITLE:

# EXISTING WATERSHED AREAS

SHEET NUMBER:

# DR-1

LEGEND:

- TREES
- IMPERVIOUS
- BUILDING
- PERVIOUS
- PROPOSED DRAINAGE DIVIDE
- LIMIT OF WORK

PR-1A
PR-1B
PR-1
PR-2
SC-1
DP-1

PROPOSED BUILDING
LOT AREA
8,640 SQ. FT.
0.20 AC.

50' NO-TOUCH ZONE
75' STRUCTURAL BUILDING LIMITS
100' WETLAND BUFFER
50' WETLAND BUFFER
PROPERTY LINE
RESIDENTIAL B
RESIDENTIAL A

N 53°32'34" E 438.49' (DEED 437')
N 43°29'51"W 141.50'
N 46°30'09" E 100.00'
N 43°29'51"W 75.00'
N 46°30'09" E 65.00'
N 43°29'51"W 501.00'
S 37°25'41"E 941.43'
S 61°04'19"W 125.80'
S 47°40'19"W 130.19'
S 47°55'19"W 79.46'
S 67°48'19" W 41.94'
S 43°29'51"E 130.70'
S 51°33'02" W 250.40'

NF JOSEPH J. & MARY A AMARAL 340 PROSPECT ST MAP 66 - LOT 214
NF JOSEPH J. & MARY A AMARAL 350 PROSPECT ST MAP 66 - LOT 215
NF JOANNE & SUSAN O'REILLY 356 PROSPECT ST MAP 65 - LOT 26
NF WILLIAM N. & KIM M. PRESCOTT 366 PROSPECT ST MAP 65 - LOT 219
NF MICHELE G. & KAREN A MACDOUGAL 375 PROSPECT ST MAP 65 - LOT 220
NF SUSAN L. BESSLER 382 PROSPECT ST MAP 65 - LOT 221
NF DONALD H. & SANDRA J. NICKERSON 392 PROSPECT ST MAP 65 - LOT 222
NF LAWRENCE J. RICHARD & BEVERLY J. RICHARD ST 398 PROSPECT ST MAP 65 - LOT 130
NF GIOVANNI & GINA ALFEGHALI 405 PROSPECT ST MAP 65 - LOT 131
NF MARIA I. & ALVARO A. REGO 420 - 422 PROSPECT ST. MAP 77 - LOT 27 & 28
NF PARK REALTY TRUST II CHRISTIE MURPHY DRIVE MAP 78 - LOT 12
NF OWNER UNKNOWN
NF RON S. & LEAH B. ABECASSIS TRUST 25 CHRISTIE MURPHY DR. MAP 78 - LOT 11
NF DAVID A. & NORMA B. SOMERS 35 CHRISTIE MURPHY DR. MAP 78 - LOT 10
NF RECUPERO FAMILY 2018 IRREVOCABLE TRUST 40 CHARLOTTE ST. MAP 78 - LOT 3

6' WHITE VINYL FENCE
CONNECT TO THE EXISTING SEWER SYSTEM AT THE STREET
PROSPECT STREET (PUBLIC)
CHARLOTTE ST. "PRIVATE" UNINSTRUCTED
IRON PIPE FOUND
CATCH BASIN
HDPE
OH
G
W

SCALE:
1" = 30'
30 15 0 30 60

NITSCH PROJECT NO. 13743


DORE + WHITTIER
MASSACHUSETTS
260 MERRIMAC STREET BUILDING 7, 2ND FLOOR
NEWBURYPORT, MA 01950
P: (978) 499-2999
VERMONT
212 BATTERY STREET
BURLINGTON, VT 05401
P: (802) 863-1428


STOUGHTON FIRE STATION No. 1

400 PROSPECT STREET
STOUGHTON, MA 02072

PROJECT NUMBER: 19-0796

SEAL AND SIGNATURE:

REVISIONS:

| NO. | DATE | TITLE |
|---|---|---|
| | | |

ISSUE TITLE AND DATE:

NOTICE OF INTENT
09/29/2022


COPYRIGHT © 2020 by Dore & Whittier Architects, Inc. (D+W). These documents are D+W's instruments of professional service and are protected by copyright and other intellectual property rights. Use of these documents without D+W's express written permission will result in copyright infringement.


KEY PLAN

ORIENTATION AND SCALE:

N
TRUE NORTH
PROJECT NORTH

SCALE: AS INDICATED

SHEET TITLE:

PROPOSED WATERSHED AREAS

SHEET NUMBER:

DR-2

## APPENDIX A

**Stormwater Management Standards Documentation**

MassDEP Checklist for Stormwater Report
Standard 3: 72-Hour Drawdown Calculations
Standard 4: TSS Removal Calculations
Standard 4: Proprietary Water Quality Structure Calculations
Standard 10: Illicit Discharge Compliance Statement

**Massachusetts Department of Environmental Protection**
Bureau of Resource Protection - Wetlands Program

# Checklist for Stormwater Report

## A. Introduction

**Important:** When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.




A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the Massachusetts Stormwater Handbook. The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.[1] This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8[2]
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

---

[1] The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

[2] For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.

**Massachusetts Department of Environmental Protection**
Bureau of Resource Protection - Wetlands Program

# Checklist for Stormwater Report

## B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

*Note:* Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

## Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature




9/29/2022

Signature and Date

## Checklist

**Project Type:** Is the application for new development, redevelopment, or a mix of new and redevelopment?

☒ New development

☐ Redevelopment

☐ Mix of New Development and Redevelopment

# Checklist for Stormwater Report

## Checklist (continued)

**LID Measures:** Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

☒ No disturbance to any Wetland Resource Areas

☐ Site Design Practices (e.g. clustered development, reduced frontage setbacks)

☐ Reduced Impervious Area (Redevelopment Only)

☒ Minimizing disturbance to existing trees and shrubs

☐ LID Site Design Credit Requested:

- ☐ Credit 1
- ☐ Credit 2
- ☐ Credit 3

☐ Use of "country drainage" versus curb and gutter conveyance and pipe

☐ Bioretention Cells (includes Rain Gardens)

☐ Constructed Stormwater Wetlands (includes Gravel Wetlands designs)

☐ Treebox Filter

☐ Water Quality Swale

☐ Grass Channel

☐ Green Roof

☒ Other (describe): Subsurface Infiltartion system

**Standard 1: No New Untreated Discharges**

☒ No new untreated discharges

☒ Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth

☐ Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.

# Checklist for Stormwater Report

## Checklist (continued)

**Standard 2: Peak Rate Attenuation**

☐ Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.

☐ Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.

☒ Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

**Standard 3: Recharge**

☒ Soil Analysis provided.

☒ Required Recharge Volume calculation provided.

☐ Required Recharge volume reduced through use of the LID site Design Credits.

☒ Sizing the infiltration, BMPs is based on the following method: Check the method used.

☒ Static ☐ Simple Dynamic ☐ Dynamic Field[1]

☐ Runoff from all impervious areas at the site discharging to the infiltration BMP.

☒ Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.

☒ Recharge BMPs have been sized to infiltrate the Required Recharge Volume.

☐ Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:

- ☐ Site is comprised solely of C and D soils and/or bedrock at the land surface
- ☐ M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
- ☐ Solid Waste Landfill pursuant to 310 CMR 19.000
- ☐ Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.

☒ Calculations showing that the infiltration BMPs will drain in 72 hours are provided.

☐ Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

[1] 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.

# Checklist for Stormwater Report

## Checklist (continued)

**Standard 3: Recharge** (continued)

☐ The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.

☐ Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

**Standard 4: Water Quality**

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
- Provisions for storing materials and waste products inside or under cover;
- Vehicle washing controls;
- Requirements for routine inspections and maintenance of stormwater BMPs;
- Spill prevention and response plans;
- Provisions for maintenance of lawns, gardens, and other landscaped areas;
- Requirements for storage and use of fertilizers, herbicides, and pesticides;
- Pet waste management provisions;
- Provisions for operation and management of septic systems;
- Provisions for solid waste management;
- Snow disposal and plowing plans relative to Wetland Resource Areas;
- Winter Road Salt and/or Sand Use and Storage restrictions;
- Street sweeping schedules;
- Provisions for prevention of illicit discharges to the stormwater management system;
- Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
- Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
- List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.

☒ A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.

☒ Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:

- ☐ is within the Zone II or Interim Wellhead Protection Area
- ☐ is near or to other critical areas
- ☒ is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
- ☐ involves runoff from land uses with higher potential pollutant loads.

☐ The Required Water Quality Volume is reduced through use of the LID site Design Credits.

☒ Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.

# Checklist for Stormwater Report

## Checklist (continued)

**Standard 4: Water Quality** (continued)

☒ The BMP is sized (and calculations provided) based on:

- ☒ The ½" or 1" Water Quality Volume or
- ☒ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.

☒ The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.

☐ A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

**Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)**

☐ The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.

☒ The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted ***prior to*** the discharge of stormwater to the post-construction stormwater BMPs.

☐ The NPDES Multi-Sector General Permit does ***not*** cover the land use.

☐ LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.

☐ All exposure has been eliminated.

☐ All exposure has ***not*** been eliminated and all BMPs selected are on MassDEP LUHPPL list.

☐ The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

**Standard 6: Critical Areas**

☐ The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.

☐ Critical areas and BMPs are identified in the Stormwater Report.

# Checklist for Stormwater Report

## Checklist (continued)

**Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable**

☐ The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:

☐ Limited Project

☐ Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.

☐ Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area

☐ Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff

☐ Bike Path and/or Foot Path

☐ Redevelopment Project

☐ Redevelopment portion of mix of new and redevelopment.

☐ Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.

☐ The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

**Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control**

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.

☒ A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.

# Checklist for Stormwater Report

## Checklist (continued)

**Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control** (continued)

☐ The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has ***not*** been included in the Stormwater Report but will be submitted ***before*** land disturbance begins.

☐ The project is ***not*** covered by a NPDES Construction General Permit.

☐ The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.

☒ The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

**Standard 9: Operation and Maintenance Plan**

☒ The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:

- ☐ Name of the stormwater management system owners;
- ☒ Party responsible for operation and maintenance;
- ☒ Schedule for implementation of routine and non-routine maintenance tasks;
- ☐ Plan showing the location of all stormwater BMPs maintenance access areas;
- ☐ Description and delineation of public safety features;
- ☐ Estimated operation and maintenance budget; and
- ☒ Operation and Maintenance Log Form.

☐ The responsible party is ***not*** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:

- ☐ A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
- ☐ A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

**Standard 10: Prohibition of Illicit Discharges**

☒ The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;

☒ An Illicit Discharge Compliance Statement is attached;

☐ NO Illicit Discharge Compliance Statement is attached but will be submitted ***prior to*** the discharge of any stormwater to post-construction BMPs.

Nitsch Engineering

2 Center Plaza, Suite 430
Boston, MA 02108-1928
T: 617-338-0063
F: 617-338-6472
www.nitscheng.com

## Form S3-G: Standard 3 – Recharge
## 72-Hour Drawdown Calculation

| | |
|---|---|
| Project Name: Stoughton Fire Station NO.1 | Nitsch Project #: 13743 |
| Location: 400 Prospect Street Stoughton | Checked by: **MV** |
| Prepared by: HA | Sheet No. 1 of 1 |
| Date: 09/29/2022 | Subsurface Infiltration |

INSTRUCTIONS:
1. In 'Method' Column, Click on Blue Cell to Activate Drop Down Menu
2. Enter the "Required recharge Volume" (in cubic feet) in Blue Cell for the appropriate chosen Method
3. Enter the "Bottom Area" (in square feet) in the blue cell as the maximum infiltration surface area. Do not use sidewalls.
4. **For "Dynamic: In-Situ Method" ONLY** (if other go to 4b) Enter hydraulic Conductivity Rate in Blue Cell
5. In 'Texture Class' Column, Click on Blue Cell to Activate Drop Down Menu

| | | | | |
|---|---|---|---|---|
| 1 | Method: | **Static** | | |
| 2 | Required Recharge Volume (in cubic feet): | *3922* | as determined by the | Static Method |
| 3 | Bottom Area (in Sq.Ft.) | *6696* | | |

| | | Hydraulic Conductivity Rate: | In-Situ Saturated Hydraulic Conductivity Rate |
|---|---|---|---|
| 4a | ONLY - If using Dynamic: In-Situ Method --> Enter Hydraulic Conductivity Rate | | 0 |

| | Texture Class | NRCS Hydrologic Soil Group (HSG) | Infiltration Rate (Inches/Hour) | |
|---|---|---|---|---|
| 4b | Sandy Loam | B | 2.41 | **Hours** |

$Time_{drawdown}$ = 2.92

**72-Hour Drawdown Requirement Check:** ***OK***

Nitsch Engineering

2 Center Plaza, Suite 430
Boston, MA 02108-1928
T: 617-338-0063
F: 617-338-6472
www.nitscheng.com

**Stoughton Fire Station No. 1**
**WATER QUALITY TREATMENT SUMMARY (09/29/2022)**

Nitsch Engineering has prepared this Water Quality Treatment Summary for the proposed Stoughton Fire Station. In compliance with MassDEP Stormwater Management Standard #4, the proposed stormwater management system is designed to remove at least 80% of the average annual post-construction load of TSS prior to discharge. The stormwater management system is designed to remove at least 44% of the average annual post-construction TSS load prior to discharge to the infiltration systems because the infiltration systems are located within areas where soils with rapid infiltration rates were observed.

A summary of treatment trains proposed to provide water quantity control and water quality improvement at the proposed project site is provided below.

**Treatment Train A**
**Catchment Areas: PR1 & PR1A**
Deep Sump & Hooded Catch Basin → Water Quality Structure→ Infiltration Basin→ Discharge

**Treatment Train B**
**Catchment Areas: PR2**
Deep Sump & Hooded Catch Basin → Water Quality Structure → Discharge

Stoughton Fire Station No. 1
400 Prospect Street
Stoughton, MA
September 29, 2022

Nitsch Engineering

**Treatment Train A :**
Deep Sump & Hooded Catch Basin → Water Quality Structure→ Infiltration Basin→ Discharge

**Pretreatment Spreadsheet**

| B<br>BMP | C<br>TSS Removal Rate | D<br>Starting TSS Load | E<br>Amount Removed (C*D) | F<br>Remaining Load (D-E) |
|---|---|---|---|---|
| **Deep Sump & Hooded Catch Basin** | **0.25** | **1.00** | **0.25** | **0.75** |
| **Water Quality Structure** | **0.75** | **0.75** | **0.56** | **0.19** |

**Total TSS Removal =** **81%** **Meets 44% TSS removal pretreatment requirement**

**Treatment Spreadsheet**

| B<br>BMP | C<br>TSS Removal Rate | D<br>Starting TSS Load | E<br>Amount Removed (C*D) | F<br>Remaining Load (D-E) |
|---|---|---|---|---|
| **Infiltration Basin** | **0.90** | **1.00** | **0.80** | **0.20** |

**Total TSS Removal =** **80%** **Meets 80% TSS removal requirement**

Stoughton Fire Station No. 1
400 Prospect Street
Stoughton, MA
September 29, 2022

**Treatment Train B :**
Deep Sump & Hooded Catch Basin → Water Quality Structure → Discharge

**Treatment Spreadsheet**

| B | C | D | E | F |
|---|---|---|---|---|
| BMP | TSS Removal Rate | Starting TSS Load | Amount Removed (C*D) | Remaining Load (D-E) |
| **Deep Sump & Hooded Catch Basin** | **0.25** | **1.00** | **0.25** | **0.75** |
| **Water Quality Structure** | **0.75** | **0.75** | **0.56** | **0.19** |

**Total TSS Removal =** **81%** **Meets 80% TSS removal requirement**

Nitsch Engineering

2 Center Plaza, Suite 430
Boston, MA 02108-1928
T: 617-338-0063
F: 617-338-6472
www.nitscheng.com

**STANDARD 10: Illicit Discharge Compliance Statement**

| | |
|---|---|
| Project Name: Stoughton Fire Station No.1 | Nitsch Project #: 13743 |
| Location: 400 Prospect Street Stoughton, MA 02072 | Checked by: MV |
| Prepared by: HA | Sheet No. 1 of 1 |
| Date: 09/29/2022 | |

**Standard 10 states: All illicit discharges to the stormwater management system are prohibited.**

This is to verify:

1. Based on the information available there are no known or suspected illicit discharges to the stormwater management system at Stoughton Fire Station site as defined in the MassDEP Stormwater Handbook.

2. The design of the stormwater system includes no proposed illicit discharges.




Marissa Valentino, PE, CFM

9/29/2022

09/29/2022

# APPENDIX B

**Existing Conditions – HydroCAD Calculations**




Subcat Reach Pond Link

**Routing Diagram for 13743-Existing Drainage Areas**
Prepared by Nitsch Engineering, Printed 9/28/2022
HydroCAD® 10.10-7a s/n 00546 © 2021 HydroCAD Software Solutions LLC

## Rainfall Events Listing (selected events)

| Event# | Event Name | Storm Type | Curve | Mode | Duration (hours) | B/B | Depth (inches) | AMC |
|---|---|---|---|---|---|---|---|---|
| 1 | 2 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 3.41 | 2 |
| 2 | 10 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 5.21 | 2 |
| 3 | 25 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 6.33 | 2 |
| 4 | 100 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 8.06 | 2 |

## Area Listing (all nodes)

| Area (acres) | CN | Description (subcatchment-numbers) |
|---|---|---|
| 0.817 | 39 | >75% Grass cover, Good, HSG A (EX-1, EX-2, EX-3, EX-4) |
| 0.657 | 98 | Paved parking, HSG A (EX-1, EX-3, EX-4) |
| 0.085 | 98 | Roofs, HSG A (EX-1) |
| 1.599 | 30 | Woods, Good, HSG A (EX-1, EX-2, EX-3, EX-4) |
| **3.158** | **48** | **TOTAL AREA** |

## Soil Listing (all nodes)

| Area (acres) | Soil Group | Subcatchment Numbers |
|---|---|---|
| 3.158 | HSG A | EX-1, EX-2, EX-3, EX-4 |
| 0.000 | HSG B | |
| 0.000 | HSG C | |
| 0.000 | HSG D | |
| 0.000 | Other | |
| **3.158** | | **TOTAL AREA** |

## Ground Covers (all nodes)

| HSG-A (acres) | HSG-B (acres) | HSG-C (acres) | HSG-D (acres) | Other (acres) | Total (acres) | Ground Cover | Subcatchment Numbers |
|---|---|---|---|---|---|---|---|
| 0.817 | 0.000 | 0.000 | 0.000 | 0.000 | 0.817 | >75% Grass cover, Good | EX-1, EX-2, EX-3, EX-4 |
| 0.657 | 0.000 | 0.000 | 0.000 | 0.000 | 0.657 | Paved parking | EX-1, EX-3, EX-4 |
| 0.085 | 0.000 | 0.000 | 0.000 | 0.000 | 0.085 | Roofs | EX-1 |
| 1.599 | 0.000 | 0.000 | 0.000 | 0.000 | 1.599 | Woods, Good | EX-1, EX-2, EX-3, EX-4 |
| **3.158** | **0.000** | **0.000** | **0.000** | **0.000** | **3.158** | **TOTAL AREA** | |

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment EX-1: EX-1** Runoff Area=96,804 sf 22.87% Impervious Runoff Depth=0.11"
Flow Length=366' Tc=7.9 min CN=47 Runoff=0.03 cfs 0.020 af

**Subcatchment EX-2: EX-2** Runoff Area=14,394 sf 0.00% Impervious Runoff Depth=0.00"
Flow Length=906' Tc=8.1 min CN=30 Runoff=0.00 cfs 0.000 af

**Subcatchment EX-3: EX-3** Runoff Area=14,946 sf 35.61% Impervious Runoff Depth=0.46"
Flow Length=792' Tc=6.4 min CN=59 Runoff=0.12 cfs 0.013 af

**Subcatchment EX-4: EX-4** Runoff Area=11,436 sf 42.75% Impervious Runoff Depth=0.66"
Tc=6.0 min CN=64 Runoff=0.17 cfs 0.014 af

**Reach DP: DESIGN POINT** Inflow=0.29 cfs 0.047 af
Outflow=0.29 cfs 0.047 af

**Total Runoff Area = 3.158 ac Runoff Volume = 0.047 af Average Runoff Depth = 0.18"**
**76.49% Pervious = 2.416 ac 23.51% Impervious = 0.743 ac**

## Summary for Subcatchment EX-1: EX-1


Runoff = 0.03 cfs @ 13.32 hrs, Volume= 0.020 af, Depth= 0.11"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 18,429 | 98 | Paved parking, HSG A |
| 3,711 | 98 | Roofs, HSG A |
| 20,464 | 39 | >75% Grass cover, Good, HSG A |
| 54,200 | 30 | Woods, Good, HSG A |
| 96,804 | 47 | Weighted Average |
| 74,664 | | 77.13% Pervious Area |
| 22,140 | | 22.87% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.1 | 50 | 0.0150 | 0.14 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 1.8 | 316 | 0.0200 | 2.87 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Paveme** Paved Kv= 20.3 fps |
| 7.9 | 366 | Total | | | |

## Subcatchment EX-1: EX-1



## Summary for Subcatchment EX-2: EX-2

[45] Hint: Runoff=Zero


Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 264 | 39 | >75% Grass cover, Good, HSG A |
| 14,130 | 30 | Woods, Good, HSG A |
| 14,394 | 30 | Weighted Average |
| 14,394 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 1.5 | 25 | 0.1360 | 0.29 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 6.6 | 881 | 0.2000 | 2.24 | | **Shallow Concentrated Flow, Shalow Concentrated Flow-Grass** Woodland Kv= 5.0 fps |
| 8.1 | 906 | Total | | | |

## Subcatchment EX-2: EX-2



## Summary for Subcatchment EX-3: EX-3


Runoff = 0.12 cfs @ 12.16 hrs, Volume= 0.013 af, Depth= 0.46"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 5,322 | 98 | Paved parking, HSG A |
| 8,544 | 39 | >75% Grass cover, Good, HSG A |
| 1,080 | 30 | Woods, Good, HSG A |
| 14,946 | 59 | Weighted Average |
| 9,624 | | 64.39% Pervious Area |
| 5,322 | | 35.61% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 2.9 | 16 | 0.0100 | 0.09 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 776 | 0.0328 | 3.68 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Pavem** Paved Kv= 20.3 fps |
| 6.4 | 792 | Total | | | |

## Subcatchment EX-3: EX-3



## Summary for Subcatchment EX-4: EX-4


Runoff = 0.17 cfs @ 12.14 hrs, Volume= 0.014 af, Depth= 0.66"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 4,889 | 98 | Paved parking, HSG A |
| 6,326 | 39 | >75% Grass cover, Good, HSG A |
| 221 | 30 | Woods, Good, HSG A |
| 11,436 | 64 | Weighted Average |
| 6,547 | | 57.25% Pervious Area |
| 4,889 | | 42.75% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment EX-4: EX-4




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.158 ac, 23.51% Impervious, Inflow Depth = 0.18" for 2 Year event
Inflow = 0.29 cfs @ 12.15 hrs, Volume= 0.047 af
Outflow = 0.29 cfs @ 12.15 hrs, Volume= 0.047 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Reach DP: DESIGN POINT



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment EX-1: EX-1** Runoff Area=96,804 sf 22.87% Impervious Runoff Depth=0.61"
Flow Length=366' Tc=7.9 min CN=47 Runoff=0.82 cfs 0.114 af

**Subcatchment EX-2: EX-2** Runoff Area=14,394 sf 0.00% Impervious Runoff Depth=0.01"
Flow Length=906' Tc=8.1 min CN=30 Runoff=0.00 cfs 0.000 af

**Subcatchment EX-3: EX-3** Runoff Area=14,946 sf 35.61% Impervious Runoff Depth=1.36"
Flow Length=792' Tc=6.4 min CN=59 Runoff=0.49 cfs 0.039 af

**Subcatchment EX-4: EX-4** Runoff Area=11,436 sf 42.75% Impervious Runoff Depth=1.72"
Tc=6.0 min CN=64 Runoff=0.50 cfs 0.038 af

**Reach DP: DESIGN POINT** Inflow=1.76 cfs 0.190 af
Outflow=1.76 cfs 0.190 af

**Total Runoff Area = 3.158 ac Runoff Volume = 0.190 af Average Runoff Depth = 0.72"**
**76.49% Pervious = 2.416 ac 23.51% Impervious = 0.743 ac**

## Summary for Subcatchment EX-1: EX-1


Runoff = 0.82 cfs @ 12.19 hrs, Volume= 0.114 af, Depth= 0.61"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 18,429 | 98 | Paved parking, HSG A |
| 3,711 | 98 | Roofs, HSG A |
| 20,464 | 39 | >75% Grass cover, Good, HSG A |
| 54,200 | 30 | Woods, Good, HSG A |
| 96,804 | 47 | Weighted Average |
| 74,664 | | 77.13% Pervious Area |
| 22,140 | | 22.87% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.1 | 50 | 0.0150 | 0.14 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 1.8 | 316 | 0.0200 | 2.87 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Paveme** Paved Kv= 20.3 fps |
| 7.9 | 366 | Total | | | |

## Subcatchment EX-1: EX-1



## Summary for Subcatchment EX-2: EX-2


Runoff = 0.00 cfs @ 24.00 hrs, Volume= 0.000 af, Depth= 0.01"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 264 | 39 | >75% Grass cover, Good, HSG A |
| 14,130 | 30 | Woods, Good, HSG A |
| 14,394 | 30 | Weighted Average |
| 14,394 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 1.5 | 25 | 0.1360 | 0.29 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 6.6 | 881 | 0.2000 | 2.24 | | **Shallow Concentrated Flow, Shalow Concentrated Flow-Grass** Woodland Kv= 5.0 fps |
| 8.1 | 906 | Total | | | |

## Subcatchment EX-2: EX-2



## Summary for Subcatchment EX-3: EX-3


Runoff = 0.49 cfs @ 12.14 hrs, Volume= 0.039 af, Depth= 1.36"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 5,322 | 98 | Paved parking, HSG A |
| 8,544 | 39 | >75% Grass cover, Good, HSG A |
| 1,080 | 30 | Woods, Good, HSG A |
| 14,946 | 59 | Weighted Average |
| 9,624 | | 64.39% Pervious Area |
| 5,322 | | 35.61% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 2.9 | 16 | 0.0100 | 0.09 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 776 | 0.0328 | 3.68 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Pavem** Paved Kv= 20.3 fps |
| 6.4 | 792 | Total | | | |

## Subcatchment EX-3: EX-3



## Summary for Subcatchment EX-4: EX-4


Runoff = 0.50 cfs @ 12.14 hrs, Volume= 0.038 af, Depth= 1.72"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 4,889 | 98 | Paved parking, HSG A |
| 6,326 | 39 | >75% Grass cover, Good, HSG A |
| 221 | 30 | Woods, Good, HSG A |
| 11,436 | 64 | Weighted Average |
| 6,547 | | 57.25% Pervious Area |
| 4,889 | | 42.75% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment EX-4: EX-4




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.158 ac, 23.51% Impervious, Inflow Depth = 0.72" for 10 Year event
Inflow = 1.76 cfs @ 12.16 hrs, Volume= 0.190 af
Outflow = 1.76 cfs @ 12.16 hrs, Volume= 0.190 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Reach DP: DESIGN POINT



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment EX-1: EX-1** Runoff Area=96,804 sf 22.87% Impervious Runoff Depth=1.08"
Flow Length=366' Tc=7.9 min CN=47 Runoff=2.02 cfs 0.200 af

**Subcatchment EX-2: EX-2** Runoff Area=14,394 sf 0.00% Impervious Runoff Depth=0.11"
Flow Length=906' Tc=8.1 min CN=30 Runoff=0.00 cfs 0.003 af

**Subcatchment EX-3: EX-3** Runoff Area=14,946 sf 35.61% Impervious Runoff Depth=2.05"
Flow Length=792' Tc=6.4 min CN=59 Runoff=0.77 cfs 0.059 af

**Subcatchment EX-4: EX-4** Runoff Area=11,436 sf 42.75% Impervious Runoff Depth=2.50"
Tc=6.0 min CN=64 Runoff=0.74 cfs 0.055 af

**Reach DP: DESIGN POINT** Inflow=3.48 cfs 0.317 af
Outflow=3.48 cfs 0.317 af

**Total Runoff Area = 3.158 ac Runoff Volume = 0.317 af Average Runoff Depth = 1.20"**
**76.49% Pervious = 2.416 ac 23.51% Impervious = 0.743 ac**

## Summary for Subcatchment EX-1: EX-1


Runoff = 2.02 cfs @ 12.17 hrs, Volume= 0.200 af, Depth= 1.08"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 18,429 | 98 | Paved parking, HSG A |
| 3,711 | 98 | Roofs, HSG A |
| 20,464 | 39 | >75% Grass cover, Good, HSG A |
| 54,200 | 30 | Woods, Good, HSG A |
| 96,804 | 47 | Weighted Average |
| 74,664 | | 77.13% Pervious Area |
| 22,140 | | 22.87% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.1 | 50 | 0.0150 | 0.14 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 1.8 | 316 | 0.0200 | 2.87 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Pavem** Paved Kv= 20.3 fps |
| 7.9 | 366 | Total | | | |

## Subcatchment EX-1: EX-1



## Summary for Subcatchment EX-2: EX-2


Runoff = 0.00 cfs @ 16.37 hrs, Volume= 0.003 af, Depth= 0.11"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 264 | 39 | >75% Grass cover, Good, HSG A |
| 14,130 | 30 | Woods, Good, HSG A |
| 14,394 | 30 | Weighted Average |
| 14,394 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 1.5 | 25 | 0.1360 | 0.29 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 6.6 | 881 | 0.2000 | 2.24 | | **Shallow Concentrated Flow, Shalow Concentrated Flow-Grass** Woodland Kv= 5.0 fps |
| 8.1 | 906 | Total | | | |

## Subcatchment EX-2: EX-2



## Summary for Subcatchment EX-3: EX-3


Runoff = 0.77 cfs @ 12.14 hrs, Volume= 0.059 af, Depth= 2.05"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 5,322 | 98 | Paved parking, HSG A |
| 8,544 | 39 | >75% Grass cover, Good, HSG A |
| 1,080 | 30 | Woods, Good, HSG A |
| 14,946 | 59 | Weighted Average |
| 9,624 | | 64.39% Pervious Area |
| 5,322 | | 35.61% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 2.9 | 16 | 0.0100 | 0.09 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 776 | 0.0328 | 3.68 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Pavem** Paved Kv= 20.3 fps |
| 6.4 | 792 | Total | | | |

## Subcatchment EX-3: EX-3



## Summary for Subcatchment EX-4: EX-4


Runoff = 0.74 cfs @ 12.13 hrs, Volume= 0.055 af, Depth= 2.50"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 4,889 | 98 | Paved parking, HSG A |
| 6,326 | 39 | >75% Grass cover, Good, HSG A |
| 221 | 30 | Woods, Good, HSG A |
| 11,436 | 64 | Weighted Average |
| 6,547 | | 57.25% Pervious Area |
| 4,889 | | 42.75% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment EX-4: EX-4




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.158 ac, 23.51% Impervious, Inflow Depth = 1.20" for 25 Year event
Inflow = 3.48 cfs @ 12.15 hrs, Volume= 0.317 af
Outflow = 3.48 cfs @ 12.15 hrs, Volume= 0.317 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Reach DP: DESIGN POINT



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment EX-1: EX-1** Runoff Area=96,804 sf 22.87% Impervious Runoff Depth=1.97"
Flow Length=366' Tc=7.9 min CN=47 Runoff=4.28 cfs 0.365 af

**Subcatchment EX-2: EX-2** Runoff Area=14,394 sf 0.00% Impervious Runoff Depth=0.43"
Flow Length=906' Tc=8.1 min CN=30 Runoff=0.03 cfs 0.012 af

**Subcatchment EX-3: EX-3** Runoff Area=14,946 sf 35.61% Impervious Runoff Depth=3.27"
Flow Length=792' Tc=6.4 min CN=59 Runoff=1.26 cfs 0.093 af

**Subcatchment EX-4: EX-4** Runoff Area=11,436 sf 42.75% Impervious Runoff Depth=3.83"
Tc=6.0 min CN=64 Runoff=1.15 cfs 0.084 af

**Reach DP: DESIGN POINT** Inflow=6.63 cfs 0.554 af
Outflow=6.63 cfs 0.554 af

**Total Runoff Area = 3.158 ac Runoff Volume = 0.554 af Average Runoff Depth = 2.11"**
**76.49% Pervious = 2.416 ac 23.51% Impervious = 0.743 ac**

## Summary for Subcatchment EX-1: EX-1


Runoff = 4.28 cfs @ 12.16 hrs, Volume= 0.365 af, Depth= 1.97"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 18,429 | 98 | Paved parking, HSG A |
| 3,711 | 98 | Roofs, HSG A |
| 20,464 | 39 | >75% Grass cover, Good, HSG A |
| 54,200 | 30 | Woods, Good, HSG A |
| 96,804 | 47 | Weighted Average |
| 74,664 | | 77.13% Pervious Area |
| 22,140 | | 22.87% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.1 | 50 | 0.0150 | 0.14 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 1.8 | 316 | 0.0200 | 2.87 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Paveme** Paved Kv= 20.3 fps |
| 7.9 | 366 | Total | | | |

## Subcatchment EX-1: EX-1



## Summary for Subcatchment EX-2: EX-2


Runoff = 0.03 cfs @ 12.56 hrs, Volume= 0.012 af, Depth= 0.43"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 264 | 39 | >75% Grass cover, Good, HSG A |
| 14,130 | 30 | Woods, Good, HSG A |
| 14,394 | 30 | Weighted Average |
| 14,394 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 1.5 | 25 | 0.1360 | 0.29 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 6.6 | 881 | 0.2000 | 2.24 | | **Shallow Concentrated Flow, Shalow Concentrated Flow-Grass** Woodland Kv= 5.0 fps |
| 8.1 | 906 | Total | | | |

## Subcatchment EX-2: EX-2



## Summary for Subcatchment EX-3: EX-3


Runoff = 1.26 cfs @ 12.14 hrs, Volume= 0.093 af, Depth= 3.27"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 5,322 | 98 | Paved parking, HSG A |
| 8,544 | 39 | >75% Grass cover, Good, HSG A |
| 1,080 | 30 | Woods, Good, HSG A |
| 14,946 | 59 | Weighted Average |
| 9,624 | | 64.39% Pervious Area |
| 5,322 | | 35.61% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 2.9 | 16 | 0.0100 | 0.09 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 776 | 0.0328 | 3.68 | | **Shallow Concentrated Flow, Shallow Concentrated Flow-Pavem** Paved Kv= 20.3 fps |
| 6.4 | 792 | Total | | | |

## Subcatchment EX-3: EX-3



## Summary for Subcatchment EX-4: EX-4


Runoff = 1.15 cfs @ 12.13 hrs, Volume= 0.084 af, Depth= 3.83"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 4,889 | 98 | Paved parking, HSG A |
| 6,326 | 39 | >75% Grass cover, Good, HSG A |
| 221 | 30 | Woods, Good, HSG A |
| 11,436 | 64 | Weighted Average |
| 6,547 | | 57.25% Pervious Area |
| 4,889 | | 42.75% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment EX-4: EX-4




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.158 ac, 23.51% Impervious, Inflow Depth = 2.11" for 100 Year event
Inflow = 6.63 cfs @ 12.15 hrs, Volume= 0.554 af
Outflow = 6.63 cfs @ 12.15 hrs, Volume= 0.554 af, Atten= 0%, Lag= 0.0 min


Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

## Reach DP: DESIGN POINT



## APPENDIX C

**Proposed Conditions – HydroCAD Calculations**




**Routing Diagram for 13743-Proposed Drainage Areas**
Prepared by Nitsch Engineering, Printed 9/28/2022
HydroCAD® 10.10-7a s/n 00546 © 2021 HydroCAD Software Solutions LLC

## Rainfall Events Listing (selected events)

| Event# | Event Name | Storm Type | Curve | Mode | Duration (hours) | B/B | Depth (inches) | AMC |
|---|---|---|---|---|---|---|---|---|
| 1 | 2 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 3.41 | 2 |
| 2 | 10 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 5.21 | 2 |
| 3 | 25 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 6.33 | 2 |
| 4 | 100 Year | NOAA 24-hr | D | Default | 24.00 | 1 | 8.06 | 2 |

## Area Listing (all nodes)

| Area (acres) | CN | Description (subcatchment-numbers) |
|---|---|---|
| 1.475 | 39 | >75% Grass cover, Good, HSG A (PR-1, PR-1A, PR-2) |
| 1.199 | 98 | Paved parking, HSG A (PR-1, PR-1A, PR-2) |
| 0.401 | 98 | Roofs, HSG A (PR-1B) |
| 0.083 | 30 | Woods, Good, HSG A (PR-2) |
| **3.159** | **69** | **TOTAL AREA** |

## Soil Listing (all nodes)

| Area (acres) | Soil Group | Subcatchment Numbers |
|---|---|---|
| 3.159 | HSG A | PR-1, PR-1A, PR-1B, PR-2 |
| 0.000 | HSG B | |
| 0.000 | HSG C | |
| 0.000 | HSG D | |
| 0.000 | Other | |
| **3.159** | | **TOTAL AREA** |

## Ground Covers (all nodes)

| HSG-A (acres) | HSG-B (acres) | HSG-C (acres) | HSG-D (acres) | Other (acres) | Total (acres) | Ground Cover | Subcatchment Numbers |
|---|---|---|---|---|---|---|---|
| 1.475 | 0.000 | 0.000 | 0.000 | 0.000 | 1.475 | >75% Grass cover, Good | PR-1, PR-1A, PR-2 |
| 1.199 | 0.000 | 0.000 | 0.000 | 0.000 | 1.199 | Paved parking | PR-1, PR-1A, PR-2 |
| 0.401 | 0.000 | 0.000 | 0.000 | 0.000 | 0.401 | Roofs | PR-1B |
| 0.083 | 0.000 | 0.000 | 0.000 | 0.000 | 0.083 | Woods, Good | PR-2 |
| **3.159** | **0.000** | **0.000** | **0.000** | **0.000** | **3.159** | **TOTAL AREA** | |

## Pipe Listing (all nodes)

| Line# | Node Number | In-Invert (feet) | Out-Invert (feet) | Length (feet) | Slope (ft/ft) | n | Width (inches) | Diam/Height (inches) | Inside-Fill (inches) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | SC-1 | 254.50 | 254.00 | 50.0 | 0.0100 | 0.013 | 0.0 | 12.0 | 0.0 |

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment PR-1: PR-1** Runoff Area=49,964 sf 71.52% Impervious Runoff Depth=1.64"
Tc=6.0 min CN=81 Runoff=2.14 cfs 0.156 af

**Subcatchment PR-1A: PR-1A** Runoff Area=7,996 sf 9.52% Impervious Runoff Depth=0.07"
Tc=6.0 min CN=45 Runoff=0.00 cfs 0.001 af

**Subcatchment PR-1B: PR-1B** Runoff Area=17,472 sf 100.00% Impervious Runoff Depth=3.18"
Tc=6.0 min CN=98 Runoff=1.26 cfs 0.106 af

**Subcatchment PR-2: PR-2** Runoff Area=62,177 sf 25.34% Impervious Runoff Depth=0.25"
Flow Length=293' Tc=8.2 min CN=53 Runoff=0.11 cfs 0.030 af

**Reach DP: DESIGN POINT** Inflow=0.11 cfs 0.030 af
Outflow=0.11 cfs 0.030 af

**Pond SC-1: SC-740-1** Peak Elev=254.94' Storage=3,597 cf Inflow=3.39 cfs 0.264 af
Discarded=0.37 cfs 0.264 af Primary=0.00 cfs 0.000 af Outflow=0.37 cfs 0.264 af

**Total Runoff Area = 3.159 ac Runoff Volume = 0.294 af Average Runoff Depth = 1.12"**
**49.33% Pervious = 1.558 ac 50.67% Impervious = 1.601 ac**

## Summary for Subcatchment PR-1: PR-1


Runoff = 2.14 cfs @ 12.13 hrs, Volume= 0.156 af, Depth= 1.64"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 35,732 | 98 | Paved parking, HSG A |
| 14,232 | 39 | >75% Grass cover, Good, HSG A |
| 49,964 | 81 | Weighted Average |
| 14,232 | | 28.48% Pervious Area |
| 35,732 | | 71.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

## Subcatchment PR-1: PR-1



## Summary for Subcatchment PR-1A: PR-1A


Runoff = 0.00 cfs @ 14.54 hrs, Volume= 0.001 af, Depth= 0.07"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 761 | 98 | Paved parking, HSG A |
| 7,235 | 39 | >75% Grass cover, Good, HSG A |
| 7,996 | 45 | Weighted Average |
| 7,235 | | 90.48% Pervious Area |
| 761 | | 9.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

## Subcatchment PR-1A: PR-1A



## Summary for Subcatchment PR-1B: PR-1B


Runoff = 1.26 cfs @ 12.13 hrs, Volume= 0.106 af, Depth= 3.18"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 17,472 | 98 | Roofs, HSG A |
| 17,472 | | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment PR-1B: PR-1B



## Summary for Subcatchment PR-2: PR-2


Runoff = 0.11 cfs @ 12.32 hrs, Volume= 0.030 af, Depth= 0.25"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 2 Year Rainfall=3.41"

| Area (sf) | CN | Description |
|---|---|---|
| 15,756 | 98 | Paved parking, HSG A |
| 42,784 | 39 | >75% Grass cover, Good, HSG A |
| 3,637 | 30 | Woods, Good, HSG A |
| 62,177 | 53 | Weighted Average |
| 46,421 | | 74.66% Pervious Area |
| 15,756 | | 25.34% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 4.7 | 50 | 0.0290 | 0.18 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 243 | 0.0280 | 1.17 | | **Shallow Concentrated Flow, Shallow Concentrated Flow** Short Grass Pasture Kv= 7.0 fps |
| 8.2 | 293 | Total | | | |

## Subcatchment PR-2: PR-2




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.159 ac, 50.67% Impervious, Inflow Depth = 0.12" for 2 Year event
Inflow = 0.11 cfs @ 12.32 hrs, Volume= 0.030 af
Outflow = 0.11 cfs @ 12.32 hrs, Volume= 0.030 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Reach DP: DESIGN POINT



## Summary for Pond SC-1: SC-740-1

Inflow Area = 1.732 ac, 71.54% Impervious, Inflow Depth = 1.83" for 2 Year event
Inflow = 3.39 cfs @ 12.13 hrs, Volume= 0.264 af
Outflow = 0.37 cfs @ 11.60 hrs, Volume= 0.264 af, Atten= 89%, Lag= 0.0 min
Discarded = 0.37 cfs @ 11.60 hrs, Volume= 0.264 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
Routed to Reach DP : DESIGN POINT

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
Peak Elev= 254.94' @ 13.09 hrs Surf.Area= 6,700 sf Storage= 3,597 cf

Plug-Flow detention time= 69.3 min calculated for 0.264 af (100% of inflow)
Center-of-Mass det. time= 69.3 min ( 881.0 - 811.7 )

| Volume | Invert | Avail.Storage | Storage Description |
|---|---|---|---|
| #1A | 254.00' | 5,201 cf | **53.75'W x 124.66'L x 3.50'H Field A**<br>23,451 cf Overall - 8,591 cf Embedded = 14,860 cf x 35.0% Voids |
| #2A | 254.50' | 8,591 cf | **ADS_StormTech SC-740 +Cap** x 187 Inside #1<br>Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf<br>Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap<br>187 Chambers in 11 Rows |
| | | 13,792 cf | Total Available Storage |

Storage Group A created with Chamber Wizard

| Device | Routing | Invert | Outlet Devices |
|---|---|---|---|
| #1 | Discarded | 254.00' | **2.410 in/hr Exfiltration over Surface area** |
| #2 | Primary | 254.50' | **12.0" Round Culvert**<br>L= 50.0' CPP, projecting, no headwall, Ke= 0.900<br>Inlet / Outlet Invert= 254.50' / 254.00' S= 0.0100 '/' Cc= 0.900<br>n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf |
| #3 | Device 2 | 257.00' | **4.0' long Sharp-Crested Rectangular Weir** 2 End Contraction(s) |
| #4 | Device 2 | 255.50' | **12.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |
| #5 | Device 2 | 255.00' | **4.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |

**Discarded OutFlow** Max=0.37 cfs @ 11.60 hrs HW=254.04' (Free Discharge)
└**1=Exfiltration** (Exfiltration Controls 0.37 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=254.00' (Free Discharge)
└**2=Culvert** ( Controls 0.00 cfs)
  ├**3=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)
  ├**4=Orifice/Grate** ( Controls 0.00 cfs)
  └**5=Orifice/Grate** ( Controls 0.00 cfs)

## Pond SC-1: SC-740-1 - Chamber Wizard Field A

**Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)**
Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf
Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing


17 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 122.66' Row Length +12.0" End Stone x 2 = 124.66' Base Length
11 Rows x 51.0" Wide + 6.0" Spacing x 10 + 12.0" Side Stone x 2 = 53.75' Base Width
6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

187 Chambers x 45.9 cf = 8,590.8 cf Chamber Storage


23,451.0 cf Field - 8,590.8 cf Chambers = 14,860.3 cf Stone x 35.0% Voids = 5,201.1 cf Stone Storage

Chamber Storage + Stone Storage = 13,791.9 cf = 0.317 af
Overall Storage Efficiency = 58.8%
Overall System Size = 124.66' x 53.75' x 3.50'

187 Chambers
868.6 cy Field
550.4 cy Stone



## Pond SC-1: SC-740-1



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment PR-1: PR-1** Runoff Area=49,964 sf 71.52% Impervious Runoff Depth=3.17"
Tc=6.0 min CN=81 Runoff=4.10 cfs 0.303 af

**Subcatchment PR-1A: PR-1A** Runoff Area=7,996 sf 9.52% Impervious Runoff Depth=0.51"
Tc=6.0 min CN=45 Runoff=0.05 cfs 0.008 af

**Subcatchment PR-1B: PR-1B** Runoff Area=17,472 sf 100.00% Impervious Runoff Depth=4.97"
Tc=6.0 min CN=98 Runoff=1.93 cfs 0.166 af

**Subcatchment PR-2: PR-2** Runoff Area=62,177 sf 25.34% Impervious Runoff Depth=0.96"
Flow Length=293' Tc=8.2 min CN=53 Runoff=1.18 cfs 0.114 af

**Reach DP: DESIGN POINT** Inflow=1.26 cfs 0.190 af
Outflow=1.26 cfs 0.190 af

**Pond SC-1: SC-740-1** Peak Elev=255.66' Storage=7,359 cf Inflow=6.07 cfs 0.477 af
Discarded=0.37 cfs 0.401 af Primary=0.41 cfs 0.076 af Outflow=0.78 cfs 0.477 af

**Total Runoff Area = 3.159 ac Runoff Volume = 0.591 af Average Runoff Depth = 2.25"**
**49.33% Pervious = 1.558 ac 50.67% Impervious = 1.601 ac**

## Summary for Subcatchment PR-1: PR-1


Runoff = 4.10 cfs @ 12.13 hrs, Volume= 0.303 af, Depth= 3.17"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 35,732 | 98 | Paved parking, HSG A |
| 14,232 | 39 | >75% Grass cover, Good, HSG A |
| 49,964 | 81 | Weighted Average |
| 14,232 | | 28.48% Pervious Area |
| 35,732 | | 71.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment PR-1: PR-1



## Summary for Subcatchment PR-1A: PR-1A


Runoff = 0.05 cfs @ 12.17 hrs, Volume= 0.008 af, Depth= 0.51"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 761 | 98 | Paved parking, HSG A |
| 7,235 | 39 | >75% Grass cover, Good, HSG A |
| 7,996 | 45 | Weighted Average |
| 7,235 | | 90.48% Pervious Area |
| 761 | | 9.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

## Subcatchment PR-1A: PR-1A



## Summary for Subcatchment PR-1B: PR-1B


Runoff = 1.93 cfs @ 12.13 hrs, Volume= 0.166 af, Depth= 4.97"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 17,472 | 98 | Roofs, HSG A |
| 17,472 | | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment PR-1B: PR-1B



## Summary for Subcatchment PR-2: PR-2


Runoff = 1.18 cfs @ 12.17 hrs, Volume= 0.114 af, Depth= 0.96"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 10 Year Rainfall=5.21"

| Area (sf) | CN | Description |
|---|---|---|
| 15,756 | 98 | Paved parking, HSG A |
| 42,784 | 39 | >75% Grass cover, Good, HSG A |
| 3,637 | 30 | Woods, Good, HSG A |
| 62,177 | 53 | Weighted Average |
| 46,421 | | 74.66% Pervious Area |
| 15,756 | | 25.34% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 4.7 | 50 | 0.0290 | 0.18 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 243 | 0.0280 | 1.17 | | **Shallow Concentrated Flow, Shallow Concentrated Flow** Short Grass Pasture Kv= 7.0 fps |
| 8.2 | 293 | Total | | | |

## Subcatchment PR-2: PR-2




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.159 ac, 50.67% Impervious, Inflow Depth = 0.72" for 10 Year event
Inflow = 1.26 cfs @ 12.19 hrs, Volume= 0.190 af
Outflow = 1.26 cfs @ 12.19 hrs, Volume= 0.190 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Reach DP: DESIGN POINT



## Summary for Pond SC-1: SC-740-1

Inflow Area = 1.732 ac, 71.54% Impervious, Inflow Depth = 3.31" for 10 Year event
Inflow = 6.07 cfs @ 12.13 hrs, Volume= 0.477 af
Outflow = 0.78 cfs @ 12.90 hrs, Volume= 0.477 af, Atten= 87%, Lag= 46.4 min
Discarded = 0.37 cfs @ 11.05 hrs, Volume= 0.401 af
Primary = 0.41 cfs @ 12.90 hrs, Volume= 0.076 af
Routed to Reach DP : DESIGN POINT

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
Peak Elev= 255.66' @ 12.90 hrs Surf.Area= 6,700 sf Storage= 7,359 cf

Plug-Flow detention time= 112.4 min calculated for 0.477 af (100% of inflow)
Center-of-Mass det. time= 112.4 min ( 913.5 - 801.1 )

| Volume | Invert | Avail.Storage | Storage Description |
|---|---|---|---|
| #1A | 254.00' | 5,201 cf | **53.75'W x 124.66'L x 3.50'H Field A**<br>23,451 cf Overall - 8,591 cf Embedded = 14,860 cf x 35.0% Voids |
| #2A | 254.50' | 8,591 cf | **ADS_StormTech SC-740 +Cap** x 187 Inside #1<br>Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf<br>Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap<br>187 Chambers in 11 Rows |
| | | 13,792 cf | Total Available Storage |

Storage Group A created with Chamber Wizard

| Device | Routing | Invert | Outlet Devices |
|---|---|---|---|
| #1 | Discarded | 254.00' | **2.410 in/hr Exfiltration over Surface area** |
| #2 | Primary | 254.50' | **12.0" Round Culvert**<br>L= 50.0' CPP, projecting, no headwall, Ke= 0.900<br>Inlet / Outlet Invert= 254.50' / 254.00' S= 0.0100 '/' Cc= 0.900<br>n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf |
| #3 | Device 2 | 257.00' | **4.0' long Sharp-Crested Rectangular Weir** 2 End Contraction(s) |
| #4 | Device 2 | 255.50' | **12.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |
| #5 | Device 2 | 255.00' | **4.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |

**Discarded OutFlow** Max=0.37 cfs @ 11.05 hrs HW=254.04' (Free Discharge)
└**1=Exfiltration** (Exfiltration Controls 0.37 cfs)

**Primary OutFlow** Max=0.41 cfs @ 12.90 hrs HW=255.66' (Free Discharge)
└**2=Culvert** (Passes 0.41 cfs of 2.43 cfs potential flow)
  ├**3=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)
  ├**4=Orifice/Grate** (Orifice Controls 0.11 cfs @ 1.37 fps)
  └**5=Orifice/Grate** (Orifice Controls 0.30 cfs @ 3.39 fps)

## Pond SC-1: SC-740-1 - Chamber Wizard Field A

**Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)**
Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf
Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing


17 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 122.66' Row Length +12.0" End Stone x 2 = 124.66' Base Length
11 Rows x 51.0" Wide + 6.0" Spacing x 10 + 12.0" Side Stone x 2 = 53.75' Base Width
6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

187 Chambers x 45.9 cf = 8,590.8 cf Chamber Storage


23,451.0 cf Field - 8,590.8 cf Chambers = 14,860.3 cf Stone x 35.0% Voids = 5,201.1 cf Stone Storage

Chamber Storage + Stone Storage = 13,791.9 cf = 0.317 af
Overall Storage Efficiency = 58.8%
Overall System Size = 124.66' x 53.75' x 3.50'

187 Chambers
868.6 cy Field
550.4 cy Stone



## Pond SC-1: SC-740-1



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment PR-1: PR-1** Runoff Area=49,964 sf 71.52% Impervious Runoff Depth=4.19"
Tc=6.0 min CN=81 Runoff=5.36 cfs 0.400 af

**Subcatchment PR-1A: PR-1A** Runoff Area=7,996 sf 9.52% Impervious Runoff Depth=0.94"
Tc=6.0 min CN=45 Runoff=0.14 cfs 0.014 af

**Subcatchment PR-1B: PR-1B** Runoff Area=17,472 sf 100.00% Impervious Runoff Depth=6.09"
Tc=6.0 min CN=98 Runoff=2.35 cfs 0.204 af

**Subcatchment PR-2: PR-2** Runoff Area=62,177 sf 25.34% Impervious Runoff Depth=1.55"
Flow Length=293' Tc=8.2 min CN=53 Runoff=2.13 cfs 0.184 af

**Reach DP: DESIGN POINT** Inflow=2.43 cfs 0.350 af
Outflow=2.43 cfs 0.350 af

**Pond SC-1: SC-740-1** Peak Elev=255.99' Storage=8,915 cf Inflow=7.84 cfs 0.618 af
Discarded=0.37 cfs 0.452 af Primary=1.29 cfs 0.166 af Outflow=1.66 cfs 0.618 af

**Total Runoff Area = 3.159 ac Runoff Volume = 0.802 af Average Runoff Depth = 3.05"**
**49.33% Pervious = 1.558 ac 50.67% Impervious = 1.601 ac**

## Summary for Subcatchment PR-1: PR-1


Runoff = 5.36 cfs @ 12.13 hrs, Volume= 0.400 af, Depth= 4.19"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 35,732 | 98 | Paved parking, HSG A |
| 14,232 | 39 | >75% Grass cover, Good, HSG A |
| 49,964 | 81 | Weighted Average |
| 14,232 | | 28.48% Pervious Area |
| 35,732 | | 71.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

## Subcatchment PR-1: PR-1



## Summary for Subcatchment PR-1A: PR-1A


Runoff = 0.14 cfs @ 12.15 hrs, Volume= 0.014 af, Depth= 0.94"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 761 | 98 | Paved parking, HSG A |
| 7,235 | 39 | >75% Grass cover, Good, HSG A |
| 7,996 | 45 | Weighted Average |
| 7,235 | | 90.48% Pervious Area |
| 761 | | 9.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment PR-1A: PR-1A



## Summary for Subcatchment PR-1B: PR-1B


Runoff = 2.35 cfs @ 12.13 hrs, Volume= 0.204 af, Depth= 6.09"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 17,472 | 98 | Roofs, HSG A |
| 17,472 | | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment PR-1B: PR-1B



## Summary for Subcatchment PR-2: PR-2


Runoff = 2.13 cfs @ 12.16 hrs, Volume= 0.184 af, Depth= 1.55"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 25 Year Rainfall=6.33"

| Area (sf) | CN | Description |
|---|---|---|
| 15,756 | 98 | Paved parking, HSG A |
| 42,784 | 39 | >75% Grass cover, Good, HSG A |
| 3,637 | 30 | Woods, Good, HSG A |
| 62,177 | 53 | Weighted Average |
| 46,421 | | 74.66% Pervious Area |
| 15,756 | | 25.34% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 4.7 | 50 | 0.0290 | 0.18 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 243 | 0.0280 | 1.17 | | **Shallow Concentrated Flow, Shallow Concentrated Flow** Short Grass Pasture Kv= 7.0 fps |
| 8.2 | 293 | Total | | | |

## Subcatchment PR-2: PR-2




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.159 ac, 50.67% Impervious, Inflow Depth = 1.33" for 25 Year event
Inflow = 2.43 cfs @ 12.19 hrs, Volume= 0.350 af
Outflow = 2.43 cfs @ 12.19 hrs, Volume= 0.350 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Reach DP: DESIGN POINT



## Summary for Pond SC-1: SC-740-1

Inflow Area = 1.732 ac, 71.54% Impervious, Inflow Depth = 4.28" for 25 Year event
Inflow = 7.84 cfs @ 12.13 hrs, Volume= 0.618 af
Outflow = 1.66 cfs @ 12.52 hrs, Volume= 0.618 af, Atten= 79%, Lag= 23.3 min
Discarded = 0.37 cfs @ 10.75 hrs, Volume= 0.452 af
Primary = 1.29 cfs @ 12.52 hrs, Volume= 0.166 af
Routed to Reach DP : DESIGN POINT

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
Peak Elev= 255.99' @ 12.52 hrs Surf.Area= 6,700 sf Storage= 8,915 cf

Plug-Flow detention time= 107.1 min calculated for 0.618 af (100% of inflow)
Center-of-Mass det. time= 107.0 min ( 903.0 - 796.0 )

| Volume | Invert | Avail.Storage | Storage Description |
|---|---|---|---|
| #1A | 254.00' | 5,201 cf | **53.75'W x 124.66'L x 3.50'H Field A**<br>23,451 cf Overall - 8,591 cf Embedded = 14,860 cf x 35.0% Voids |
| #2A | 254.50' | 8,591 cf | **ADS_StormTech SC-740 +Cap** x 187 Inside #1<br>Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf<br>Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap<br>187 Chambers in 11 Rows |
| | | 13,792 cf | Total Available Storage |

Storage Group A created with Chamber Wizard

| Device | Routing | Invert | Outlet Devices |
|---|---|---|---|
| #1 | Discarded | 254.00' | **2.410 in/hr Exfiltration over Surface area** |
| #2 | Primary | 254.50' | **12.0" Round Culvert**<br>L= 50.0' CPP, projecting, no headwall, Ke= 0.900<br>Inlet / Outlet Invert= 254.50' / 254.00' S= 0.0100 '/' Cc= 0.900<br>n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf |
| #3 | Device 2 | 257.00' | **4.0' long Sharp-Crested Rectangular Weir** 2 End Contraction(s) |
| #4 | Device 2 | 255.50' | **12.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |
| #5 | Device 2 | 255.00' | **4.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |

**Discarded OutFlow** Max=0.37 cfs @ 10.75 hrs HW=254.04' (Free Discharge)
└**1=Exfiltration** (Exfiltration Controls 0.37 cfs)

**Primary OutFlow** Max=1.28 cfs @ 12.52 hrs HW=255.99' (Free Discharge)
└**2=Culvert** (Passes 1.28 cfs of 2.97 cfs potential flow)
  ├**3=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)
  ├**4=Orifice/Grate** (Orifice Controls 0.90 cfs @ 2.38 fps)
  └**5=Orifice/Grate** (Orifice Controls 0.38 cfs @ 4.36 fps)

## Pond SC-1: SC-740-1 - Chamber Wizard Field A

**Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)**
Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf
Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing


17 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 122.66' Row Length +12.0" End Stone x 2 = 124.66' Base Length
11 Rows x 51.0" Wide + 6.0" Spacing x 10 + 12.0" Side Stone x 2 = 53.75' Base Width
6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

187 Chambers x 45.9 cf = 8,590.8 cf Chamber Storage


23,451.0 cf Field - 8,590.8 cf Chambers = 14,860.3 cf Stone x 35.0% Voids = 5,201.1 cf Stone Storage

Chamber Storage + Stone Storage = 13,791.9 cf = 0.317 af
Overall Storage Efficiency = 58.8%
Overall System Size = 124.66' x 53.75' x 3.50'

187 Chambers
868.6 cy Field
550.4 cy Stone



## Pond SC-1: SC-740-1



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment PR-1: PR-1** Runoff Area=49,964 sf 71.52% Impervious Runoff Depth=5.80"
Tc=6.0 min CN=81 Runoff=7.30 cfs 0.554 af

**Subcatchment PR-1A: PR-1A** Runoff Area=7,996 sf 9.52% Impervious Runoff Depth=1.77"
Tc=6.0 min CN=45 Runoff=0.33 cfs 0.027 af

**Subcatchment PR-1B: PR-1B** Runoff Area=17,472 sf 100.00% Impervious Runoff Depth=7.82"
Tc=6.0 min CN=98 Runoff=2.99 cfs 0.261 af

**Subcatchment PR-2: PR-2** Runoff Area=62,177 sf 25.34% Impervious Runoff Depth=2.61"
Flow Length=293' Tc=8.2 min CN=53 Runoff=3.83 cfs 0.310 af

**Reach DP: DESIGN POINT** Inflow=6.26 cfs 0.635 af
Outflow=6.26 cfs 0.635 af

**Pond SC-1: SC-740-1** Peak Elev=256.55' Storage=11,277 cf Inflow=10.62 cfs 0.843 af
Discarded=0.37 cfs 0.518 af Primary=3.29 cfs 0.324 af Outflow=3.67 cfs 0.843 af

**Total Runoff Area = 3.159 ac Runoff Volume = 1.153 af Average Runoff Depth = 4.38"**
**49.33% Pervious = 1.558 ac 50.67% Impervious = 1.601 ac**

## Summary for Subcatchment PR-1: PR-1


Runoff = 7.30 cfs @ 12.13 hrs, Volume= 0.554 af, Depth= 5.80"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 35,732 | 98 | Paved parking, HSG A |
| 14,232 | 39 | >75% Grass cover, Good, HSG A |
| 49,964 | 81 | Weighted Average |
| 14,232 | | 28.48% Pervious Area |
| 35,732 | | 71.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

### Subcatchment PR-1: PR-1



## Summary for Subcatchment PR-1A: PR-1A


Runoff = 0.33 cfs @ 12.14 hrs, Volume= 0.027 af, Depth= 1.77"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 761 | 98 | Paved parking, HSG A |
| 7,235 | 39 | >75% Grass cover, Good, HSG A |
| 7,996 | 45 | Weighted Average |
| 7,235 | | 90.48% Pervious Area |
| 761 | | 9.52% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

## Subcatchment PR-1A: PR-1A



## Summary for Subcatchment PR-1B: PR-1B


Runoff = 2.99 cfs @ 12.13 hrs, Volume= 0.261 af, Depth= 7.82"
Routed to Pond SC-1 : SC-740-1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 17,472 | 98 | Roofs, HSG A |
| 17,472 | | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 6.0 | | | | | **Direct Entry, Direct Entry** |

## Subcatchment PR-1B: PR-1B



## Summary for Subcatchment PR-2: PR-2


Runoff = 3.83 cfs @ 12.16 hrs, Volume= 0.310 af, Depth= 2.61"
Routed to Reach DP : DESIGN POINT

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
NOAA 24-hr D 100 Year Rainfall=8.06"

| Area (sf) | CN | Description |
|---|---|---|
| 15,756 | 98 | Paved parking, HSG A |
| 42,784 | 39 | >75% Grass cover, Good, HSG A |
| 3,637 | 30 | Woods, Good, HSG A |
| 62,177 | 53 | Weighted Average |
| 46,421 | | 74.66% Pervious Area |
| 15,756 | | 25.34% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|---|---|---|---|---|---|
| 4.7 | 50 | 0.0290 | 0.18 | | **Sheet Flow, Sheet Flow** Grass: Short n= 0.150 P2= 3.41" |
| 3.5 | 243 | 0.0280 | 1.17 | | **Shallow Concentrated Flow, Shallow Concentrated Flow** Short Grass Pasture Kv= 7.0 fps |
| 8.2 | 293 | Total | | | |

## Subcatchment PR-2: PR-2




## Summary for Reach DP: DESIGN POINT

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 3.159 ac, 50.67% Impervious, Inflow Depth = 2.41" for 100 Year event
Inflow = 6.26 cfs @ 12.20 hrs, Volume= 0.635 af
Outflow = 6.26 cfs @ 12.20 hrs, Volume= 0.635 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Reach DP: DESIGN POINT



## Summary for Pond SC-1: SC-740-1

Inflow Area = 1.732 ac, 71.54% Impervious, Inflow Depth = 5.84" for 100 Year event
Inflow = 10.62 cfs @ 12.13 hrs, Volume= 0.843 af
Outflow = 3.67 cfs @ 12.32 hrs, Volume= 0.843 af, Atten= 65%, Lag= 11.3 min
Discarded = 0.37 cfs @ 10.05 hrs, Volume= 0.518 af
Primary = 3.29 cfs @ 12.32 hrs, Volume= 0.324 af
Routed to Reach DP : DESIGN POINT

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
Peak Elev= 256.55' @ 12.32 hrs Surf.Area= 6,700 sf Storage= 11,277 cf

Plug-Flow detention time= 98.4 min calculated for 0.842 af (100% of inflow)
Center-of-Mass det. time= 98.4 min ( 888.1 - 789.7 )

| Volume | Invert | Avail.Storage | Storage Description |
|---|---|---|---|
| #1A | 254.00' | 5,201 cf | **53.75'W x 124.66'L x 3.50'H Field A**<br>23,451 cf Overall - 8,591 cf Embedded = 14,860 cf x 35.0% Voids |
| #2A | 254.50' | 8,591 cf | **ADS_StormTech SC-740 +Cap** x 187 Inside #1<br>Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf<br>Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap<br>187 Chambers in 11 Rows |
| | | 13,792 cf | Total Available Storage |

Storage Group A created with Chamber Wizard

| Device | Routing | Invert | Outlet Devices |
|---|---|---|---|
| #1 | Discarded | 254.00' | **2.410 in/hr Exfiltration over Surface area** |
| #2 | Primary | 254.50' | **12.0" Round Culvert**<br>L= 50.0' CPP, projecting, no headwall, Ke= 0.900<br>Inlet / Outlet Invert= 254.50' / 254.00' S= 0.0100 '/' Cc= 0.900<br>n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf |
| #3 | Device 2 | 257.00' | **4.0' long Sharp-Crested Rectangular Weir** 2 End Contraction(s) |
| #4 | Device 2 | 255.50' | **12.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |
| #5 | Device 2 | 255.00' | **4.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads |

**Discarded OutFlow** Max=0.37 cfs @ 10.05 hrs HW=254.04' (Free Discharge)
└**1=Exfiltration** (Exfiltration Controls 0.37 cfs)

**Primary OutFlow** Max=3.28 cfs @ 12.32 hrs HW=256.54' (Free Discharge)
└**2=Culvert** (Passes 3.28 cfs of 3.71 cfs potential flow)
  ├**3=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)
  ├**4=Orifice/Grate** (Orifice Controls 2.79 cfs @ 3.55 fps)
  └**5=Orifice/Grate** (Orifice Controls 0.49 cfs @ 5.65 fps)

## Pond SC-1: SC-740-1 - Chamber Wizard Field A

**Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)**
Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf
Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing


17 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 122.66' Row Length +12.0" End Stone x 2 = 124.66' Base Length
11 Rows x 51.0" Wide + 6.0" Spacing x 10 + 12.0" Side Stone x 2 = 53.75' Base Width
6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

187 Chambers x 45.9 cf = 8,590.8 cf Chamber Storage


23,451.0 cf Field - 8,590.8 cf Chambers = 14,860.3 cf Stone x 35.0% Voids = 5,201.1 cf Stone Storage

Chamber Storage + Stone Storage = 13,791.9 cf = 0.317 af
Overall Storage Efficiency = 58.8%
Overall System Size = 124.66' x 53.75' x 3.50'

187 Chambers
868.6 cy Field
550.4 cy Stone



## Pond SC-1: SC-740-1



# APPENDIX D

**Closed Drainage System Design**

**The Rational Method for Closed Drainage System Design**

The Rational Method is a widely accepted rainfall-runoff model used for estimating peak design flows when modeling closed drainage system hydraulics. It is typically used when analyzing runoff rates from drainage areas to individual catch basins due to its simplicity and advantages on smaller scales over other models. Nitsch Engineering used the Rational Method for the project stormwater calculations to estimate the runoff into catch basins and the closed drainage system.

The general formula for the rational method is:

$$Q = C\,i\,A$$

where

$Q$ = *volumetric rate of runoff, in cubic feet per second*
$C$ = *dimensionless runoff coefficient*
$i$ = *peak rainfall intensity, in inches per hour*
$A$ = *contributing drainage area (subcatchment), in acres*

The volumetric flow rate $Q$ at which the runoff reaches a catch basin or other drainage inlet is determined by a number of factors: the slope and flow lengths of the subcatchment area, the soil type, the surface cover and size of the subcatchment area, and the chosen rainfall return period and associated intensity.

**Drainage Areas**

A drainage area, or subcatchment, is a portion of land that contributes runoff to a catch basin, inlet or another design point. This design point is the focus of the runoff analysis for that individual subcatchment and is considered to be the outflow point for the subcatchment. Peak rates of runoff are calculated at this point and then used to model the receiving pipe network hydraulics to determine pipe sizes, rates of flow, and velocities.

**The Runoff Coefficient**

The dimensionless runoff coefficient $C$ is determined from a number of factors which are generally related to the surface cover of each individual subcatchment. The surface cover on a site is defined as impervious or pervious and can take the form of lawn, roof, pavement, brush, woods, etc.

Certain types of cover create more opportunities for water to be absorbed into the ground. A site covered with impermeable surfaces, such as pavement, typically has a runoff coefficient of 0.90. This value implies that almost all of the rain that falls on pavement or other impermeable covers will be converted to runoff. A site covered by permeable surfaces, such as grass or other landscaping, will allow some of the water to be absorbed into the ground and can have coefficients which vary from 0.20-0.40 reflecting the associated reduction of runoff due to absorption. These different cover types within a drainage area are assigned a runoff coefficient and then weighted to determine an overall drainage area runoff coefficient $C$ for each subcatchment.

**Flow Length and Time of Concentration**

As rainfall lands on a portion of the drainage area and produces runoff, this runoff must travel to across the surface to the point of discharge, such as a catch basin, before contributing to the closed drainage hydraulic model. To achieve a maximum flow rate from a subcatchment using the Rational Method, all portions of a drainage area must first contribute to the discharge point. This point in time is known as the *time of concentration* and is determined by identifying the longest flow path of a watershed with respect to the time of travel. To do this, Nitsch Engineering reviewed several factors of each watershed, including slope, surface cover type, and length and types of flow. As is standard practice, the analysis assumes a minimum time of concentration of six minutes for any subcatchment.

The type of surface along the runoff flow path affects the time of concentration. In general, “smooth” surfaces such as roofs and pavements will offer less resistance to flow allowing for runoff to move more quickly. “Rough” surfaces such as lawns or woods offer more resistance to flow, and therefore runoff typically moves more slowly across these types of surfaces.

In addition, runoff travels across the surface of a drainage area in two types of flow geometry. “Sheet” flow occurs over short distances, typically up to a maximum of fifty feet. Sheet flow is generally very shallow and spreads out across a wide flow path. An example of sheet flow is the runoff between the crown of a roadway to the curb and gutter. Sheet flow eventually gathers together and channelizes into “shallow concentrated” flow which carries runoff more quickly. Flow in the gutter of a road is an example of shallow concentrated flow.

The slope of the shallow concentrated or sheet flow path also affects the travel time. A site with steep slopes will produce more runoff and transport it at a faster rate than a flat site. The slope of the site is easily determined by using an existing conditions survey, proposed grading plans, or by a field examination.

**Rainfall Intensity-Duration-Frequency Curves**

Rainfall Intensity-Duration-Frequency curves, or IDF curves, describe the probabilistic relationships between average rainfall peak intensities, the duration of the watershed analysis, and the frequency (in years) at which the peak intensity should be expected. The *intensity* of a storm refers to the average rate at which rainfall lands on the surface of a drainage area, typically measured in inches of rainfall per hour. A higher intensity will produce more runoff. For the rational method, *duration* refers to the length of time between the start of the analysis and the point of time when the entire watershed contributes to the discharge point and is equal to the time of concentration. A longer duration lowers the intensity value and therefore the peak runoff rate. The *frequency*, or return period, refers to the average number of years between occurrences of a specified peak intensity. For example, if rainfall intensities of equal to or greater than six inches per hour were recorded ten times over a 100-year period, then the return period (frequency) of a 6-inch rainfall would be once every ten years. Put more simply, this is known as a “10-year” storm and has a 1/10, or 10%, statistical chance of occurring during any given year.

IDF curves are important to stormwater designers when developing closed drainage system models. They provide a meaningful basis for use when considering the cost-benefit relationships for new stormwater infrastructure and the flood risk associated with the chosen return period. Nitsch

Engineering uses the Steel Formula to develop IDF curves. The Steel Formula is an empirical equation based in historic rainfall data and is used for defining the Intensity-Duration-Frequency relationships depending on the proposed return periods. For the project, Nitsch Engineering has determined that a 25-year Steel Formula Intensity-Duration-Frequency curve is appropriate for design.

**AutoDesk® Storm and Sanitary Analysis Software v. 6.4**

Nitsch Engineering used AutoDesk® Storm and Sanitary Analysis Software ("SSA") to estimate storm system inflows by the Rational Method and to size, the proposed closed drainage systems. SSA contains several hydraulic modeling capabilities used to route calculated runoff through drainage system networks

**SSA & Free-Flow in Storm Pipes**

The closed drainage system has been designed to maintain free-flow conditions. Stormwater in drainage system pipes is considered to be "free-flowing" when the upstream and downstream ends of the pipes are not submerged and the flow within the pipe is below the capacity of the pipe. For these cases, SSA calculates the storm pipe capacity using *Manning's Equation* which considers pipe slope, material, and interior pipe diameter to estimate capacity. In general, when pipe diameters and slopes increase, capacities increase. Rougher pipe materials will create greater frictional forces which restrict flow when compared to smoother pipe materials. Using Manning's Equation, SSA also calculates the water surface elevation through pipes and at the pipe beginning and end. This elevation is more commonly known as the "Hydraulic Grade Line" or "HGL" and helps determine flow conditions and losses through pipe systems.

Stormwater in drainage system pipes is considered to be "surcharged" when the outlet is submerged or when the flow through the pipe is greater than the capacity of the pipe, thus submerging the inlet. These scenarios create different calculations for capacities through the pipes that must be considered when there is a tidal or submerged outlet condition.

As a general rule, water will seek a stable level. In submerged storm pipes, water will flow from the end of the pipe with the higher water elevation to the end with the lower water elevation until these two elevations are equal and no new flow is introduced into the system. Along with the diameter, material, and slope of the pipe, in submerged flow, the difference in elevation between the HGL at the pipe inlet and HGL at the pipe outlet influences the volumetric rate of flow through the pipe. It is important for design engineers to understand this relationship to properly estimate the size of storm pipes to prevent the HGL from rising above the rims of design structures and flooding the surface. For these cases, SSA uses the *St. Venant Equations* to simultaneously determine the storm system capacities with relation to the upstream and downstream HGLs for all pipes, structures, and outlets in the systems.]

**SSA & Manning's Equation**

SSA software uses *Manning's Equation* to calculate the full flow capacity of pipes. *Manning's Equation* is a regularly used formula to calculate the flow within stormwater pipes for free flow conditions. It is commonly written as:

$$Q = {}^{1.49}/_{n}\, A\, R^{2/3}\, S^{1/2}$$

where

| | | | | | |
|---|---|---|---|---|---|
| $Q$ | = | *volumetric capacity of flow* | $n$ | = | *pipe roughness factor* |
| $A$ | = | *cross-sectional area of pipe at full flow* | $R$ | = | *hydraulic radius at full flow* |
| $S$ | = | *pipe slope* | | | |

It should be noted that the inclusion of the cross-sectional pipe flow area *A* is a common modification to the standard *Manning's Equation*. The pipe flow area may be removed from the formula to calculate velocity *V* of flow within the pipe. The addition of flow area allows stormwater designers to understand the distance at which a two-dimensional area *A* can move through a pipe over a given time period, typically measured in one second. This enables the calculation of a volumetric flow rate *Q.* For example, if a pipe has a cross-sectional flow area *A* of two square feet and the calculated velocity *V* through the pipe is five feet per second, then the distance that this two square foot area "moves" in one second is five feet. This creates an imaginary cylinder of water that is five feet long. Therefore, the volume of water that flows through the pipe over this one second time period is equal to two square feet multiplied by five lineal feet, or ten cubic feet. This is important to engineers because it allows the design of stormwater systems to relate to the hydrology calculations which are similarly measured in volumetric flow rates.

A quick assessment of the equation reveals that the pipe geometry and material are significant factors in determining the capacity of flow. The pipe roughness factor, *n*, is an experimentally derived value related to the chosen pipe material. Many elements affect this, including age and condition, material, and shape of the pipe wall (ie, corrugated interiors versus smooth-walled pipes). Generally, as roughness factor increases, the frictional resistance to flow through the pipe increases, thus lowering overall speed of flow and capacity.

When considering this frictional resistance, it is important to note that resistance only occurs along the surfaces of contact between the water flow area and the pipe wall. This contact surface is known as the wetted perimeter. For full flow in circular pipes, this is considered to be the perimeter of the interior pipe wall and is equal to the diameter of the pipe multiplied by pi.

The wetted perimeter is a significant factor in determining actual flow through a pipe when the pipe is not flowing full, as the surface of the water in the pipe does not contact a pipe wall or contribute to the frictional resistance. The equation accounts for this by applying a ratio of the area of flow to the actual wetted perimeter, otherwise known as the hydraulic radius, or *R.* In the case of full circular pipe flow, the hydraulic radius is equal to the diameter of the pipe divided by four.

The pipe flow area, or *A*, defines the two-dimensional space within the pipe that can be used to pass stormwater flow. Logically, the larger the area and pipe diameter, the greater volume of water the pipe can transmit over a given time period.

**SSA & the St. Venant Equations**

Flow in submerged pipes acts differently than flow within unsubmerged, or free-flow, pipe systems. As such, when the inflow into a pipe system is greater than the free flow capacity of the pipe calculated using *Manning's Equation*, a different set of equations and rules govern the flow capacity.

This is important for engineers to understand when developing estimates for the hydraulic grade line within a storm sewer. The Saint Venant Equations include:

the *Continuity Equation; and*

$$v\frac{\partial A}{\partial x} + A\frac{\partial v}{\partial x} + b\frac{\partial h}{\partial t} = 0$$

the *Dynamic*, or *Momentum, Equation*

$$g\frac{\partial h}{\partial x} + v\frac{\partial v}{\partial x} + \frac{\partial v}{\partial t} = g(i - j)$$

Though they appear complex, the *Continuity Equation* and the *Momentum Equation* describe fundamental principles of stormwater flow which are easily understood. Therefore, it is beyond the scope of this document to define all of the terms and mathematical derivations of the partial differential formulas – rather, the intention is to explain, in relative terms, what each equation means to the SSA calculations and the data contained within the reports.

*The Continuity Equation and Stormwater*

Water is considered to be an incompressible fluid. When the normal pressures, like those found in submerged stormwater flow, are applied to a volume of water in a closed system or container, the applied pressure does not change the volume of the water. Therefore, the addition of water to a closed drainage system cannot change the volume of the water already contained within the system but must either be stored within free spaces of the pipes and manholes or flow out of the system. The *Continuity Equation,* when applied to stormwater flow, simply means that the volume of water entering the drainage system is equal to the volume of water which leaves the system over a defined period of time. This principle applies regardless of the depth at the inlets and outlets of pipes.

*The Momentum Equation and Stormwater*

A specific volume of stormwater moving through a storm pipe generates a physical property known as *momentum*. Momentum is composed of two characteristics of this flow, velocity, and mass, and can be described in mathematical terms as velocity multiplied by mass. The *Momentum Equation* states that the momentum generated by a certain volume of stormwater at the upstream end of a pipe must equal the momentum at the downstream end of the pipe. This is important to stormwater models when determining the change in area and depth when the flow of certain cross-sectional area, speed, and depth (ie, from an unsubmerged, 12-inch pipe) interacts with a downstream condition with different characteristics (ie, at a static tidal condition).

Taken together, SSA uses both equations to explain how velocities through pressurized pipes must increase as flow rates increase and vice versa. These conservation principles mean that a) when two or more flow patterns with different cross-sections and velocities interact, the resulting flow pattern maintains the summation of momentum from these flow areas and b) when two or more flow patterns with different flow rates interact, the resulting flow rate will be equal to the summation of the contributing flow rates.

**SSA & Modeling of Hydraulic Losses**

Hydraulic Losses through a closed storm drainage network refer to the actions of natural forces which work to restrict flow rates and velocities or otherwise alter the nature of flow in pipe systems. Losses are important to stormwater design because they change the depth of flow in pipes,

sometimes significantly, and must be factored into flow systems to obtain accurate hydraulic grade lines and minimize the occurrence of street flooding.

Friction between the moving column of water and pipe wall is more commonly known as *major losses*. Flow through storm pipes is generally accomplished by the pull of gravity on the water in the pipe acting to accelerate it from the higher end of the pipe to the lower end. The force of friction between the water and the pipe acts to resist the pull of gravity, and this resistance increases with the velocity of flow. As such, the pull of gravity can either be greater than the pull of friction (*subcritical flow)* or the pull of friction can be greater than the pull of gravity (*supercritical flow).* Subcritical flow tends to be deeper and slower, and supercritical flow tends to be shallower and faster. SSA uses *Manning's Equation* to determine the relationships between flow depth and velocity in free-flow conditions. In addition, SSA is able to determine the point at which friction forces overcome gravitational forces causing a *hydraulic jump,* or a point in the flow regime where depth quickly increases and flow quickly decreases due to a rapid change in velocity. In submerged pipe flow, the pressure of the elevated water column within an upstream structure acts to push flow through the pipe. SSA uses the Saint Venant equations to estimate flow rates through these pipes, then applies the calculated velocity to a form of the *Manning's Equation* to determine the loss in the pipe due to friction. Major losses in submerged pipes tend to be larger than major losses in free-flowing pipes because of the increases in velocity required to push stormwater through the drain line.

Other types of losses include changes in the flow direction or flow cross-section, such as bends, expansions from smaller to larger pipes, or entrances to or exits from storm drainage structures like manholes. These are more commonly known as *minor losses*. For the calculation of minor losses, SSA uses scientifically derived formulas which are typical of the industry.

Losses are measured in units of length, typically in linear feet for closed system design. This is easily understood when considering that the speed of the water at the outfall of a pipe is directly calculated from the change in vertical distance over which gravity acts. Typically, the larger this change in height, the steeper the slope of the pipe, and the faster the column of water will travel through the pipe. In submerged flow assuming a constant velocity, the difference in real elevation between the downstream structure's HGL and the upstream structure's HGL is generally equal to the sum of the losses minus the change in height from the pipe beginning to end. Over long distances, these losses can become substantial, in the order of several feet. SSA uses this information and applies it to the height of vertical columns of water in closed drainage systems to determine actual HGLs relative to the rim grades of structures.

**AutoDesk® Storm and Sanitary Analysis: Understanding this Report**

Nitsch Engineering used AutoDesk® Storm and Sanitary Analysis Software ("SSA") to estimate storm system inflows by the Rational Method and to size, the proposed closed drainage systems. SSA contains several hydraulic modeling capabilities which are used to simultaneously route

calculated runoff through complicated drainage system networks. The software can support both free-flow and surcharged pipe conditions. The results of these analyses are automatically compiled into tabular reports by the program as described below. This document is intended to help explain the definition of terms and the interpretation in stormwater design.

The following includes definitions of the different reports, data, and terms as generated by the SSA model for this project.

**"Project Description" Section:**

File Name: The name of the stormwater model computer file

**"Rainfall Details" Section:**

Return Period: The selected return period of the IDF curve chosen for the hydrologic model

**"Subbasin Summary" Section:**

This section contains a summary of the inputs and calculations of all subbasins, or drainage areas, within the hydrology model.

SN: The assigned subbasin number

Subbasin ID: The name assigned to the subbasin

Area: The area of the drainage subbasin used to calculate the Peak Runoff Rate

Weighted Runoff Coefficient: The dimensionless Rational *C* value for the drainage subbasin reflecting the subbasin's surface cover and ability to absorb rainfall

Peak Runoff: The calculated volumetric flow rate using the Rational Method

Time of Concentration: The length of time between the start of the analysis and the time when the Peak Flow Rate *Q* is achieved

**"Link Summary" Section:**

This section contains a summary of the calculations for the closed drainage pipe network.

From (Inlet) Node: The upstream structure, or node, of the pipe

Inlet Invert Elevation: The elevation of the upstream invert of the pipe used to calculate Pipe Slope

To (Outlet) Node: The downstream structure, or node, of the pipe

Outlet Invert Elevation: The elevation of the downstream invert of the pipe used to calculate Pipe Slope

Length: The length of the pipe used to calculate the Pipe Slope

| | |
|---|---|
| Pipe Slope: | The slope of the pipe calculated by subtracting the Outlet Invert Elevation from the Inlet Invert Elevation and dividing by pipe Length |
| Pipe Diameter: | The interior diameter of the pipe used to calculate the Pipe Design Capacity, Peak Flow Velocity, and Peak Flow Depth |
| Manning's Roughness: | A dimensionless coefficient describing the relative roughness of the interior pipe surface as determined from the pipe material. This coefficient is used to calculate the Pipe Flow Velocity and Pipe Design Capacity |
| Peak Flow Q: | The peak volumetric flow rate through the pipe. This is calculated from the contributing subbasin hydrology. This is used to calculate Peak Flow Velocity, Q/Qf Ratio, and Peak Flow Depth |
| Peak Flow Velocity: | The average speed of the runoff moving through the pipe during Peak Flow |
| Pipe Design Capacity Qf: | The maximum capacity of the pipe as calculated using *Manning's Equation* |
| Q/Qf Ratio: | The ratio of the Peak Flow Q to Pipe Design Capacity Qf. Values of less than 1.00 indicate that the Peak Flow Rate Q does not exceed the capacity of the pipe. Values of greater than 1.00 indicate that the pipe is under capacity and flows under submerged conditions. |
| Peak Flow Depth: | The depth of the flow, in feet, as measured from the invert of the pipe at the point of maximum depth. For free flow conditions, this value is assumed to be uniform throughout the pipe. |

**"Subbasin Hydrology" Sections:**

These sections contain the full calculations and results for the individual subbasins, or drainage areas, including the Weighted Rational Coefficients, Times of Concentration, and Rational Method Runoff calculations that are included as a part of the hydrologic model and subbasin summary report.

## Rainfall Details

Return Period..... 25 year(s)

## Subbasin Summary

| Subbasin Name | Area (ac) | Weighted Runoff Coefficient | Peak Runoff (cfs) | Time of Concentration (days hh:mm:ss) |
|---|---|---|---|---|
| DA-AD-300 | 0.21 | 0.34 | 0.47 | 0 00:05:00 |
| DA-CB-200 | 0.24 | 0.90 | 1.42 | 0 00:05:00 |
| DA-CB-201 | 0.04 | 0.90 | 0.24 | 0 00:05:00 |
| DA-DCB-202A | 0.15 | 0.90 | 0.89 | 0 00:05:00 |
| DA-DCB-202B | 0.15 | 0.90 | 0.89 | 0 00:05:00 |
| DA-DCB-400 | 0.69 | 0.90 | 4.08 | 0 00:05:00 |
| DA-DCB-401 | 0.41 | 0.74 | 1.99 | 0 00:05:00 |
| DA-RD-1 | 0.20 | 0.90 | 1.18 | 0 00:05:00 |
| DA-RD-2 | 0.20 | 0.90 | 1.18 | 0 00:05:00 |
| DA-WQI-502 | 0.14 | 0.79 | 0.73 | 0 00:05:00 |

# Link Summary

| Pipe Name | From (Inlet) Node | Inlet Invert Elevation | To (Outlet) Node | Outlet Invert Elevation | Pipe Length | Pipe Slope | Pipe Diameter | Manning's Roughness | Peak Flow Q | Peak Flow Velocity | Pipe Design Capacity Qf | Q/Qf Ratio |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | (ft) | | (ft) | (ft) | (%) | (in) | | (cfs) | (ft/sec) | (cfs) | |
| Pipe - (133) | CB-201 | 247.30 | WQS-600 | 246.80 | 48 | 2.48 | 48 | 0.0120 | 0.23 | 2.62 | 6.08 | 0.04 |
| Pipe - (135) | CB-200 | 247.10 | WQS-600 | 246.80 | 48 | 1.41 | 48 | 0.0120 | 1.40 | 4.33 | 4.59 | 0.31 |
| Pipe - (136) | RD-1 | 258.00 | DMH-102 | 257.67 | 48 | 0.96 | 48 | 0.0120 | 1.15 | 2.92 | 3.78 | 0.31 |
| Pipe - (152) | AD-300 | 258.22 | DMH-102 | 257.67 | 48 | 1.02 | 48 | 0.0120 | 0.46 | 2.28 | 3.89 | 0.12 |
| Pipe - (157) | RD-2 | 258.00 | DMH-101 | 257.07 | 48 | 5.60 | 48 | 0.0120 | 1.18 | 3.72 | 9.13 | 0.13 |
| Pipe - (158) | DMH-101 | 256.97 | Out-1Pipe - (158) | 254.50 | 48 | 2.59 | 48 | 0.0120 | 1.85 | 6.49 | 6.21 | 0.30 |
| Pipe - (160) | WQI-502 | 257.50 | DMH-101 | 257.07 | 48 | 0.64 | 48 | 0.0120 | 0.70 | 2.99 | 3.08 | 0.23 |
| Pipe - (163) | DMH-102 | 257.57 | DMH-103 | 256.79 | 48 | 1.00 | 48 | 0.0120 | 1.57 | 4.26 | 3.86 | 0.41 |
| Pipe - (164) | DMH-103 | 256.69 | Out-1Pipe - (164) | 255.65 | 48 | 0.50 | 48 | 0.0120 | 1.51 | 3.47 | 2.73 | 0.55 |
| Pipe - (167) | DCB-400 | 256.15 | WQS-602 | 254.75 | 48 | 0.83 | 48 | 0.0120 | 3.99 | 5.08 | 3.52 | 1.13 |
| Pipe - (170) | DCB-402 | 245.40 | WQS-601 | 244.75 | 48 | 0.61 | 48 | 0.0120 | 1.69 | 3.71 | 3.02 | 0.56 |
| Pipe - (171) (1) | WQS-601 | 244.55 | DMH-104 | 244.15 | 48 | 0.51 | 48 | 0.0120 | 1.68 | 3.06 | 2.76 | 0.61 |
| Pipe - (173) | INF SYS | 256.00 | OCS-100 | 255.85 | 48 | 1.06 | 48 | 0.0120 | 0.00 | 0.00 | 3.97 | 0.00 |
| Pipe - (174) | OCS-100 | 255.85 | DMH-105 | 253.60 | 48 | 3.49 | 48 | 0.0120 | 0.00 | 0.00 | 7.21 | 0.00 |
| Pipe - (174) (1) | DMH-105 | 253.50 | DMH-104 | 250.00 | 48 | 3.80 | 48 | 0.0120 | 0.00 | 0.00 | 7.53 | 0.00 |
| Pipe - (175) | DCB-401 | 255.20 | WQS-602 | 254.75 | 48 | 0.94 | 48 | 0.0120 | 1.99 | 2.69 | 3.74 | 0.53 |
| Pipe - (176) | WQS-602 | 254.65 | Out-1Pipe - (176) | 254.50 | 48 | 0.59 | 48 | 0.0120 | 5.97 | 7.65 | 2.97 | 2.01 |
| Pipe - (178) | WQS-600 | 246.60 | DMH-104 | 246.30 | 48 | 1.68 | 48 | 0.0120 | 1.63 | 4.67 | 5.00 | 0.33 |
| Pipe - (179) | DMH-104 | 244.05 | Out-1Pipe - (179) | 243.78 | 48 | 0.97 | 48 | 0.0120 | 3.24 | 4.68 | 6.90 | 0.47 |

# Junction Input

| Juntion Name | Invert Elevation | Rim Elevation |
|---|---|---|
| | (ft) | (ft) |
| AD-300 | 258.22 | 261.00 |
| CB-200 | 247.10 | 254.30 |
| CB-201 | 247.30 | 254.15 |
| DCB-400 | 256.15 | 259.15 |
| DCB-401 | 255.20 | 258.70 |
| DCB-402 | 245.40 | 247.90 |
| DMH-101 | 256.97 | 261.96 |
| DMH-102 | 257.57 | 261.17 |
| DMH-103 | 256.69 | 262.00 |
| DMH-104 | 244.05 | 259.00 |
| DMH-105 | 253.50 | 256.55 |
| DMH-108 | 257.57 | 261.17 |
| INF SYS | 256.00 | 257.16 |
| OCS-100 | 255.85 | 258.45 |
| RD-1 | 258.00 | 259.16 |
| RD-2 | 258.00 | 259.16 |
| WQI-502 | 257.50 | 261.77 |
| WQS-600 | 246.60 | 253.85 |
| WQS-601 | 244.55 | 251.10 |
| WQS-602 | 254.65 | 258.55 |

## APPENDIX E

**Long-Term Pollution Prevention and Stormwater Operation and Maintenance Plan**
**(Provided Under Separate Cover)**

Nitsch Engineering

2 Center Plaza, Suite 430
Boston, MA 02108-1928
T: 617-338-0063
F: 617-338-6472
www.nitscheng.com

# LONG-TERM POLLUTION PREVENTION PLAN AND STORMWATER OPERATION AND MAINTENANCE PLAN

Stoughton Fire Station No. 1, Stoughton, MA

## TABLE OF CONTENTS

**1.0 INTRODUCTION ..... 1**

**2.0 LONG-TERM POLLUTION PREVENTION PLAN ..... 2**

2.1 Storage of Hazardous Materials ..... 2
2.2 Storage of Waste Products ..... 2
2.3 Spill Prevention and Response ..... 2
2.4 Minimize Soil Erosion ..... 2
2.5 Vehicle Washing ..... 2
2.6 Maintenance of Lawns, Gardens, and other Landscaped Areas ..... 3
2.7 Management of Deicing Chemicals and Snow ..... 3
2.8 Coordination with other Permits and Requirements ..... 3

**3.0 STORMWATER MANAGEMENT SYSTEM OPERATION AND MAINTENANCE PLAN 4**

3.1 Introduction ..... 4
3.2 Stormwater Operation and Maintenance Requirements ..... 4

Deep Sump and Hooded Catch Basins ..... 4
Area Drains ..... 5
Water Quality Units (Proprietary Separators) ..... 5
Subsurface Detention/Infiltration Structures/Perforated Pipe and Stone ..... 5
Stormwater Outfalls ..... 5

3.3 Street Sweeping ..... 5
3.4 Repair of the Stormwater Management System ..... 5
3.5 Reporting ..... 5

**STORMWATER MANAGEMENT SYSTEM INSPECTION FORM ..... 6**

## FIGURES

Figure 1 – Stormwater Management System Location Map
Figure 2 – Snow Storage Map

## 1.0 INTRODUCTION

The purpose of this document is to specify the pollution prevention measures and stormwater management system operation and maintenance for the Stoughton Fire Station No. 1 project site. The Responsible Party indicated below shall implement the management practices outlined in this document and proactively conduct operations at the project site in an environmentally responsible manner. Compliance with this Manual does not in any way dismiss the responsible party, owner, property manager, or occupants from compliance with other applicable federal, state or local laws.

Responsible Party: Marc Tisdelle
Interim Town Manager
10 Pearl Street, Stoughton, MA
781-341-1300

This Document has been prepared in compliance with Standards 4 and 9 of the 2008 Massachusetts Department of Environmental Protection (MassDEP) Stormwater Management Standards, which state:

Standard 4:
The Long Term Pollution Prevention Plan shall include the proper procedures for the following:

- Good housekeeping
- Storing materials and waste products inside or under cover
- Vehicle washing
- Routine inspections of stormwater best management practices
- Spill prevention and response
- Maintenance of lawns, gardens, and other landscaped areas
- Storage and use of fertilizers, herbicides, and pesticides
- Pet waste management
- Operation and management of septic systems
- Proper management of deicing chemicals and snow

Standard 9:
The Long-Term Operation and Maintenance Plan shall at a minimum include:

- Stormwater management system(s) owner(s)
- The party or parties responsible for operation and maintenance, including how future property owners shall be notified of the presence of the stormwater management system and the requirement for operation and maintenance
- The routine and non-routine maintenance tasks to be undertaken after construction is complete and a schedule for implementing those tasks
- A plan that is drawn to scale and shows the location of all stormwater BMPs in each treatment train along with the discharge point
- A description and delineation of public safety features
- An estimated operations and maintenance budget

## 2.0 LONG-TERM POLLUTION PREVENTION PLAN

The Responsible Party shall implement the following good housekeeping procedures at the project site to reduce the possibility of accidental releases and to reduce safety hazards.

### 2.1 Storage of Hazardous Materials

To prevent leaks and spills, keep hazardous materials and waste products under cover or inside. Use drip pans or spill containment systems to prevent chemicals from entering the drainage system. Inspect storage areas for materials and waste products at least once per year to determine amount and type of the material on site, and if the material requires disposal.

Securely store liquid petroleum products and other liquid chemicals in federally- and state-approved containers. Restrict access to maintenance personnel and administrators.

### 2.2 Storage of Waste Products

Collect and store all waste materials in securely lidded dumpster(s) or other secure containers as applicable to the material. Keep dumpster lids closed and the areas around them clean. Do not fill the dumpsters with liquid waste or hose them out. Sweep areas around the dumpster regularly and put the debris in the garbage, instead of sweeping or hosing it into the parking lot. Legally dispose of collected waste on a regular basis.

Segregate liquid wastes from solid waste and recycle through hazardous waste disposal companies, whenever possible. Contact a hazardous waste hauler for proper disposal to a hazardous waste collection center.

### 2.3 Spill Prevention and Response

Implement spill response procedures for releases of significant materials such as fuels, oils, or chemical materials onto the ground or other area that could reasonably be expected to discharge to surface or groundwater.

- For minor spills, keep fifty (50) gallon spill control kits and Speedy Dry at all shop and work areas.
- Immediately contact applicable Federal, State, and local agencies for reportable quantities as required by law.
- Immediately perform applicable containment and cleanup procedures following a spill release.
- Promptly remove and dispose of all material collected during the response in accordance with Federal, State and local requirements. A licensed emergency response contractor may be required to assist in cleanup of releases depending on the amount of the release, and the ability of the Contractor to perform the required response.
- Reportable quantities of chemicals, fuels, or oils are established under the Clean Water Act and enforced through Massachusetts Department of Environmental Protection (DEP).

### 2.4 Minimize Soil Erosion

Soil erosion facilitates mechanical transport of nutrients, pathogens, and organic matter to surface water bodies. Repair all areas where erosion is occurring throughout the project site. Stabilize bare soil with riprap, seed, mulch, or vegetation.

### 2.5 Vehicle Washing

Will not occur on site

### 2.6 Maintenance of Lawns, Gardens, and other Landscaped Areas

Pesticides and fertilizers shall not be used in the landscaped areas associated with the project site and shall not be stored on-site. Dumping of lawn wastes, brush or leaves or other materials or debris is not permitted in any Resource Area. Grass clippings, pruned branches and any other landscaped waste should be disposed of or composted in an appropriate location. No irrigation shall be used in the landscaped areas for this project.

### 2.7 Management of Deicing Chemicals and Snow

The qualified contractor selected for snow plowing and deicing shall be made fully aware of the requirements of this section.

No road salt (sodium chloride) shall be stored on-site. The use of magnesium chloride de-icing product with a 0.5 to 1.0 percent sodium chloride mix for snow and ice treatment is permitted. The product shall be stored in a locked room inside the building and shall be used at exterior stairs and walkways. The snow plow contractor shall adhere to these magnesium chloride use and storage requirements.

During typical snow plowing operations, snow shall be pushed to the designated snow removal areas noted on the Snow Storage Plan (Figure 2). Snow shall not be stockpiled in wetland resource areas or the 100-foot Buffer Zone, catch basins, or bioretention basins. In severe conditions where snow cannot be stockpiled on site, the snow shall be removed from the site and properly disposed of in accordance with DEP Guideline BRP601-01.

Use of sand is permitted only for impervious roadways and parking areas. If sand is applied, the snow plowed from impervious areas shall not be stored on porous asphalt.

Before winter begins, the property owner and the contractor shall review snow plowing, deicing, and stockpiling procedures. Areas designated for stockpiling should be cleaned of any debris. Street and parking lot sweeping should be followed in accordance with the Operation and Maintenance Plan.

### 2.8 Coordination with other Permits and Requirements

Certain conditions of other approvals affecting the long term management of the property shall be considered part of this Long Term Pollution Prevention Plan. The Owner shall become familiar with those documents and comply with the guidelines set forth in those documents.

## 3.0 STORMWATER MANAGEMENT SYSTEM OPERATION AND MAINTENANCE PLAN

### 3.1 Introduction

This Operation and Maintenance Plan (O&M Plan) for the Stoughton Fire Station No. 1 project site is required under Standard 9 of the 2008 MassDEP Stormwater Handbook to provide best management practices for implementing maintenance activities for the stormwater management system in a manner that minimizes impacts to wetland resource areas.

The Owner shall implement this O&M Plan and proactively conduct operations at the site in an environmentally responsible manner. Compliance with this O&M Plan does not in any way dismiss the Owner from compliance with other applicable Federal, State or local laws.

Routine maintenance during construction and post-development phases of the project, as defined in the Operation and Maintenance Plan, shall be permitted without amendment to the Order of Conditions. A continuing condition in the Certificate of Compliance shall ensure that maintenance can be performed without triggering further filings under the Wetlands Protection Act.

All stormwater best management practices (BMPs) shall be operated and maintained in accordance with the design plans and the Operation and Maintenance Plan approved by the issuing authority. The Owner shall:

a. Maintain an operation and maintenance log for the last three years, including inspections, repairs, replacement and disposal (for disposal the log shall indicate the type of material and the disposal location). This is a rolling log in which the responsible party records all operation and maintenance activities for the past three years.

b. Make this log available to MassDEP and the Conservation Commission upon request; and

c. Allow members and agents of the MassDEP and the Conservation Commission to enter and inspect the premises to evaluate and ensure that the Owner complies with the Operation and Maintenance requirements for each BMP.

### 3.2 Stormwater Operation and Maintenance Requirements

Inspect and maintain the stormwater management system as directed below. Refer to the Stormwater Management System Location Map (Figure 1) for the location of each component of the system. Repairs to any component of the system shall be made as soon as possible to prevent any potential pollutants (including silt) from entering the resource areas.

<u>Deep Sump and Hooded Catch Basins</u>

Inspect or clean catch basins four times per year and at the end of foliage and snow-removal seasons. Other inspection and maintenance requirements include:

- Remove organic material, sediment and hydrocarbons four times per year or whenever the depth of deposits is greater than or equal to one half the depth from the bottom of the invert of the lowest pipe in the basin.
- Always clean out catch basins after street sweeping. If any evidence of hydrocarbons is found during inspection, immediately remove the material using absorbent pads or other suitable measures and dispose of legally. Remove other accumulated debris as necessary.
- If handling runoff from land uses with higher potential pollutant loads or discharging runoff near or to a critical area, more frequent cleaning may be necessary.

- Transport and disposal of accumulated sediment off-site shall be in accordance with applicable local, state and federal guidelines and regulations.

Area Drains

Inspect area drains at least once per month and remove debris from the grate. Clean out accumulated sediments at least once per year and more frequently as necessary.

Water Quality Units (Proprietary Separators)

Maintain water quality units according to the recommendations set forth by the manufacturer. General inspection and maintenance procedures for proprietary devices are provided below:

- Inspect units following completion of construction, prior to being put into service.
- Inspect units at least twice per year following installation and no less than once per year thereafter.
- Inspect units immediately after any oil, fuel or chemical spill.
- All inspections shall include checking the oil level and sediment depth in the unit. Removal of sediments/oils shall occur per manufacturer recommendations.
- A licensed waste management company shall remove captured petroleum waste products from any oil, chemical or fuel spills and dispose.
- OSHA confined space entry protocols shall be followed if entry into the unit is required.

Subsurface Detention/Infiltration Structures/Perforated Pipe and Stone

- Inspect subsurface detention/infiltration structures twice per year. Inspect the inlets and observation ports to determine if there is accumulated sediment within the system. Remove all debris and accumulated sediment that may clog the system.

Stormwater Outfalls

Inspect flared end sections and associated riprap spillways at least once per year and after major storm events (rainfall totals greater than 2.5 inches in 24 hours) to ensure that the stability of the outlet area is maintained. Keep the outfall area clear of debris such as trash, branches, and sediment. Make repairs immediately if riprap displacement or downstream channel scour is observed.

### 3.3 Street Sweeping

Perform street sweeping at least twice per year, whenever there is significant debris present on roads and parking lots. Street sweeping shall occur in the spring and fall. Sweepings must be handled and disposed of properly according to the Stoughton Conservation Commission.

### 3.4 Repair of the Stormwater Management System

The stormwater management system shall be maintained. The repair of any component of the system shall be made as soon as possible to prevent any potential pollutants including silt from entering the resource areas or the existing closed drainage system.

### 3.5 Reporting

The Owner shall maintain a record of drainage system inspections and maintenance (per this Plan) and submit a yearly report to the Stoughton Conservation Commission.

## STORMWATER MANAGEMENT SYSTEM INSPECTION FORM

**STOUGHTON FIRE STATION NO. 1** **Inspected by:_____**
**Stoughton, MA** **Date:_____**

| Component | Status/Inspection | Action Taken |
|---|---|---|
| Deep Sump Catch Basins, Area Drains and Drain Manholes | | |
| Water Quality Units | | |
| Subsurface Infiltration System | | |
| Stormwater Outfalls & Level Spreaders | | |
| General site conditions – evidence of erosion, etc. | | |

**SUBMIT COPIES OF STORMWATER MANAGEMENT SYSTEM INSPECTION FORM TO THE STOUGHTON CONSERVATION COMMISSION WITH THE YEARLY REPORT.**





DORE + WHITTIER

**MASSACHUSETTS**
260 MERRIMAC STREET BUILDING 7, 2ND FLOOR
NEWBURYPORT, MA 01950
P: (978) 499-2999

**VERMONT**
212 BATTERY STREET
BURLINGTON, VT 05401
P: (802) 863-1428


# STOUGHTON FIRE STATION No. 1

400 PROSPECT STREET
STOUGHTON, MA 02072

PROJECT NUMBER: 19-0796

SEAL AND SIGNATURE:

REVISIONS:

| NO. | DATE | TITLE |
|---|---|---|

ISSUE TITLE AND DATE:

NOTICE OF INTENT
09/29/2022


**COPYRIGHT** © 2020 by Dore & Whittier Architects, Inc. (D+W). These documents are D+W's instruments of service and as such D+W retains all copyrights, common law, and statutory rights. Use of these documents without D+W's express written permission will result in copyright infringement.


KEY PLAN

ORIENTATION AND SCALE:

N
TRUE NORTH

PROJECT NORTH

SCALE: AS INDICATED

SHEET TITLE:

STORMWATER MANAGEMENT SYSTEM LOCATION MAP

SHEET NUMBER:

FIG. 1





DORE + WHITTIER

**MASSACHUSETTS**
260 MERRIMAC STREET BUILDING 7, 2ND FLOOR
NEWBURYPORT, MA 01950
P: (978) 499-2999

**VERMONT**
212 BATTERY STREET
BURLINGTON, VT 05401
P: (802) 863-1428


# STOUGHTON FIRE STATION No. 1

400 PROSPECT STREET
STOUGHTON, MA 02072

PROJECT NUMBER: 19-0796

SEAL AND SIGNATURE:

REVISIONS:

| NO. | DATE | TITLE |
|---|---|---|
| | | |

ISSUE TITLE AND DATE:

NOTICE OF INTENT
09/29/2022


**COPYRIGHT** © 2020 by Dore & Whittier Architects, Inc. (D+W). These documents are D+W's instruments of service and as such D+W retains all copyrights, common law, and statutory rights. Use of these documents without D+W's express written permission will result in copyright infringement.


KEY PLAN

ORIENTATION AND SCALE:

N TRUE NORTH

**PROJECT NORTH**

SCALE: AS INDICATED

SHEET TITLE:

## SNOW STORAGE MAP

SHEET NUMBER:

# FIG. 2

NITSCH PROJECT NO. 13743

## APPENDIX F

**DRAFT Stormwater Pollution Prevention Plan (SWPPP)**
**(Provided Under Separate Cover)**

# DRAFT Stormwater Pollution Prevention Plan (SWPPP)

**For Construction Activities At:**

**Stoughton Fire Station No. 1**
400 Prospect Street
Stoughton, MA, 02072
Site Telephone Number: TBD

**SWPPP Prepared For:**

**Dore + Whittier**
260 Merrimac Street, Building 7
Newburyport, MA, 01950
T: 978-499-2999

**SWPPP Prepared By:**

**Nitsch Engineering**
Marissa Valentino
2 Center Plaza
Boston, MA 02108
T: 617-338-0063
F: 617-338-6472

**SWPPP Preparation Date:**

**08/09/2022**

**Estimated Project Dates:**

**Project Start Date: TBD**
**Project Completion Date: TBD**

Nitsch Engineering

**Contents**

**SECTION 1: CONTACT INFORMATION/RESPONSIBLE PARTIES ..... 1**

***1.1 Operator(s) / Subcontractor(s)*** ..... 1

***1.2 Stormwater Team*** ..... 3

**SECTION 2: SITE EVALUATION, ASSESSMENT, AND PLANNING ..... 4**

***2.1 Project/Site Information*** ..... 4

***2.2 Discharge Information*** ..... 5

***2.3 Nature of the Construction Activities*** ..... 7

***2.4 Sequence and Estimated Dates of Construction Activities*** ..... 8

***2.5 Authorized Non-Stormwater Discharges*** ..... 8

***2.6 Site Maps*** ..... 9

**SECTION 3: DOCUMENTATION OF COMPLIANCE WITH OTHER FEDERAL REQUIREMENTS ..... 10**

***3.1 Endangered Species Protection*** ..... 10

***3.2 Historic Properties Screening Process*** ..... 12

***3.3 Safe Drinking Water Act Underground Injection Control Requirements*** ..... 14

**SECTION 4: EROSION AND SEDIMENT CONTROLS REQUIREMENTS ..... 15**

***4.1 Natural Buffers or Equivalent Sediment Controls*** ..... 15

***4.2 Perimeter Controls*** ..... 16

***4.3 Sediment Track-Out*** ..... 17

***4.4 Stockpiled Sediment or Soil*** ..... 18

***4.5 Minimize Dust*** ..... 19

***4.6 Minimize the Disturbance of Steep Slopes*** ..... 20

***4.7 Preserve Native Topsoil*** ..... 21

***4.8 Minimize Soil Compaction*** ..... 21

***4.9 Storm Drain Inlets*** ..... 22

***4.10 Minimize Erosion of Stormwater Conveyances*** ..... 22

***4.11 Sediment Basins*** ..... 23

***4.12 Chemical Treatment*** ..... 24

***4.13 Dewatering Practices*** ..... 24

***4.14 Other Stormwater Controls*** ..... 25

***4.15 Site Stabilization*** ..... 25

**SECTION 5: POLLUTION PREVENTION STANDARDS ..... 26**

***5.1 Potential Sources of Pollution*** ..... 26

***5.2 Spill Prevention and Response*** ..... 28

***5.3 Fueling and Maintenance of Equipment or Vehicles*** ..... 28

***5.4 Washing of Equipment and Vehicles*** ..... 29

***5.5 Storage, Handling, and Disposal of Construction Products, Materials, and Wastes*** 29

***5.6 Washing of Applicators and Containers used for Paint, Concrete, or Other Materials*** 32

***5.7 Fertilizers*** ..... 33

***5.8 Other Pollution Prevention Practices*** ..... 33

**SECTION 6: INSPECTION, MAINTENANCE, AND CORRECTIVE ACTION ..... 34**

***6.1 Inspection Personnel and Procedures*** ..... 34

***6.2 Corrective Action*** ..... 35

***6.3 Delegation of Authority*** ..... 35

**SECTION 7: SWPPP TRAINING LOG ..... 36**

**SECTION 8: CERTIFICATION AND NOTIFICATION ..... 37**

**SECTION 9: TURBIDITY BENCHMARK MONITORING FOR DEWATERING DISCHARGES 38**

**SWPPP ATTACHMENTS ..... 40**

## SECTION 1: CONTACT INFORMATION/RESPONSIBLE PARTIES

### *1.1 Operator(s) / Subcontractor(s)*

**Operator(s):**

**Construction Manager Responsibilities:**

Construction Manager shall maintain the Stormwater Pollution Prevention Plan (SWPPP) documentation and will conduct and document self-inspections required under the 2022 Construction General Permit (CGP) once every 7 days and within 24 hours of a storm event 0.25" or greater and within 24 hours of a snowmelt from a storm event that produces 3.25 inches or more of snow. Construction Manager will provide copies of inspections reports to the Owner's Representative within 24 hours following each inspection. Incidents of non-compliance will be immediately brought to the attention of the Owner's Representative. Construction Manager shall be responsible for maintaining compliance with the SWPPP, including all requirements in the CGP and will maintain erosion and sediment control Best Management Practices (BMPs) in all areas of the site under its day-to-day control.

Construction Manager shall file a Notice of Intent (NOI) to be covered by the CGP and obtain coverage by the Environmental Protection Agency (EPA) before beginning construction at the project. Permit coverage will be maintained throughout the project. Construction Manager shall not file a Notice of Termination (NOT) until all disturbed areas of the site under its day-to-day control have been fully stabilized with permanent erosion controls that satisfy the final stabilization requirements in the CGP or have met another criteria of the NOT. Photo documentation shall be included with the NOT. Construction Manager will maintain a clean site and construction trash and debris will be picked up and disposed of properly by the end of each day.

Each Operator is responsible for advising employees and subcontractors working on this project of the requirements in the CGP and SWPPP. Particular emphasis should be placed on ensuring that employees and subcontractors do not damage BMPs and maintain compliance with the CGP.

Construction Manager TBD
Construction Manager Contact Person, TBD
Street Address
Town, State, Zip Code
T: xxx-xxx-xxxx
Email address:

**Owner's Representative Responsibilities:**

Owner's Representative shall provide general oversight of the project including review of the SWPPP and any amendments, inspection reports, and corrective actions. Owner's Representative shall file a NOI to be covered by the CGP and obtain coverage by the EPA before beginning construction at the project. Permit coverage will be maintained throughout the project. Owner's Representative shall not file a notice of Termination until all disturbed areas of the site have been fully stabilized with permanent erosion controls that satisfy the final stabilization requirements in the CGP. Photo documentation shall be included with the NOT. Owner's Representative will coordinate with the Construction Manager to maintain a clean site so that trash and debris will be picked up and disposed of properly by the end of the day.

Each Operator is responsible for advising employees and subcontractors working on this project of the requirements in the CGP and SWPPP. Particular emphasis should be placed on ensuring that employees and subcontractors do not damage BMPs and maintain compliance with the CGP.

Owner's Representative Company Name
Owner's Representative Contact person, Position
Street Address
Town, State, Zip Code
T: xxx-xxx-xxxx
Email Address:

**Site Contractor:**

Company Name
Contact person, Position
Street Address
Town, State, Zip Code
T: xxx-xxx-xxxx
Email Address:

**Emergency 24-Hour Contact:**

Company
Emergency Contact person, Position
T: xxx-xxx-xxxx

### *1.2 Stormwater Team*

**Construction Manager: TBD**

**Stormwater Role/Responsibility:** Responsible for overseeing the development of the SWPPP, modifications and updates to the SWPPP, and for compliance with the requirements in the CGP (e.g., installing and maintaining stormwater controls, conducting site inspections, picking up trash, application and storage of treatment chemicals (if applicable), taking corrective actions where required, etc.). Responsible for having ready access to an electronic or paper copy of the 2022 CGP and the SWPPP.

**Contact:**
Construction Manager TBD
T: xxx-xxx-xxxx
Email address

I, Construction Manager Contact Person, have read the CGP and Understand the Applicable Requirements and have completed Training Required by CGP Part 6.2.
☐ Yes
Date: _____

**Site Contractor: Company**

**Stormwater Role/Responsibility:** Responsible for compliance with the requirements in this permit (e.g., installing and maintaining stormwater controls, conducting site inspections, repairing controls and taking corrective actions where required, etc.). Responsible for having ready access to an electronic or paper copy of the 2022 CGP and the SWPPP.

**Contact:**
Contact Person, TBD
T: xxx-xxx-xxxx
Email Address

I, Site Contractor Contact Person, have read the CGP and Understand the Applicable Requirements and have completed Training Required by CGP Part 6.2.
☒ Yes
Date: _____

Refer to the Subcontractor Certifications/Agreements in Attachment G.
Refer to SWPPP Training Documentation in Attachment I.

## SECTION 2: SITE EVALUATION, ASSESSMENT, AND PLANNING

### *2.1 Project/Site Information*

**Project Name and Address**

Project/Site Name: Stoughton Fire Station No. 1
Project Street/Location: 400 Prospect Street
City/Town: Stoughton
State: Massachusetts
ZIP Code: 02072
County or Similar Subdivision: Norfolk

**Project Latitude/Longitude**

(Use **one** of three possible formats, and specify method)

Latitude:
1. 42.1214º (degrees, decimals)

Longitude:
1. -71.0882º (degrees, decimals)

Method for determining latitude/longitude:
☐ USGS topographic map (specify scale: _____) ☒ GPS
☐ Other (please specify):

Horizontal Reference Datum:
☐ NAD 27 ☒ NAD 83 ☐ WGS 84

If you used a U.S.G.S topographic map, what was the scale? _____

**Additional Project Information**

Is the project/site located on Indian country lands, or located on a property of religious or cultural significance to an Indian tribe? ☐ Yes ☒ No

Are you applying for permit coverage as a "federal operator" as defined in Appendix A of the CGP?
☐ Yes ☒ No

Will there be demolition of any structure built or renovated before January 1, 1980?
☒ Yes ☐ No

If yes, do any of the structures being demolished have at least 10,000 square feet of floor space?
☐ Yes ☒ No

Was pre-development land use used for agriculture (see Appendix A of the CGP for definition of "agricultural land")?
☐ Yes ☒ No

Type of Construction Site (check all that apply): ☐ Single-Family Residential
☐ Multi-Family Residential ☐ Commercial ☐ Industrial ☐ Institutional ☐ Highway or Road
☐ Utility ☒ Other: Fire Station

### *2.2 Discharge Information*

Does your project/site discharge stormwater into a Municipal Separate Storm Sewer System (MS4)?
☒ Yes ☐ No

Are there any surface waters that are located within 50 feet of your construction disturbances?
☐ Yes ☒ No

**Table 1 – Names of Receiving Waters**

| Name(s) of the first surface water that receives stormwater directly from your site and/or from the MS4 (note: multiple rows provided where your site has more than one point of discharge that flows to different surface waters) |
|---|
| **001. Dorchester Brook** |
| **002.** |
| **003.** |

**Table 2 – Impaired Waters / TMDLs** (Answer the following for each surface water listed in Table 1 above)

| | Is this surface water listed as "impaired" on the CWA303(d) list? | If you answered yes, then answer the following: | | | |
|---|---|---|---|---|---|
| | | What pollutant(s) are causing the impairment? | Has a TMDL been completed? | Title and ID of the TMDL document | Pollutant(s) for which there is a TMDL |
| **001.** | ☐ YES ☒ NO | | ☐ YES ☐ NO | | |
| **002.** | ☐ YES ☐ NO | | ☐ YES ☐ NO | | |
| **003.** | ☐ YES ☐ NO | | ☐ YES ☐ NO | | |

**Table 3 – Tier 2, 2.5, or 3 Waters** (Answer the following for each surface water listed in Table 1 above)

| | Is this surface water designated as a Tier 2, Tier 2.5, or Tier 3 water? | If you answered yes, specify which Tier (2, 2.5, or 3) the surface water is designated as? |
|---|---|---|
| **001.** | ☐ YES ☒ NO | |
| **002.** | ☐ YES ☐ NO | |
| **003.** | ☐ YES ☐ NO | |

## *2.3 Nature of the Construction Activities*

**General Description of Project**

The project consists of a new development of the Stoughton Fire Station which will include the construction of a new building, site access roadways and associated parking. Along with the new construction, there will be installation of new stormwater infrastructure.

**Size of Construction Project**

Size of Property: 8.56 acres
Total Area of Construction Disturbances: 3.47 acres
Maximum Area to be Disturbed at Any One Time: 3.47 acres

**Type of Construction Site (check all that apply):**

| | | | |
|---|---|---|---|
| ☐ Single-Family Residential | ☐ Multi-Family Residential | ☐ Commercial | ☐ Industrial |
| ☐ Institutional | ☐ Highway or Road | ☐ Utility | ☒ Other |

| | | |
|---|---|---|
| Will you be discharging dewatering water from your site? | ☐ Yes | ☒ No |
| If yes, will you be discharging dewatering water from a current or former Federal or State remediation site? | ☐ Yes | ☐ No |

**Construction Support Activities**

Contact Information for Construction Support Activity:
Name: TBD
Telephone: TBD
Email: TBD
Address and/or Latitude and Longitude:

**Business Hours**

TBD

### *2.4 Sequence and Estimated Dates of Construction Activities*

**Phase I: Name of Phase**

- TBD
- Schedule: TBD
- Area Disturbed During Phase: TBD
- Description of stormwater controls that will be installed/maintained during phase TBD

### *2.5 Authorized Non-Stormwater Discharges*

**List of Allowable Non-Stormwater Discharges Present at the Site**

| **Type of Allowable Non-Stormwater Discharge** | **Likely to be Present at Your Site?** |
|---|---|
| Discharges from emergency fire-fighting activities | ☐ YES ☒ NO |
| Fire hydrant flushings | ☒ YES ☐ NO |
| Landscape irrigation | ☐ YES ☒ NO |
| Waters used to wash vehicles and equipment, provided that there is no discharge of soaps, solvents, or detergents used for such purposes | ☐ YES ☒ NO |
| Water used to control dust | ☒ YES ☐ NO |
| Potable water including uncontaminated water line flushings | ☒ YES ☐ NO |
| External building washdown, provided soaps, solvents, and detergents are not used, and external surfaces do not contain hazardous substances (as defined in Appendix A of the CGP) (e.g., paint or caulk containing polychlorinated biphenyls (PCBs)) | ☒ YES ☐ NO |
| Pavement wash waters, provided spills or leaks of toxic or hazardous substances have not occurred (unless all spill material has been removed) and where soaps, solvents, and detergents are not used. | ☐ YES ☒ NO |
| Uncontaminated air conditioning or compressor condensate | ☒ YES ☐ NO |
| Uncontaminated, non-turbid discharges of ground water or spring water | ☒ YES ☐ NO |
| Foundation or footing drains where flows are not contaminated with process materials such as solvents or contaminated groundwater | ☒ YES ☐ NO |
| Uncontaminated construction dewatering water discharged in accordance with Part 2.4 of the CGP | ☒ YES ☐ NO |

Note: You are prohibited from directing pavement wash waters directly into any water of the U.S., storm drain inlet, or stormwater conveyance, unless the conveyance is connected to a sediment basin, sediment trap, or similarly effective control.

### *2.6 Site Maps*

Site Maps must include the following:

a) Boundaries of the property. The map(s) in the SWPPP must show the overall boundary of the property.
b) Locations where construction activities will occur. The map(s) in the SWPPP must show the locations where construction activities will occur, including
    i. Locations where earth-disturbing activities will occur (note any phasing), including any demolition activities;
    ii. Approximate slopes before and after major grading activities (note any steep slopes);
    iii. Locations where sediment, soil, or other construction materials will be stockpiled;
    iv. Any water of the U.S. crossings;
    v. Designated points where vehicles will exit onto paved roads;
    vi. Locations of structures and other impervious surfaces upon completion of construction; and
    vii. Locations of onsite and off-site construction support activity areas covered by the permit (see Part 1.2.1.c).
c) Locations of any receiving waters, including wetlands within and one mile downstream of the site's discharge point(s). Also identify if any are listed as impaired, or are identified as a Tier 2, Tier 2.5, or Tier 3 water.
d) Areas of federally-listed critical habitats for endangered or threatened species within the site and/or at discharge locations.
e) Type and extent of pre-construction cover on the site (e.g., vegetative cover, forest, pasture, pavement, structures).
f) Drainage patterns of stormwater and authorized non-stormwater before and after major grading activities.
g) Stormwater and authorized non-stormwater discharge locations. The permit requires the site map to show information pertaining to discharge locations including:
    i. Locations where stormwater and/or authorized non-stormwater will be discharged to storm drain inlets, including a notation of whether the inlet conveys stormwater to a sediment basin, sediment trap, or similarly effective control; and
    ii. Locations where stormwater or allowable non-stormwater will be discharged directly to receiving waters, including wetlands (i.e., not via a storm drain inlet).
    iii. Locations where turbidity benchmark monitoring will take place to comply with Part 3.3, if applicable to your site.
h) Locations of all potential pollutant-generating activities identified in Part 7.2.3.g. The permit requires identification in the site map of all potential pollutant-generating activities identified in Part 7.2.3.g.
i) Designated areas where construction wastes that are covered by the exception in Part 2.3.3e.ii (i.e., they are not pollutant-generating) will be stored.
j) Locations of stormwater controls, including natural buffer areas and any shared controls utilized to comply with this permit. The permit requires identification on the site map of the location of stormwater control measures.
k) Locations where polymers, flocculants, or other treatment chemicals will be used and stored. The permit requires identification on the site map of the locations where polymers, flocculants, or other treatment chemicals will be used and stored.

Refer to Attachment A

## SECTION 3: DOCUMENTATION OF COMPLIANCE WITH OTHER FEDERAL REQUIREMENTS

### *3.1 Endangered Species Protection*

The following section identifies which criterion the project is eligible for coverage under the 2022 CGP using information from both the National Marine Fisheries Services (NMFS) and U.S. Fish and Wildlife Service (USFWS) to identify Endangered Species Act-listed (ESA-listed) species and designated critical habitat.

**Eligibility Criterion**

Under which criterion listed in Appendix D of the CGP are you eligible for coverage under this permit?

☐ **A** ☐ **B** ☒ **C** ☐ **D** ☐ **E** ☐ F

☐ Check to confirm you have provided documentation in your SWPPP as required by CGP Appendix D.

For reference purposes, the eligibility criteria listed in Appendix D of the CGP are as follows:

**Criterion A.** No ESA-listed species and/or designated critical habitat present in action area. Using the process outlined in Appendix D of the CGP, you certify that ESA-listed species and designated critical habitat(s) under the jurisdiction of the USFWS or NMFS are not likely to occur in your site's "action area" as defined in Appendix A of the CGP. Note: NMFS' jurisdiction includes ESA-listed marine and estuarine species that spawn in inland rivers.

**Criterion B.** Eligibility requirements met by another operator under the 2022 CGP. The construction site's discharges and discharge-related activities were already addressed in another operator's valid certification of eligibility for your action area under eligibility Criterion A, C, D, E, or F of the 2022 CGP and you have confirmed that no additional ESA-listed species and/or under the jurisdiction of USFWS and/or NMFS not considered in the prior certification may be present or located in the "action area". To certify your eligibility under this Criterion, there must be no lapse of NPDES permit coverage in the other operator's certification. By certifying eligibility under this Criterion, you agree to comply with any conditions upon which the other upon which the other CGP operator's certification was based. You must include in your NOI the NPDES ID from the other operator's notification of authorization under this permit and list any measures that you must comply with. If your certification is based on another 2022 CGP operator's certification under Criterion C, you must provide EPA with the relevant supporting information required of existing dischargers in Criterion C in your NOI form.

**Criterion C.** Discharges not likely to result in any short- or long-term adverse effects to ESA-listed species and/or designated critical habitat. ESA-listed species and/or designated critical habitat(s) under the jurisdiction of the USFWS and/or NMFS are likely to occur in or near your site's "action area," and you certify to EPA that your site's discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects to ESA-listed threatened or endangered species and/or designated critical habitat. This certification may include consideration of any stormwater controls and/or management practices you will adopt to ensure that your discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects to ESA-listed species and/or designated critical habitat. To certify your eligibility under this criterion, indicate in your NOI: 1) the ESA-listed species and/or designated habitat located in your "action area" using the process outlined in Appendix D of this permit; 2) the distance between the site and the listed species and/or designated critical habitat in the action area (in miles); and 3) a rationale describing specifically how short- or long-term adverse effects to ESA-listed species will be avoided from the discharges and discharge-related activities. Note: You must also include a copy of your site map from your SWPPP showing the upland and in-water extent of your "action area" with your NOI.)

**Criterion D.** Coordination with USFWS and/or NMFS has successfully concluded. Coordination between you and the USFWS and/or NMFS has concluded. The coordination must have addressed the effects of your site's discharges and discharge-related activities on ESA-listed species and/or designated critical habitat under the jurisdiction of USFWS and/or NMFS, and resulted in a written confirmation from USFWS and/or NMFS that the effects of your site's discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects By certifying eligibility under this criterion, you agree to comply with any conditions you must meet for your site's discharges and discharge-related activities to not likely result in any short- or long-term adverse effects. You must include copies of the correspondence between yourself and the Services in your SWPPP and your NOI.

**Criterion E.** ESA Section 7 consultation has successfully concluded. Consultation between a Federal Agency and the USFWS and/or NMFS under section 7 of the ESA has been concluded. Consultation can be either formal or informal, and would have occurred only as a result of a separate Federal action (e.g. during application for an individual wastewater discharge permit or the issuance of a wetlands dredge and fill permit), and the consultation must have addressed the effects of the construction site activity's discharges and discharge-related activities on all ESA-listed threatened or endangered species and all designated critical habitat under the jurisdiction of each Service, as appropriate, in your action area. The result of this consultation must be either:

i. a biological opinion currently in effect that determined that the action in question (taking into account the effects of your site's discharges and discharge-related activities) is likely to adversely affect, but is not likely to jeopardize the continued existence of listed species or result in the destruction or adverse modification of critical habitat; The biological opinion must have included the effects of your facility's discharges and discharge-related activities on all the listed species and designated critical habitat in your action area under the jurisdiction of each Service, as appropriate. To be eligible under (i), any reasonable and prudent measures specified in the incidental take statement must be implemented;

ii. written concurrence (e.g. letter of concurrence) from the applicable Service(s) with a determination that your site's discharges and discharge-related activities are not likely to adversely affect USFWS and/or NMFS as part of this worksheet. ESA-listed species and/or designated critical habitat. The concurrence letter must have included the effects of your facility's discharges and discharge-related activities on all the ESA-listed species and/or designated critical habitat on your species list(s) acquired

The consultation does not warrant reinitiation under 50 CFR §402.16; or, if reinitiation of consultation is required (e.g., due to a new species listing, critical habitat designation, or new information), the Federal action agency has reinitiated the consultation and the result of the consultation is consistent with the statements above. (Note: you must include any reinitiation documentation from the Services or consulting Federal agency with your NOI.)

You must include copies of the correspondence between yourself and the Services in your SWPPP and your NOI.

**Criterion F.** Issuance of section 10 permit. Your construction activities are authorized through the issuance of a permit under section 10 of the ESA, and this authorization addresses the effects of the site's discharges and discharge-related activities on federally-listed species and federally-designated critical habitat. You must include copies of the correspondence between yourself and the Services in your SWPPP and your NOI.

**For criterion C**, provide the following information:

- Northern Long-eared Bat, from communication with USFWS.
- Threatened

Provide a brief summary of the basis used for determining that your site's discharges and discharge-related activities are not likely to adversely affect listed species or critical habitat:

### *3.2 Historic Properties Screening Process*

**Appendix E (of the CGP), Step 1**

Do you plan on installing any of the following stormwater controls at your site? Check all that apply below, and proceed to Appendix E, Step 2.

- ☐ Dike
- ☐ Berm
- ☒ Catch Basin
- ☐ Pond
- ☒ Stormwater Conveyance Channel (e.g., ditch, trench, perimeter drain, swale, etc.)
- ☐ Culvert
- ☒ Other type of ground-disturbing stormwater control: Subsurface Infiltration System, Drain Manhole

If you will not be installing any ground-disturbing stormwater controls, no further documentation is required for Section 3.2 of the Template.

**Appendix E, Step 2**

If you answered yes in Step 1, have prior cultural resource surveys or other evaluations determined that historic properties do not exist, or that prior disturbances at the site have precluded the existence of historic properties? ☐ YES ☐ NO

If yes, provide documentation of the basis for your determination. If no, proceed to Appendix E, Step 3.

**Appendix E, Step 3**

If you are installing any stormwater controls that require subsurface earth disturbance, you must determine if these activities will have an effect on historic properties. This assessment may be based on historical sources, knowledge of the area, an assessment of the types of earth-disturbing activities you are engaging in, considerations of any controls and/or management practices you will adopt to ensure that your stormwater control related earth-disturbing activities will not have an effect on historic properties, and any other relevant factors.

Does your determination demonstrate that earth disturbances related to the installation of your stormwater controls will have no effect on historic properties? ☐ YES ☐ NO

If yes, provide documentation of the basis for your determination. If no, proceed to Appendix E, Step 4.

**Appendix E, Step 4**

If you are installing any stormwater controls that require subsurface earth disturbance and you have not satisfied the conditions in Steps 1-3, you must contact and consult with the appropriate historic preservation authorities including the State Historic Preservation Officer (SHPO), Tribal Historic Preservation Office (THPO), or other tribal representative (whichever applies). Your request should include the information outlined in Appendix E of the CGP.

Did SHPO, THPO, or another tribal representative respond to you within 15 calendar days after their receipt to indicate whether the subsurface earth disturbances caused by the installation of stormwater controls affect historic properties? ☐ YES ☐ NO

If no, no further documentation is required for Section 3.2 of the Template.

If yes, describe the nature of their response:

- ☐ Written indication that no historic properties will be affected by the installation of stormwater controls.
- ☐ Written indication that adverse effects to historic properties from the installation of stormwater controls can be mitigated by agreed upon actions.
- ☐ No agreement has been reached regarding measures to mitigate effects to historic properties from the installation of stormwater controls.
- ☐ Other:

If within 15 days of receipt of your request the applicable SHPO, THPO, or other tribal representative responds with a request for additional information or for further consultation, you must comply with this request and proceed to Step 5.

**Appendix E, Step 5**

If, following your discussions with the appropriate historic preservation authorities in Step 4, the applicable SHPO, THPO, or tribal representative requests additional information or further consultation, you must respond with such information or consult to determine impacts to historic properties that may be caused by the installation of stormwater controls on your site and appropriate measures for treatment or mitigation of such impacts. If as a result of your discussions with the applicable SHPO, THPO, or tribal representative, you enter into, and comply with, a written agreement regarding treatment and/or mitigation of impacts on your site, then you may indicate this on your NOI, and no further screening steps are necessary.

If, however, agreement on an appropriate treatment or mitigation plan cannot be reached between you and the SHPO, THPO, or other tribal representative within 30 days of your response to the SHPO, THPO, or other tribal representative's request for additional information or further consultation, you may submit your NOI, but you must indicate that you have not negotiated measures to avoid or mitigate such effects. You must also include in your SWPPP the following documentation:

1. Copies of any written correspondence between you and the SHPO, THPO, or other tribal representative; and
2. A description of any significant remaining disagreements as to mitigation measures between you and the SHPO, THPO, or other tribal representative.

After submitting your NOI, and during the 14-day waiting period, the SHPO, THPO, ACHP, or other tribal representative may request that EPA place a hold on authorization based upon concerns regarding potential adverse effects to historic properties. EPA, in coordination with the ACHP, will evaluate any such request and notify you if any additional measures to address adverse effects to historic properties are necessary.

### *3.3 Safe Drinking Water Act Underground Injection Control Requirements*

Do you plan to install any of the following controls? Check all that apply below.

☒ Infiltration trenches (if stormwater is directed to any bored, drilled, driven shaft or dug hole that is deeper than its widest surface dimension, or has a subsurface fluid distribution system);

☒ Commercially manufactured pre-cast or pre-built proprietary subsurface detention vaults, chambers, or other devices designed to capture and infiltrate stormwater flow; and

☒ Drywells, seepage pits, or improved sinkholes (if stormwater is directed to any bored, drilled, driven shaft or dug hole that is deeper than its widest surface dimension, or has a subsurface fluid distribution system)

## SECTION 4: EROSION AND SEDIMENT CONTROLS REQUIREMENTS

Section 4 of this document describes the stormwater controls that will be implemented throughout construction. The operator must install and maintain all stormwater controls in compliance with Parts 2.2 and 2.3 of the CGP. The operator must install stormwater controls by the time construction activity in any givern portion of the site begins.

The stormwater controls shall be designed and installed in accordance with good engineering practices and applicable design specifications. Specifications titled “312500- Erosion and Sedimentation Controls,” dated TBD and prepared by Nitsch Engineering and details titled “Erosion and Sedimentation Control Details,” dated TBD and prepared by Nitsch Engineering have been provided to the contractor under separate cover.

### *4.1 Natural Buffers or Equivalent Sediment Controls*

**Buffer Compliance Alternatives**

Are there any surface waters within 50 feet of your project’s earth disturbances? ☐ YES ☒ NO

(Note: If no, no further documentation is required for Part 4.1 in the SWPPP Template. Continue to Part 4.2.)

Check the compliance alternative that you have chosen:

☐ I will provide and maintain a 50-foot undisturbed natural buffer.

(Note [1]: You must show the 50-foot boundary line of the natural buffer on your site map.)

(Note [2]: You must show on your site map how all discharges from your construction disturbances through the natural buffer area will first be treated by the site’s erosion and sediment controls. Also, show on the site map any velocity dissipation devices used to prevent erosion within the natural buffer area.)

☐ I will provide and maintain an undisturbed natural buffer that is less than 50 feet and is supplemented by additional erosion and sediment controls, which in combination achieves the sediment load reduction equivalent to a 50-foot undisturbed natural buffer.

(Note [1]: You must show the boundary line of the natural buffer on your site map.)

(Note [2]: You must show on your site map how all discharges from your construction disturbances through the natural buffer area will first be treated by the site’s erosion and sediment controls. Also, show on the site map any velocity dissipation devices used to prevent erosion within the natural buffer area.)

☐ It is infeasible to provide and maintain an undisturbed natural buffer of any size, therefore I will implement erosion and sediment controls that achieve the sediment load reduction equivalent to a 50-foot undisturbed natural buffer.

☐ I qualify for one of the exceptions in Appendix G Section G.2.2 of the CGP. (If you have checked this box, provide information on the applicable buffer exception that applies, below.)

**Buffer Exceptions**

Which of the following exceptions to the buffer requirements applies to your site?

☐ Construction and buffer disturbances are approved under a CWA Section 404 permit.

(Note [1]: If this exception applies, no further documentation is required for Section 4.1 of this Template.)

(Note [2]: This exception only applies to the limits of disturbance authorized under the Section 404 permit, and does not apply to any upland portion of the construction project.)

☐ Buffer disturbances will occur for the construction of a water-dependent structure or water access area (e.g., pier, boat ramp, and trail).
(Note [1]: If this exception applies, no further documentation is required for Section 4.1 of the Template.)

☐ There is no discharge of stormwater to the waters of the U.S. through the area between the disturbed portions of the site and any waters of the U.S. located within 50 feet of your site.
(Note: If this exception applies, no further documentation is required for this section of the Template.)

☐ No natural buffer exists due to preexisting development disturbances that occurred prior to the initiation of planning for this project.
(Note (1): If this exception applies, no further documentation is required for this section of the Template.)
(Note (2): Where some natural buffer exists but portions of the area within 50 feet of the surface water are occupied by preexisting development disturbances, you must still comply with the one of the CGP Part 2.1.2.1.a compliance alternatives.)

☐ For a "linear construction site" (defined in Appendix A of the CGP), site constraints (e.g., limited right-of-way) make it infeasible for me to meet any of the CGP Part G.2.1 compliance alternatives.

☐ The project qualifies as "small residential lot" construction (defined in Part 2.1.2.1.e.iv and in Appendix A of the CGP) as a lot being developed for residential purposes that will disturb less than 1 acre of land, but is part of a larger residential project that will ultimately disturb greater than or equal to 1 acre.
Insert information regarding how you complied with the "small residential lot" compliance alternative in Part G.3 of Appendix G of the CGP.

### *4.2 Perimeter Controls*

**General**
The site will be enclosed by a temporary construction fence as shown on the Erosion and Sedimentation Control Plan in Attachment A. Construction gates will be located at the entrance to the site as shown on the Erosion and Sedimentation Control Plan and all entrances will have stabilized construction entrances. All gates and entrances to the site will be secured during non-working hours. The areas of the site that will receive pollutant discharges will be surrounded by a Specific Perimeter Control listed below as shown on the Erosion and Sedimentation Control Plan in Attachment A. Sediment tracked offsite must be removed by the end of the same workday.

**Specific Perimeter Controls**

*Perimeter Control # 1*

- BMP Description: Silt Fence.
- Installation Schedule: Prior to the Start of Construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as described in part 2.1.4 of the CGP.
  Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Perimeter Control # 2*

- BMP Description: Silt Fence with Wattles.
- Installation Schedule: Prior to the Start of Construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or

greater.

- Maintenance: Ensure that all stormwater controls remain in effective condition as described in part 2.1.4 of the CGP. Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Perimeter Control # 3*

- BMP Description: Super Silt Fence.
- Installation Schedule: Prior to the Start of Construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as described in part 2.1.4 of the CGP. Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Perimeter Control # 4*

- BMP Description: Wattles.
- Installation Schedule: Prior to the Start of Construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as described in part 2.1.4 of the CGP. Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.3 Sediment Track-Out*

**General**

Gates will be located as shown on the Erosion and Sedimentation Control Plan in Attachment A to allow for construction vehicle access. Construction access points will have a stabilized construction entrance station or wheel wash station to minimize the track-out of sediment onto off-site streets, other paved areas, and sidewalks from vehicles exiting the construction site. Where sediment has been tracked out from your site onto paved roads, sidewalks, or other paved areas outside of your site, remove the deposited sediment by the end of the same business day in which the track-out occurs or by the end of the next business day if track-out occurs on a non-business day. Remove the track-out by sweeping, shoveling, or vacuuming these surfaces, or by using other similarly effective means of sediment removal. You are prohibited from hosing or sweeping tracked out sediment into any stormwater conveyance, storm drain inlet, or water of the U.S.

**Specific Track-Out Controls**

*Track-Out Control # 1*

- BMP Description: Street Sweeping.
- Installation Schedule: Start of construction.
- Inspection Schedule: The areas adjacent to the site should be inspected daily to determine if street sweeping is required.
- Responsible Staff Construction Manager and Site Contractor(s).

*Track-Out Control # 2*

- BMP Description: Stabilized Construction Entrance.
- Installation Schedule: Start of construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as described in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Track-Out Control # 3*

- BMP Description: Wheel Wash Station.
- Installation Schedule: Start of construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective. condition as described in part 2.1.4 of the CGP(s). The operator must provide an effective means of minimizing the discharge of pollutants from equipment and vehicle washing, wheel wash water, and other types of wash waters. The operator must ensure there is no discharge of soaps, solvents, or detergents in equipment and vehicle wash water. For storage of soaps, detergents, or solvents, the operator shall provide either a cover to minimze the exposure of these detergents to precipitation and to stormwater, or a similarily effective means designed to minimze discharge of pollutants from these areas.
- Responsible Staff: Construction Manager and Site Contractor.

### *4.4 Stockpiled Sediment or Soil*

**General**

All soil stockpiles will be located outside of any natural buffers and away from existing and proposed catch basins and area drains and outside of proposed infiltration system footprints. A sediment barrier shall be installed along all downgradient perimeter areas. Examples of sediment barriers include silt fence, super silt fence, or wattles.

You are prohibited from hosing down or sweeping soil or sediment accumulated on pavement or other impervious surfaces into any stormwater conveyance, storm drain inlet, or water of the U.S.

For stockpiles that will be unused for 14 or more days, a cover such as a tarp or blown straw shall be provided or temporary stabilization should be provided (consistent with Part 2.2.14 of the CGP). Exposure while adding or removing materials from a pile shall be minimized.

**Specific Stockpile Controls**

*Stockpile Control # 1*

- BMP Description: Silt Fence.
- Installation Schedule: Immediately after stockpile is established.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP. Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Stockpile Control # 2*

- BMP Description: Wattles.
- Installation Schedule: Immediately after stockpile is established.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
  Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Stockpile Control # 3*

- BMP Description: Tarp.
- Installation Schedule: When stockpile will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
  Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Stockpile Control # 4*

- BMP Description: Blown Straw.
- Installation Schedule: When stockpile will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
  Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Stockpile Control # 5*

- BMP Description: Hydroseeding.
- Installation Schedule: When stockpile will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
  Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.5 Minimize Dust*

**General**

Disturbed land will be temporarily stabilized as required by the CGP. Dust will be minimized using measures including sprinkling/irrigation, vegetative cover, mulch, and/or stone. Stockpiles will be handled in accordance with section 4.4 of the SWPPP.

Earth-disturbing activities are considered temporarily ceased when work will not resume for a period of 14 or more calendar days. Stabilization shall be initiated when earth-disturbing activities are temporarily or permanently ceased. Stabilization activities shall be complete within 14 calendar days after the initiation of soil stabilization measures.

**Specific Dust Controls**

*Dust Control # 1*

- BMP Description: Sprinkling/Irrigation.
- Installation Schedule: As needed throughout earthwork activities as determined by the site contractor and construction manager.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Dust Control # 2*

- BMP Description: Straw or Mulch.
- Installation Schedule: As needed throughout earthwork activities as determined by the site contractor and construction manager. When disturbed land will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.6 Minimize the Disturbance of Steep Slopes*

**General**

Steep slopes (defined as slopes of 15% or greater in grade) are expected to be disturbed onsite. Disturbances to steep slopes will be minimized by phasing disturbances to those areas and by using stabilization practices designed to be used on steep grades.

**Specific Steep Slope Controls**

*Steep Slope Control # 1*

- BMP Description: Straw or Mulch.
- Installation Schedule: When disturbed land will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective. condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Steep Slope Control # 2*

- BMP Description: Hydroseeding.
- Installation Schedule: When disturbed land will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Steep Slope Control # 3*

- BMP Description: Soil Stabilization Mats.
- Installation Schedule: When disturbed land will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Steep Slope Control # 4*

- BMP Description: Rip-Rap.
- Installation Schedule: When disturbed land will remain inactive for 14 or more calendar days.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.7 Preserve Native Topsoil*

Onsite native topsoil shall be preserved, unless infeasible. Preserving native topsoil is not required where the intended function of a specific area of the site dictates that the topsoil be disturbed or removed.

Stockpiling topsoil at off-site locations or transferring topsoil to other locations is an example of a way to preserve native topsoil.

The contractor shall perform construction sequencing such that earth materials are exposed for a minimum of time before they are covered, seeded, or otherwise stabilized.

### *4.8 Minimize Soil Compaction*

**General**

In areas where infiltration practices will be installed or areas of the site where final vegetative stabilization will occur, soil compaction shall be minimized. This includes restricting vehicle access and equipment use.

Areas used for post-construction infiltration shall be constructed after all ground surfaces are fully stabilized when feasible. If proposed infiltration areas are constructed prior to the site being fully stabilized, additional erosion controls shall be installed. All stockpiled and material storage areas shall be located outside of the areas proposed for post-construction infiltration.

Areas of post-construction landscaping shall be constructed after all ground surface are fully stabilized. If proposed landscaped areas are constructed prior to the site being fully stabilized, additional erosion controls shall be installed. All soil stockpiles and material storage areas shall be located outside of the areas proposed for post-construction landscaping where feasible. Where this is not feasible, use techniques that rehabilitate and condition the soils as necessary to support vegetative growth prior to planting.

### *4.9 Storm Drain Inlets*

**General**
All existing and proposed storm drain inlets affected by construction activities should be protected using an Inlet Sediment Filter as shown on the Erosion and Sedimentation Control Plan provided in Attachment A.

Clean or remove and replace the protection measures as sediment accumulates, the filter becomes clogged, and/or performance is compromised. Where there is evidence of sediment accumulation adjacent to the inlet protection measure, remove the deposited sediment by the end of the same business day in which it is found or by the end of the following business day if removal by the same business day is not feasible.

**Specific Storm Drain Inlet Controls**

*Storm Drain Inlet Control # 1*

- BMP Description: Inlet Sediment Filter.
- Installation Schedule: Prior to the Start of Construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective. condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Storm Drain Inlet Control # 2*

- BMP Description: Inlet Protection with Gravel.
- Installation Schedule: Prior to the Start of Construction .
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Storm Drain Inlet Control # 3*

- BMP Description: Inlet Protection with Block and Gravel.
- Installation Schedule: Prior to the Start of Construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.10 Minimize Erosion of Stormwater Conveyances*

The contractor shall minimize erosion of stormwater conveyance channels and their embankments, outlets, adjacent streambanks, slopes, and downstream waters. The contractor shall install erosion controls and velocity

dissipation devices within and along the length of any stormwater conveyance channel and at any outlet to slow down runoff to minimize erosion.

*Stormwater Conveyance Control # 1*

- BMP Description: Check Dam.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Stormwater Conveyance Control # 2*

- BMP Description: Sediment Trap.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Stormwater Conveyance Control # 3*

- BMP Description: Rip Rap.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.11 Sediment Basins*

All sediment basins should be located outside of any waterbody, resource area, and buffer zones. Sediment basins shall be sized to provide storage for either the volume of runoff from a 2-year, 24-hour storm or 3,600 cubic feet per acre drained.

Where feasible, outlet structures that withdraw water from the surface of the sediment basin shall be used. Erosion and velocity dissipation devices shall be installed at inlets and outlets to prevent erosion.

Accumulated sediment shall be removed to maintain at least one-half of the design capacity. The basin shall be maintained so that it remains in effective operating condition.

*Sediment Basin Control # 1*

- BMP Description: Check Dam.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Sediment Basin Control # 2*

- BMP Description: Sediment Trap.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s)

*Sediment Basin Control # 3*

- BMP Description: Rip Rap.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.12 Chemical Treatment*

There are no proposed chemical treatments associated with this project.

### *4.13 Dewatering Practices*

Dewatering will occur in a way that minimizes the discharge of pollutants in ground water or accumulated stormwater that is removed from excavations, trenches, foundations, vaults, or other similar points of accumulation. Dewatering water shall be treated in compliance with Section 2.4 of the CGP and water with visible floating solids or foam may not be discharged.

At a minimum, for backwash water shall be hauled away for disposal or returned to the beginning of the treatment process, and filter media used in dewatering devices shall be replaced and cleaned when the pressure differential equals or exceeds the manufacturer's specifications.
Any applicable permits shall be obtained from local permitting authorities.

*Dewatering Control # 1*

- BMP Description: Sediment basin or Sediment Trap.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Dewatering Control # 2*

- BMP Description: Sediment socks.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Dewatering Control # 3*

- BMP Description: Dewatering Tanks.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater and as required by the manufacturer.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Dewatering Control # 4*

- BMP Description: Filtration Systems.
- Installation Schedule: Start of construction of stormwater conveyance channel.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater and as required by the manufacturer.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *4.14 Other Stormwater Controls*

Any changes in construction activity that that include means of stormwater control not included in this document will be identified, the SWPPP will be amended, and the appropriate erosion and sedimentation controls will be implemented.

### *4.15 Site Stabilization*

Initiate the installation of stabilization measures immediately in any areas of exposed soil where construction activities have permanently ceased or will be temporarily inactive for 14 or more calendar days. Complete the installation of stabilization measures as soon as practicable, but no later than 7 calendar days after stabilization has been initiated.

**Site Stabilization Practice #1**
☐ *Vegetative* ☒ *Non-Vegetative*
☒ *Temporary* ☐ *Permanent*

- BMP Description: Soil Stabilization Mat.
- Installation Schedule: As/if required.
- Maintenance and Inspection: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Responsible Staff: Construction Manager and Site Contractor(s).

**Site Stabilization Practice #2**
☒ *Vegetative* ☐ *Non-Vegetative*
☒ *Temporary* ☐ *Permanent*

- BMP Description: Temporary Seeding.
- Installation Schedule: As/if required.
- Maintenance and Inspection: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Responsible Staff: Construction Manager and Site Contractor(s).

# SECTION 5: POLLUTION PREVENTION STANDARDS

## *5.1 Potential Sources of Pollution*

Potential sources of sediment to stormwater runoff:

- Stockpiles and construction staging
- Clearing and grubbing operations
- Grading and site excavation
- Topsoil stripping
- Landscape operations
- Soil tracking offsite from construction vehicles
- Runoff from unstabilized areas
- Construction debris

Potential pollutants and sources, other than sediment, to stormwater runoff:

- Combined Staging Area – fueling activities, equipment maintenance, sanitary facilities, and hazardous waste storage
- Materials Storage Area – building materials, solvents, adhesives, paving materials, paints, aggregates, trash, etc.
- Construction Activity-paving, curb installation, concrete pouring, and building construction

Staging areas are shown on the Erosion and Sedimentation Control Plan provided in Attachment A.

**Construction Site Pollutants**

| **Pollutant-Generating Activity** | **Pollutants or Pollutant Constituents** (that could be discharged if exposed to stormwater) | **Location on Site** (or reference SWPPP site map where this is shown) |
|---|---|---|
| Pesticides (insecticides, fungicides, herbicides, rodenticides) | Chlorinated hydrocarbons, organophosphates, carbonates, arsenic | Herbicides used for noxious weed control |
| Fertilizers | Nitrogen, phosphorous | Newly seeded areas |
| Plaster | Calcium sulphate, calcium carbonate, sulfuric acid | Building construction |
| Cleaning Solvents | Perchloroethylene, methylene chloride, trichloroethylene, petroleum distillates | No equipment cleaning allowed in project limits |
| Asphalt | Oil, petroleum distillates | Streets and parking lots |
| Concrete | Limestone, sand pH, chromium | Curb and gutter, sidewalk, building construction |
| Glue, Adhesives | Polymers, epoxies | Building construction |
| Paints | Metal oxides, Stoddard solvent, talc, calcium carbonate, arsenic | Building construction |
| Curing compounds | Naphtha | Curb and gutter, building construction |
| Wood preservatives | Stoddard solvent, petroleum distillates, arsenic, copper, chromium | Timber pads, bracing, building construction |
| Hydraulic Oils/fluids | Mineral oil | Leaks/broken hoses from equipment |
| Gasoline | Benzene, ethyl benzene, toluene, xylene, MTBE | Secondary containment/staging area |
| Diesel Fuel | Petroleum distillate, oil & grease, naphthalene, xylenes | Secondary containment/staging area |
| Kerosene | Coal oil, petroleum distillates | Secondary containment/staging area |
| Antifreeze/coolant | Ethylene glycol, propylene glycol, heavy metals (copper, lead, zinc) | Leaks or broken hoses from equipment |
| Sanitary toilets | Bacteria, parasites, and viruses | Staging area |

### *5.2 Spill Prevention and Response*

**BMP Description: Spill kit, vehicle washing, silt sack catch basin protection, silt fence**
Installation Schedule: Start of construction activity
Maintenance and Inspection: Minimum weekly & as necessary
Responsible Staff: Construction Manager and Site Contractor

- Major vehicle maintenance onsite is prohibited
- Re-fueling of vehicles within 25 feet of a drainage structure is prohibited
- Spill kit shall be kept onsite consisting of:
    - Gloves
    - Absorbent mats
    - Drip pan

**Spill Prevention and Control Plan**

- Refer to contractor's Spill Plan.
- Manufacturers' recommended spill control methods will be posted onsite and site personnel will be made aware of the requirements.
- Cleanup supplies will be kept onsite in a materials storage area. This equipment will include: goggles, brooms, dustpans, mops, rags, gloves, oil absorbent, sawdust, plastic and metal trash cans, and other materials and supplies specifically designated for cleanup.
- All spills will be immediately cleaned up after discovery.
- The spill area will be well ventilated.
- Cleanup personnel will wear suitable protective clothing.
- Spills of toxic and/or hazardous material will be reported to state, local, and Federal authorities, as required by law. Spills shall also be reported immediately to the owner.
- A spill incident report will be filed detailing the amount and extent of the spill, material(s) involved, and effectiveness of the cleanup. This report will be on file at the Construction Manager/Site Contractor office, as well as kept onsite in the field office. A copy shall also be filed with the Hazard Communication Coordinator (HCC).

The Construction Manager/Site Contractor will designate someone onsite that will serve as the Spill Cleanup Coordinator. At least two other personnel will be designated as alternate spill coordinators. All spill control personnel will be trained in spill prevention, control, and cleanup. The names of the responsible personnel will be posted at the jobsite office of the Construction Manager/ Site Contractor.

### *5.3 Fueling and Maintenance of Equipment or Vehicles*

**General**

Minor vehicle and equipment emergency maintenance can be performed onsite away from drainage structures. Major vehicle and equipment maintenance must be performed offsite. Equipment/vehicle storage areas and any onsite fuel tanks will be inspected weekly and after storm events. Equipment and vehicles will be inspected for leaks, equipment damage, and other service problems on each day of use. Any leaks will be repaired immediately or the equipment/vehicle will be removed from the site.

Minor vehicle and equipment emergency maintenance shall occur when a vehicle cannot be safely removed from the site. The vehicle should be repaired so it can be taken off-site so that the rest of the maintenance can occur.

Major vehicle maintenance onsite is prohibited. Re-fueling or maintenance of vehicles within 25 feet of a drainage structure shall be prohibited. Drip pans, drip cloths, or absorbent pads should be used when replacing spent fluids. Secondary containment and cover should be provided where appropriate. The fluids should be collect and stored prior to being disposed of offsite. Spill kits should be readily available.

*Specific Pollution Prevention Practice #1*

- BMP Description: Spill Kit.
- Installation Schedule: Onsite throughout construction.
- Responsible Staff: Construction Manager and Site Contractor.

*Specific Pollution Prevention Practice #1*

- BMP Description: Drip Pans, Drip Cloths, Absorbent Pads.
- Installation Schedule: Onsite throughout construction.
- Responsible Staff: Construction Manager and Site Contractor.

### *5.4 Washing of Equipment and Vehicles*

**General**

Vehicle and equipment washout areas shall be constructed by the contractor away from receiving water and storm drain inlets or constructed or natural site drainage features so that no untreated water enters the storm drain system. Soaps, detergents, or solvents must be stored in a way to prevent these detergents from coming into contact with rainwater, or a similarly effective means designed to prevent the discharge of pollutants from these areas.

**Specific Pollution Prevention Practices**

*Pollution Prevention Practice # 1*

- BMP Description: Designated vehicle/equipment washing areas
- Installation Schedule: Start of construction.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Responsible Staff: Construction Manager and Site Contractor

*Pollution Prevention Practice # 2*

- BMP Description: Spill kit, vehicle washing, straw bale catch basin protection, silt fence
- Installation Schedule: Start of construction activity
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25” or greater.
- Responsible Staff: Construction Manager and Site Contractor

### *5.5 Storage, Handling, and Disposal of Construction Products, Materials, and Wastes*

#### *5.5.1 Building Products*

**General**

The contractor will recycle all construction materials possible. For materials that cannot be recycled, solid waste will be disposed of in accordance with DEP Regulations for Solid Waste Facilities, 310 CMR 10.00.

Any building materials required to be stored onsite will be stored at a combined staging and materials storage area as shown on the CMP. Larger items will be elevated by appropriate methods to minimize contact with runoff. The storage area will be inspected weekly and after storm events. It will be kept clean, organized, and equipped with appropriate cleaning supplies.

Building product usage shall follow the following good housekeeping BMPs:

- The Responsible Staff: Construction Manager or Site Contractor representative will inspect daily for inspection of the work area to ensure proper management of waste materials.
- Store only enough material onsite required for that job as to satisfy current construction needs.
- Store required materials in tightly lidded containers under cover.
- Store materials in original containers with clearly legible labels.
- Separate and store materials apart from each other.
- Do not mix materials unless specifically in accordance with manufacturers' recommendations.
- Use all products from a container before disposing of the container.
- Follow manufacturers' instructions for handling, storage, and disposing of all materials.
- All materials shall be stored in an area to prevent the discharge of pollutants from building products.

**Specific Pollution Prevention Practices**

*Pollution Prevention Practice # 1*

- BMP Description: Perimeter Protection control around Stockpiles.
- Installation Schedule: Start of construction/ Immediately after stockpile is established.
- Inspection Schedule: Once every 7 days and within 24 hours of a storm event 0.25" or greater.
- Maintenance: Ensure that all stormwater controls remain in effective condition as decribed in part 2.1.4 of the CGP.
  Remove any sediment before it has accumulated to one-half of the above-ground height of any perimeter control.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *5.5.2 Pesticides, Herbicides, Insecticides, Fertilizers, and Landscape Materials*

- In storage areas, provide either (1) cover to minimize the exposure of these chemicals to precipitation and to stormwater or (2) a similarly effective means designed to minimize the discharge of pollutants from these areas.
- Comply with all application and disposal requirements included on the registered pesticide, herbicide, insecticide, and fertilizer label.

### *5.5.3 Diesel Fuel, Oil, Hydraulic Fluids, Other Petroleum Products, and Other Chemicals*

**General**

- Only skilled personnel in a designated area will perform fueling of vehicles onsite.
- Vehicles used onsite will be monitored for fuel and oil leaks.
- Vehicles used onsite will be maintained in good working order.
- Asphalt substances will be applied in accordance with manufacturers' recommendations.
- The use of petroleum products as a release agent for asphalt transport trucks is prohibited.
- Vehicle fueling will only be done in vehicle fueling areas located by the contractor. See section 5.3 of the SWPPP.
- The contractor shall be responsible for locating the fuel storage and re-fueling area onsite to minimize disturbance to construction activates and site area.
- Construction equipment not in active use for 5 minutes or more will be turned off.

### *5.5.4 Hazardous or Toxic Waste*

(Note: Examples include paints, solvents, petroleum-based products, wood preservatives, additives, curing compounds, acids.)

**General**

- Keep products in their original containers.
- Original container labels should be clearly visible.
- Material safety data sheets will be kept onsite and be available.
- Follow all state, local, and Federal regulations regarding the handling, use, storage, and disposal of hazardous material.

Paints:

- All paint containers will be tightly sealed when not in use.
- Remove excess paint in original labeled containers from the jobsite.
- Paint will not be disposed of onsite. Remove excess paint material from the site and legally dispose of.
- Paint shall not be disposed of in the storm drain system.

### *5.5.5 Construction and Domestic Waste*

**General**
The contractor will manage domestic waste onsite. The contractor will provide waste containers of sufficient size and number to contain construction and domestic wastes. The waste container lids will be kept closed when not in use and lids will be closed at the end of the business day for those containers that are actively used throughout the day. For waste containers that do not have lids, provide either a cover or a similarly effective means designed to minimize discharge of pollutants. Clean up immediately if containers overflow.

*Pollution Prevention Practice # 1*

- BMP Description: Dumpster.
- Installation Schedule: Start of construction.
- Maintenance and Inspection: Weekly and covered daily.
- Responsible Staff: Construction Manager and Site Contractor(s).

*Pollution Prevention Practice # 2*

- BMP Description: Litter/debris pick-up.
- Installation Schedule: Start of construction.
- Maintenance and Inspection: Daily.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *5.5.6 Sanitary Waste*

All sanitary waste portable toilets shall be positioned so that they are secure and will not be tipped or knocked over, and located away from any stormwater inlets or conveyances.

*Pollution Prevention Practice # 1*

- BMP Description: Porta John.
- Installation Schedule: Start of construction.
- Maintenance and Inspection: As manufacturer requires.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *5.6 Washing of Applicators and Containers used for Paint, Concrete, or Other Materials*

**General**
Washing of applicators and containers used for paint, concrete, or other materials shall follow the following good housekeeping BMPs:

- An effective means of eliminating the discharge of water from the washout and cleanout of stucco, paint, concrete, form release oils, curing compounds, and other construction materials.
- All washwater must be directed into a leak-proof container or leak-proof pit. The container or pit must be designed so that no overflows can occur due to inadequate sizing or precipitation.
- Washout and cleanout wastes should be handled as follows:
  - Do not dump liquid wastes into storm sewers.
  - Dispose of liquid wastes in accordance with applicable requirements.
  - Remove and dispose of hardened concrete waste consistent with the handling of other construction wastes.
- Locate any washout or cleanout activities as far away as possible from surface waters and stormwater inlets or conveyances, and to the extent practicable, designate areas to be used for these activities and conduct such activities only in these areas.

*Pollution Prevention Practice # 1*

- BMP Description: Designated applicator and container washing areas.
- Installation Schedule: Start of construction.
- Maintenance and Inspection: Daily.
- Responsible Staff: Construction Manager and Site Contractor(s).

### *5.7 Fertilizers*

**General**
If fertilizer is required onsite, installation will follow the following guidelines:

- Fertilizers will be used at the application rates called for in the specifications for the project.
- Once applied, fertilizer will be worked into the soil to minimize wash off from irrigation and stormwater.
- Fertilizer will be stored under cover.
- The contents of partially used fertilizer bags will be transferred to re-sealable, watertight containers clearly labeled with their contents.
- Avoid applying before heavy rains.
- Never apply to frozen ground.
- Never apply to stormwater conveyance channels with flowing water.

### *5.8 Other Pollution Prevention Practices*

Other pollution prevention practices aren't expected to occur onsite.

## SECTION 6: INSPECTION, MAINTENANCE, AND CORRECTIVE ACTION

### *6.1 Inspection Personnel and Procedures*

**Personnel Responsible for Inspections**

Construction Manager TBD

Site Contractor TBD

(Note: All personnel conducting inspections must be considered a "qualified person." CGP Part 4.1.1 clarifies that a "qualified person" is a person knowledgeable in the principles and practices of erosion and sediment controls and pollution prevention, who possesses the skills to assess conditions at the construction site that could impact stormwater quality, and the skills to assess the effectiveness of any stormwater controls selected and installed to meet the requirements of this permit.)

**Inspection Schedule**

Specific Inspection Frequency

The contractor shall inspect and maintain erosion control measures, and remove sediment therefrom, once every 7 days and within 24 hours of a storm event 0.25" or greater.

Rain Gauge Location:
Latitude 42°14'40", Longitude 71°00'16" NAD83
Norfolk County, Massachusetts, Hydrologic Unit 01090001
Datum of gage: 14.12 feet above NAVD88.

Reductions in Inspection Frequency (if applicable):

Inspection frequency may be reduced to twice per month (no more than 14 days apart) for the first month in areas of the site where the stabilization steps outlines in Parts 2.2.14 of the CGP have been completed. After the first month, inspection frequency may be reduced to once per month. If construction activity resumes in this portion of the site at a later date, the inspection frequency immediately increases to that required in Parts 4.2 and 4.3 as applicable. You must document the beginning and ending dates of this period in the SWPPP.

Inspection frequency may be reduced to once per month and within 24 hours of the occurrence of a storm event of 0.25 inches or greater if the project is located in an arid, semi-arid, or drought-stricken area and construction is occurring during the seasonally dry period or a period in which drought is predicted to occur. If this inspection frequency is followed, you must document the beginning and ending dates of this period in the SWPPP.

Inspections can be temporarily suspended under the following conditions:

- Earth-disturbing activity is suspended due to frozen condition;
- Runoff is unlikely due to continuous frozen conditions that are likely to continue at the site for at least three months based on historic seasonal averaged. **If unexpected weather conditions make discharges likely, the operators must immediately resume the regular inspection schedule**;
- Land disturbances have been suspended; and

- All disturbed areas of the site have been stabilized in accordance with Part 2.2.14a of the CGP.

Inspection frequency may be reduced to once per month under the following conditions:

- The operator is still conducting earth disturbing activities under frozen conditions;
- Runoff is unlikely due to continuous frozen conditions that are likely to continue at the site for at least three months based on historic seasonal averages. **If unexpected weather conditions make discharges likely, the operator must immediately resume the regular inspection schedule**; and
- Except for areas in which the operator is conducting earth-disturbing activities, disturbed areas of the site have been stabilized in accordance with Part 2.2.14a of the CGP.

**Inspection Report Forms**
Copies of inspection reports are in Attachment D.

### *6.2 Corrective Action*

**Personnel Responsible for Corrective Actions**
Contact Person, TBD
Contact Person, Site Contractor TBD

**Corrective Action Forms**
A copy of the Corrective Action Form is in Attachment E.

### *6.3 Delegation of Authority*

**Duly Authorized Representative(s) or Position(s):**
Construction Manager Company TBD
Contact Person
Contact Person Title
Street Address
Town/City, State Zip Code
xxx-xxx-xxxx
Email address

## SECTION 7: SWPPP TRAINING DOCUMENTATION

Refer to Attachment I for a Training Log to be completed for each SWPPP training session.

**Refer to Attachment I for certificates from completion of EPA Inspector course**

**Table 7-1: Documentation for Completion of Training**

| Name | Date Training Completed |
|---|---|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## SECTION 8: CERTIFICATION AND NOTIFICATION

**Operator – Owner's Representative**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name: _____ Title: _____

Signature: _____ Date: _____

**Operator – Construction Manager**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name: _____ Title: _____

Signature: _____ Date: _____

## SECTION 9: TURBIDITY BENCHMARK MONITORING FOR DEWATERING DISCHARGES

**If required to comply with Part 3.3 turbidity benchmark monitoring requirements for discharging to sensitive waters, the following procedures will be followed.**

- **Take one turbidity sample each day**
- **Default benchmark is 50 NTUs unless an alternative benchmark is approved by the EPA.**
- **Corrective action must be taken if weekly average is over 50 NTU or if any one sample is over 350 NTU. Corrective action may include shutting off controls and discharge, determining ineffective controls causing exceedance, and making changes to lower turbidity levels.**
- **Weekly averages must be submitted to the EPA electronically no later than 30 days following the end of each monitoring year.**

**Procedures:**

| | |
|---|---|
| **Collecting and evaluating samples** | |
| **Reporting results and keeping monitoring information records** | |
| **Taking corrective action when necessary** | |

**Turbidity Meter:**

| | |
|---|---|
| **Type of turbidity meter** | |

**Turbidity meter manuals and manufacturer instructions**

**Coordinating Arrangements for Turbidity Monitoring (if applicable):**

| | |
|---|---|
| **Permitted operator name** | |
| **Permitted operator NPDES ID** | |
| **Coordinating Arrangement** | |

*[Repeat as necessary.]*

**Alternate turbidity benchmark (if applicable – alternate benchmarks must be approved by EPA):**

| | |
|---|---|
| **Alternate turbidity benchmark (NTU)** | |
| **Data and documentation used to request the alternate benchmark** | |

**SWPPP ATTACHMENTS**

***Attachment A – Site Maps***

***Attachment B – 2022 Construction General Permit***

***Attachment C – NOI and EPA Authorization Email***

***Attachment D – Site Inspection Form and Dewatering Inspection Form (If Applicable)***

***Attachment E – Corrective Action Form***

***Attachment F – SWPPP Amendment Log***

***Attachment G – Subcontractor Certifications/Agreements***

***Attachment H – Grading and Stabilization Activities Log***

***Attachment I – SWPPP Training Documentation***

***Attachment J – Delegation of Authority Form***

***Attachment K – Endangered Species Documentation***

***Attachment L – Historic Preservation Documentation***

***Attachment M – Rainfall Gauge Recording***

***Attachment N – Turbidity Meter Manual and Manufacturer's Instructions***

**Attachment A – Site Maps**





# Figure 1: Locus Map

8/9/2022

Stoughton Fire Station No. 1
400 Prospect Streett,
Stoughton, MA 02072

Data Source: MassGIS
Nitsch Project #13743

Nitsch Engineering




# Figure 3: MassDEP Wetland

8/10/2022

Stoughton Fire Station No. 1
400 Prospect Streett,
Stoughton, MA 02072

Data Source: MassGIS
Nitsch Project #13743

Nitsch Engineering




# Figure 5: Mass Historic Commision

8/10/2022

Stoughton Fire Station No. 1
400 Prospect Streett,
Stoughton, MA 02072

Data Source: MassGIS
Nitsch Project #13743

Nitsch Engineering




# Figure 4: NHESP

8/10/2022

Stoughton Fire Station No. 1
400 Prospect Streett,
Stoughton, MA 02072

Data Source: MassGIS
Nitsch Project #13743

Nitsch Engineering





**Figure 2: USGS Map**

8/9/2022

Stoughton Fire Station No. 1
400 Prospect Streett,
Stoughton, MA 02072

Data Source: MassGIS
Nitsch Project #13743

Nitsch Engineering

**Attachment B – 2022 Construction General Permit**

**Attachment C – NOI and EPA Authorization Email**

**National Pollutant Discharge Elimination System (NPDES)**
**Construction General Permit (CGP) for Stormwater Discharges from Construction Activities**

In compliance with the provisions of the Clean Water Act, 33 U.S.C. §1251 et. seq., (hereafter CWA), as amended by the Water Quality Act of 1987, P.L. 100-4, "operators" of construction activities (defined in Appendix A) that meet the requirements of Part 1.1 of this National Pollutant Discharge Elimination System (NPDES) Construction General Permit (CGP), are authorized to discharge pollutants in accordance with the effluent limitations and conditions set forth herein. Permit coverage is required from the "commencement of construction activities" (see Appendix A) until one of the conditions for terminating CGP coverage has been met (see Part 8.2).

This permit becomes effective on 12:00 am, February 17, 2022.

This permit and the authorization to discharge expire at 11:59pm, February 16, 2027.

Signed and issued this 18 day of January 2022

DEBORAH SZARO
Digitally signed by DEBORAH SZARO
Date: 2022.01.18 08:31:14 -05'00'

Deborah Szaro,
Acting Regional Administrator, EPA Region 1.

Signed and issued this 18 day of January 2022

JAVIER LAUREANO
Digitally signed by JAVIER LAUREANO
Date: 2022.01.18 11:21:16 -05'00'

Javier Laureano,
Director, Water Division, EPA Region 2.

Signed and issued this 18 day of January 2022

CARMEN GUERRERO PEREZ
Digitally signed by CARMEN GUERRERO PEREZ
Date: 2022.01.18 10:19:51 -04'00'

Carmen Guerrero-Perez,
Director, Caribbean Environmental Protection Division, EPA Region 2.

Signed and issued this 18 day of January 2022

CATHERINE LIBERTZ
Digitally signed by CATHERINE LIBERTZ
Date: 2022.01.18 12:05:24 -05'00'

Catherine A. Libertz,
Director, Water Division, EPA Region 3.

Signed and issued this 18 day of January 2022

JEANEANNE GETTLE
Digitally signed by JEANEANNE GETTLE
Date: 2022.01.18 13:09:48 -05'00'

Jeaneanne Gettle,
Director, Water Division, EPA Region 4.

Signed and issued this 18 day of January 2022

Digitally signed by TERA FONG
Date: 2022.01.18 13:03:49 -06'00'

Tera Fong,
Director, Water Division, EPA Region 5.

Signed and issued this 18 day of January 2022

CHARLES MAGUIRE
Digitally signed by CHARLES MAGUIRE
DN: c=US, o=U.S. Government, ou=Environmental Protection Agency, cn=CHARLES MAGUIRE, 0.9.2342.19200300.100.1.1=68001003650036
Date: 2022.01.18 14:06:55 -06'00'

Charles W. Maguire,
Director, Water Division, EPA Region 6.

Signed and issued this 18 day of January 2022

JEFFERY ROBICHAUD
Digitally signed by JEFFERY ROBICHAUD
Date: 2022.01.18 14:41:37 -06'00'

Jeffery Robichaud,
Director, Water Division, EPA Region 7.

Signed and issued this 18 day of January 2022

DARCY OCONNOR
Digitally signed by DARCY OCONNOR
Date: 2022.01.18 14:00:05 -07'00'

Darcy O'Connor,
Director, Water Division, EPA Region 8.

Signed and issued this 18 day of January 2022

TOMAS TORRES
Digitally signed by TOMAS TORRES
Date: 2022.01.18 13:30:16 -08'00'

Tomás Torres,
Director, Water Division, EPA Region 9.

Signed and issued this 18 day of January 2022

DANIEL OPALSKI
Digitally signed by DANIEL OPALSKI
Date: 2022.01.18 15:10:20 -08'00'

Daniel D. Opalski,
Director, Water Division, EPA Region 10.

**CONTENTS**

**1 How to Obtain Coverage Under the Construction General Permit (CGP) ..... 1**
1.1 Eligibility Conditions ..... 1
1.2 Types of Discharges Authorized ..... 3
1.3 Prohibited Discharges ..... 4
1.4 Submitting your Notice of Intent (NOI) ..... 5
1.5 Requirement to Post a Notice of Your Permit Coverage ..... 7
**2 Technology-Based Effluent Limitations ..... 8**
2.1 General Stormwater Control Design, Installation, and Maintenance Requirements ..... 8
2.2 Erosion and Sediment Control Requirements ..... 10
2.3 Pollution Prevention Requirements ..... 17
2.4 Construction Dewatering Requirements ..... 22
**3 Water Quality-Based Effluent Limitations ..... 23**
3.1 General Effluent Limitation to Meet Applicable Water Quality Standards ..... 23
3.2 Water Quality-based Conditions for Sites Discharging to Sensitive Waters[44] ..... 23
3.3 Water quality-based conditions For sites discharging To Sensitive Waters From Construction Dewatering activities ..... 24
**4 Site Inspection Requirements ..... 28**
4.1 Person(s) Responsible for Inspecting Site ..... 28
4.2 Frequency of Inspections ..... 28
4.3 Increase in Inspection Frequency for Certain Sites. ..... 29
4.4 Reductions in Inspection Frequency ..... 30
4.5 Areas that Must Be Inspected ..... 31
4.6 Requirements for Inspections ..... 32
4.7 Inspection Report ..... 33
4.8 Inspections By EPA ..... 34
**5 Corrective Actions ..... 34**
5.1 Conditions Triggering Corrective Action ..... 34
5.2 Corrective Action Deadlines ..... 35
5.3 Corrective Action Required by EPA ..... 36
5.4 Corrective Action Log ..... 36
**6 Stormwater Team Formation/ Staff Training Requirements ..... 36**
6.1 Stormwater Team ..... 36
6.2 General Training Requirements For Stormwater Team Members ..... 37
6.3 Training Requirements For Persons Conducting Inspections ..... 37
6.4 Stormwater Team's Access To Permit Documents ..... 38

**7 Stormwater Pollution Prevention Plan (SWPPP) ..... 38**
7.1 General Requirements ..... 38
7.2 SWPPP Contents ..... 38
7.3 On-Site Availability of Your SWPPP ..... 46
7.4 SWPPP Modifications ..... 46
**8 How to Terminate Coverage ..... 47**
8.1 Minimum Information Required in NOT ..... 47
8.2 Conditions for Terminating CGP Coverage ..... 47
8.3 How to Submit Your NOT ..... 48
8.4 Deadline for Submitting the NOT ..... 49
8.5 Effective Date of Termination of Coverage ..... 49
**9 Permit Conditions Applicable to Specific States, Indian Country Lands, or Territories ..... 49**
**Appendix A: Definitions ..... A-1**
**Appendix B: Permit Areas Eligible for Coverage and EPA Regional Addresses ..... B-1**
**Appendix C: Small Construction Waivers and Instructions ..... C-1**
**Appendix D: Eligibility Procedures Relating to Threatened & Endangered Species Protection. D-1**
**Appendix E: Historic Property Screening Process ..... E-1**
**Appendix F: Buffer Requirements ..... F-1**
**Appendix G: Standard Permit Conditions ..... G-1**
**Appendix H: Notice of Intent (NOI) Form and Instructions ..... H-1**
**Appendix I: Notice of Termination (NOT) Form and Instructions ..... I-1**
**Appendix J: Suggested Format for Request for Chemical Treatment ..... J-1**
**Appendix K: Turbidity Benchmark Monitoring Report Form ..... K-1**

# 1 HOW TO OBTAIN COVERAGE UNDER THE CONSTRUCTION GENERAL PERMIT (CGP)

To be covered under this permit, you must meet the eligibility conditions and follow the requirements for obtaining permit coverage in this Part.

## 1.1 ELIGIBILITY CONDITIONS

**1.1.1** You are an "operator" of a construction site for which discharges will be covered under this permit. For the purposes of this permit and in the context of stormwater discharges associated with construction activity, an "operator" is any party associated with a construction project that meets either of the following two criteria:

**a.** The party has operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; or

**b.** The party has day-to-day operational control of those activities at a project that are necessary to ensure compliance with the permit conditions.

Where there are multiple operators associated with the same project, all operators must obtain permit coverage.[1] Subcontractors generally are not considered operators for the purposes of this permit.

**1.1.2 Your site's construction activities:**

**a.** Will disturb one or more acres of land, or will disturb less than one acre of land but are part of a common plan of development or sale (as defined in Appendix A) that will ultimately disturb one or more acres of land; or

**b.** Have been designated by EPA as needing permit coverage under 40 CFR § 122.26(a)(1)(v) or 40 CFR § 122.26(b)(15)(ii);

**1.1.3** Your site is located in an area where EPA is the permitting authority and where coverage under this permit is available (see Appendix B);

**1.1.4 Discharges from your site are not:**

**a.** Already covered by a different NPDES permit for the same discharge; or

**b.** In the process of having coverage under a different NPDES permit for the same discharge denied, terminated, or revoked.[2, 3]

**1.1.5** You can demonstrate you meet one of the criteria in the Endangered Species Protection section of the Notice of Intent (NOI) that you submit for coverage under this permit, per Part 1.4, with respect to the protection of Federally listed endangered or threatened species and Federally designated critical habitat under the Endangered Species Act

[1] If the operator of a "construction support activity" (see Part 1.2.1c) is different than the operator of the main site, that operator must also obtain permit coverage. See Part 7.1 for clarification on the sharing of permit-related functions between and among operators on the same site and for conditions that apply to developing a SWPPP for multiple operators associated with the same site.

[2] Parts 1.1.4a and 1.1.4b do not include sites currently covered under the 2017 CGP that are in the process of obtaining coverage under this permit, nor sites covered under this permit that are transferring coverage to a different operator.

[3] Notwithstanding a site being made ineligible for coverage under this permit because it falls under the description of Parts 1.1.4a or 1.1.4b, above, EPA may waive the applicable eligibility requirement after specific review if it determines that coverage under this permit is appropriate.

(ESA). If the EPA Regional Office grants you a waiver from electronic reporting per Part 1.4.2, you must complete the ESA worksheet in Appendix D to demonstrate you meet one of the criteria and submit it with your paper NOI (Appendix I).

**1.1.6** You have completed the screening process in Appendix E relating to the protection of historic properties; and

**1.1.7** You have complied with all requirements in Part 9 imposed by the applicable State, Indian Tribe, or Territory in which your construction activities and/or discharge will occur.

**1.1.8** For "new sources" (as defined in Appendix A) only:

**a.** EPA has not, prior to authorization under this permit, determined that discharges from your site will not meet applicable water quality standards. Where such a determination is made prior to authorization, EPA may notify you that an individual permit application is necessary. However, EPA may authorize your coverage under this permit after you have included appropriate controls and implementation procedures designed to bring your discharge into compliance with this permit, specifically the requirement to meet water quality standards. In the absence of information demonstrating otherwise, EPA expects that compliance with the requirements of this permit, including the requirements applicable to such discharges in Part 3, will result in discharges that meet applicable water quality standards.

**b.** Discharges from your site to a Tier 2, Tier 2.5, or Tier 3 water[4] will not lower the water quality of the applicable water. In the absence of information demonstrating otherwise, EPA expects that compliance with the requirements of this permit, including the requirements applicable to such discharges in Part 3.2, will result in discharges that will not lower the water quality of such waters.

**1.1.9** If you plan to add "cationic treatment chemicals" (as defined in Appendix A) to stormwater and/or authorized non-stormwater prior to discharge, you may not submit your NOI until you notify your applicable EPA Regional Office (see Appendix J) in advance and the EPA Regional Office authorizes coverage under this permit after you have included appropriate controls and implementation procedures designed to ensure that your use of cationic treatment chemicals will result in discharges that meet applicable water quality standards.

[4] Note: Your site will be considered to discharge to a Tier 2, Tier 2.5, or Tier 3 water if the first receiving water to which you discharge is identified by a State, Tribe, or EPA as a Tier 2, Tier 2.5, or Tier 3 water. For discharges that enter a storm sewer system prior to discharge, the first receiving water to which you discharge is the waterbody that receives the stormwater discharge from the storm sewer system. The current list of Tier 2, Tier 2.5, and Tier 3 waters located in the areas eligible for coverage under this permit can be found at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates. You can also use EPA's Discharge Mapping Tool (https://www.epa.gov/npdes/epas-stormwater-discharge-mapping-tools) to assist you in identifying whether any receiving waters to which you discharge are listed as impaired (and the pollutant for which it is impaired) and whether an approved total maximum daily load (TMDL) exists for that waterbody.

## 1.2 TYPES OF DISCHARGES AUTHORIZED[5]

**1.2.1** The following stormwater discharges are authorized under this permit provided that appropriate stormwater controls are designed, installed, and maintained (see Parts 2 and 3):

- **a.** Stormwater discharges, including stormwater runoff, snowmelt runoff, and surface runoff and drainage, associated with construction activity under 40 CFR § 122.26(b)(14) or § 122.26(b)(15)(i);
- **b.** Stormwater discharges designated by EPA as needing a permit under 40 CFR §122.26(a)(1)(v) or § 122.26(b)(15)(ii);
- **c.** Stormwater discharges from on or off-site construction support activities (e.g., concrete or asphalt batch plants, equipment staging yards, material storage areas, excavated material disposal areas, borrow areas) provided that:
  - **i.** The support activity is directly related to the construction site required to have permit coverage for stormwater discharges;
  - **ii.** The support activity is not a commercial operation, nor does it serve multiple unrelated construction sites;
  - **iii.** The support activity does not continue to operate beyond the completion of the construction activity at the site it supports; and
  - **iv.** Stormwater controls are implemented in accordance with Part 2 and Part 3 for discharges from the support activity areas; and
- **d.** Stormwater discharges from earth-disturbing activities associated with the construction of staging areas and the construction of access roads conducted prior to active mining.

**1.2.2** The following non-stormwater discharges associated with your construction activity are authorized under this permit provided that, with the exception of water used to control dust and to irrigate vegetation in stabilized areas, these discharges are not routed to areas of exposed soil on your site and you comply with any applicable requirements for these discharges in Parts 2 and 3:

- **a.** Discharges from emergency fire-fighting activities;
- **b.** Fire hydrant flushings;
- **c.** Landscape irrigation;
- **d.** Water used to wash vehicles and equipment, provided that there is no discharge of soaps, solvents, or detergents used for such purposes;
- **e.** Water used to control dust;
- **f.** Potable water including uncontaminated water line flushings;

[5] See "Discharge" as defined in Appendix A. Note: Any discharges not expressly authorized in this permit cannot become authorized or shielded from liability under CWA Section 402(k) by disclosure to EPA, State, or local authorities after issuance of this permit via any means, including the Notice of Intent (NOI) to be covered by the permit, the SWPPP, or during an inspection.

**g.** External building washdown, provided soaps, solvents, and detergents are not used, and external surfaces do not contain hazardous substances (as defined in Appendix A) (e.g., paint or caulk containing polychlorinated biphenyls (PCBs));

**h.** Pavement wash waters, provided spills or leaks of toxic or hazardous substances have not occurred (unless all spill material has been removed) and where soaps, solvents, and detergents are not used. You are prohibited from directing pavement wash waters directly into any receiving water, storm drain inlet, or constructed or natural site drainage features, unless the feature is connected to a sediment basin, sediment trap, or similarly effective control;

**i.** Uncontaminated air conditioning or compressor condensate;

**j.** Uncontaminated, non-turbid discharges of ground water or spring water;

**k.** Foundation or footing drains where flows are not contaminated with process materials such as solvents or contaminated ground water; and

**l.** Uncontaminated construction dewatering water[6] discharged in accordance with Part 2.4.

**1.2.3** Also authorized under this permit are discharges of stormwater listed above in Part 1.2.1, or authorized non-stormwater discharges listed above in Part 1.2.2, commingled with a discharge authorized by a different NPDES permit and/or a discharge that does not require NPDES permit authorization.

### 1.3 PROHIBITED DISCHARGES[7]

The discharges listed in this Part are prohibited outright or authorized only under the identified conditions. To prevent the discharges in Parts 1.3.1 through 1.3.5, operators must comply with the applicable pollution prevention requirements in Part 2.3 or ensure the discharge is authorized by another NPDES permit consistent with Part 1.2.3 for commingled discharges.

**1.3.1** Wastewater from washout of concrete, unless managed by an appropriate control as described in Part 2.3.4;

**1.3.2** Wastewater from washout and/or cleanout of stucco, paint, form release oils, curing compounds, and other construction materials;

**1.3.3** Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance;

**1.3.4** Soaps, solvents, or detergents used in vehicle and equipment washing or external building washdown; and

**1.3.5** Toxic or hazardous substances from a spill or other release.

[6] EPA notes that operators may need to comply with additional procedures to verify that the dewatering discharge is uncontaminated. Operators should review Part 9 to determine if any of these requirements apply to their discharge and should ensure that they have complied with any State, Tribal, or local dewatering requirements that apply.

[7] EPA includes these prohibited non-stormwater discharges here as a reminder to the operator that the only non-stormwater discharges authorized by this permit are at Part 1.2.2. Any unauthorized non-stormwater discharges must be covered under an individual permit or alternative general permit.

## 1.4 SUBMITTING YOUR NOTICE OF INTENT (NOI)

All "operators" (as defined in Appendix A) associated with your construction site who meet the Part 1.1 eligibility conditions, and who seek coverage under this permit, must submit to EPA a complete and accurate NOI in accordance with the deadlines in Table 1 prior to commencement of construction activities (as defined in Appendix A).

**Exception:** If you are conducting construction activities in response to a public emergency (e.g., mud slides, earthquake, extreme flooding conditions, widespread disruption in essential public services), and the related work requires immediate authorization to avoid imminent endangerment to human health, public safety, or the environment, or to reestablish essential public services, you may discharge on the condition that a complete and accurate NOI is submitted within 30 calendar days after commencing construction activities (see Table 1) establishing that you are eligible for coverage under this permit. You must also provide documentation in your Stormwater Pollution Prevention Plan (SWPPP) to substantiate the occurrence of the public emergency pursuant to Part 7.2.3i.

### 1.4.1 Prerequisite for Submitting Your NOI

You must develop a SWPPP consistent with Part 7 before submitting your NOI for coverage under this permit.

### 1.4.2 How to Submit Your NOI

You must use EPA's NPDES eReporting Tool (NeT) to electronically prepare and submit your NOI for coverage under the 2022 CGP unless you received a waiver from your applicable EPA Regional Office.

To access NeT, go to https://cdx.epa.gov/cdx.

Waivers from electronic reporting may be granted based on one of the following conditions:

**a.** If your operational headquarters is physically located in a geographic area (i.e., ZIP code or census tract) that is identified as under-served for broadband Internet access in the most recent report from the Federal Communications Commission; or

**b.** If you have limitations regarding available computer access or computer capability.

If the EPA Regional Office grants you approval to use a paper NOI, and you elect to use it, you must complete the form in Appendix H.

### 1.4.3 Deadlines for Submitting Your NOI and Your Official Date of Permit Coverage

Table 1 provides the deadlines for submitting your NOI and the official start date of your permit coverage, which differ depending on when you commence construction activities.

***Table 1 NOI Submittal Deadlines and Official Start Date for Permit Coverage.***

| Type of Operator | NOI Submittal Deadline[8] | Permit Authorization Date[9] |
|---|---|---|
| **Operator of a new site** (i.e., a site where construction activities commence on or after February 17, 2022) | At least 14 calendar days before commencing construction activities. | 14 calendar days after EPA notifies you that it has received a complete NOI, unless EPA notifies you that your authorization is delayed or denied. |
| **Operator of an existing site** (i.e., a site with 2017 CGP coverage where construction activities commenced prior to February 17, 2022) | No later than May 18, 2022. | 14 calendar days after EPA notifies you that it has received a complete NOI, unless EPA notifies you that your authorization is delayed or denied.<br>Provided you submit your NOI no later than May 18, 2022, your authorization under the 2017 CGP is automatically continued until you have been granted coverage under this permit or an alternative NPDES permit, or coverage is otherwise terminated. |
| **New operator of a permitted site** (i.e., an operator that through transfer of ownership and/or operation replaces the operator of an already permitted construction site that is either a "new site" or an "existing site") | At least 14 calendar days before the date the transfer to the new operator will take place. | 14 calendar days after EPA notifies you that it has received a complete NOI, unless EPA notifies you that your authorization is delayed or denied. |
| **Operator of an "emergency-related project"** (i.e., a project initiated in response to a public emergency (e.g., mud slides, earthquake, extreme flooding conditions, disruption in essential public services), for which the related work requires immediate authorization to avoid imminent endangerment to human health or the environment, or to reestablish essential public services) | No later than 30 calendar days after commencing construction activities. | You are considered provisionally covered under the terms and conditions of this permit immediately, and fully covered 14 calendar days after EPA notifies you that it has received a complete NOI, unless EPA notifies you that your authorization is delayed or denied. |

[8] If you miss the deadline to submit your NOI, any and all discharges from your construction activities will continue to be unauthorized under the CWA until they are covered by this or a different NPDES permit. EPA may take enforcement action for any unpermitted discharges that occur between the commencement of construction activities and discharge authorization.

[9] Discharges are not authorized if your NOI is incomplete or inaccurate or if you are not eligible for permit coverage.

### 1.4.4 Modifying your NOI

If after submitting your NOI you need to correct or update any fields, you may do so by submitting a "Change NOI" form using NeT. Waivers from electronic reporting may be granted as specified in Part 1.4.2. If the EPA Regional Office has granted you approval to submit a paper NOI modification, you may indicate any NOI changes on the same NOI form in Appendix H.

When there is a change to the site's operator, the new operator must submit a new NOI, and the previous operator must submit a Notice of Termination (NOT) form as specified in Part 8.3.

The following modifications to an NOI form will result in a 14-day review process:

- Changes to the name of the operator;
- Changes to the project or site name;
- Changes to the estimated area to be disturbed;
- Changes to the name of the receiving water[10], or additions to the applicable receiving waters;
- Changes to eligibility information related to endangered species protection or historic preservation;
- Changes to information provided related to the use of chemical treatment at your site; and
- Changes to answers provided regarding the demolition of structures over 10,000 square feet of floor space built or renovated before January 1, 1980.

During the 14-day review process, you may continue to operate based on the information provided in your original NOI, but you must wait until the review period has ended before you may commence or continue activities on any portion of your site that would be affected by any of the above modifications, unless EPA notifies you that the authorization is delayed or denied.

### 1.4.5 Your Official End Date of Permit Coverage

Once covered under this permit, your coverage will last until the date that:

**a.** You terminate permit coverage consistent with Part 8; or

**b.** You receive permit coverage under a different NPDES permit or a reissued or replacement version of this permit after expiring on February 16, 2027; or

**c.** You fail to submit an NOI for coverage under a reissued or replacement version of this permit before the deadline for existing construction sites where construction activities continue after this permit has expired.

## 1.5 REQUIREMENT TO POST A NOTICE OF YOUR PERMIT COVERAGE

You must post a sign or other notice of your permit coverage at a safe, publicly accessible location in close proximity to the construction site. The notice must be located so it is visible from the public road that is nearest to the active part of the construction

[10] As defined in Appendix A, a "receiving water" is "a "Water of the United States" as defined in 40 CFR §122.2 into which the regulated stormwater discharges.

site, and it must use a font large enough to be readily viewed from a public right-of-way.[11] At a minimum, the notice must include:

**a.** The NPDES ID (i.e., permit tracking number assigned to your NOI and the EPA webpage where a copy of the NOI can be found (https://permitsearch.epa.gov/epermit-search/ui/search));

**b.** A contact name and phone number for obtaining additional construction site information;

**c.** The Uniform Resource Locator (URL) for the SWPPP (if available), or the following statement: "If you would like to obtain a copy of the Stormwater Pollution Prevention Plan (SWPPP) for this site, contact the EPA Regional Office at [*include the appropriate CGP Regional Office contact information found at* https://www.epa.gov/npdes/contact-us-stormwater#regional];" and

**d.** The following statement "If you observe indicators of stormwater pollutants in the discharge or in the receiving water, contact the EPA through the following website: https://www.epa.gov/enforcement/report-environmental-violations."

## 2 TECHNOLOGY-BASED EFFLUENT LIMITATIONS

You must comply with the following technology-based effluent limitations in this Part for all authorized discharges.[12]

### 2.1 GENERAL STORMWATER CONTROL DESIGN, INSTALLATION, AND MAINTENANCE REQUIREMENTS

You must design, install, and maintain stormwater controls required in Parts 2.2, 2.3, and 2.4 to minimize the discharge of pollutants in stormwater from construction activities.[13] To meet this requirement, you must:

#### 2.1.1 Account for the following factors in designing your stormwater controls:

**a.** The expected amount, frequency, intensity, and duration of precipitation;[14]

**b.** The nature of stormwater runoff (i.e., flow) and run-on at the site, including factors such as expected flow from impervious surfaces, slopes, and site drainage features. You must design stormwater controls to control stormwater volume, velocity, and peak flow rates to minimize discharges of pollutants in stormwater and to minimize channel and streambank erosion and scour in the immediate vicinity of discharge points; and

**c.** The soil type and range of soil particle sizes expected to be present on the site.

[11] If the active part of the construction site is not visible from a public road, then place the notice of permit coverage in a position that is visible from the nearest public road and as close as possible to the construction site.

[12] For each of the effluent limits in Part 2, as applicable to your site, you must include in your SWPPP (1) a description of the specific control(s) to be implemented to meet the effluent limit; (2) any applicable design specifications; (3) routine maintenance specifications; and (4) the projected schedule for installation/implementation. See Part 7.2.6.

[13] The permit does not recommend or endorse specific products or vendors.

[14] Stormwater controls must be designed using the most recent data available to account for recent precipitation patterns and trends.

If your site is exposed to or has previously experienced major storms, such as hurricanes, storm surge, extreme/heavy precipitation, and flood events, you should also include consideration of and contingencies for whether implementing structural improvements, enhanced/resilient stormwater controls, and other mitigation measures may help minimize impacts from stormwater discharges from such major storm events.

**2.1.2 Design and install all stormwater controls in accordance with good engineering practices, including applicable design specifications.[15]**

**2.1.3 Complete installation of stormwater controls by the time each phase of construction activities has begun.**

**a.** By the time construction activity in any given portion of the site begins, install and make operational any downgradient sediment controls (e.g., buffers, perimeter controls, exit point controls, storm drain inlet protection) that control discharges from the initial site clearing, grading, excavating, and other earth-disturbing activities.[16]

**b.** Following the installation of these initial controls, install and make operational all stormwater controls needed to control discharges prior to subsequent earth-disturbing activities.

**2.1.4 Ensure all stormwater controls are maintained and remain in effective operating condition during permit coverage and are protected from activities that would reduce their effectiveness.**

**a.** Comply with any specific maintenance requirements for the stormwater controls listed in this permit, as well as any recommended by the manufacturer.[17]

**b.** If at any time you find that a stormwater control needs routine maintenance (i.e., minor repairs or other upkeep performed to ensure the site's stormwater controls remain in effective operating condition, not including significant repairs or the need to install a new or replacement control), you must immediately initiate the needed work, and complete such work by the close of the next business day. If it is infeasible to complete the routine maintenance by the close of the next business day, you must document why this is the case and why the repair or other upkeep to be performed should still be considered routine maintenance in your inspection report under Part 4.7.1c and complete such work no later than seven (7) calendar days from the time of discovery of the condition requiring maintenance.

**c.** If you must repeatedly (i.e., three (3) or more times) make the same routine maintenance fixes to the same control at the same location, even if the fix can be completed by the close of the next business day, you must either:

**i.** Complete work to fix any subsequent repeat occurrences of this same problem under the corrective action procedures in Part 5, including keeping any records

[15] Design specifications may be found in manufacturer specifications and/or in applicable erosion and sediment control manuals or ordinances. Any departures from such specifications must reflect good engineering practices and must be explained in your SWPPP. You must also comply with any additional design and installation requirements specified for the effluent limits in Parts 2.2, 2.3, and 2.4.

[16] Note that the requirement to install stormwater controls prior to each phase of construction activities for the site does not apply to the earth disturbance associated with the actual installation of these controls. Operators should take all reasonable actions to minimize the discharges of pollutants during the installation of stormwater controls.

[17] Any departures from such maintenance recommendations made by the manufacturer must reflect good engineering practices and must be explained in your SWPPP.

of the condition and how it was corrected under Part 5.4; or

**ii.** Document in your inspection report under Part 4.7.1c why the specific reoccurrence of this same problem should still be addressed as a routine maintenance fix under this Part.[18]

**d.** If at any time you find that a stormwater control needs a significant repair or that a new or replacement control is needed, you must comply with the corrective action deadlines for completing such work in in Part 5.2.1c.

## 2.2 EROSION AND SEDIMENT CONTROL REQUIREMENTS

You must implement erosion and sediment controls in accordance with the following requirements to minimize the discharge of pollutants in stormwater from construction activities.

### 2.2.1 Provide and maintain natural buffers and/or equivalent erosion and sediment controls for discharges to any receiving waters that is located within 50 feet of the site's earth disturbances.

**a. Compliance Alternatives.** For any discharges to receiving waters located within 50 feet of your site's earth disturbances, you must comply with one of the following alternatives:

**i.** Provide and maintain a 50-foot undisturbed natural buffer; or

**ii.** Provide and maintain an undisturbed natural buffer that is less than 50 feet and is supplemented by erosion and sediment controls that achieve, in combination, the sediment load reduction equivalent to a 50-foot undisturbed natural buffer; or

**iii.** If infeasible to provide and maintain an undisturbed natural buffer of any size, implement erosion and sediment controls to achieve the sediment load reduction equivalent to a 50-foot undisturbed natural buffer.

See Appendix F, Part F.2 for additional conditions applicable to each compliance alternative.

**b. Exceptions.** See Appendix F, Part F.2 for exceptions to the compliance alternatives.

### 2.2.2 Direct stormwater to vegetated areas and maximize stormwater infiltration and filtering to reduce pollutant discharges, unless infiltration would be inadvisable due to the underlying geology (e.g., karst topography) and ground water contamination concerns, or infeasible due to site conditions.[19]

[18] Such documentation could include, for example, that minor repairs completed within the required timeframe are all that is necessary to ensure that the stormwater control continues to operate as designed and installed and that the stormwater control remains appropriate for the flow reaching it.

[19] Operators should consider whether factors such as specific contaminant concerns from the construction site, the underlying soils or geology, hydrology, depth to the ground water table, or proximity to source water or wellhead protection area(s) make the site unsuitable for infiltrating construction stormwater. Site conditions that may be of particular concern include proximity to: a current or future drinking water aquifer; a drinking water well or spring (including private/household wells); highly conductive geology such as karst; known pollutant hot spots, such as hazardous waste sites, landfills, gas stations, brownfields; an on-site sewage system or underground storage tank; or soils that do not allow for infiltration. Operators may find it helpful to consult EPA's Drinking Water Mapping Application to Protect Source Waters (DWMAPS). DWMAPS is an online mapping tool that can be used to locate drinking water providers, potential sources of contamination, polluted waterways, and information on protection initiatives in the site area.

**2.2.3 Install sediment controls along any perimeter areas of the site that are downslope from any exposed soil or other disturbed areas.[20]**

**a.** The perimeter control must be installed upgradient of any natural buffers established under Part 2.2.1, unless the control is being implemented pursuant to Part 2.2.1a.ii-iii;

**b.** To prevent stormwater from circumventing the edge of the perimeter control, install the perimeter control on the contour of the slope and extend both ends of the control up slope (e.g., at 45 degrees) forming a crescent rather than a straight line;

**c.** After installation, to ensure that perimeter controls continue to work effectively:

**i.** Remove sediment before it has accumulated to one-half of the above-ground height of any perimeter control; and

**ii.** After a storm event, if there is evidence of stormwater circumventing or undercutting the perimeter control, extend controls and/or repair undercut areas to fix the problem.

**d. Exception**. For areas at "linear construction sites" (as defined in Appendix A) where perimeter controls are infeasible (e.g., due to a limited or restricted right-of-way), implement other practices as necessary to minimize pollutant discharges to perimeter areas of the site.

**2.2.4 Minimize sediment track-out.**

**a.** Restrict vehicle use to properly designated exit points;

**b.** Use appropriate stabilization techniques[21] at all points that exit onto paved roads;

**i. Exception**: Stabilization is not required for exit points at linear utility construction sites that are used only episodically and for very short durations over the life of the project, provided other exit point controls[22] are implemented to minimize sediment track-out;

**c.** Implement additional track-out controls[23] as necessary to ensure that sediment removal occurs prior to vehicle exit; and

**d.** Where sediment has been tracked-out from your site onto paved roads, sidewalks, or other paved areas outside of your site, remove the deposited sediment by the end of the same business day in which the track-out occurs or by the end of the next business day if track-out occurs on a non-business day. Remove the track-out by sweeping, shoveling, or vacuuming these surfaces, or by using other similarly effective means of sediment removal. You are prohibited from hosing or sweeping tracked-out

[20] Examples of perimeter controls include filter berms; different types of silt fence such as wire-backed silt fence, super silt fence, or multi-layer geotextile silt fence; compost filter socks; gravel barriers; and temporary diversion dikes.

[21] Examples of appropriate stabilization techniques include the use of aggregate stone with an underlying geotextile or non-woven filter fabric, and turf mats.

[22] Examples of other exit point controls include preventing the use of exit points during wet periods; minimizing exit point use by keeping vehicles on site to the extent possible; limiting exit point size to the width needed for vehicle and equipment usage; using scarifying and compaction techniques on the soil; and avoiding establishing exit points in environmentally sensitive areas (e.g., *karst areas; steep slopes)*.

[23] Examples of additional track-out controls include the use of wheel washing, rumble strips, and rattle plates.

sediment into any constructed or natural site drainage feature, storm drain inlet, or receiving water.[24]

**2.2.5 Manage stockpiles or land clearing debris piles composed, in whole or in part, of sediment and/or soil:[25]**

**a.** Locate the piles outside of any natural buffers established under Part 2.2.1 and away from any constructed or natural site drainage features, storm drain inlets, and areas where stormwater flow is concentrated;

**b.** Install a sediment barrier along all downgradient perimeter areas of stockpiled soil or land clearing debris piles;[26]

**c.** For piles that will be unused for 14 or more days, provide cover[27] or appropriate temporary stabilization (consistent with Part 2.2.14);

**d.** You are prohibited from hosing down or sweeping soil or sediment accumulated on pavement or other impervious surfaces into any constructed or natural site drainage feature, storm drain inlet, or receiving water.

**2.2.6 Minimize dust.** On areas of exposed soil, minimize dust through the appropriate application of water or other dust suppression techniques to control the generation of pollutants that could be discharged in stormwater from the site.

**2.2.7 Minimize steep slope disturbances.** Minimize the disturbance of "steep slopes" (as defined in Appendix A).[28]

**2.2.8 Preserve native topsoil, unless infeasible.[29]**

**2.2.9 Minimize soil compaction.[30]** In areas of your site where final vegetative stabilization will occur or where infiltration practices will be installed:

---

[24] Fine grains that remain visible (e.g., staining) on the surfaces of off-site streets, other paved areas, and sidewalks after you have implemented sediment removal practices are not a violation of Part 2.2.4.

[25] The requirements in Part 2.2.5 do not apply to the storage of rock, such as rip rap, landscape rock, pipe bedding gravel, and boulders. Refer to Part 2.3.3a for the requirements that apply to these types of materials.

[26] Examples of sediment barriers include berms, dikes, fiber rolls, silt fences, sandbags, gravel bags, or straw bale.

[27] Examples of cover include tarps, blown straw and hydroseeding.

[28] Where disturbance to steep slopes cannot be avoided, operators should consider implementing controls suitable for steep slope disturbances that are effective at minimizing erosion and sediment discharge (e.g., preservation of existing vegetation, hydraulic mulch, geotextiles and mats, compost blankets, earth dikes or drainage swales, terraces, velocity dissipation devices). To identify slopes and soil types that are of comparatively higher risk for sediment discharge in areas of the country where the CGP is in effect, operators can use the tables in Appendix F (see Tables F-2 thru F-6).

[29] Stockpiling topsoil at off-site locations, or transferring topsoil to other locations, is an example of a practice that is consistent with the requirements in Part 2.2.8. Preserving native topsoil is not required where the intended function of a specific area of the site dictates that the topsoil be disturbed or removed. For example, some sites may be designed to be highly impervious after construction, and therefore little or no vegetation is intended to remain, or may not have space to stockpile native topsoil on site for later use, in which case it may not be feasible to preserve topsoil.

[30] Minimizing soil compaction is not required where the intended function of a specific area of the site dictates that it be compacted.

**a.** Restrict vehicle and equipment use in these locations to avoid soil compaction; and

**b.** Before seeding or planting areas of exposed soil that have been compacted, use techniques that rehabilitate and condition the soils as necessary to support vegetative growth.

**2.2.10 Protect storm drain inlets.**

**a.** Install inlet protection measures that remove sediment from discharges prior to entry into any storm drain inlet that carries stormwater from your site to a receiving water, provided you have authority to access the storm drain inlet.[31] Inlet protection measures are not required for storm drain inlets that are conveyed to a sediment basin, sediment trap, or similarly effective control; and

**b.** Clean, or remove and replace, the inlet protection measures as sediment accumulates, the filter becomes clogged, and/or performance is compromised. Where there is evidence of sediment accumulation adjacent to the inlet protection measure, remove the deposited sediment by the end of the same business day in which it is found or by the end of the following business day if removal by the same business day is not feasible.

**2.2.11 Control stormwater discharges, including both peak flowrates and total stormwater volume, to minimize channel and streambank erosion and scour in the immediate vicinity of discharge points.[32]**

**2.2.12 If you install a sediment basin or similar impoundment:**

**a.** Situate the basin or impoundment outside of any receiving water. and any natural buffers established under Part 2.2.1;

**b.** Design the basin or impoundment to avoid collecting water from wetlands;

**c.** Design the basin or impoundment to provide storage for either:

**i.** The calculated volume of runoff from a 2-year, 24-hour storm;[33] or

**ii.** 3,600 cubic feet per acre drained.

**d.** Utilize outlet structures that withdraw water from the surface of the sediment basin or similar impoundment, unless infeasible;[34]

**e.** Use erosion controls and velocity dissipation devices to prevent erosion at inlets and outlets; and

---

[31] Inlet protection measures can be removed in the event of flood conditions or to prevent erosion.

[32] Examples of stormwater controls that can be used to comply with this requirement include the use of erosion controls and/or velocity dissipation devices (e.g., check dams, sediment traps), within and along the length of a constructed site drainage feature and at the outfall to slow down stormwater.

[33] Operators may refer to https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates for guidance on determining the volume of precipitation associated with their site's local 2-year, 24-hour storm event.

[34] The circumstances in which it is infeasible to design outlet structures in this manner are rare. Exceptions may include areas with extended cold weather, where using surface outlets may not be feasible during certain time periods (although they must be used during other periods). If you determine that it is infeasible to meet this requirement, you must provide documentation in your SWPPP to support your determination, including the specific conditions or time periods when this exception will apply.

**f.** Remove accumulated sediment to maintain at least one-half of the design capacity and conduct all other appropriate maintenance to ensure the basin or impoundment remains in effective operating condition.

**2.2.13 If using treatment chemicals** (e.g., *polymers, flocculants, coagulants*):

**a. Use conventional erosion and sediment controls before and after the application of treatment chemicals.** Chemicals may only be applied where treated stormwater is directed to a sediment control *(e.g., sediment basin, perimeter control)* before discharge.

**b. Select appropriate treatment chemicals***.* Chemicals must be appropriately suited to the types of soils likely to be exposed during construction and present in the discharges being treated *(i.e., the expected turbidity, pH, and flow rate of stormwater flowing into the chemical treatment system or area)*.

**c. Minimize discharge risk from stored chemicals.** Store all treatment chemicals in leak-proof containers that are kept under storm-resistant cover and surrounded by secondary containment structures *(e.g., spill berms, dikes, spill containment pallets),* or provide equivalent measures designed and maintained to minimize the potential discharge of treatment chemicals in stormwater or by any other means *(e.g., storing chemicals in a covered area, having a spill kit available on site and ensuring personnel are available to respond expeditiously in the event of a leak or spill)*.

**d. Comply with State/local requirements.** Comply with applicable State and local requirements regarding the use of treatment chemicals.

**e. Use chemicals in accordance with good engineering practices and specifications of the chemical provider/supplier.** Use treatment chemicals and chemical treatment systems in accordance with good engineering practices, and with dosing specifications and sediment removal design specifications provided by the provider/supplier of the applicable chemicals, or document in your SWPPP specific departures from these specifications and how they reflect good engineering practice.

**f. Ensure proper training.** Ensure all persons who handle and use treatment chemicals at the construction site are provided with appropriate, product-specific training prior to beginning application of treatment chemicals. Among other things, the training must cover proper dosing requirements.

**g. Perform additional measures specified by the EPA Regional Office for the authorized use of cationic chemicals.** If you have been authorized to use cationic chemicals at your site pursuant to Part 1.1.9, you must perform all additional measures as conditioned by your authorization to ensure the use of such chemicals will not result in discharges that do not meet water quality standards.

**2.2.14 Stabilize exposed portions of the site.** Implement and maintain stabilization measures (*e.g., seeding protected by erosion controls until vegetation is established,*[35] *sodding, mulching, erosion control blankets, hydromulch, gravel*) that minimize erosion from any areas of exposed soil on the site in accordance with Part.

[35] If you will be evaluating the use of some type of erosion control netting to the site as part of your site stabilization, EPA encourages you to consider employing products that have been shown to minimize

### a. Stabilization Deadlines:[36]

***Table 2 Deadlines for Initiating and Completing Site Stabilization.***

| **Total Amount of Land Disturbance Occurring At Any One Time[37]** | **Deadline** |
|---|---|
| **i. Five acres or less (≤5.0)**<br><br>**Note: this includes sites disturbing more than five acres (>5.0) total over the course of a project, but that limit disturbance at any one time (i.e., *phase the disturbance*) to five acres or less (≤5.0)** | • Initiate the installation of stabilization measures immediately[38] in any areas of exposed soil where construction activities have permanently ceased or will be temporarily inactive for 14 or more calendar days;[39] and<br>• Complete the installation of stabilization measures as soon as practicable, but no later than 14 calendar days |

impacts on wildlife. For instance, the U.S. Fish & Wildlife Service provides recommendations on the type of netting practices that are considered "wildlife friendly," including those that use natural fiber or 100 percent biodegradable materials and that use a loose weave with a non-welded, movable jointed netting, as well as those products that are not wildlife friendly including square plastic netting that are degradable (e.g., photodegradable, UV-degradable, oxo-degradable), netting made from polypropylene, nylon, polyethylene, or polyester. Other recommendations include removing the netting product when it is no longer needed. See https://www.fws.gov/midwest/eastlansing/library/pdf/WildlifeFriendlyErosionControlProducts_revised.pdf for further information. There also may be State, Tribal, or local requirements about using wildlife friendly erosion control products.

[36] EPA may determine, based on an inspection carried out under Part 4.8 and corrective actions required under Part 5.3, that the level of sediment discharge on the site makes it necessary to require a faster schedule for completing stabilization. For instance, if sediment discharges from an area of exposed soil that is required to be stabilized are compromising the performance of existing stormwater controls, EPA may require stabilization to correct this problem.

[37] Limiting disturbances to five (5) acres or less at any one time means that at no time during the project do the cumulative earth disturbances exceed five (5) acres. The following examples would qualify as limiting disturbances at any one time to five (5) acres or less:

1. The total area of disturbance for a project is five (5) acres or less.
2. The total area of disturbance for a project will exceed five (5) acres, but the operator ensures that no more than five (5) acres will be disturbed at any one time through implementation of stabilization measures. In this way, site stabilization can be used to "free up" land that can be disturbed without exceeding the five (5)-acre cap to qualify for the 14-day stabilization deadline. For instance, if an operator completes stabilization of two (2) acres of land on a five (5)-acre disturbance, then two (2) additional acres could be disturbed while still qualifying for the longer 14-day stabilization deadline.

[38] The following are examples of activities that would constitute the immediate initiation of stabilization:

1. Prepping the soil for vegetative or non-vegetative stabilization as long as seeding, planting, and/or installation of non-vegetative stabilization products takes place as soon as practicable, but no later than one (1) calendar day of completing soil preparation;
2. Applying mulch or other non-vegetative product to the exposed area;
3. Seeding or planting the exposed area;
4. Starting any of the activities in # 1 – 3 on a portion of the entire area that will be stabilized; and
5. Finalizing arrangements to have stabilization product fully installed in compliance with the deadlines for completing stabilization.

[39] The requirement to initiate stabilization immediately is triggered as soon as you know that construction work on a portion of the site is temporarily ceased and will not resume for 14 or more days, or as soon as you know that construction work is permanently ceased. In the context of this provision, "immediately" means as soon as practicable, but no later than the end of the next business day, following the day when the construction activities have temporarily or permanently ceased.

| Total Amount of Land Disturbance Occurring At Any One Time[37] | Deadline |
|---|---|
| | after stabilization has been initiated.[40] |
| **ii. More than five acres (>5.0)** | • Initiate the installation of stabilization measures immediately[41] in any areas of exposed soil where construction activities have permanently ceased or will be temporarily inactive for 14 or more calendar days;[42] and<br>• Complete the installation of stabilization measures as soon as practicable, but no later than seven (7) calendar days after stabilization has been initiated.[43] |

**b. Exceptions:**

**i. Arid, semi-arid, and drought-stricken areas** (as defined in Appendix A)**.** If it is the seasonally dry period (as defined in Appendix A)[44] or a period in which drought is occurring, and vegetative stabilization measures are being used:

(a) Immediately initiate and, within 14 calendar days of temporary or permanent cessation of work in any portion of your site, complete the installation of temporary non-vegetative stabilization measures to the extent necessary to prevent erosion;

(b) As soon as practicable, given conditions or circumstances on the site, complete all activities necessary to seed or plant the area to be stabilized; and

(c) If construction is occurring during the seasonally dry period, indicate in your SWPPP the beginning and ending dates of the seasonally dry period and your site conditions. Also include the schedule you will follow for initiating and completing vegetative stabilization.

**ii. Unforeseen circumstances.** Operators that are affected by unforeseen circumstances[45] that delay the initiation and/or completion of vegetative stabilization:

[40] If vegetative stabilization measures are being implemented, stabilization is considered "installed" when all activities necessary to seed or plant the area are completed, including the application of any non-vegetative protective cover (e.g., mulch, erosion control blanket), if applicable. If non-vegetative stabilization measures are being implemented, stabilization is considered "installed" when all such measures are implemented or applied.

[41] See footnote 38.

[42] See footnote 39.

[43] See footnote 40.

[44] The term "seasonally dry period" as defined in Appendix A refers to a month in which the long-term average total precipitation is less than or equal to 0.5 inches. Refer to EPA's Seasonally Dry Period Locator Tool at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates and supporting maps for assistance in determining whether a site is operating during a seasonally dry period for the area.

[45] Examples include problems with the supply of seed stock or with the availability of specialized equipment and unsuitability of soil conditions due to excessive precipitation and/or flooding.

(a) Immediately initiate and, within 14 calendar days, complete the installation of temporary non-vegetative stabilization measures to prevent erosion;

(b) Complete all soil conditioning, seeding, watering or irrigation installation, mulching, and other required activities related to the planting and initial establishment of vegetation as soon as conditions or circumstances allow it on your site; and

(c) Document in the SWPPP the circumstances that prevent you from meeting the deadlines in Part 2.2.14a and the schedule you will follow for initiating and completing stabilization.

**iii. Discharges to a sediment- or nutrient-impaired water or to a water that is identified by your State, Tribe, or EPA as Tier 2, Tier 2.5, or Tier 3 for antidegradation purposes.** Complete stabilization as soon as practicable, but no later than seven (7) calendar days after stabilization has been initiated.

**c. Final Stabilization Criteria** (for any areas not covered by permanent structures)**:**

**i.** Establish uniform, perennial vegetation *(*i.e.*, evenly distributed, without large bare areas)* to provide 70 percent or more of the vegetative cover native to local undisturbed areas; and/or

**ii.** Implement permanent non-vegetative stabilization measures[46] to provide effective cover of any areas of exposed soil.

**iii. Exceptions:**

(a) **Arid, semi-arid, and drought-stricken areas** (as defined in Appendix A). Final stabilization is met if the area has been seeded or planted to establish vegetation that provides 70 percent or more of the vegetative cover native to local undisturbed areas within three (3) years and, to the extent necessary to prevent erosion on the seeded or planted area, non-vegetative erosion controls have been applied to provide cover for at least three years without active maintenance.

(b) **Disturbed areas on agricultural land that are restored to their preconstruction agricultural use.** The Part 2.2.14c final stabilization criteria do not apply.

(c) **Areas that need to remain disturbed.** In limited circumstances, stabilization may not be required if the intended function of a specific area of the site necessitates that it remain disturbed, and only the minimum area needed remains disturbed *(*e.g.*, dirt access roads, utility pole pads, areas being used for storage of vehicles, equipment, materials)*.

## 2.3 POLLUTION PREVENTION REQUIREMENTS[47]

You must implement pollution prevention controls in accordance with the following requirements to minimize the discharge of pollutants in stormwater and to prevent the discharge of pollutants from spilled or leaked materials from construction activities.

[46] Examples of permanent non-vegetative stabilization measures include riprap, gravel, gabions, and geotextiles.

[47] Under this permit, you are not required to minimize exposure for any products or materials where the exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk of stormwater contamination (such as final products and materials intended for outdoor use).

**2.3.1 For equipment and vehicle fueling and maintenance:**

**a.** Provide an effective means of eliminating the discharge of spilled or leaked chemicals, including fuels and oils, from these activities;[48]

**b.** If applicable, comply with the Spill Prevention Control and Countermeasures (SPCC) requirements in 40 CFR part 112 and Section 311 of the CWA;

**c.** Ensure adequate supplies are available at all times to handle spills, leaks, and disposal of used liquids;

**d.** Use drip pans and absorbents under or around leaky vehicles;

**e.** Dispose of or recycle oil and oily wastes in accordance with other Federal, State, Tribal, or local requirements; and

**f.** Clean up spills or contaminated surfaces immediately, using dry clean up measures (do not clean contaminated surfaces by hosing the area down), and eliminate the source of the spill to prevent a discharge or a continuation of an ongoing discharge.

**2.3.2 For equipment and vehicle washing:**

**a.** Provide an effective means of minimizing the discharge of pollutants from equipment and vehicle washing, wheel wash water, and other types of wash waters;[49]

**b.** Ensure there is no discharge of soaps, solvents, or detergents in equipment and vehicle wash water; and

**c.** For storage of soaps, detergents, or solvents, provide either (1) cover *(*e.g., *plastic sheeting, temporary roofs)* to minimize the exposure of these detergents to precipitation and to stormwater, or (2) a similarly effective means designed to minimize the discharge of pollutants from these areas.

**2.3.3 For storage, handling, and disposal of building products, materials, and wastes:[50]**

**a.** *For building materials and building products*,[51] provide either (1) cover (e.g., *plastic sheeting, temporary roofs*) to minimize the exposure of these products to

[48] Examples of effective means include:

- Locating activities away from receiving waters, storm drain inlets, and constructed or natural site drainage feature so that stormwater coming into contact with these activities cannot reach waters of the U.S.;
- Providing secondary containment (e.g., *spill berms, dikes, spill containment pallets*) and cover where appropriate; and
- Having a spill kit available on site and ensuring personnel are available to respond expeditiously in the event of a leak or spill.

[49] Examples of effective means include locating activities away from receiving waters and storm drain inlets or constructed or natural site drainage features and directing wash waters to a sediment basin or sediment trap, using filtration devices, such as filter bags or sand filters, or using other similarly effective controls.

[50] Compliance with the requirements of this permit does not relieve compliance requirements with respect to Federal, State, or local laws and regulations governing the storage, handling, and disposal of solid, hazardous, or toxic wastes and materials.

[51] Examples of building materials and building products typically present at construction sites include asphalt sealants, copper flashing, roofing materials, adhesives, concrete admixtures, and gravel and mulch stockpiles.

precipitation and to stormwater, or (2) a similarly effective means designed to minimize the discharge of pollutants from these areas.

Exception: Minimization of exposure is not required in cases where the exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk of stormwater contamination (such as final products and materials intended for outdoor use).

**b.** *For pesticides, herbicides, insecticides, fertilizers, and landscape materials:*

**i.** In storage areas, provide either (1) cover (e.g., *plastic sheeting, temporary roofs*) to minimize the exposure of these chemicals to precipitation and to stormwater, or (2) a similarly effective means designed to minimize the discharge of pollutants from these areas; and

**ii.** Comply with all application and disposal requirements included on the registered pesticide, herbicide, insecticide, and fertilizer label (see also Part 2.3.5).

**c.** *For diesel fuel, oil, hydraulic fluids, other petroleum products, and other chemicals:* The following requirements apply to the storage and handling of chemicals on your site. If you are already implementing controls as part of an SPCC or other spill prevention plan that meet or exceed the requirements of this Part, you may continue to do so and be considered in compliance with these provisions provided you reference the applicable parts of the SPCC or other plans in your SWPPP as required in Part 7.2.6b.viii.

**i.** If any chemical container has a storage capacity of less than 55 gallons:

(a) The containers must be water-tight, and must be kept closed, sealed, and secured when not being actively used;

(b) If stored outside, use a spill containment pallet or similar device to capture small leaks or spills; and

(c) Have a spill kit available on site that is in good working condition (i.e., not damaged, expired, or used up) and ensure personnel are available to respond immediately in the event of a leak or spill.

**ii.** If any chemical container has a storage capacity of 55 gallons or more:

(a) The containers must be water-tight, and must be kept closed, sealed, and secured when not being actively used;

(b) Store containers a minimum of 50 feet from receiving waters, constructed or natural site drainage features, and storm drain inlets. If infeasible due to site constraints, store containers as far away from these features as the site permits. If site constraints prevent you from storing containers 50 feet away from receiving waters or the other features identified, you must document in your SWPPP the specific reasons why the 50-foot setback is infeasible, and how you will store containers as far away as the site permits;

(c) Provide either (1) cover (e.g., temporary roofs) to minimize the exposure of these containers to precipitation and to stormwater, or (2) secondary containment (e.g., curbing, spill berms, dikes, spill containment pallets, double-wall, above-ground storage tank); and

(d) Have a spill kit available on site that is in good working condition (i.e., not

damaged, expired, or used up) and ensure personnel are available to respond immediately in the event of a leak or spill. Additional secondary containment measures are listed at 40 CFR § 112.7(c)(1).

**iii.** Clean up spills immediately, using dry clean-up methods where possible, and dispose of used materials properly. You are prohibited from hosing the area down to clean surfaces or spills. Eliminate the source of the spill to prevent a discharge or a furtherance of an ongoing discharge.

**d.** *For hazardous or toxic wastes:*[52]

**i.** Separate hazardous or toxic waste from construction and domestic waste;

**ii.** Store waste in sealed containers, constructed of suitable materials to prevent leakage and corrosion, and labeled in accordance with applicable Resource Conservation and Recovery Act (RCRA) requirements and all other applicable Federal, State, Tribal, or local requirements;

**iii.** Store all outside containers within appropriately-sized secondary containment (e.g., *spill berms, dikes, spill containment pallets*) to prevent spills from being discharged, or provide a similarly effective means designed to prevent the discharge of pollutants from these areas *(*e.g., *storing chemicals in a covered area, having a spill kit available on site);*

**iv.** Dispose of hazardous or toxic waste in accordance with the manufacturer's recommended method of disposal and in compliance with Federal, State, Tribal, and local requirements;

**v.** Clean up spills immediately, using dry clean-up methods, and dispose of used materials properly. You are prohibited from hosing the area down to clean surfaces or spills. Eliminate the source of the spill to prevent a discharge or a furtherance of an ongoing discharge; and

**vi.** Follow all other Federal, State, Tribal, and local requirements regarding hazardous or toxic waste.

**e.** *For construction and domestic wastes:*[53]

**i.** Provide waste containers *(*e.g., *dumpster, trash receptacle)* of sufficient size and number to contain construction and domestic wastes;

(a) For waste containers with lids, keep waste container lids closed when not in use, and close lids at the end of the business day and during storm events. For waste containers without lids, provide either (1) cover *(*e.g., *a tarp, plastic sheeting, temporary roof)* to minimize exposure of wastes to precipitation, or (2) a similarly effective means designed to minimize the discharge of pollutants *(*e.g., *secondary containment)*;

(b) On business days, clean up and dispose of waste in designated waste

[52] Examples of hazardous or toxic waste that may be present at construction sites include paints, caulks, sealants, fluorescent light ballasts, solvents, petroleum-based products, wood preservatives, additives, curing compounds, and acids.

[53] Examples of construction and domestic wastes include packaging materials, scrap construction materials, masonry products, timber, pipe and electrical cuttings, plastics, styrofoam, concrete, demolition debris; and other trash or discarded materials.

containers; and

(c) Clean up immediately if containers overflow, and if there is litter elsewhere on the site from escaped trash.

**ii.** Waste containers are not required for the waste remnant or unused portions of construction materials or final products that are covered by the exception in Part 2.2.3a provided that:

(a) These wastes are stored separately from other construction or domestic wastes addressed by Part 2.3.3e.i (i.e., wastes not covered by the exception in Part 2.3.3a). If the wastes are mixed, they must be stored in waste containers as required in Part 2.3.3e.i; and

(b) These wastes are stored in designated areas of the site, the wastes are described in the SWPPP (see Part 7.2.6b.ix), and identified in the site plan (see Part 7.2.4i).

**f.** *For sanitary waste*, position portable toilets so they are secure and will not be tipped or knocked over, and are located away from receiving waters, storm drain inlets, and constructed or natural site drainage features.

**2.3.4 For washing applicators and containers used for stucco, paint, concrete, form release oils, curing compounds, or other materials:**

**a.** Direct wash water into a leak-proof container or leak-proof and lined pit designed so no overflows can occur due to inadequate sizing or precipitation;

**b.** Handle washout or cleanout wastes as follows:

**i.** For liquid wastes:

(a) Do not dump liquid wastes or allow them to enter into constructed or natural site drainage features, storm inlets, or receiving waters;

(b) Do not allow liquid wastes to be disposed of through infiltration or to otherwise be disposed of on the ground;

(c) Comply with applicable State, Tribal, or local requirements for disposal

**ii.** Remove and dispose of hardened concrete waste consistent with your handling of other construction wastes in Part 2.3.3e; and

**c.** Locate any washout or cleanout activities as far away as possible from receiving waters, constructed or natural site drainage features, and storm drain inlets, and, to the extent feasible, designate areas to be used for these activities and conduct such activities only in these areas.

**2.3.5 For the application of fertilizers:**

**a.** Apply at a rate and in amounts consistent with manufacturer's specifications, or document in the SWPPP departures from the manufacturer specifications where appropriate in accordance with Part 7.2.6b.x;

**b.** Apply at the appropriate time of year for your location, and preferably timed to coincide as closely as possible to the period of maximum vegetation uptake and growth;

**c.** Avoid applying before heavy rains that could cause excess nutrients to be discharged;

**d.** Never apply to frozen ground;

**e.** Never apply to constructed or natural site drainage features; and

**f.** Follow all other Federal, State, Tribal, and local requirements regarding fertilizer application.

### 2.3.6 Emergency Spill Notification Requirements

Discharges of toxic or hazardous substances from a spill or other release are prohibited, consistent with Part 1.3.5. Where a leak, spill, or other release containing a hazardous substance or oil in an amount equal to or in excess of a reportable quantity established under either 40 CFR part 110, 40 CFR part 117, or 40 CFR part 302 occurs during a 24-hour period, you must notify the National Response Center (NRC) at (800) 424-8802 or, in the Washington, DC metropolitan area, call (202) 267-2675 in accordance with the requirements of 40 CFR part 110, 40 CFR part 117, and 40 CFR part 302 as soon as you have knowledge of the release. You must also, within seven (7) calendar days of knowledge of the release, provide a description of the release, the circumstances leading to the release, and the date of the release. State, Tribal, or local requirements may necessitate additional reporting of spills or discharges to local emergency response, public health, or drinking water supply agencies.

## 2.4 CONSTRUCTION DEWATERING REQUIREMENTS

Comply with the following requirements to minimize the discharge of pollutants from dewatering[54] operations.

**2.4.1** Route dewatering water through a sediment control (e.g., sediment trap or basin, pumped water filter bag) designed to prevent discharges with visual turbidity; [55]

**2.4.2** Do not discharge visible floating solids or foam;

**2.4.3** The discharge must not cause the formation of a visible sheen on the water surface, or visible oily deposits on the bottom or shoreline of the receiving water. Use an oil-water separator or suitable filtration device (such as a cartridge filter) designed to remove oil, grease, or other products if dewatering water is found to or expected to contain these materials;

**2.4.4** To the extent feasible, use well-vegetated (e.g., grassy or wooded), upland areas of the site to infiltrate dewatering water before discharge.[56] You are prohibited from using receiving waters as part of the treatment area;

**2.4.5** To prevent dewatering-related erosion and related sediment discharges:

**a.** Use stable, erosion-resistant surfaces (e.g., well-vegetated grassy areas, clean filter stone, geotextile underlayment) to discharge from dewatering controls;

---

[54] "Dewatering" is defined in Appendix A as "the act of draining accumulated stormwater and/or ground water from building foundations, vaults, and trenches, or other similar points of accumulation."

[55] For the purposes of this permit, visual turbidity is present where there is a sediment plume in the discharge or the discharge appears cloudy, or opaque, or has a visible contrast that can be identified by an observer.

[56] See footnote 19.

**b.** Do not place dewatering controls, such as pumped water filter bags, on steep slopes (as defined in Appendix A); and

**c.** At all points where dewatering water is discharged, comply with the velocity dissipation requirements of Part 2.2.11.

**2.4.6** For backwash water, either haul it away for disposal or return it to the beginning of the treatment process;

**2.4.7** Replace and clean the filter media used in dewatering devices when the pressure differential equals or exceeds the manufacturer's specifications; and

**2.4.8** Comply with dewatering-specific inspection requirements in Part 4.

## 3 WATER QUALITY-BASED EFFLUENT LIMITATIONS

### 3.1 GENERAL EFFLUENT LIMITATION TO MEET APPLICABLE WATER QUALITY STANDARDS

Discharges must be controlled as necessary to meet applicable water quality standards. Discharges must also comply with any additional State or Tribal requirements that are in Part 9.

In the absence of information demonstrating otherwise, EPA expects that compliance with the conditions in this permit will result in stormwater discharges being controlled as necessary to meet applicable water quality standards. If at any time you become aware, or EPA determines, that discharges are not being controlled as necessary to meet applicable water quality standards, you must take corrective action as required in Parts 5.1 and 5.2, and document the corrective actions as required in Part 5.4.

EPA may insist that you install additional controls (to meet the narrative water quality-based effluent limit above) on a site-specific basis, or require you to obtain coverage under an individual permit, if information in your NOI or from other sources indicates that your discharges are not controlled as necessary to meet applicable water quality standards. This includes situations where additional controls are necessary to comply with a wasteload allocation in an EPA-established or approved TMDL.

If during your coverage under a previous permit, you were required to install and maintain stormwater controls specifically to meet the assumptions and requirements of an EPA-approved or established TMDL (for any parameter) or to otherwise control your discharge to meet water quality standards, you must continue to implement such controls as part of your coverage under this permit.

### 3.2 WATER QUALITY-BASED CONDITIONS FOR SITES DISCHARGING TO CERTAIN IMPAIRED AND HIGH QUALITY RECEIVING WATERS

For any portion of the site that discharges to a sediment or nutrient-impaired water or to a water that is identified by your State, Tribe, or EPA as Tier 2, Tier 2.5, or Tier 3 for antidegradation purposes,[57] you must comply with the inspection frequency specified in Part 4.3 and you must comply with the stabilization deadline specified in Part 2.2.14b.iii.[58]

[57] Refer to Appendix A for definitions of "impaired water" and "Tier 2," "Tier 2.5," and "Tier 3" waters. For assistance in determining whether your site discharges to impaired waters, EPA has developed a tool that is available at https://www.epa.gov/npdes/epas-stormwater-discharge-mapping-tools. For assistance in determining whether your site discharges to a Tier 2, 2.5, or 3 water, refer to the list of such waters at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates.

[58] If you qualify for any of the reduced inspection frequencies in Part 4.4, you may conduct inspections in

If you discharge to a water that is impaired for a parameter other than a sediment-related parameter or nutrients, EPA will inform you if any additional controls are necessary for your discharge to be controlled as necessary to meet water quality standards. These controls might include those necessary for your discharge to be consistent with the assumptions of any available wasteload allocation in any applicable TMDL. In addition, EPA may require you to apply for and obtain coverage under an individual NPDES permit.

In addition, on a case-by-case basis, EPA may notify operators of new sites or operators of existing sites with increased discharges that additional analyses, stormwater controls, and/or other measures are necessary to comply with the applicable antidegradation requirements, or notify you that an individual permit application is necessary.

If you discharge to a water that is impaired for polychlorinated biphenyls (PCBs) and are engaging in demolition of any structure with at least 10,000 square feet of floor space built or renovated before January 1, 1980, you must:

**a.** Implement controls[59] to minimize the exposure of PCB-containing building materials, including paint, caulk, and pre-1980 fluorescent lighting fixtures, to precipitation and to stormwater; and

**b.** Ensure that disposal of such materials is performed in compliance with applicable State, Federal, and local laws.

### 3.3 TURBIDITY BENCHMARK MONITORING FOR SITES DISCHARGING DEWATERING WATER TO PROTECT THE WATER QUALITY OF SENSITIVE WATERS

For sites discharging dewatering water to "sensitive waters" (i.e., receiving waters listed as impaired for sediment or a sediment-related parameter (as defined in Appendix A), or receiving waters designated as a Tier 2, Tier 2.5, or Tier 3 for antidegradation purposes) you are required to comply with the benchmark monitoring requirements in this Part and document the procedures you will use at your site in your SWPPP pursuant to Part 7.2.8. A summary of these requirements is included in Table 1.

EPA notes that the benchmark threshold is not an effluent limitation, rather it is an indicator that the dewatering controls may not be working to protect water quality, which the operator must investigate and correct as appropriate. A benchmark exceedance is not a permit violation. However, if a benchmark exceedance triggers corrective action in Part 5.1.5a, failure to conduct any required action is a permit violation.

Where there are multiple operators associated with the same site, the operators may coordinate with one another to carry out the monitoring requirements of this Part in order to avoid duplicating efforts. Such coordinating arrangements must be described in the SWPPP consistent with Part 7.2.8. Regardless of how the operators divide the

accordance with Part 4.4 for any portion of your site that discharges to a sensitive water.

[59] Examples of controls to minimize exposure of PCBs to precipitation and stormwater include separating work areas from non-work areas and selecting appropriate personal protective equipment and tools, constructing a containment area so that all dust or debris generated by the work remains within the protected area, and using tools that minimize dust and heat (<212°F). For additional information, refer to Part 2.3.3 of the CGP Fact Sheet.

responsibilities for monitoring and reporting, each operator remains responsible for compliance with these requirements.[60]

### 3.3.1 Turbidity monitoring requirements[61]

a. **Sampling frequency.** You must collect at least one turbidity sample from your dewatering discharge each day a discharge occurs.

b. **Sampling location.** Samples must be taken at all points where dewatering water is discharged. Samples must be taken after the dewatering water has been treated by installed treatment devices pursuant to Parts 2.4.1 and 2.4.3 and prior to its discharge off site into a receiving water, constructed or natural site drainage feature, or storm drain inlet.

c. **Representative samples.** Samples taken must be representative of the dewatering discharge for any given day as required in Appendix G (standard permit conditions), Part G.10.2.

d. **Test methods.** Samples must be measured using a turbidity meter that reports results in nephelometric turbidity units (NTUs) and conforms with a Part 136-approved method (e.g., methods 180.1 and 2130). You are required to use the meter, and conduct a calibration verification prior to each day's use, consistent with the manufacturer's instructions.

### 3.3.2 Turbidity benchmark

a. The benchmark threshold for turbidity for this permit is 50 NTUs (referred to elsewhere in this permit as the "standard 50 NTU benchmark") unless EPA has authorized the use of an alternate benchmark in accordance with Part 3.3.2b.

b. **Request for alternate benchmark threshold.**

i. At any time prior to or during your coverage under this permit, you may request that EPA approve a benchmark for your site that is higher than 50 NTUs if you have information demonstrating the higher number is the same as your receiving water's water quality standard for turbidity. Unless EPA approves an alternate benchmark, you will be required to use the standard 50 NTU benchmark. To request approval of an alternate benchmark, you must submit the following information to your applicable EPA Regional Office (see Appendix K):
(a) The current turbidity water quality standard that applies to your receiving

[60] For instance, if Operator A relies on Operator B to meet the Part 3.3.1 turbidity monitoring requirements, the Part 3.3.4 reporting and recordkeeping requirements, and the Part 5.2.2 corrective action provisions when applicable, Operator A does not have to duplicate these same functions if Operator B is implementing them for both operators to be in compliance with the permit. However, Operator A remains responsible for complying with these permit requirements if Operator B fails to take actions that were necessary for Operator A to comply with the permit. See also footnote 83. EPA notes that both Operator A and B are required to submit turbidity monitoring reports as required under Part 3.3.4, however, Operator A's report does not need to include the data collected by Operator B as long as Operator B submits the required data and Operator A's report indicates that it is relying on Operator B to report the data. See Part 3.3.4a.

[61] Operators may find it useful to consult EPA's *Monitoring and Inspection Guide for Construction Dewatering*, available at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates, which provides guidelines on how to correctly monitor for turbidity, determine if the weekly average exceeds the benchmark, and, if so, how to proceed with corrective action.

water and the source/citation.[62]

(b) If the applicable turbidity water quality standard requires information on natural or background turbidity levels (e.g., "no more than 10 NTU above natural turbidity levels") to determine the specific standard for the receiving water, include available data that can be used to establish the natural turbidity levels of your receiving water (including literature studies or Federal, State, Tribal, or local government data). Data must be representative of the natural turbidity levels of your specific receiving water. Identify the source(s) of all data provided, including if the data are from samples you collected of the receiving water.

**ii.** EPA will inform you of its decision on whether to approve the requested alternate benchmark within 30 days. EPA may approve your request, request additional time (e.g., if additional information is needed to substantiate the data you provided), or deny your request. Unless and until EPA approves your request to use an alternate benchmark, you are required to use the standard benchmark of 50 NTUs and take any required corrective actions if an exceedance occurs.

**3.3.3 Comparison of turbidity samples to benchmark.** Compare the weekly average[63] of your turbidity monitoring results to the standard 50 NTU benchmark, or alternate benchmark if approved by EPA.

**a.** If the weekly average of your turbidity monitoring results exceeds the standard benchmark (or your approved alternate benchmark), you are required to conduct follow-up corrective action in accordance with Part 5.2.2 and document any corrective action taken in your corrective action log in accordance with Part 5.4.

**b.** For averaging purposes, a "monitoring week" starts with a Monday and ends on Sunday. Once a new monitoring week starts, you will need to calculate a new average for that week of turbidity monitoring results.[64] A weekly average may consist of one or more turbidity monitoring results.

**c.** Although you are not required to collect and analyze more than one turbidity sample per day from your dewatering discharge, if you do collect and analyze more than one sample on any given day, you must include any additional results in the

[62] For instance, if your site is located in Washington, DC, and you are discharging to a Class B water, for which the water quality standard is that turbidity may not increase above ambient levels by more than 20 percent, you would reference "Water Quality Standards for the District of Columbia, Chapter 11, Section 1104.8."

[63] A "weekly average" is defined as the sum of all of the turbidity samples taken during a "monitoring week" divided by the number of samples measured during that week. Average values should be calculated to the nearest whole number.

[64] For example, if turbidity samples from your dewatering discharge in week 1 result in values of 30 NTU on Tuesday, 40 NTU on Wednesday, and 45 NTU on Thursday, your weekly average turbidity value would be 38.33 NTU ((30+40+45) ÷ 3 = 38 NTU). If in week 2, your turbidity samples resulted in values of 45 NTU on Monday, 30 NTU on Tuesday, 25 NTU on Wednesday, and 15 NTU on Thursday, you would calculate a new average for that week, which would yield an average turbidity value of 28.75 NTU ((45+30+25+15) ÷ 4 = 29 NTU). By comparison, if your samples on consecutive days from Friday to Monday were 60 NTU, 45 NTU, 40 NTU, and 43 NTU, respectively, and there are no other dewatering discharges for the remainder of the week, you would calculate one weekly average for the Friday to Sunday to be 48 NTU ((60+45+40) ÷ 3 = 48 NTU), and a separate weekly average for the one Monday to be 43 NTU (43 ÷ 1 = 43 NTU).

calculation of your weekly average (i.e., add all individual results for that monitoring week and divide by the total number of samples).[65]

**d.** If you are conducting turbidity monitoring for more than one dewatering discharge point, you must calculate a weekly average turbidity value for each discharge point and compare each to the turbidity benchmark.

### 3.3.4 Reporting and recordkeeping.

**a.** You must submit reports of your weekly average turbidity data to EPA no later than 30 days following the end of each monitoring quarter. If there are monitoring weeks in which there was no dewatering discharge, or if there is a monitoring quarter with no dewatering discharge, indicate this in your turbidity monitoring report. If another operator associated with your same site is conducting turbidity monitoring on your behalf pursuant to Part 3.3, indicate this in your turbidity monitoring report.

**b.** For the purposes of this permit, the following monitoring quarters and reporting deadlines apply:

***Table 3. Monitoring Quarters and Deadlines for Reporting Turbidity Benchmark Monitoring Data.***

| **Monitoring Quarter #** | **Months** | **Reporting Deadline** (no later than 30 days after end of the monitoring quarter) |
|---|---|---|
| 1 | January 1 – March 31 | April 30 |
| 2 | April 1 – June 30 | July 30 |
| 3 | July 1 – September 30 | October 30 |
| 4 | October 1 – December 31 | January 30 |

**c.** You must use EPA's NPDES eReporting Tool (NeT) to electronically submit your quarterly turbidity data, unless, consistent with Part 1.4.2, you received a waiver from your applicable EPA Regional Office. If the EPA Regional Office grants you approval to use a paper turbidity monitoring report form, and you elect to use it, you must complete the form in Appendix K. If EPA approves of your request to use an alternate turbidity benchmark pursuant to Part 3.3.2b, EPA will substitute the alternate benchmark in your NeT account.

**d.** For each day in which you are required to monitor, you must record the monitoring information required by Appendix G, Parts G.10.2 and G.10.3 and retain all such information for a period of at least three years from the date this permit expires or from the date your authorization is terminated.

[65] For example, if during a monitoring week you take two turbidity samples on Tuesday with a value of 30 NTU and 35 NTU, three samples on Wednesday with a value of 40 NTU, 45 NTU, and 48 NTU, and one sample on Thursday with a value of 45 NTU, your weekly average turbidity value for this week would be 41 NTU ((30+35+40+45+48+45) ÷ 6 = 41 NTU).

***Table 4. Summary of Turbidity Benchmark Monitoring Requirements.***

| Applicability | Sampling Requirement | Turbidity Benchmark | Corrective Action | Reporting |
|---|---|---|---|---|
| Sites discharging dewatering water to a sediment-impaired water or to a water designated as a Tier 2, Tier 2.5, or Tier 3 for antidegradation purposes. | Collect at least one turbidity sample per day, from each discharge point, on any day there is a dewatering discharge.<br>Use turbidity sampling procedures specified in Part 3.3.1. | Compare the weekly average of your turbidity monitoring results to the 50 NTU benchmark (or alternate benchmark if approved by EPA). | If the weekly average of turbidity monitoring results exceeds the 50 NTU turbidity benchmark (or alternate benchmark if approved by EPA), you are required to take follow-up corrective action in accordance with Part 5.2.2. | Report all weekly average turbidity monitoring results on a quarterly basis via NeT-CGP (unless use of the paper monitoring form in Appendix K is approved by EPA) no later than 30 days following the end of each monitoring quarter. |

## 4 INSPECTION REQUIREMENTS

### 4.1 PERSON(S) RESPONSIBLE FOR CONDUCTING SITE AND DEWATERING INSPECTIONS

The person(s) inspecting your site may be a person on your staff or a third party you hire to conduct such inspections. You are responsible for ensuring that any person conducting inspections pursuant to this Part is a "qualified person." A qualified person is someone who has completed the training required by Part 6.3.

### 4.2 FREQUENCY OF INSPECTIONS.[66]

At a minimum, you must conduct a site inspection in accordance with one of the two schedules listed below, unless you are subject to the Part 4.3 site inspection frequency for discharges to sediment or nutrient-impaired or high quality waters, or qualify for a Part 4.4 reduction in the inspection frequency:

**4.2.1** At least once every seven (7) calendar days; *or*

**4.2.2** Once every 14 calendar days *and* within 24 hours[67] of the occurrence of:

- **a.** A storm event that produces 0.25 inches or more of rain within a 24-hour period.
  - **i.** If a storm event produces 0.25 inches or more of rain within a 24-hour period (including when there are multiple, smaller storms that alone produce less than 0.25 inches but together produce 0.25 inches or more in 24 hours), you are required to conduct one inspection within 24 hours of when 0.25 inches of rain or more has fallen.

[66] Inspections are only required during the site's normal working hours.

[67] For the purposes of the inspection requirements in this Part, conducting an inspection "within 24 hours" means that once either of the two conditions in Parts 4.2.2a or 4.2.2b are met you have 24 hours from that time to conduct an inspection. For clarification, the 24 hours is counted as a continuous passage of time, and not counted by business hours (e.g., 3 business days of 8 hours each). When the 24-hour inspection time frame occurs entirely outside of normal working hours, you must conduct an inspection by no later than the end of the next business day.

**ii.** If a storm event produces 0.25 inches or more of rain within a 24-hour period on the first day of a storm and continues to produce 0.25 inches or more of rain on subsequent days, you must conduct an inspection within 24 hours of the first day of the storm and within 24 hours after the last day of the storm that produces 0.25 inches or more of rain (i.e., only two inspections would be required for such a storm event).[68]

**b.** A discharge caused by snowmelt from a storm event that produces 3.25 inches[69] or more of snow within a 24-hour period. You are required to conduct one inspection once the discharge of snowmelt from a 3.25-inch or more snow accumulation occurs. Additional snowmelt inspections are only required if following the discharge from the first snowmelt, there is a discharge from a separate storm event that produces 3.25 inches or more of snow.

**4.2.3** To determine whether a storm event meets either of the thresholds in Parts 4.2.2a or 4.2.2b:

**a.** For rain, you must either keep a properly maintained rain gauge on your site, or obtain the storm event information from a weather station that is representative of your location. For any 24-hour period during which there is 0.25 inches or more of rainfall, you must record the total rainfall measured for that day in accordance with Part 4.7.1d.

**b.** For snow, you must either take measurements of snowfall at your site,[70] or rely on similar information from a local weather forecasting provider that is representative of your location.

**4.3 INCREASE IN INSPECTION FREQUENCY FOR CERTAIN SITES.**

The increased inspection frequencies established in this Part take the place of the Part 4.2 inspection frequencies for the portion of the site affected.

**4.3.1 For any portion of the site that discharges to a sediment or nutrient-impaired water or to a water that is identified by your State, Tribe, or EPA as Tier 2, Tier 2.5, or Tier 3 for antidegradation purposes (see Part 3.2),** you must conduct an once every seven (7) calendar days *and* within 24 hours of the occurrence of a storm event that produces 0.25 inches or more of rain within a 24-hour period, or within 24 hours of a snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period.

[68] For example, if 0.30 inches of rain falls on Day 1, 0.25 inches of rain falls on Day 2, and 0.10 inches of rain fall on Day 3, you would be required to conduct a first inspection within 24 hours of the Day 1 rainfall and a second inspection within 24 hours of the Day 2 rainfall, but a third inspection would not be required within 24 hours of the Day 3 rainfall.

[69] This is the amount of snow that is equivalent to 0.25 inches of rain, based on information from the National Oceanic and Atmospheric Administration (NOAA) indicating that 13 inches of snow is, on average, equivalent to 1 inch of rain. See https://www.nssl.noaa.gov/education/svrwx101/winter/faq/.

[70] For snowfall measurements, EPA suggests use of NOAA's National Weather Service guidelines at https://www.weather.gov/jkl/snow_measurement. These guidelines recommend use of a "snowboard" (a piece of wood about 16 inches by 16 inches) that is placed in an unobstructed part of the site on a hard surface.

Refer to Parts 4.2.3a and 4.2.3b for the requirements to determine if a storm event produces enough rain or snow to trigger the inspection requirement.

**4.3.2 For sites discharging dewatering water,** you must conduct an inspection in accordance with Part 4.6.3 during the discharge once per day on which the discharge occurs. The Part 4.2 inspection frequency still applies to all other portions of the site, unless the site is affected by either the increased frequency in Part 4.3.1 or the reduced frequency in Part 4.4.

## 4.4 REDUCTIONS IN INSPECTION FREQUENCY

### 4.4.1 Stabilized areas.

**a.** You may reduce the frequency of inspections to twice per month for the first month, no more than 14 calendar days apart, then once per month until permit coverage is terminated consistent with Part 8 in any area of your site where the stabilization steps in Part 2.2.14a have been completed. If construction activity resumes in this portion of the site at a later date, the inspection frequency immediately increases to that required in Parts 4.2 and 4.3, as applicable. You must document the beginning and ending dates of this period in your SWPPP.

**b. Exception.** For "linear construction sites" (as defined in Appendix A) where disturbed portions have undergone final stabilization at the same time active construction continues on others, you may reduce the frequency of inspections to twice per month for the first month, no more than 14 calendar days apart, in any area of your site where the stabilization steps in Part 2.2.14a have been completed. After the first month, inspect once more within 24 hours of the occurrence of a storm event that produces 0.25 inches of rain or more within a 24-hour period, or within 24 hours of a snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period. If there are no issues or evidence of stabilization problems, you may suspend further inspections. If "wash-out" of stabilization materials and/or sediment is observed, following re-stabilization, inspections must resume at the inspection frequency required in Part 4.4.1a. Inspections must continue until final stabilization is visually confirmed following a storm event that produces 0.25 inches of rain or more within a 24-hour period.

**4.4.2 Arid, semi-arid, or drought-stricken areas** (as defined in Appendix A). If it is the seasonally dry period[71] or a period in which drought is occurring, you may reduce the frequency of inspections to once per month and within 24 hours of the occurrence of a storm event that produces 0.25 inches of rain or more within a 24-hour period, or within 24 hours of a snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period. You must document that you are using this reduced schedule and the beginning and ending dates of the seasonally dry period in your SWPPP. Follow the procedures in Part 4.2.3a and 4.2.3b, accordingly, to determine if a storm event occurs that produces 0.25 inches or more of rain or 3.25 inches or more of snow within a 24-hour period. For any 24-hour period during which there is 0.25 inches or more of rainfall, or 3.25 inches or more of snow, you must record the total rainfall or snow measured for that day in accordance with Part 4.7.1d.

[71] See footnote 44.

**4.4.3 Frozen conditions:**

**a.** If you are suspending construction activities due to frozen conditions, you may temporarily suspend inspections on your site until thawing conditions (as defined in Appendix A) begin to occur if:

**i.** Discharges are unlikely due to continuous frozen conditions that are likely to continue at your site for at least three (3) months based on historic seasonal averages.[72] If unexpected weather conditions (such as above freezing temperatures or rain events) make discharges likely, you must immediately resume your regular inspection frequency as described in Parts 4.2 and 4.3, as applicable;

**ii.** Land disturbances have been suspended; and

**iii.** All disturbed areas of the site have been stabilized in accordance with Part 2.2.14a.

**b.** If you are still conducting construction activities during frozen conditions, you may reduce your inspection frequency to once per month if:

**i.** Discharges are unlikely due to continuous frozen conditions that are likely to continue at your site for at least three (3) months based on historic seasonal averages. If unexpected weather conditions (such as above freezing temperatures or rain events) make discharges likely, you must immediately resume your regular inspection frequency as described in Parts 4.2 and 4.3, as applicable; and

**ii.** Except for areas in which you are actively conducting construction activities, disturbed areas of the site have been stabilized in accordance with Part 2.2.14a.

You must document the beginning and ending dates of this period in your SWPPP.

**4.5 AREAS THAT MUST BE INSPECTED**

During your site inspection, you must at a minimum inspect the following areas of your site:

**4.5.1** All areas that have been cleared, graded, or excavated and that have not yet completed stabilization consistent with Part 2.2.14a;

**4.5.2** All stormwater controls, including pollution prevention controls, installed at the site to comply with this permit;[73]

**4.5.3** Material, waste, borrow, and equipment storage and maintenance areas that are covered by this permit;

**4.5.4** All areas where stormwater typically flows within the site, including constructed or natural site drainage features designed to divert, convey, and/or treat stormwater;

**4.5.5** All areas where construction dewatering is taking place, including controls to treat the dewatering discharge and any channelized flow of water to and from those controls;

[72] Use data sets that include the most recent data available to account for recent precipitation patterns and trends.

[73] This includes the requirement to inspect for sediment that has been tracked out from the site onto paved roads, sidewalks, or other paved areas consistent with Part 2.2.4.

**4.5.6** All points of discharge from the site; and

**4.5.7** All locations where stabilization measures have been implemented.

You are not required to inspect areas that, at the time of the inspection, are considered unsafe to your inspection personnel.

**4.6 REQUIREMENTS FOR INSPECTIONS**

**4.6.1** During each site inspection, you must at a minimum:

**a.** Check whether all stormwater controls *(*i.e.*, erosion and sediment controls and pollution prevention controls)* are properly installed, appear to be operational, and are working as intended to minimize pollutant discharges.

**b.** Check for the presence of conditions that could lead to spills, leaks, or other accumulations of pollutants on the site.

**c.** Identify any locations where new or modified stormwater controls are necessary to meet the requirements of Parts 2 and/or 3.

**d.** Check for signs of visible erosion and sedimentation *(*i.e.*, sediment deposits)* that have occurred and are attributable to your discharge at points of discharge and, if applicable, on the banks of any receiving waters flowing within or immediately adjacent to the site;

**e.** Check for signs of sediment deposition that are visible from your site and attributable to your discharge (e.g., sand bars with no vegetation growing on top in receiving waters or in other constructed or natural site drainage features, or the buildup of sediment deposits on nearby streets, curbs, or open conveyance channels).

**f.** Identify any incidents of noncompliance observed.

**4.6.2** If a discharge is occurring during your inspection:

**a.** Identify all discharge points at the site; and

**b.** Observe and document the visual quality of the discharge, and take note of the characteristics of the stormwater discharge, including color; odor; floating, settled, or suspended solids; foam; oil sheen; and other indicators of stormwater pollutants. Check also for signs of these same pollutant characteristics that are visible from your site and attributable to your discharge in receiving waters or in other constructed or natural site drainage features.

**4.6.3** For dewatering inspections conducted pursuant to Parts 4.3.2, record the following in a report within 24 hours of completing the inspection:

**a.** The inspection date;

**b.** Names and titles of personnel making the inspection;

**c.** Approximate times that the dewatering discharge began and ended on the day of inspection;[74]

**d.** Estimates of the rate (in gallons per day) of discharge on the day of inspection;

[74] If the dewatering discharge is a continuous discharge that continues after normal business hours, indicate that the discharge is continuous.

**e.** Whether or not any of the following indications of pollutant discharge were observed at the point of discharge to any receiving waters flowing through or immediately adjacent to the site and/or to constructed or natural site drainage features or storm drain inlets:[75]

**i.** a sediment plume, suspended solids, unusual color, presence of odor, decreased clarity, or presence of foam; and/or

**ii.** a visible sheen on the water surface or visible oily deposits on the bottom or shoreline of the receiving water; and

**f.** Photographs of (1) the dewatering water prior to treatment by a dewatering control(s) and the final discharge after treatment; (2) the dewatering control(s); and (3) the point of discharge to any receiving waters flowing through or immediately adjacent to the site and/or to constructed or natural site drainage features, storm drain inlets, and other conveyances to receiving waters.

You must also comply with the Part 4.7.2, 4.7.3, and 4.7.4 requirements for signing the reports, keeping them available on site, and retaining copies.

**4.6.4** Based on the results of your inspection:

**a.** Complete any necessary maintenance repairs or replacements under Part 2.1.4 or under Part 5, whichever applies; and

**b.** Modify your SWPPP site map in accordance with Part 7.4.1 to reflect changes to your stormwater controls that are no longer accurately reflected on the current site map.

### 4.7 INSPECTION REPORT

**4.7.1** You must complete an inspection report within 24 hours of completing any site inspection. Each inspection report (except for dewatering inspection reports, which are covered in Part 4.6.3) must include the following:

**a.** The inspection date;

**b.** Names and titles of personnel making the inspection;

**c.** A summary of your inspection findings, covering at a minimum the observations you made in accordance with Part 4.6, including any problems found during your inspection that make it necessary to perform routine maintenance pursuant to Part 2.1.4b or corrective action pursuant to Part 5. Include also any documentation as to why the corrective action procedures under Part 5 are unnecessary to fix a problem that repeatedly occurs as described in Part 2.1.4c;

**d.** If you are inspecting your site at the frequency specified in Part 4.2.2, Part 4.3, or Part 4.4.1b, and you conducted an inspection because of a storm event that produced rainfall measuring 0.25 inches or more within a 24-hour period, you must include the applicable rain gauge or weather station readings that triggered the inspection. Similarly, if you conducted an inspection because of a snowmelt discharge from a storm event that produced 3.25 inches or more of snow within a 24-hour period, you must include any measurements taken of snowfall at your site, or weather station information you relied on; and

[75] If the operator observes any of these indicators of pollutant discharge, corrective action is required consistent with Parts 5.1.5b and 5.2.2.

**e.** If you determined that it is unsafe to inspect a portion of your site, you must describe the reason you found it to be unsafe and specify the locations to which this condition applies.

**4.7.2** Each inspection report must be signed by the operator's signatory in accordance with Appendix G, Part G.11 of this permit.

**4.7.3** You must keep a copy of all inspection reports at the site or at an easily accessible location, so that it can be made immediately available at the time of an on-site inspection or upon request by EPA.[76]

**4.7.4** You must retain all inspection reports completed for this Part for at least three (3) years from the date that your permit coverage expires or is terminated.

### 4.8 INSPECTIONS BY EPA

You must allow EPA, or an authorized representative of EPA, to conduct the following activities at reasonable times. To the extent that you are utilizing shared controls, that are not on site, to comply with this permit, you must make arrangements for EPA to have access at all reasonable times to those areas where the shared controls are located.

**4.8.1** Enter onto all areas of the site, including any construction support activity areas covered by this permit, any off-site areas where shared controls are utilized to comply with this permit, discharge locations, adjoining waterbodies, and locations where records are kept under the conditions of this permit;

**4.8.2** Access and copy any records that must be kept under the conditions of this permit;

**4.8.3** Inspect your construction site, including any construction support activity areas covered by this permit (see Part 1.2.1c), any stormwater controls installed and maintained at the site, and any off-site shared controls utilized to comply with this permit; and

**4.8.4** Sample or monitor for the purpose of ensuring compliance.

## 5 CORRECTIVE ACTIONS

### 5.1 CONDITIONS TRIGGERING CORRECTIVE ACTION.

You must take corrective action to address any of the following conditions identified at your site:

**5.1.1** A stormwater control needs a significant repair or a new or replacement control is needed, or, in accordance with Part 2.1.4c, you find it necessary to repeatedly (i.e., three (3) or more times) conduct the same routine maintenance fix to the same control at the same location (unless you document in your inspection report under Part 4.7.1c that the specific reoccurrence of this same problem should still be addressed as a routine maintenance fix under Part 2.1.4); or

**5.1.2** A stormwater control necessary to comply with the requirements of this permit was never installed, or was installed incorrectly; or

[76] Inspection reports may be prepared, signed, and kept electronically, rather than in paper form, if the records are: (a) in a format that can be read in a similar manner as a paper record; (b) legally dependable with no less evidentiary value than their paper equivalent; and (c) immediately accessible to the inspector during an inspection to the same extent as a paper copy stored at the site would be, if the records were stored in paper form. For additional guidance on the proper practices to follow for the electronic retention of inspection report records, refer to the Fact Sheet discussion related to Part 4.7.3.

**5.1.3** Your discharges are not meeting applicable water quality standards;

**5.1.4** A prohibited discharge has occurred (see Part 1.3); or

**5.1.5** During discharge from site dewatering activities:

**a.** The weekly average of your turbidity monitoring results exceeds the 50 NTU benchmark (or alternate benchmark if approved by EPA pursuant to Part 3.3.2b); or

**b.** You observe or you are informed by EPA, State, or local authorities of the presence of the conditions specified in Part 4.6.3e.

### 5.2 CORRECTIVE ACTION DEADLINES

**5.2.1** If responding to any of the Part 5.1.1, 5.1.2, 5.1.3, or 5.1.4 triggering conditions, you must:

**a.** Immediately take all reasonable steps to address the condition, including cleaning up any contaminated surfaces so the material will not discharge in subsequent storm events; and

**b.** When the problem does not require a new or replacement control or significant repair, the corrective action must be completed by the close of the next business day; or

**c.** When the problem requires a new or replacement control or significant repair, install the new or modified control and make it operational, or complete the repair, by no later than seven (7) calendar days from the time of discovery. If it is infeasible to complete the installation or repair within seven (7) calendar days, you must document in your records why it is infeasible to complete the installation or repair within the 7-day timeframe and document your schedule for installing the stormwater control(s) and making it operational as soon as feasible after the 7-day timeframe. Where these actions result in changes to any of the stormwater controls or procedures documented in your SWPPP, you must modify your SWPPP accordingly within seven (7) calendar days of completing this work.

**5.2.2** If responding to either of the Part 5.1.5 triggering conditions related to site dewatering activities, you must:

**a.** Immediately take all reasonable steps to minimize or prevent the discharge of pollutants until you can implement a solution, including shutting off the dewatering discharge as soon as possible depending on the severity of the condition[77] taking safety considerations into account;

**b.** Determine whether the dewatering controls are operating effectively and whether they are causing the conditions; and

**c.** Make any necessary adjustments, repairs, or replacements to the dewatering controls to lower the turbidity levels below the benchmark or remove the visible plume or sheen.

[77] For instance, if the weekly average of your turbidity monitoring results or a single sample is extremely high (e.g., a single turbidity sample results in 355 NTUs or higher), you should take action to safely shut off the discharge so that you can evaluate the cause of the high turbidity. Note: A single turbidity sample of 355 NTUs or higher means that the weekly average turbidity value will exceed 50 NTU regardless of the turbidity values the other days during the week.

When you have completed these steps and made any changes deemed necessary, you may resume discharging from your dewatering activities.

### 5.3 CORRECTIVE ACTION REQUIRED BY EPA

You must comply with any corrective actions required by EPA as a result of permit violations found during an inspection carried out under Part 4.8.

### 5.4 CORRECTIVE ACTION LOG

**5.4.1** For each corrective action taken in accordance with this Part, you must record the following in a corrective action log:

- **a.** Within 24 hours of identifying the corrective action condition, document the specific condition and the date and time it was identified.
- **b.** Within 24 hours of completing the corrective action (in accordance with the deadlines in Part 5.2), document the actions taken to address the condition, including whether any SWPPP modifications are required.

**5.4.2** Each entry into the corrective action log, consisting of the information required by both Parts 5.4.1a and 5.4.1b, must be signed by the operator's signatory in accordance with Appendix G, Part G.11.2 of this permit.

**5.4.3** You must keep a copy of the corrective action log at the site or at an easily accessible location, so that it can be made immediately available at the time of an on-site inspection or upon request by EPA.[78]

**5.4.4** You must retain the corrective action log for at least three (3) years from the date that your permit coverage expires or is terminated.

## 6 STORMWATER TEAM FORMATION/STAFF TRAINING REQUIREMENTS

### 6.1 STORMWATER TEAM

Each operator, or group of multiple operators, must assemble a "stormwater team" that will be responsible for carrying out activities necessary to comply with this permit. The stormwater team must include the following people:

- **a.** Personnel who are responsible for the design, installation, maintenance, and/or repair of stormwater controls (including pollution prevention controls);
- **b.** Personnel responsible for the application and storage of treatment chemicals (if applicable);
- **c.** Personnel who are responsible for conducting inspections as required in Part 4.1; and
- **d.** Personnel who are responsible for taking corrective actions as required in Part 5.

Members of the stormwater team must be identified in the SWPPP pursuant to Part 7.2.2.

[78] The corrective action log may be prepared, signed, and kept electronically, rather than in paper form, if the records are: (a) in a format that can be read in a similar manner as a paper record; (b) legally dependable with no less evidentiary value than their paper equivalent; and (c) immediately accessible to the inspector during an inspection to the same extent as a paper copy stored at the site would be, if the records were stored in paper form. For additional guidance on the proper practices to follow for the electronic retention of corrective action log records, refer to the Fact Sheet discussion related to Part 4.7.3.

### 6.2 GENERAL TRAINING REQUIREMENTS FOR STORMWATER TEAM MEMBERS

Prior to the commencement of construction activities, you must ensure that all persons[79] assigned to the stormwater team understand the requirements of this permit and their specific responsibilities with respect to those requirements, including the following related to the scope of their job duties:

**a.** The permit requirements and deadlines associated with installation, maintenance, and removal of stormwater controls, as well as site stabilization;

**b.** The location of all stormwater controls on the site required by this permit and how they are to be maintained;

**c.** The proper procedures to follow with respect to the permit's pollution prevention requirements; and

**d.** When and how to conduct inspections, record applicable findings, and take corrective actions. Specific training requirements for persons conducting site inspections are included in Part 6.3.

You are responsible for ensuring that all activities on the site comply with the requirements of this permit. You are not required to provide or document formal training for subcontractors or other outside service providers (unless the subcontractors or outside service providers are responsible for conducting the inspections required in Part 4, in which case you must provide such documentation consistent with Part 7.2.2), but you must ensure that such personnel understand any requirements of this permit that may be affected by the work they are subcontracted to perform.

### 6.3 TRAINING REQUIREMENTS FOR PERSONS CONDUCTING INSPECTIONS

For projects that receive coverage under this permit on or after February 17, 2023, to be considered a qualified person under Part 4.1 for conducting inspections under Part 4, you must, at a minimum, either:

**a.** Have completed the EPA construction inspection course developed for this permit and have passed the exam; or

**b.** Hold a current valid construction inspection certification or license from a program that, at a minimum, covers the following:[80]

- **i.** Principles and practices of erosion and sediment control and pollution prevention practices at construction sites;
- **ii.** Proper installation and maintenance of erosion and sediment controls and pollution prevention practices used at construction sites; and
- **iii.** Performance of inspections, including the proper completion of required reports and documentation, consistent with the requirements of Part 4.

[79] If the person requiring training is a new employee who starts after you commence construction activities, you must ensure that this person has the proper understanding as required above prior to assuming particular responsibilities related to compliance with this permit. For emergency-related projects, the requirement to train personnel prior to commencement of construction activities does not apply, however, such personnel must have the required training prior to NOI submission.

[80] If one of the following topics (e.g., installation and maintenance of pollution prevention practices) is not covered by the non-EPA training program, you may consider supplementing the training with the analogous module of the EPA course (e.g., Module 4) that covers the missing topic.

For projects that receive coverage under this permit prior to February 17, 2023, any personnel conducting site inspections pursuant to Part 4 on your site must, at a minimum, be a person knowledgeable in the principles and practice of erosion and sediment controls and pollution prevention, who possesses the appropriate skills and training to assess conditions at the construction site that could impact stormwater quality, and the appropriate skills and training to assess the effectiveness of any stormwater controls selected and installed to meet the requirements of this permit.[81]

### 6.4 STORMWATER TEAM'S ACCESS TO PERMIT DOCUMENTS

Each member of the stormwater team must have easy access to an electronic or paper copy of applicable portions of this permit, the most updated copy of your SWPPP, and other relevant documents or information that must be kept with the SWPPP.

## 7 STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

### 7.1 GENERAL REQUIREMENTS

All operators associated with a construction site under this permit must develop a SWPPP consistent with the requirements in Part 7 prior to their submittal of the NOI.[82, 83, 84] The SWPPP must be kept up-to-date throughout coverage under this permit.

If a SWPPP was prepared under a previous version of this permit, the operator must review and update the SWPPP to ensure that this permit's requirements are addressed prior to submitting an NOI for coverage under this permit.

### 7.2 SWPPP CONTENTS

At a minimum, the SWPPP must include the information specified in this Part and as specified in other parts of this permit.

**7.2.1 All Site Operators.** Include a list of all other operators who will be engaged in construction activities at the site, and the areas of the site over which each operator has control.

[81] If you receive coverage for a project prior to February 17, 2023, and construction activities for the same project will continue after February 17, 2023, the personnel conducting inspections do not need to take the additional training specified in Parts 6.3a and 6.3b for inspections conducted on the project site. If the same operator obtains coverage for a different project on or after February 17, 2023, personnel conducting inspections would be required to meet the requirements for a qualified person by completing the training in either Part 6.3a or Part 6.3b.

[82] The SWPPP does not establish the effluent limits and/or other permit terms and conditions that apply to your site's discharges; these limits, terms, and conditions are established in this permit.

[83] Where there are multiple operators associated with the same site, they may develop a group SWPPP instead of multiple individual SWPPPs. Regardless of whether there is a group SWPPP or multiple individual SWPPPs, each operator is responsible for compliance with the permit's terms and conditions. In other words, if Operator A relies on Operator B to satisfy its permit obligations, Operator A does not have to duplicate those permit-related functions if Operator B is implementing them such that both operators are in compliance with the permit. However, Operator A remains responsible for permit compliance if Operator B fails to take actions necessary for Operator A to comply with the permit. In addition, all operators must ensure, either directly or through coordination with other operators, that their activities do not cause a violation or compromise any other operators' controls and/or any shared controls. See also footnote 60.

[84] There are a number of commercially available products to assist operators in developing the SWPPP, as well as companies that can be hired to help develop a site-specific SWPPP. The permit does not state which are recommended, nor does EPA endorse any specific products or vendors. Where operators choose to rely on these products or services, the choice of which ones to use to comply with the requirements of this Part is a decision for the operator alone.

**7.2.2 Stormwater Team.** Identify the personnel (by name and position) that you have made part of the stormwater team pursuant to Part 6.1, as well as their individual responsibilities, including which members are responsible for conducting inspections.

Include verification that each member of the stormwater team has received the training required by Part 6.2. Include documentation that members of the stormwater team responsible for conducting inspections pursuant to Part 4 have received the training required by Part 6.3. If personnel on your team elect to complete the EPA inspector training program pursuant to Part 6.3a, you must include copies of the certificate showing that the relevant personnel have completed the training and passed the exam. If personnel on your team elect to complete a non-EPA inspector training program pursuant to Part 6.3b, you must include documentation showing that these persons have successfully completed the program and their certification or license is still current. You must also confirm that the non-EPA inspector training program satisfies the minimum elements for such programs in Part 6.3b.

**7.2.3 Nature of Construction Activities**. Include the following:

- **a.** A description of the nature of your construction activities, including the age or dates of past renovations for structures that are undergoing demolition;
- **b.** The size of the property (in acres or length in miles if a linear construction site);
- **c.** The total area expected to be disturbed by the construction activities (to the nearest quarter acre or nearest quarter mile if a linear construction site);
- **d.** A description of any on-site and off-site construction support activity areas covered by this permit (see Part 1.2.1c);
- **e.** The maximum area expected to be disturbed at any one time, including on-site and off-site construction support activity areas;
- **f.** A description and projected schedule for the following:[85]
  - **i.** Commencement of construction activities in each portion of the site, including clearing and grubbing, mass grading, demolition activities, site preparation (i.e., excavating, cutting and filling), final grading, and creation of soil and vegetation stockpiles requiring stabilization;
  - **ii.** Temporary or permanent cessation of construction activities in each portion of the site;
  - **iii.** Temporary or final stabilization of exposed areas for each portion of the site; and
  - **iv.** Removal of temporary stormwater controls and construction equipment or vehicles, and the cessation of construction-related pollutant-generating activities.

[85] If plans change due to unforeseen circumstances or for other reasons, the requirement to describe the sequence and estimated dates of construction activities is not meant to "lock in" the operator to meeting these dates. When departures from initial projections are necessary, this should be documented in the SWPPP itself, or in associated records, as appropriate.

**g.** A list and description of all pollutant-generating activities[86] on the site. For each pollutant-generating activity, include an inventory of pollutants or pollutant constituents (e.g., *sediment, fertilizers, pesticides, paints, caulks, sealants, fluorescent light ballasts, contaminated substrates, solvents, fuels*) associated with that activity, which could be discharged in stormwater from your construction site. You must take into account where potential spills and leaks could occur that contribute pollutants to stormwater discharges, and any known hazardous or toxic substances, such as PCBs and asbestos, that will be disturbed or removed during construction;

**h.** Business days and hours for the project;

**i.** If you are conducting construction activities in response to a public emergency (see Part 1.4), a description of the cause of the public emergency *(*e.g., *mud slides, earthquake, extreme flooding conditions, widespread disruption in essential public services)*, information substantiating its occurrence *(*e.g., *State disaster declaration or similar State or local declaration)*, and a description of the construction necessary to reestablish affected public services.

**7.2.4 Site Map.** Include a legible map, or series of maps, showing the following features of the site:

**a.** Boundaries of the property;

**b.** Locations where construction activities will occur, including:

**i.** Locations where earth-disturbing activities will occur (note any phasing), including any demolition activities;

**ii.** Approximate slopes before and after major grading activities (note any steep slopes (as defined in Appendix A));

**iii.** Locations where sediment, soil, or other construction materials will be stockpiled;

**iv.** Any receiving water crossings;

**v.** Designated points where vehicles will exit onto paved roads;

**vi.** Locations of structures and other impervious surfaces upon completion of construction; and

**vii.** Locations of on-site and off-site construction support activity areas covered by this permit (see Part 1.2.1c).

**c.** Locations of any receiving waters within the site and all receiving waters within one mile downstream of the site's discharge point(s). Also identify if any of these receiving waters are listed as impaired or are identified as a Tier 2, Tier 2.5, or Tier 3 water;

**d.** Any areas of Federally listed critical habitat within the action area of the site as defined in Appendix A;

**e.** Type and extent of pre-construction cover on the site (e.g., vegetative cover, forest, pasture, pavement, structures);

**f.** Drainage patterns of stormwater and authorized non-stormwater before and after major grading activities;

[86] Examples of pollutant-generating activities include paving operations; concrete, paint, and stucco washout and waste disposal; solid waste storage and disposal; and dewatering activities.

**g.** Stormwater and authorized non-stormwater discharge locations, including:

**i.** Locations where stormwater and/or authorized non-stormwater will be discharged to storm drain inlets, including a notation of whether the inlet conveys stormwater to a sediment basin, sediment trap, or similarly effective control;[87]

**ii.** Locations where stormwater or authorized non-stormwater will be discharged directly to receiving waters (i.e., not via a storm drain inlet); and

**iii.** Locations where turbidity benchmark monitoring will take place to comply with Part 3.3, if applicable to your site.

**h.** Locations of all potential pollutant-generating activities identified in Part 7.2.3g;

**i.** Designated areas where construction wastes that are covered by the exception in Part 2.3.3e.ii because they are not pollutant-generating will be stored;

**j.** Locations of stormwater controls, including natural buffer areas and any shared controls utilized to comply with this permit; and

**k.** Locations where polymers, flocculants, or other treatment chemicals will be used and stored.

**7.2.5 Non-Stormwater Discharges.** Identify all authorized non-stormwater discharges in Part 1.2.2 that will or may occur.

**7.2.6 Description of Stormwater Controls.**

**a.** For each of the Part 2.2 erosion and sediment control requirements, Part 2.3 pollution prevention requirements, and Part 2.4 construction dewatering requirements, as applicable to your site, you must include the following:

**i.** A description of the specific control(s) to be implemented to meet these requirements;

**ii.** The design specifications for controls described in Part 7.2.6a.i (including references to any manufacturer specifications and/or erosion and sediment control manuals/ordinances relied upon);[88]

**iii.** Routine stormwater control maintenance specifications; and

**iv.** The projected schedule for stormwater control installation/implementation.

**b.** You must also include any of the following additional information as applicable.

**i.** **Natural buffers and/or equivalent sediment controls** (see Part 2.2.1 and Appendix F). You must include the following:

(a) The compliance alternative to be implemented;

(b) If complying with alternative 2, the width of natural buffer retained;

[87] The requirement to show storm drain inlets in the immediate vicinity of the site on your site map only applies to those inlets that are easily identifiable from your site or from a publicly accessible area immediately adjacent to your site.

[88] Design specifications may be found in manufacturer specifications and/or in applicable erosion and sediment control manuals or ordinances. Any departures from such specifications must reflect good engineering practice and must be explained in the SWPPP.

(c) If complying with alternative 2 or 3, the erosion and sediment control(s) you will use to achieve an equivalent sediment reduction, and any information you relied upon to demonstrate the equivalency;

(d) If complying with alternative 3, a description of why it is infeasible for you to provide and maintain an undisturbed natural buffer of any size;

(e) For "linear construction sites" where it is infeasible to implement compliance alternative 1, 2, or 3, a rationale for this determination, and a description of any buffer width retained and/or supplemental erosion and sediment controls installed; and

(f) A description of any disturbances that are exempt under Part 2.2.1 that occur within 50 feet of a receiving water.

**ii. Perimeter controls for a "linear construction site"** (see Part 2.2.3d). For areas where perimeter controls are not feasible, include documentation to support this determination and a description of the other practices that will be implemented to minimize discharges of pollutants in stormwater associated with construction activities.

Note: Routine maintenance specifications for perimeter controls documented in the SWPPP must include the Part 2.2.3c.i requirement that sediment be removed before it has accumulated to one-half of the above-ground height of any perimeter control.

**iii. Sediment track-out controls** (see Parts 2.2.4b and 2.2.4c). Document the specific stabilization techniques and/or controls that will be implemented to remove sediment prior to vehicle exit.

**iv. Inlet protection measures** (see Part 2.2.10a). Where inlet protection measures are not required because the storm drain inlets to which your site discharges are conveyed to a sediment basin, sediment trap, or similarly effective control, include a short description of the control that receives the stormwater flow from the site.

**v. Sediment basins** (see Part 2.2.12). In circumstances where it is infeasible to utilize outlet structures that withdraw water from the surface, include documentation to support this determination, including the specific conditions or time periods when this exception will apply.

**vi. Treatment chemicals** (see Part 2.2.13), you must include the following:

(a) A listing of the soil types that are expected to be exposed during construction in areas of the project that will drain to chemical treatment systems. Also include a listing of soil types expected to be found in fill material to be used in these same areas, to the extent you have this information prior to construction;

(b) A listing of all treatment chemicals to be used at the site and why the selection of these chemicals is suited to the soil characteristics of your site;

(c) If the applicable EPA Regional Office authorized you to use cationic treatment chemicals for sediment control, include the specific controls and implementation procedures designed to ensure that your use of cationic

treatment chemicals will not lead to a discharge that does not meet water quality standards;

(d) The dosage of all treatment chemicals to be used at the site or the methodology to be used to determine dosage;

(e) Information from any applicable Safety Data Sheet (SDS);

(f) Schematic drawings of any chemically enhanced stormwater controls or chemical treatment systems to be used for application of the treatment chemicals;

(g) A description of how chemicals will be stored consistent with Part 2.2.13c;

(h) References to applicable State or local requirements affecting the use of treatment chemicals, and copies of applicable manufacturer's specifications regarding the use of your specific treatment chemicals and/or chemical treatment systems; and

(i) A description of the training that personnel who handle and apply chemicals have received prior to permit coverage, or will receive prior to use of the treatment chemicals at your site.

**vii. Stabilization measures** (see Part 2.2.14). You must include the following:

(a) The specific vegetative and/or non-vegetative practices that will be used;

(b) The stabilization deadline that will be met in accordance with Part 2.2.14;

(c) If complying with the deadlines for sites in arid, semi-arid, or drought-stricken areas, the beginning and ending dates of the seasonally dry period (as defined in Appendix A)[89] and the schedule you will follow for initiating and completing vegetative stabilization; and

(d) If complying with deadlines for sites affected by unforeseen circumstances that delay the initiation and/or completion of vegetative stabilization, document the circumstances and the schedule for initiating and completing stabilization.

**viii. Spill prevention and response procedures** (see Parts 1.3.5, 2.3.3c, 2.3.3d, and 2.3.6). You must include the following:

(a) Procedures for expeditiously stopping, containing, and cleaning up spills, leaks, and other releases. Identify the name or position of the employee(s) responsible for detection and response of spills or leaks; and

(b) Procedures for notification of appropriate facility personnel, emergency response agencies, and regulatory agencies where a leak, spill, or other release containing a hazardous substance or oil in an amount equal to or in excess of a reportable quantity consistent with Part 2.3.6 and established under either 40 CFR part 110, 40 CFR part 117, or 40 CFR part 302, occurs

[89] See footnote 44.

during a 24-hour period. Contact information must be in locations that are readily accessible and available to all employees.

You may also reference the existence of SPCC plans developed for the construction activity under Section 311 of the CWA, or spill control programs otherwise required by an NPDES permit for the construction activity, provided that you keep a copy of that other plan on site.[90]

**ix. Waste management procedures** (see Part 2.3.3). Describe the procedures you will follow for handling, storing, and disposing of all wastes generated at your site consistent with all applicable Federal, State, Tribal, and local requirements, including clearing and demolition debris, sediment removed from the site, construction and domestic waste, hazardous or toxic waste, and sanitary waste. You must also include the following additional information:

(a) If site constraints prevent you from storing chemical containers 50 feet away from receiving waters or the other site drainage features as required in Part 2.3.3c.ii(b), document in your SWPPP the specific reasons why the 50-foot setback is not feasible, and how you will store containers as far away as the site permits; and

(b) If there are construction wastes that are subject to the exception in Part 2.3.3e.ii, describe the specific wastes that will be stored on your site.

**x. Application of fertilizers** (see Part 2.3.5). Document any departures from the manufacturer specifications where appropriate.

**7.2.7 Procedures for Inspection, Maintenance, and Corrective Action.** Describe the procedures you will follow for maintaining your stormwater controls, conducting site inspections, and, where necessary, taking corrective actions, in accordance with Part 2.1.4, Part 4, and Part 5 of this permit, accordingly. Also include:

**a.** The inspection schedule you will follow, which is based on whether your site is subject to Part 4.2 or Part 4.3, or whether your site qualifies for any of the reduced inspection frequencies in Part 4.4;

**b.** If you will be conducting inspections in accordance with the inspection schedule in Part 4.2.2, Part 4.3, or Part 4.4.1b, the location of the rain gauge or the address of the weather station you will be using to obtain rainfall data;

**c.** If you will be reducing your inspection frequency in accordance with Part 4.4.1b, the beginning and ending dates of the seasonally defined arid period for your area or the valid period of drought;

**d.** If you will be reducing your inspection frequency in accordance with Part 4.4.3, the beginning and ending dates of frozen conditions on your site; and

**e.** Any maintenance or inspection checklists or other forms that will be used.

**7.2.8 Procedures for Turbidity Benchmark Monitoring from Dewatering Discharges (if applicable).** If you are required to comply with the Part 3.3 turbidity benchmark

[90] Even if you already have an SPCC or other spill prevention plan in existence, your plans will only be considered adequate if they meet all of the requirements of this Part, either as part of your existing plan or supplemented as part of the SWPPP.

monitoring requirements, describe the procedures you will follow to collect and evaluate samples, report results to EPA and keep records of monitoring information, and take corrective action when necessary. Include the specific type of turbidity meter you will use for monitoring, as well as any manuals or manufacturer instructions on how to operate and calibrate the meter. Describe any coordinating arrangement you may have with any other permitted operators on the same site with respect to compliance with the turbidity monitoring requirements, including which parties are tasked with specific responsibilities. If EPA has approved of an alternate turbidity benchmark pursuant to Part 3.3.2b, include any data and other documentation you relied on to request use of the specific alternative benchmark.

**7.2.9 Compliance with Other Requirements.**

**a. Threatened and Endangered Species Protection.** Include documentation required in the Endangered Species Protection section of the NOI in NeT, or the ESA worksheet in Appendix D, supporting your eligibility with regard to the protection of threatened and endangered species and designated critical habitat.

**b. Historic Properties.** Include documentation required in Appendix E supporting your eligibility with regard to the protection of historic properties.

**c. Safe Drinking Water Act Underground Injection Control (UIC) Requirements for Certain Subsurface Stormwater Controls.** If you are using any of the following stormwater controls at your site, document any contact you have had with the applicable State agency[91] or EPA Regional Office responsible for implementing the requirements for underground injection wells in the Safe Drinking Water Act and EPA's implementing regulations at 40 CFR § 144 -147. Such controls would generally be considered Class V UIC wells:

**i.** Infiltration trenches (if stormwater is directed to any bored, drilled, driven shaft or dug hole that is deeper than its widest surface dimension, or has a subsurface fluid distribution system);

**ii.** Commercially manufactured pre-cast or pre-built proprietary subsurface detention vaults, chambers, or other devices designed to capture and infiltrate stormwater flow; and

**iii.** Drywells, seepage pits, or improved sinkholes (if stormwater is directed to any bored, drilled, driven shaft or dug hole that is deeper than its widest surface dimension, or has a subsurface fluid distribution system).

**7.2.10 SWPPP Certification.** Your signatory must sign and date your SWPPP in accordance with Appendix G, Part G.11.

**7.2.11 Post-Authorization Additions to the SWPPP.** Once you are authorized for coverage under this permit, you must include the following documents as part of your SWPPP:

**a.** A copy of your NOI submitted to EPA along with any correspondence exchanged between you and EPA related to coverage under this permit;

**b.** A copy of the acknowledgment letter you receive from NeT assigning your NPDES ID (i.e.*, permit tracking number*);

[91] For State UIC program contacts, refer to the following EPA website: https://www.epa.gov/uic.

**c.** A copy of this permit (an electronic copy easily available to the stormwater team is also acceptable).

### 7.3 ON-SITE AVAILABILITY OF YOUR SWPPP

You must keep a current copy of your SWPPP at the site or at an easily accessible location so that it can be made available at the time of an on-site inspection or upon request by EPA; a State, Tribal, or local agency approving stormwater management plans; the operator of a storm sewer system receiving discharges from the site; or representatives of the U.S. Fish and Wildlife Service (USFWS) or the National Marine Fisheries Service (NMFS).[92]

EPA may provide access to portions of your SWPPP to a member of the public upon request. Confidential Business Information (CBI) will be withheld from the public, but may not be withheld from EPA, USFWS, or NMFS.[93]

If an on-site location is unavailable to keep the SWPPP when no personnel are present, notice of the plan's location must be posted near the main entrance of your construction site.

### 7.4 SWPPP MODIFICATIONS

**7.4.1** You must modify your SWPPP, including the site map(s), within seven (7) days of any of the following conditions:

**a.** Whenever new operators become active in construction activities on your site, or you make changes to your construction plans, stormwater controls, or other activities at your site that are no longer accurately reflected in your SWPPP. This includes changes made in response to corrective actions triggered under Part 5. You do not need to modify your SWPPP if the estimated dates in Part 7.2.3f change during the course of construction;

**b.** To reflect areas on your site map where operational control has been transferred (and the date of transfer) since initiating permit coverage;

**c.** If inspections or investigations by EPA or its authorized representatives determine that SWPPP modifications are necessary for compliance with this permit;

**d.** Where EPA determines it is necessary to install and/or implement additional controls at your site in order to meet the requirements of this permit, the following must be included in your SWPPP:

**i.** A copy of any correspondence describing such measures and requirements; and

[92] The SWPPP may be prepared, signed, and kept electronically, rather than in paper form, if the records are: (a) in a format that can be read in a similar manner as a paper record; (b) legally dependable with no less evidentiary value than their paper equivalent; and (c) immediately accessible to the inspector during an inspection to the same extent as a paper copy stored at the site would be, if the records were stored in paper form. For additional guidance on the proper practices to follow for the electronic retention of the SWPPP, refer to the Fact Sheet discussion related to Part 4.7.3.

[93] Information covered by a claim of confidentiality will be disclosed by EPA only to the extent of, and by means of, the procedures set forth in 40 CFR part 2, Subpart B. In general, submitted information protected by a business confidentiality claim may be disclosed to other employees, officers, or authorized representatives of the United States concerned with implementing the CWA. The authorized representatives, including employees of other executive branch agencies, may review CBI during the course of reviewing draft regulations.

**ii.** A description of the controls that will be used to meet such requirements.

**e.** To reflect any revisions to applicable Federal, State, Tribal, or local requirements that affect the stormwater controls implemented at the site; and

**f.** If applicable, if a change in chemical treatment systems or chemically enhanced stormwater control is made, including use of a different treatment chemical, different dosage rate, or different area of application.

**7.4.2** You must maintain records showing the dates of all SWPPP modifications. The records must include the name of the person authorizing each change (see Part 7.2.9 above) and a brief summary of all changes.

**7.4.3** All modifications made to the SWPPP consistent with Part 7.4 must be authorized by a person identified in Appendix G, Part G.11.b.

**7.4.4** Upon determining that a modification to your SWPPP is required, if there are multiple operators covered under this permit, you must immediately notify any operators who may be impacted by the change to the SWPPP.

## 8 HOW TO TERMINATE COVERAGE

Until you terminate coverage under this permit, you must comply with all conditions and effluent limitations in the permit. To terminate permit coverage, you must submit to EPA a complete and accurate Notice of Termination (NOT), which certifies that you have met the requirements for terminating in Part 8.

### 8.1 MINIMUM INFORMATION REQUIRED IN NOT

**8.1.1** NPDES ID (i.e*., permit tracking number)* provided by EPA when you received coverage under this permit;

**8.1.2** Basis for submission of the NOT (see Part 8.2);

**8.1.3** Operator contact information;

**8.1.4** Name of site and address (or a description of location if no street address is available); and

**8.1.5** NOT certification.

### 8.2 CONDITIONS FOR TERMINATING CGP COVERAGE

You may terminate CGP coverage only if one or more of the conditions in Parts 8.2.1, 8.2.2, or 8.2.3 has occurred. Until your termination is effective consistent with Part 8.5, you must continue to comply with the conditions of this permit.

**8.2.1** You have completed all construction activities at your site and, if applicable, construction support activities covered by this permit (see Part 1.2.1c), and you have met all of the following requirements:

**a.** For any areas that (1) were disturbed during construction, (2) are not covered by permanent structures, and (3) over which you had control during the construction activities, you have met the requirements for final vegetative or non-vegetative stabilization in Part 2.2.14c.

To document that you have met these stabilization requirements, you must take either ground or aerial photographs that show your site's compliance with the Part 2.2.14 stabilization requirements and submit them with your NOT. If any portion of your

site is covered by one of the exceptions in Part 2.2.14c.iii, indicate which exception applies and include a supplementary explanation with your photographs that provides the necessary context for why this portion of the site is in compliance with the final stabilization criteria even though it appears to be unstabilized. You are not required to take photographs of every distinct part of your site that is being stabilized, however, the conditions of the site portrayed in any photographs that are submitted must be substantially similar[94] to those of the areas that are not photographed. You must also comply with the following related to these photographs:

**i.** Take photographs both before and after the site has met the final stabilization criteria in Part 2.2.14c;

**ii.** All photographs must be clear and in focus, and in the original format and resolution; and

**iii.** Include the date each photograph was taken, and a brief description of the area of the site captured by the photograph (e.g., photo shows application of seed and erosion control mats to remaining exposed surfaces on northeast corner of site).

**b.** You have removed and properly disposed of all construction materials, waste and waste handling devices, and have removed all equipment and vehicles that were used during construction, unless intended for long-term use following your termination of permit coverage;

**c.** You have removed all stormwater controls that were installed and maintained during construction, except those that are intended for long-term use following your termination of permit coverage or those that are biodegradable (as defined in Appendix A); and

**d.** You have removed all potential pollutants and pollutant-generating activities associated with construction, unless needed for long-term use following your termination of permit coverage; or

**8.2.2** You have transferred control of all areas of the site for which you are responsible under this permit to another operator, and that operator has submitted an NOI and obtained coverage under this permit; or

**8.2.3** Coverage under an individual or alternative general NPDES permit has been obtained.

### 8.3 HOW TO SUBMIT YOUR NOT

You must use EPA's NPDES eReporting Tool (NeT) to electronically prepare and submit an NOT for the 2022 CGP.

To access NeT, go to https://cdx.epa.gov/cdx.

Waivers from electronic reporting may be granted as specified in Part 1.4.2. If the EPA Regional Office grants you approval to use a paper NOT, and you elect to use it, you must complete the form in Appendix I.

[94] Stabilization conditions that are substantially similar would include areas that are using the same type of stabilization measures and that have similar slopes, soils, and topography, and have achieved the same level of stabilization.

### 8.4 DEADLINE FOR SUBMITTING THE NOT

You must submit an NOT within 30 calendar days after any one of the conditions in Part 8.2 occurs.

### 8.5 EFFECTIVE DATE OF TERMINATION OF COVERAGE

Your authorization to discharge under this permit terminates at midnight of the calendar day that a complete NOT is submitted to EPA.

## 9 PERMIT CONDITIONS APPLICABLE TO SPECIFIC STATES, INDIAN COUNTRY LANDS, OR TERRITORIES

The provisions in this Part provide additions to the applicable conditions of this permit to reflect specific additional conditions required as part of the State or Tribal CWA Section 401 certification process, or the Coastal Zone Management Act (CZMA) certification process, or as otherwise established by the permitting authority. The specific additional revisions and requirements only apply to activities in those specific States, Indian country, and areas in certain States with Federal Facilities or areas subject to construction projects by Federal Operators. States, Indian country, and other areas not included in this Part do not have any additions to the applicable conditions of this permit.

### 9.1 EPA REGION 1

#### 9.1.1 NHR100000 State of New Hampshire

**a.** Should the permit coverage for an individual applicant be insufficient to achieve water quality standards, the New Hampshire Department of Environmental Services (NHDES) may prepare additional 401 certification conditions for that applicant. Any additional 401 certification conditions will follow all required NHDES public participation requirements.

**b.** If you disturb 100,000 square feet or more of contiguous area, you must also comply with RSA 485-A:17 and Env-Wq 1500, and, unless exempt, apply for an Alteration of Terrain (AoT) permit from NHDES. This requirement also applies to a lower disturbance threshold of 50,000 square feet or more when construction occurs within the protected shoreline under the Shoreland Water Quality Protection Act (see RSA 483-B and Env-Wq 1400). A permit application must also be filed if your project disturbs an area of greater than 2,500 square feet, is within 50 feet of any surface water, and has a flow path of 50 feet or longer disturbing a grade of 25 percent or greater. Project sites with disturbances smaller than those discussed above, that have the potential to adversely affect state surface waters, are subject to the conditions of an AoT General Permit by Rule (Env-Wq 1503.03).

**c.** You must determine that any excavation dewatering discharges are not contaminated before they will be authorized as an allowable non-stormwater discharge under this permit (see Part 1.2.2 of the Construction General Permit or CGP). In the absence of information demonstrating otherwise, the water is considered uncontaminated if there is no groundwater contamination within 1,000 feet of the groundwater dewatering location. Information on groundwater contamination can be generated over the Internet via the NHDES web site http:// des.nh.gov/ by using the One Stop Data Mapper. For a toxic substance included in the New Hampshire surface water quality standards, see Env-Wq 1703.21 (see https://www.des.nh.gov/sites/g/fi1es/ehbemt 341/files/documents/2020-01/Env-Wg

1700.pdf). If it is determined that the groundwater to be dewatered is near a remediation or other waste site, you must apply for the Remediation General Permit (see https://www3.epa.gov/region1/npdes/rgp.html)

**d.** As a minimum, you must treat any uncontaminated excavation "dewatering" discharges and "stormwater" discharges, as those terms are defined in Appendix A of the CGP, as necessary, to remove suspended solids and turbidity so that the surface waters receiving the construction discharges[95] meet New Hampshire surface water quality standards for turbidity (Env-Wq 1703.11 and Env-Wq 1703.03(c)(1)c), benthic deposits (Env-Wq 1703.03(c)(1)a), and Env-Wq 1703.08) and foam, debris, scum or other visible substances (i.e., plumes or visual turbidity)[96] (Env-Wq 1703.03(c)(1)b).

**i.** For all Construction Activities covered under this CGP, the following shall apply to ensure compliance with the aforementioned regulations for turbidity, benthic deposits and visible substances:

Unless otherwise specified, site inspection requirements shall comply with Part 4 of the CGP. As a minimum site inspection frequency shall be in accordance with Part 4.2.2 of the CGP (and Part 4.3.2 of the CGP for sites discharging dewatering water). Site inspection frequency may be reduced in accordance with Part 4.4 of the CGP (Reductions in Inspection Frequency). Monitoring of the receiving water for visible turbidity and benthic sediment deposits shall be conducted each site inspection and results reported in the Inspection Report required in Part 4.7 of the CGP. Should visible turbidity or benthic sediment deposits attributable or partly attributable to your construction activities be present in the receiving water, the "Corrective Actions" specified in Part 5 shall be immediately implemented to correct the water quality standard violations. In addition, daily monitoring (including photographs) of the receiving water shall be conducted until there is no visible turbidity or benthic deposits. Inspection Reports required in Part 4.7 of the CGP shall include, but not be limited to, the distance downstream and the percent of the river width[97] where visible turbidity was observed, and the period of time that the visible turbidity persisted. A copy of the Inspection Report(s) shall be made available to NHDES within 24 hours of receiving a written request from NHDES.

**ii.** For Construction Activities, disturbing 5 acres or more of land at any one time (excluding areas that have been completely stabilized in accordance with the final stabilization criteria specified in Part 2.2.14.c of the CGP), the following shall

[95] Construction Discharges include uncontaminated "dewatering" and "stormwater" discharges as those terms are defined in Appendix A of the CGP. Controlled construction discharges are construction discharges where the rate of flow can be regulated such as from a construction settling basin or NHDES approved flocculation system.

[96] For the definition of visual turbidity, see the definition for "Non-Turbid" in Appendix A of the CGP, which states the following:" "Non-Turbid" - a discharge that is free from visual turbidity. For the purposes of this permit, visual turbidity refers to a sediment plume or other cloudiness in the water caused by sediment that can be identified by an observer." *[EPA interprets the text of this footnote as intending to reference the Appendix A definitions of "visual turbidity" and "non-turbid" in the final permit.]*

[97] The distance downstream and the percent of river width where visible turbidity (i.e., plume) is observed is required to determine the extent of the river affected and to determine if there was a "zone of passage" (i.e., a portion of the receiving water where there was no visible turbidity where mobile organisms could pass without being adversely impacted). The percent of river width affected is equal 100 multiplied by the width of the plume (in feet) divided by the width of the receiving water (in feet).

apply to ensure compliance with the aforementioned regulations for turbidity, benthic deposits and visible substances.

Item 9.1.1.d.i) above shall apply to all construction discharges and the minimum site inspection frequency shall comply with Part 4.3.1 of the CGP (and Part 4.3.2 of the CGP for sites discharging dewatering water). Site inspection frequency may be reduced in accordance with Part 4.4 of the CGP (Reductions in Inspection Frequency).

With regards to controlled construction discharges, if there is no visible turbidity (i.e., plumes) or benthic deposits, and, in the absence of information demonstrating otherwise, turbidity measurements of less than or equal to 50 nephelometric turbidity units (NTU) in the controlled construction discharges at the outlet prior to mixing with the receiving surface waters, shall be presumed to meet New Hampshire surface water quality standards for the parameters listed above. As a minimum, the controlled construction discharges must be sampled at each site inspection.

If any controlled construction discharge exceeds 50 NTU, or if visible turbidity or benthic sediment deposits attributable or partly attributable to any construction discharge are observed in the receiving water, then the "Corrective Actions" specified in Part 5 of the CGP shall be immediately implemented.

In addition, should such violation occur, and, in order to determine compliance with surface water quality standards for turbidity (Env-Wq 1703.11 and Env-Wq 1703.03(c)(1)c), benthic deposits (Env-Wq 1703.03(c)(1)a), and Env-Wq 1703.08) and foam, debris, scum or other visible substances (Env-Wq 1703.03(c)(1)b)), turbidity monitoring shall be immediately implemented as specified below:

Turbidity samples of the receiving water shall be immediately taken in the receiving water upstream and beyond the influence of the construction activity, and, unless a mixing zone[98] is approved by NHDES, no more than 75 feet downstream of each controlled construction discharge that exceeded 50 NTU and no more than 75 feet downstream of each construction discharge that caused visible turbidity.

Downstream samples shall be taken at locations in the receiving water that are most likely influenced by the discharge (e.g., if visible turbidity (i.e., a plume) is present, the sample shall be taken in the plume). Samples shall be collected a minimum of 2 times per day during the daylight hours at times when construction activities are most likely to cause turbidity in the receiving water and shall continue until the turbidity water quality standards are met in the receiving water (i.e., the difference between the upstream and downstream turbidity level is no greater than 10 NTU).

[98] Permittees may request a distance greater than 75 feet downstream of a construction discharge for determining compliance with turbidity standards in Class B surface waters, by submitting a mixing zone request to NHDES that complies with Env-Wq 1707.02. If a mixing zone is approved, NHDES is required to include conditions to ensure that the criteria on which the approval is based are met (Env-Wq 1707.03).

If water quality standards are not met during daylight hours on any day, sampling shall resume the next day and continue no fewer than 2 times per day until water quality standards are met. The date, time, location and results of turbidity measurements, as well as a summary identifying the cause of the violations, corrective actions that were implemented, the period of time that the receiving water exceeded turbidity standards and the distance downstream and the percent of the river width where visible turbidity was observed, and the period of time that the visible turbidity persisted, shall be recorded and included in the Inspection Report required in Part 4.7 of the CGP. Turbidity measurements shall be conducted via a field meter in accordance with the requirements for turbidity specified in Table 1B in 40 CFR 136.3 (see 40 CFR §136.3 Identification of test procedures - Code of Federal Regulations ecfr.io). Field meters shall be calibrated every day sampling is conducted and prior to the first sample.

**e.** Construction site owners and operators are encouraged to consider opportunities for post- construction groundwater recharge using infiltration best management practices (BMPs) during site design and preparation of the SWPPP in order to assure compliance with Env-Wq 1703.03 and Env-Wq 1703.11. If your construction site is in a town that is required to obtain coverage under the NPDES General Permit for discharges from Municipal Separate Storm Sewer Systems (MS4) you may be required to use such practices. The SWPPP must include a description of any on-site infiltration that will be installed as a post-construction stormwater management measure or reasons for not employing such measures such as 1) The facility is located in a wellhead protection area as defined in RSA 485- C:2; or 2) The facility is located in an area where groundwater has been reclassified to GAA, GA1 or GA2 pursuant to RSA 485-C and Env-DW 901; or 3) Any areas that would be exempt from the groundwater recharge requirements contained in Env-Wq 1507.04, including all land uses or activities considered to be a "High-load Area" (see Env-Wq 1502.30). For design considerations for infiltration measures see Env-Wq 1508.06. Note that there may be additional local requirements that fall under the NH MS4 permittee's Authorization to Discharge Permit for those regulated areas.

**f.** Appendix F of the CGP contains information regarding Tier 2, or high quality waters in the various states. ***[EPA notes that this information has now been moved to https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates]*** Although there is no official list of tier 2 waters for New Hampshire, it can be assumed that all New Hampshire surface waters are tier 2 for turbidity unless 1) the surface water that you are proposing to discharge into is listed as impaired for turbidity in the states listing of impaired waters (see https://nhdes-surface-water-quality-assessment-site-nhdes.hub.arcgis.com/) or 2) sampling upstream of the proposed discharge location shows turbidity values greater than 10 NTU (Env-Wq 1703.11). A single grab sample collected during dry weather (no precipitation within 48 hours) is acceptable.

**g.** To ensure compliance with RSA 485-C, RSA 485-A, RSA 485-A:13, I(a), Env-Wq 1700 and Env-Wq 302, the following information may be requested by NHDES. This information must be kept on site unless you receive a written request from NHDES that it be sent to the address shown below in 9.1.1.h.

**i.** A list of all non-stormwater discharges that occur at the facility, including their source locations and the control measures being used (see Part 1.2.2 of the CGP).

**ii.** Records of sampling and analysis required for construction dewatering and stormwater discharges (see 9.1.1.d above).

**h.** All required or requested documents must be sent to: NH Department of Environmental Services, Watershed Management Bureau, P.O. Box 95 Concord, NH 03302-0095.

### 9.1.2 MAR100000 Commonwealth of Massachusetts (except Indian country)

**a.** All discharges covered by the Construction General Permit shall comply with the provisions pursuant to 314 CMR 3.00, 314 CMR 4.00, 314 CMR 9.00, including applicable construction stormwater standards and 310 CMR 10.00.

**b.** Pursuant to 314 CMR 3.11 (2)(a)6., and in accordance with MassDEP's obligation under 314 CMR 4.05(5)(e) to maintain surface waters free from pollutants in concentrations or combinations that are toxic to humans, aquatic life, or wildlife, permittees are prohibited from discharging dewatering water under the CGP from sites that are designated as Superfund/CERCLA or RCRA, and must make accommodations to dispose of the dewatering discharges appropriately, such as coverage under the Remediation General Permit (RGP).

**c.** Pursuant to 314 CMR 3.11 (2)(a), and in accordance with MassDEP's obligation to protect Outstanding Resource Waters under 314 CMR 4.04(3), applicants seeking coverage under the 2022 CGP that propose to carry out construction activities near Outstanding Resource Waters as identified in 314 CMR 4.06, shall submit to MassDEP for review:

**i.** a copy of the Stormwater Pollution Prevention Plan (SWPPP),

**ii.** a copy of the EPA NOI, and

**iii.** MassDEP's Stormwater BMP Checklist.

For purposes of this review, the permittee shall submit these documents to MassDEP at the same time they are submitted to EPA. Instructions on how to submit these documents to MassDEP and where to find the MassDEP Stormwater BMP Checklist and obtain authorization to discharge can be found here: https://www.mass.gov/how-to/wm-15-npdes-general-permit-notice-of- intent.

**d.** Pursuant to 314 CMR 3.11 (2)(a)6., and in accordance with MassDEP's obligation under 314 CMR 4.05(5)(e) to maintain surface waters free from pollutants in concentrations or combinations that are toxic to humans, aquatic life, or wildlife, applicants that propose to dewater under the 2022 CGP and plan to discharge to certain waters as described below, shall determine that any dewatering discharges are not contaminated by testing the proposed discharge as described below as part of the application for WM15 authorization. Unless otherwise specified, testing described in this section should be conducted using the methods in 40 CFR 136.

**i.** Applicants for sites that plan to discharge to Outstanding Resource Waters as identified in 314 CMR 4.06 shall test one sample of the proposed dewatering discharge water for pH, E. Coli (for discharges to freshwater), fecal coliform (for

discharges to salt water), Enterococci (for discharges to salt water), total suspended solids, oil and grease, total nitrogen, total phosphorus, and all parameters with numeric criteria listed in the Massachusetts Surface Water Quality Standards at 314 CMR 4.05(e). Results shall be reported to MassDEP as part of the WM15 application. To determine if the dewatering discharge could be covered under the 2022 CGP, the effluent at zero dilution must meet numeric water quality criteria. If the effluent does not meet numeric water quality criteria, the applicant shall contact EPA Region 1 to discuss coverage under the Remediation General Permit.

**ii.** Applicants for sites that propose to discharge to Public Water Supplies (314 CMR 4.06(1)(d)1) shall also test one sample of the proposed dewatering discharge water for per- and polyfluoroalkyl substances (PFAS), as outlined in the table below. Results shall be reported to MassDEP as part of the WM15 application. If any PFAS compounds are detected, the applicant shall apply for coverage under the NPDES Remediation General Permit for Massachusetts if required.

| **PFAS Testing Parameters for Discharges to Public Drinking Water Supplies[99]** | |
|---|---|
| Perfluorohexanesulfonic acid (PFHxS), grab | Report ng/L |
| Perfluoroheptanoic acid (PFHpA), grab | Report ng/L |
| Perfluorononanoic acid (PFNA), grab | Report ng/L |
| Perfluorooctanesulfonic acid (PFOS), grab | Report ng/L |
| Perfluorooctanoic acid (PFOA), grab | Report ng/L |
| Perfluorodecanoic acid (PFDA), grab | Report ng/L |

**iii.** Applicants for sites that propose to discharge to an impaired water as identified in the most recent final Massachusetts Integrated List of Waters,shall test one sample of the proposed dewatering discharge water for the parameter(s) for which the waterbody is impaired. To determine if the dewatering discharge could be covered under the 2022 CGP, the effluent at zero dilution must meet numeric water quality criteria. If the effluent does not meet numeric water quality criteria, the applicant shall contact EPA Region 1 to discuss coverage under the Remediation GeneralPermit and shall apply for RGP coverage if required.

**iv.** For dewatering discharges to all other waters, if any pollutants are knownor believed present in the proposed dewatering discharge water, the applicant shall apply for coverage under the NPDES Remediation General Permit for Massachusetts if required. For the purposes of this condition, a pollutant is "known present" if measured above the analytical detection limit using a sufficiently sensitive test method in an environmental sample, and "believed present" if a pollutant has not been measured in an environmental sample but will be added or generated prior to discharge, such as through a treatment process. Consequently, a pollutant is "known absent" if measured as non-detect relative to the analytical detection limit using a sufficiently sensitive test method in an environmental sample, and "believed absent" if a pollutant has not been measured in an environmentalsample but will not be added or generated prior to discharge and is not a parameter that applies to the applicable activity category for a site. If any pollutants are known or believed present in the

[99] PFAS testing shall follow established EPA methods 537 or 537.1 for drinking water until EPA Method 3512 for non-potable water becomes available.

proposed dewatering discharge water, the applicant shall test one sample of the proposed dewatering discharge water for the pollutants known or believed to be present. To determine if the dewatering discharge could be covered under the 2022 CGP, the effluent at zero dilution must meet numeric water quality criteria. If the effluent does not meet numeric water quality criteria, the applicant shall contact EPA Region 1 to discuss coverage under the Remediation General Permit.

**e.** Pursuant to 314 CMR 3.11 (2)(a), and in accordance with MassDEP's obligation to protect Outstanding Resource Waters under 314 CMR 4.04(3), applicants that propose to dewater under the 2022 CGP and discharge to Outstanding Resource Waters as identified in 314 CMR 4.06, shall submit the SWPPP and associated documents to MassDEP to review. MassDEP shall complete review within 30 daysof receipt.

**f.** Pursuant to 314 CMR 3.11 (2)(a)6., and in accordance with MassDEP's obligation under 314 CMR 4.05 to maintain surface waters free from color and turbidity in concentrations or combinations that are aesthetically objectionable or would impair any use assigned to the waterbody, permittees that have been authorized to dewater under the 2022 CGP and that discharge to Outstanding Resource Waters as identified in 314 CMR 4.06 shall carry out daily benchmark monitoring for turbidity[100] for the duration of dewatering. Permittees shall compare the weekly average of the turbidity monitoring results with the established benchmark turbidity value of 25 Nephelometric Turbidity Units (NTU). If a permittee's weekly average turbidity results exceed the benchmark, the operator shall conduct follow-up corrective action to determine the source of the problem and to make any necessary repairs or upgrades to the dewatering controls to lower the turbidity levels. The permittee shall document any corrective action taken in its corrective action log. Furthermore, permittees at these sites shall carry out inspections at higher frequency, specifically, daily inspections of the dewatering discharge treatment for the duration of the discharge. The permittee shall inspect the site for sediment plume or whether a hydrocarbon sheen is visible at the point of discharge, estimate the flow rate at the point of discharge, and inspect the site downstream to assess whether sedimentation is attributable to the dewatering discharges.

**g.** Pursuant to 314 CMR 3.11 (2)(a)6., and in accordance with MassDEP's obligation under 314 CMR 4.05 to maintain surface waters free from color and turbidity in concentrations or combinations that are aesthetically objectionable or would impair any use assigned to the waterbody, permittees shall store materials outside the Base Flood Elevation[101] when feasible to prevent displacing runoff and erosion.

**h.** Pursuant to 314 CMR 3.11 (2)(a), and in accordance with MassDEP's obligation to maintain surface waters free from nutrients in concentrations that would cause or contribute to impairment of existing or designated uses under 314 CMR 4.05(5)(c), all applicants who apply for coverage under the 2022 CGP shall follow guidelines on fertilizer application, including use of fertilizer containing no phosphorus, in accordance with 330 CMR 31.00 Plant Nutrient Application Requirements for

[100] Applicants shall follow EPA Method 180.1 to monitor for turbidity

[101] Base Flood Elevation (BFE) is the elevation of surface water resulting from a flood that has a 1% chance of equaling or exceeding that level in any given year. The BFE is shown on the Flood Insurance Rate Map (FIRM) for zones AE, AH, A1–A30, AR, AR/A, AR/AE, AR/A1– A30, AR/AH, AR/AO, V1–V30 and VE. (Source: https://www.fema.gov/node/404233).

Agricultural Land and Non-Agricultural Turf and Lawns. Further, fertilizer shall never be applied to a site when a rain event greater than 0.5 inches is forecast in the next 48 hours.

**i.** Pursuant to 314 CMR 3.11 (2)(a), all applicants who apply for coverage under the 2022 CGP and elect to carry out site inspections every 14 days shall also inspect sites within 24 hours of 0.25 inches of precipitation events or greater over 24 hours,or within 24 hours of a discharge that occurred due to snowmelt from 3.25 inches or greater of snow accumulation.[102] During the high flow periods in spring (i.e., months of April to June), inspection frequency shall be increased to once per week for all sites.

  **i.** To determine whether 3.25 inches or greater of snow accumulation has occurred at a site, snowfall measurements can be taken at the site,[103] or theoperator can rely on similar information from a local weather forecast.

**j.** Implementing structural improvements, enhanced/resilient pollution prevention measures, and other mitigation measures can help to minimize impacts from stormwater discharges from major storm events such as hurricanes, storm surge, extreme/heavy precipitation,[104] and flood events. Pursuant to 314 CMR 3.11 (2)(a), if such stormwater control measures are already in place due to existing requirements mandated by other state, local or federal agencies, the SWPPP shall include a brief description of the controls and a reference to the existing requirement(s). If the site may be exposed to or has previously experienced suchmajor storm events[105], additional stormwater control measures that may be considered, and implemented as necessary, include, but are not limited to:

  **i.** Reinforce materials storage structures to withstand flooding and additional exertion of force;

  **ii.** Prevent floating of semi-stationary structures by elevating to the Base Flood Elevation (BFE) level or securing with non-corrosive device;

  **iii.** When a delivery of exposed materials is expected, and a storm is anticipated within 48 hours, delay delivery until after the storm or storematerials as appropriate (refer to emergency procedures);

[102] This is the amount of snow that is equivalent to 0.25 inches of rain, based on information from the National Oceanic and Atmospheric Administration (NOAA) indicating that 13 inches of snow is, on average, equivalent to 1 inch of rain. See https://www.nssl.noaa.gov/education/svrwx101/winter/faq/.

[103] NOAA's National Weather Service has guidelines on snowfall measurements at https://www.weather.gov/jkl/snow_measurement. These guidelines recommend use of a "snowboard" (a piece of wood about 16 inches by 16 inches) that is placed in an unobstructed part of the site on a hard surface.

[104] Heavy precipitation refers to instances during which the amount of rain or snow experienced in a location substantially exceeds what is normal. What constitutes a period of heavy precipitation varies according to location and season. Heavy precipitation does not necessarily mean the total amount of precipitation at a location has increased— just that precipitation is occurring in more intense or more frequent events.

[105] To determine if your facility is susceptible to an increased frequency of major storm events that could impact the discharge of pollutants in stormwater, you may reference FEMA, NOAA, or USGS flood map products at https://www.usgs.gov/faqs/where-can-i-find-flood-maps?qt-news_science_products=0#qtnews_science_products.

**iv.** Temporarily store materials and waste above the Base Flood Elevation ***[EPA notes that it has deleted a footnote reference to the term "Base Flood Elevation" since the same footnote is already included in Part 9.1.2.g, above.]*** level;

**v.** Temporarily reduce or eliminate outdoor storage;

**vi.** Temporarily relocate any mobile vehicles and equipment to higher ground;

**vii.** Develop scenario-based emergency procedures for major storms that are complementary to regular stormwater pollution prevention planning andidentify emergency contacts for staff and contractors; and

**viii.** Conduct staff training for implementing your emergency procedures atregular intervals.

**k.** Pursuant to 314 CMR 3.11 (2)(a)6., and in accordance with MassDEP's obligation under 314 CMR 4.05(5)(e) to maintain surface waters free from pollutants in concentrations or combinations that are toxic to humans, aquatic life, or wildlife, permittees who seek coverage under the 2022 CGP and anticipate to carry out dust control shall limit their dust control methodology to using water only and specifically avoid using other techniques, such as solutions containing calcium chloride.

**l.** If MassDEP requests a copy of the Stormwater Pollution Prevention Plan (SWPPP) for any construction site at any time, the permittee shall submit the SWPPP to MassDEP within 14 days of such a request. MassDEP may conduct an inspection of any site covered by this permit to ensure compliance with state lawrequirements, including state water quality standards.

### 9.1.3 MTR10F000 Areas in the State of Vermont located at a federal facility

**a.** Earth disturbance at any one time is limited to five acres.

**b.** All areas of earth disturbance must have temporary or final stabilization within 14 days of the initial disturbance. After this time, disturbed areas must be temporarily or permanently stabilized in advance of any runoff producing event. A runoff producing event is an event that produces runoff from the construction site. Temporary stabilization is not required if precipitation is not forecast and work is to continue in the next 24-hours or if the work is occurring in a self-contained excavation (i.e. no outlet) with a depth of two feet or greater (e.g. house foundation excavation, utility trenches). Areas of a construction site that drain to sediment basins are not considered eligible for this exemption, and the exemption applies only to the excavated area itself.

**c.** Site inspections on active construction sites shall be conducted daily during the period from October 15 through April 15.

**d.** The use of chemical treatments (e.g. polymers, flocculants, and coagulants) for the settling and/or removal of sediment from stormwater runoff associated with construction and construction-related activities requires prior written approval and an approved site and project-specific plan, from the Vermont Agency of Natural Resources. In addition, the use of cationic polymers is prohibited unless approved by the Vermont Agency of Natural Resources under a site and project-specific plan.

**e.** Any applicant under EPA's CGP shall allow authorized Vermont Agency of Natural Resources representatives, at reasonable times and upon presentation of credentials, to enter upon the project site for purposes of inspecting the project and determining

compliance with this Certification.

**f.** The Vermont Agency of Natural Resources may reopen and alter or amend the conditions of this Certification over the life of the EPA 2022 Construction General Permit when such action is necessary to assure compliance with the VWQS.

## 9.2 EPA REGION 2

### 9.2.1 NYR10I000 Indian country within the State of New York

#### a. Saint Regis Mohawk Tribe

**i.** Any Responsible-Person/Decision-Maker required under the CGP to submit a Notice of Intent (NOI) to EPA for coverage under the CGP, must concurrently submit an electronic copy of the NOI to the SRMT Environmental Division, Water Resource Program Manager. Additionally, an electronic copy of the Notice of Termination (NOT) must be provided within three business days after electronic confirmation is received from EPA that the NOT has been accepted. The NOI and NOT must be electronically provided to the following addresses:

Mr. Tieman W. Smith
Water Resources Program Manager Saint Regis Mohawk Tribe
449 Frogtown Road
Akwesasne, NY 13655 Tiernan.Smith@srmt-nsn.gov 518.358.2272 ext. 5073

**ii.** Any Responsible-Person/Decision-Maker that is required as part of the CGP to prepare a Discharge Management Plan (OMP) or Storm Water Management Plan (SWMP) and/or Storm Water Pollution Prevention Plan (SWPPP) must submit an electronic copy of the DMP, SWMP and/or SWPPP to the SRMT Environment Division, Water Resources Program Manager IO business days prior to the start of construction of any work to be conducted under the CGP. The applicable documents must be provided to the electronic address listed above.

**iii.** Any Responsible-Person/Decision-Maker that is required under the CGP to submit an annual report to EPA must submit an electronic copy of the annual report concurrently to the SRMT Water Resource Program. Additionally, any correspondences between the applicant and EPA related to analytical data, written reports, corrective action, enforcement, monitoring, or an adverse incident must likewise be routed to the SRMT Water Resources Program at the above electronic address.

**iv.** An "Authorization to Proceed Letter" with site-specific mitigation requirements may be sent out to the permittee when a review of the NOI and OMP, SWMP and /or SWPPP on a case-by-case basis, is completed by the SRMT Environment Division, Water Resource Program. This approval will allow the application to proceed if all mitigation requirements are met.

#### b. Seneca Nation

**i.** Under Part 1.1.5 of the CGP, the Seneca Nation requests that an applicant must demonstrate that they meet the eligibility criteria listed in Appendix D (certify in your Notice of Intent (NOI) that you meet one of the eligibility criteria [Criterion A-F]) as well as species and critical habitats that are listed under the Seneca Nation's "Fishing and Conservation Laws" and the "Seneca Nation of Indians Comprehensive Conservation Law".

**ii.** The Tribal Historic Preservation Office (THPO) was established in 2000 after the Seneca Nation received a recognition letter from the National Park Service (NPS); therefore under Part 1.1.6 of the CGP (Appendix E) and prior to submitting a Notice of Intent (NOI) operators must complete the Nation's TPHO, Project Review Form (https://sni.org/media/246603/sni-thpo-project-review-form.pdf) and submit the completed form with associated information to the Tribal Historic Preservation Officer at 90 Ohi:yo' Way, Salamanca, NY 14779. Federal agencies engaging in construction activities must provide for construction review by a certified construction reviewer in accordance with 7 Del. C. §§4010 & 4013 and 7 DE Admin. Code 5101, subsection 6.1.6.

**iii.** Under Part 1.2 of the CGP, discharges must also follow the Section 13 of the Guide for Construction (Seneca Nation of Indians Source Water Code) and respectively, Council Resolution, dated April 13, 2013 (CN: R-04-13-13-11) to ensure that the health, safety and welfare of the citizens of the Seneca Nation, and all other within the Lands and Territories of the Seneca Nation of Indians, and to facilitate the adequate provisions of water through the elimination or prevention of ground water contamination in the vicinity of wells that supply drinking water for the Nation. The area is known as the Source Water Protection Area (SWPA) and specified activities are regulated within this SWPA, as cited in Section 13 of the Guide for Construction and Section VI, of CN: R-04-13-13-11.

**iv.** Under Part 1.4, any operator who seeks coverage of the CGP, and is required to submit a notice of intent NOI and Notice of Termination (NOT) (as necessary) to the EPA for coverage, under Part 1.4.2 must also submit a copy of the NOI to the Seneca Nation's Environmental Protection Department (EPD) within three business days of submittal to the EPA, (address shown below). Respectively, a copy of the NOT (as described under Part 8.3 of the CGP), which certifies that you have met the requirements of Part 8, must be provided within three business days after electronic confirmation is received from the EPA that the NOT has been accepted. In addition to a NOI and NOT, the Seneca Nation (Environmental Protection Department [EPD]) would require an Environmental Impact Assessment (EA) (Long Form), as shown in Section 2 of the Seneca Nation of Indians Laws, Ordinances & Policies (Guide for Construction), to be completed and submitted to the EPD prior to any project to determine whether the impacts from a project would create significant and detrimental effects to the Nation's lands, water (violate WQS), and environment. The NOI, NOT, and EA must be submitted electronically to epd@sni.org and provided to the following address:

Seneca Nation
Environmental Protection Department (EPD) Attn: Director of EPD
12837 Route 438
Irving, NY 14081

**v.** Under Part 3.0 of the CGP, discharges must be controlled as necessary to meet applicable WQS. The Seneca Nation is working actively towards finalizing and implementing the; therefore, the EPD would require an applicant to submit or grant access to the permit to obtain information on the impact of effluents on receiving waters, including the capability of receiving waters to support future designated uses and achieve the WQS of the Nation; and to advise prospective dischargers of discharge requirements, and coordinate with the appropriate

permitting agencies. As stated in the Decision Document, under Section 303(c) of the CWA, 33 U.S.C. § 1313(c), states develop, review, and revise (as appropriate) water quality standards for surface waters of the United States. At a minimum, such standards are to include designated water uses, water quality criteria to protect such uses, and an antidegradation policy. 40 C.F.R. § 131.6. In addition, under Section 401 of the CWA states may grant, condition, or deny "certification" for federally permitted or licensed activities that may result in a discharge to the waters of the United States 33 U.S.C. § 1341.

**vi.** Under Part 7.2.8(a)(b)(c) and for Part 9 of the CGP, the following Sections of the Seneca Nation's Guide for Construction shall be considered, in conjunction with the CGP:

(a) Section 1. Executive Order - To Establish a Policy for Governing Access to Nation Territories and Facilities by Officials of Foreign Government, dated March 31, 2011

(b) Section 3. Natural Resources Committee, Sand and Gravel Law (CN: R-06-24-05-08)

(c) Section 4. Fishing and Conservation Laws - Part 1.1.5 of the CGP

(d) Section 5. Seneca Nation of Indians Comprehensive Conservation Law, adopted January 14, 2012

(e) Section 9. Food is Our Medicine (FIOM) Program/Native Planting Policy (CN: R-03- 08-14-14)

(f) Section 10. Forestry Management Plan (CN: R-08-14-10-23)

(g) Section 11. Timber Ordinance #411-092, dated May 8, 1982

(h) Section 14. Flood Damage Prevention Local Law, dated September 27, 1988

(i) Section 16. Utilities Ordinance No. 87-100

(j) Authorizing Emergency Action and Contingency Plan to Restrain Pollution of Nations Waters, (Council Resolution: R-03-01-18-10), dated March 10, 2018 Seneca Nation of Indians Permit Application for Construction within Waterways Permit, Form NR98-01.00

## 9.3 EPA REGION 3

### 9.3.1 DCR100000 District of Columbia

**a.** Discharges authorized by this permit shall comply with the District of Columbia Water Pollution Control Act of 1984, as amended (DC Official Code § 8-103.01 and § 8-103.06, et seq.) to ensure that District of Columbia waters, waters in adjacent and downstream states, and the beneficial uses of these waters will not be harmed or degraded by the discharges.

**b.** Discharges authorized by this permit must comply with §§ 1104.1 and 1104.8 of Chapter 11 and the provisions of Chapter 19 of Title 21of District of Columbia Municipal Regulations in order to attain and maintain designated uses of the District of Columbia waters.

**c.** The permittee shall comply with the District of Columbia Stormwater Management and Soil Erosion and Sediment Control regulations in Chapter 5 of Title 21 of the District of Columbia Municipal Regulations.

**d.** The permittee shall comply with the District of Columbia Flood Management Control regulations in Chapter 31 of Title 20 of the District of Columbia Municipal Regulations.

**e.** The permittee shall submit a copy of the Stormwater Pollution Prevention Plan (SWPPP) to the Regulatory Review Division, Department of Energy & Environment, Government of the District of Columbia, 1200 First Street, NE, 5th Floor, Washington, DC 20002, during the review and approval of the permittee's DOEE Erosion and Sediment Control Plan in accordance with the provisions of Chapter 542 of Title 21 of the District of Columbia Municipal Regulations.

**f.** Upon request, the permittee shall submit all inspection and monitoring reports as required by this permit and 40 CFR § 122.41 to the Associate Director, Inspection and Enforcement Division, Department of Energy & Environment, Government of the District of Columbia, 1200 First Street, NE, 5th Floor, Washington, DC 20002; telephone (202) 535-2226, or by email at Joshua.Rodriguez@dc.gov.

**g.** In the event the permittee intends to discharge dewatering water, groundwater, or groundwater comingled with stormwater from a known contaminated site, the permittee shall contact the Regulatory Review Division, Department of Energy & Environment, Government of the District of Columbia, 1200 First Street, NE, 5th Floor, Washington, DC 20002; telephone (202) 535-2600, or by email at MS4DischargeAuthorization@dc.gov to request authorization to discharge dewatering water, groundwater, or groundwater comingled with stormwater to the District's Municipal Separate Storm Sewer System (MS4) or to a surface water body pursuant to §§ 8-103.02, 8-103.06, and 8-103.07 of the District of Columbia Water Pollution Control Act of 1984, as amended.

### 9.3.2 DER10F000 Areas in the State of Delaware located at a federal facility (as defined in Appendix A)

**a.** Federal agencies must submit a sediment and stormwater management plan (SSMP) and receive Department approval prior to undertaking any land clearing, soil movement or construction activity unless conducting an exempt activity.

**b.** Federal construction activities are required to have a third-party Certified Construction Reviewer (CCR) perform weekly reviews to ensure the adequacy of construction activities pursuant to the approved SSMP and regulations.

Implementation of approved SSMPs requires the daily oversight of construction activity by certified responsible personnel.

**c.** Implementation of approved SSMPs requires the daily oversight of construction activity by certified responsible personnel.

**d.** A current copy of the SSMP must be maintained at the construction site.

**e.** Unless authorized by the Department, not more than 20 acres may be disturbed at any one time.

## 9.4 EPA REGION 4

No additional conditions

## 9.5 EPA REGION 5

### 9.5.1 MIR10I000 Indian country within the State of Minnesota

**a. Fond du Lac Reservation**

**i.** New dischargers wishing to discharge to an Outstanding Reservation Resource Water (ORRW)[106] must obtain an individual permit from EPA for storm water discharges from large and small construction activities.

**ii.** A copy of the Storm Water Pollution Prevention Plan (SWPPP) must be submitted to the Office of Water Protection at least fifteen (15) days in advance of sending the Notice of Intent to EPA. The SWPPP can be submitted electronically to richardgitar@FDLREZ.com or by hardcopy sent to:

Fond du Lac Reservation
Office of Water Protection
1720 Big Lake Road
Cloquet, MN 55720

**iii.** Copies of the Notice of Intent (NOI) and the Notice of Termination (NOT) must be sent to the Fond du Lac Office of Water Protection at the same time they are submitted to EPA. [The condition helps the Office of Water Protection keep track of when a project is about to start and when it has ended. FDL Water Quality Certification Ordinance, Section 204 (a) (2)).

**iv.** If the project will entail a discharge to any watercourse or open water body, the turbidity limit shall NOT exceed 10% of natural background within the receiving water(s) as determined by Office of Water Protection staff. For such discharges, turbidity sampling must take place within 24 hours of a ½-inch or greater rainfall event. The results of the sampling must be reported to the Office of Water Protection within 7 days of the sample collection. All sample reporting must include the date and time, location (GPS: UTM/Zone 15), and NTU. CGP applicants are encouraged to work with the Office of Water Protection in determining the most appropriate location(s) for sampling. [This condition helps both the Office of Water Protection and the project proponent in knowing whether or not their erosion control efforts are effective. FDL Water Quality Certification, Section 204 (b) (1)).

**v.** Receiving waters with open water must be sampled for turbidity prior to any authorized discharge as determined by Office of Water Protection staff. This requirement only applies to receiving waters which no ambient turbidity data exists. [This condition allows the Office of Water Protection to obtain a baseline turbidity sample in which to compare to other samples. FDL Water Quality Certification Ordinance, Section 204 (b) (2)].

**vi.** All work shall be carried out in such a manner as will prevent violations of water quality criteria as stated in the Water Quality Standards of the Fond du Lac Reservation, Ordinance #12/98, as amended. This includes, but is not limited to, the prevention of any discharge that causes a condition in which visible solids, bottom deposits, or turbidity impairs the usefulness of water of the Fond du Lac

[106] Although additional waters may be designated in the future, currently Perch Lake, Rice Portage Lake, Miller Lake, Deadfish Lake, and Jaskari Lake are designated as ORRWs.

Reservation for any of the uses designated in the Water Quality Standards of the Fond du Lac Reservation. These uses include wildlife, aquatic life, warm water fisheries, cold water fisheries, subsistence fishing (netting), primary contact recreation, secondary contact recreation, cultural, wild rice areas, aesthetic waters, agriculture, navigation, commercial and wetlands. It also includes the designated uses of wetlands including, but not limited to, baseflow discharge, cultural opportunities, flood flow attenuation, groundwater recharge, indigenous floral and fauna) diversity and abundance, nutrient cycling, organic carbon export/cycling, protection of downstream water quality, recreation, resilience against climactic effects, sediment/shoreline stabilization, surface water storage, wild rice, and water dependent wildlife. [In addition to listing the designated uses of waters of the Fond du Lac Reservation, this condition also limits the project proponent to discharges that will not violate our Water Quality Standards. FDL Water Quality Certification Ordinance, Section 204 (a) (7)).

**vii.** Appropriate steps shall be taken to ensure that petroleum products or other chemical pollutants are prevented from entering waters of the Fond du Lac Reservation. All spills must be reported to the appropriate emergency management Agency (National Response Center AND the State Duty Officer), and measures shall be taken immediately to prevent the pollution of waters of the Fond du Lac Reservation, including groundwater. The Fond du Lac Office of Water Protection must also be notified immediately of any spill regardless of size. [This condition helps protect water quality and also reminds project proponents of their responsibility in reporting spill events. FDL Water Quality Certification Ordinance, Section 204 (b) (3)).

**viii.** All seed mixes, whether used for temporary stabilization or permanent seeding, shall NOT contain any annual ryegrass (Lolium species). Wild rye (Elymus species) or Oats (Avena species) may be used as a replacement in seed mixes. [This condition prevents the use of annual ryegrass on the Reservation. Annual ryegrass is allelopathic, which means it produces biochemical in its roots that inhibit the growth of native plants. If used in seed mixes, annual ryegrass could contribute to erosion, especially on slopes. However, the condition also specifies substitute grasses that germinate almost as fast as annual ryegrass for use as a cover crop to help prevent erosion. FDL Water Quality Certification Ordinance, Section 204 (t) (1)).

**ix.** To prevent the introduction of invasive species, ALL contractors and subcontractors MUST disclose information stating prior equipment location(s) and ALL known invasive species potentially being transported from said location(s). All equipment MUST undergo a high pressure wash (including any equipment mats) BEFORE ENTERING the Fond du Lac Reservation. Personal equipment such as work boots, gloves, vest, etc. MUST be clean of debris, dirt and plant and animal material BEFORE ENTERING the Fond du Lac Reservation. Equipment being transported from known infested areas MUST undergo a high pressure wash as soon as possible after leaving the infested site and again BEFORE ENTERING the Fond du Lac Reservation, to avoid transport of invasive species into areas surrounding the Reservation. Written certification of equipment cleaning MUST be provided to the Fond du Lac Office of Water Protection. Upon arrival, ALL contractor and subcontractor equipment will be inspected by appointed Fond du Lac staff. If equipment is deemed unsatisfactory, the equipment MUST

undergo a high pressure washing until the equipment is cleared by the inspector, until such time, minimal travel will be allowed through the Reservation. The contractor shall be held responsible for the control of any invasive species introduced as a result of their project. [This condition requires the project proponent to prevent the inadvertent introduction of invasive species by taking an active role in cleaning all vehicles, equipment, and equipment mats before entering the Reservation. This condition has been placed in certifications since 2012, due to the introduction of Wild Parsnip in 2011 from a pipeline contractor. It is much easier to prevent the introduction of an invasive species than it is to eradicate it once it has been introduced. Many invasive plant species form monocultures, preventing native plants from growing. This situation often leads to cases of erosion, which in turn effects water quality. FOL Water Quality Certification Ordinance, Section 204 (g) (1)].

**x.** A copy of this certification MUST be kept by the contractor on-site at all times and be available for viewing by all personnel, including inspectors. [This condition ensures that the information contained in the certification, especially the conditions, is readily available onsite for reference. FOL Water Quality Certification Ordinance, Section 204 (a) (9)].

**b. The Grand Portage Band of Lake Superior Chippewa**

**i.** The CGP authorization is for construction activities that may occur within the exterior boundaries of the Grand Portage Reservation in accordance to the Grand Portage Land Use Ordinance. The CGP regulates stormwater discharges associated with construction sites of one acre or more in size. Only those activities specifically authorized by the CGP are authorized by this certification (the "Certification").

**ii.** All construction stormwater discharges authorized by the CGP must comply with the Water Quality Standards and Water Resources Ordinance, as well as Applicable Federal Standards (as defined in the Water Resources Ordinance).

**iii.** All appropriate steps must be taken to ensure that petroleum products or other chemical pollutants are prevented from entering the Waters of the Reservation. All spills must be reported to the appropriate emergency-management agency, and measures must be taken to prevent the pollution of the Waters of the Reservation, including groundwater.

**iv.** The 2022 CGP requires inspections and monitoring reports of the construction site stormwater discharges by a qualified person. Monitoring and inspection reports must comply with the minimum requirements contained in the 2022 CGP. The monitoring plan must be prepared and incorporated into the Storm Water Pollution Prevention Plan (the "SWPP"). A copy of the SWPP must be submitted to the Board at least 30 days in advance of sending the requisite Notice of Intent to EPA. The SWPP should be sent to:

Grand Portage Environmental Resources Board

P.O. Box 428

Grand Portage, MN 55605

Copies of the Notice of Intent and Notice of Termination required under the General Permit must be submitted to the Board at the address above at the same time they are submitted to the EPA.

**v.** If requested by the Grand Portage Environmental Department, the permittee must provide additional information necessary for a case-by-case eligibility determination to assure compliance with the Water Quality Standards and any Applicable Federal Standards. The burden is on the applicant to demonstrate compliance with the Water Quality Standards, the Water Resources Ordinance, and Applicable Federal Standards whether or not the application is ultimately eligible for the CGP.

**vi.** CGP discharges must not cause nuisance conditions as defined in Grand Portage Water Quality Standards.

**vii.** The Board retains full authority to ensure compliance with and to enforce the provisions of the Water Resource Ordinance and Water Quality Standards, Applicable Federal Standards, and these Certification conditions. Nothing herein affects the scope or applicability of other controlling tribal or federal requirements, including but not limited to impacts to cultural, historical, or archeological features or sites, or properties that may be eligible for listing on the National Register of Historic Places under the National Historic Preservation Act, 54 U.S.C. §§ 300101 et seq.

**viii.** Appeals related to Board actions taken in accordance with any of the preceding conditions may be heard by the Grand Portage Tribal Court.

**c. Leech Lake Band of Ojibwe**

**i.** The water quality standards that apply to the construction site are the standards at the time the operator submits its Notice of Intent (NOI) to EPA and the LLBO WRP (see conditions # 2 and # 3).

**ii.** A copy of the Stormwater Pollution Prevention Plan (SWPPP) must be submitted to the LLBO WRP at least 30 days in advance of sending the NOI for the project to EPA. See attached LLBO 401 Water Quality Certification Ordinance. Section 304(a)(1). The SWPPP should be submitted electronically to Jeff.Harper@llojibwe.net and by hardcopy sent to:

Leech Lake Band of Ojibwe
ATTN: Water Resources Program - 401 Cert
Division of Resource Management
190 Sailstar Drive NW
Cass Lake, Minnesota 56633

**iii.** Copies of the NOI and the Notice of Termination (NOT) must be submitted to the LLBO WRP at the same time they are submitted to EPA. See attached LLBO 401 Water Quality Certification Ordinance, Section 304(a)(2). The NOI and NOT should be submitted electronically to Jeff.Harper@llojibwe.net and sent by hardcopy to the address cited in condition # 2.

**iv.** Any and all other conditions listed in Section 304 of the attached LLBO 401 Water Quality Certification Ordinance shall be observed unless the LLBO WRP deems that certain conditions therein are not applicable to the project in need of a permit under this certification.

**v.** A copy of this certification MUST be kept by the contractor on-site at all times and be available for viewing by all personnel, including inspectors.

**vi.** Upon consideration of the NOI, if the LLBO WRP finds that the discharge will not be controlled as necessary to meet applicable water quality standards, the LLBO WRP may insist, consistent with Part 3.1 of the CGP, that additional controls are installed to meet applicable water quality standards, or recommend to EPA that the operator obtain coverage under an individual permit.

### 9.5.2 WIR10I000 Indian country within the State of Wisconsin

#### a. Bad River Band of Lake Superior Tribe of Chippewa Indians

**i.** Only those activities specifically authorized by the CGP are authorized by this Certification. This Certification does not authorize impacts to cultural properties, orhistorical sites, or properties that may be eligible for listing as such.

**ii.** All projects which are eligible for coverage under the CGP and are located within the exterior boundaries of the Bad River Reservation shall be implemented in such a manner that is consistent with the Tribe's Water Quality Standards (WQS). The Tribe's WQS can be viewed at: http://www.badriver-nsn.gov/wp-content/uploads/2020/01/NRD_WaterQualityStandards_2011.pdf

**iii.** Operators are not eligible to obtain authorization under the CGP for all new discharges to an Outstanding Tribal Resource Water (OTRW or Tier 3 water). OTRWs, or Tier 3 waters, include the following: Kakagon Slough and the lower wetland reaches of its tributaries that support wild rice, Kakagon River, Bad River Slough, Honest John Lake, Bog Lake, a portion of Bad River, from where it enters the Reservation through the confluence with the White River, and Potato River. OTRWs can be viewed at: https://www.arcgis.com/apps/View/index.html?appid=6f44c371217e4ee8b5f1c2c705c 7c7c5

**iv.** An operator proposing to discharge to an Outstanding Resource Water (ORW or Tier 2.5 water) under the CGP must comply with the antidegradation provisions of the Tribe's WQS. ORWs, or Tier 2.5 waters, include the following: a portion of Bad River, from downstream the confluence with the White River to Lake Superior, White River, Marengo River, Graveyard Creek, Bear Trap Creek, Wood Creek, Brunsweiler River, Tyler Forks, Bell Creek, and Vaughn Creek. ORWs can be viewed at: https://www.arcgis.com/apps/View/index.html?appid=6f44c371217e4ee8b5f1c2c705c 7c7c5. The antidegradation demonstration materials described in provision E.4.iii., and included on the antidegradation demonstration template found at: https://www.badriver-nsn.gov/natural-resources/projectreviews/, must be submitted to the following address:

Bad River Tribe's Natural Resources Department

Attn: Water Regulatory Specialist

P.O. Box 39 Odanah, WI 54861

WaterReg@badriver-nsn.gov

**v.** An operator proposing to discharge to an Exceptional Resource Water (ERW or Tier 2 water) under the CGP must comply with the antidegradation provisions of the Tribe's WQS. ERWs, or Tier 2 waters, include the following: any surface water within the exterior boundaries of the Reservation that is not specifically classified as an Outstanding Resource Water (Tier 2.5 water) or an Outstanding Tribal Resource Water (Tier 3 water). ERWs can be viewed at:

https://www.arcgis.com/apps/View/index.html?appid=6f44c371217e4ee8b5f1c2c705c 7c7c5. The antidegradation demonstration materials described in provision E.4.ii., and included on the antidegradation demonstration template found at: https://www.badriver-nsn.gov/natural-resources/projectreviews/, must be submitted to the following address:

Bad River Tribe's Natural Resources Department
Attn: Water Regulatory Specialist
P.O. Box 39 Odanah, WI 54861
WaterReg@badriver-nsn.gov

**vi.** Projects utilizing cationic treatment chemicals within the Bad River Reservation boundaries are not eligible for coverage under the CGP.

**vii.** A discharge to a surface water within the Bad River Reservation boundaries shall not cause or contribute to an exceedance of the turbidity criterion included in the Tribe's WQS, which states: Turbidity shall not exceed 5 NTU over natural background turbidity when the background turbidity is 50 NTU or less, or turbidity shall not increase more than 10% when the background turbidity is more than 50 NTU.

**viii.** All projects which are eligible for coverage under the CGP within the exterior boundaries of the Bad River Reservation must comply with the Bad River Reservation Wetland and Watercourse Protection Ordinance, or Chapter 323 of the Bad River Tribal Ordinances, including the erosion and sedimentation control, natural buffer, and stabilization requirements. Questions regarding Chapter 323 and requests for permit applications can be directed to the Wetlands Specialist in the Tribe's Natural Resources Department at (715) 682-7123 or wetlands@badriver-nsn.gov.

**ix.** An operator of a project, which is eligible for coverage under the CGP, that would result in an allowable discharge under the CGP occurring within the exterior boundaries of the Bad River Reservation must notify the Tribe prior to the commencing earth-disturbing activities. The operator must submit a copy of the Notice of Intent (NOI) to the following addresses at the same time it is submitted to the U.S. EPA:

Bad River Tribe's Natural Resources Department
Attn: Water Regulatory Specialist
P.O. Box 39 Odanah, WI 54861
WaterReg@badriver-nsn.gov

Bad River Tribe's Natural Resources Department
Attn: Tribal Historic Preservation Officer (THPO)
P.O. Box 39 Odanah, WI 54861
THPO@badriver-nsn.gov

The operator must also submit a copy of the Notice of Termination (NOT) to the above addresses at the same time it is submitted to the U.S. EPA. Photographs showing the current site conditions must be included as part of the NOT to document the stabilization requirements have been met.

**x.** The THPO must be provided 30 days to comment on the project.

**xi.** The operator must obtain THPO concurrence in writing. This written concurrence will outline measures to be taken to prevent or mitigate effects to historic properties. For more information regarding the specifics of the cultural resources process, see 36 CFR Part 800. A best practice for an operator is to consult with the THPO during the planning stages of an undertaking.

**xii.** An operator of a project, which is eligible for coverage under the CGP, that would result in an allowable discharge under the CGP occurring within the exterior boundaries of the Bad River Reservation must submit a copy of the Stormwater Pollution Prevention Plan (SWPPP) to the following address at the same time as submitting the NOI:

Bad River Tribe's Natural Resources Department
Attn: Water Regulatory Specialist
P.O. Box 39 Odanah, WI 54861
WaterReg@badriver-nsn.gov

**xiii.** Any corrective action reports that are required under the CGP must be submitted to the following address within one (1) working day of the report completion:

Bad River Tribe's Natural Resources Department
P.O. Box 39 Odanah, WI 54861
WaterReg@badriver-nsn.gov

**xiv.** An operator of a project, which is eligible for coverage under the CGP, that would result in an allowable discharge under the CGP occurring within the exterior boundaries of the Bad River Reservation must submit a copies of the inspection reports (including photographs) to the following address within 24 hours of completing any site inspection required:

Bad River Tribe's Natural Resources Department Attn: Water Regulatory Specialist
P.O. Box 39 Odanah, WI 54861
WaterReg@badriver-nsn.gov

**xv.** An operator shall be responsible for meeting any additional permit requirements imposed by the U.S. EPA necessary to comply with the Tribe's antidegradation policies if the discharge point is located upstream of waters designated by the Tribe.

## 9.6 EPA REGION 6

### 9.6.1 NMR100000 State of New Mexico, except Indian country

**a.** In Outstanding National Resource Waters (ONRWs) in New Mexico, no degradation is permitted except in limited, specifically defined instances. Therefore, Operators are not eligible to obtain authorization under this general permit for stormwater discharges to waters classified as ONRWs listed in Paragraph D of 20.6.4.9 New Mexico Administrative Code (NMAC), also referred to as "Tier 3 waters" as defined in Appendix A of this permit. Exception: When construction activities are in response to a public emergency (e.g., wildfire, extreme flooding, etc.) and the related work requires immediate authorization to avoid a threat to public health or safety.

**i.** Operators who conduct construction activities in response to a public emergency to mitigate an immediate threat to public health or safety shall

adhere to the requirements in 20.6.4.8(A)(3)(c) NMAC, including notifying the New Mexico Environment Department (NMED) within seven days of initiation of the emergency action and providing NMED with a summary of the action taken within 30 days of initiation of the emergency action.

**ii.** For all other scenarios, Operators with proposed discharges to ONRWs in New Mexico shall obtain coverage from EPA under an NPDES Individual Permit and will comply with the additional standards and regulations related to discharges to ONRWs in 20.6.4.8(A) NMAC. Additional information is available from:

New Mexico Environment Department Surface Water Quality Bureau
P.O. Box 5469
Santa Fe, NM 87502-5469 Telephone: 505-827-0187
https://www.env.nm.gov/surface-water-quality/wqs/
https://gis.web.env.nm.gov/oem/?map=swqb

**b.** If construction dewatering activities are anticipated at a construction site and non-stormwater discharges of groundwater, subsurface water, spring water, and/or other dewatering water are anticipated, the Operators/Permittees must complete the following steps:

1. Review the state's Ground Water Quality Bureau Mapper (https://gis.web.env.nm.gov/GWQB/) and Petroleum Storage Tank Bureau Mapper (https://gis.web.env.nm.gov/GWQB/).

   Check if the following sources are located within the noted distance from the anticipated construction dewatering activity. At a minimum, a list of the following potential sources of contaminants and pollutants at the noted distance is to be kept in the SWPPP.

| Source of Potential Contamination or Pollutants* | Constituents likely to be required for testing* |
|---|---|
| Within 0.5 mile of an open Leaking Underground Storage Tank (LUST) site | BTEX (Benzene, Toluene, Ethylbenzene, and Xylene) plus additional parameters depending on site conditions** |
| Within 0.5 mile of an open Voluntary Remediation site | All applicable parameters or pollutants listed in 20.6.4.13, 20.6.4.52, 20.6.4.54, 20.6.4.97 thru 20.6.4.99, 20.6.4.101 through 20.6.4.899, and 20.6.4.900 NMAC (or an alternate list approved by the NMED-SWQB)* |
| Within 0.5 mile of an open RCRA Corrective Action Site | |
| Within 0.5 mile of an open Abatement Site | |
| Within 0.5 mile of an open Brownfield Site | |
| Within 1.0 mile or more of a Superfund site or National Priorities List (NPL) site with associated groundwater contamination. | |
| Construction activity contaminants and/or natural water pollutants | Additional parameters depending on site activities and conditions (Contact NMED- SWQB for an alternate list)* |

*For further assistance determining whether dewatering may encounter contaminated sources, please contact the NMED Ground Water Quality Bureau at 505-827-2965 or NMED Surface Water Quality Bureau (SWQB) at 505-827-0187.

** EPA approved sufficiently sensitive methods must be used. For known PCB sources and analysis, EPA Method 1668C must be used (see https://www.epa.gov/cwa-methods).

2. If dewatering activities are anticipated, information on the flow rate and potential to encounter contaminated groundwater, subsurface water, spring water, or dewatering water must be provideddirectly to NMED at the following address:

   NMED Surface Water Quality Bureau

   Program Manager, Point Source Regulation
   SectionPO Box 5469, Santa Fe, NM 87502

   *Please call the SWQB to obtain the appropriate email address (505-827-0187).*

3. In addition, the Operator/Permittee must characterize the quality of the groundwater and subsurface water, spring water, or dewatering water being considered for discharge according to the table above and including dissolved hardness and pH. Considering the contaminant sources listed in the table above, water quality data may already be available. For further assistance, contactthe

NMED Surface Water Quality Bureau (505-827-0187), Ground Water Quality Bureau (505-827- 2965), Petroleum Storage Tank Bureau (505-476-4397), or Hazardous Waste Bureau (505-476- 6000).

i. The Operator/Permittee must submit recent analytical test results (i.e., within the past 5 years) according to the table above, and including dissolved hardness and pH, to the EPA Region 6 Stormwater Permit Contact and the NMED Surface Water Quality Bureau (see contact information in #2 above). If the test data exceed applicable water quality standards, then the groundwater, subsurface water, spring water, or dewatering water cannot be discharged into surface waters under this general permit. Operators/Permittees may submit an NPDES Individual Permit application to treat and discharge to waters of the U.S. or find alternative disposal measures. No discharges to surface waters are allowed until authorized.

ii. If the discharge has the potential to affect groundwater (e.g., land application), the Operator/Permittee must submit an NOI to the NMED Ground Water Quality Bureau (see 20.6.2.1201 NMAC – Notice of Intent to Discharge).

4. The Operator/Permittee must document any findings and all correspondence with NMED and EPA in the SWPPP.

**c.** Operators who intend to obtain authorization under this permit for new and existing storm water dischargesfrom construction sites must satisfy the following condition:

**i.** The SWPPP must include site-specific interim and permanent stabilization, managerial, and structural solids, erosion and sediment control best management practices (BMPs) and/or other controls that are designed to prevent to the maximum extent practicable an increase in the sediment yield and flow velocity from pre-construction, pre-development conditions to assure thatapplicable standards in 20.6.4 NMAC, including the antidegradation policy, and TMDL waste load allocations (WLAs) are met. This requirement applies to discharges both during construction and after construction operations have been completed. The SWPPP must identify and document the rationale for selecting these BMPs and/or other controls. The SWPPP must also describe design specifications, construction specifications, maintenance schedules (including a long-term maintenance plan), criteria for inspections, and expected performance and longevity of these BMPs.For sites greater than 5 acres in size, BMP selection must be made based on the use of appropriatesoil loss prediction models (i.e. SEDCAD, RUSLE, SEDIMOT, MULTISED, etc.) OR equivalent generallyaccepted (by professional erosion control specialists) soil loss prediction tools.

**ii.** For all sites, the Operator(s) must demonstrate, and include documentation in the SWPPP, that implementation of the site-specific practices will ensure that the applicable standards and TMDL WLAs are met, and will result in sediment yields and flow velocities that, to the maximum extent practicable, will not be greater than the sediment yield levels and flow velocities from preconstruction, pre-development conditions.

**iii.** All SWPPPs must be prepared in accordance with good engineering practices by qualified (e.g., CPESC certified, engineers with appropriate training) erosion control specialists familiar with the use of soil loss prediction models and design of erosion and sediment control systems based on these models (or equivalent soil

loss prediction tools). Qualifications of the preparer (e.g., professional certifications, description of appropriate training) must be documented in the SWPPP.The Operator(s) must design, implement, and maintain BMPs in the manner specified in the SWPPP.

NMED supports the use of EPA's small residential lot template if a site qualifies to use it as explained inthe permit, as long as it is consistent with the above requirements. NMED's requirement does not preclude small residential sites from using the template, but it may require an additional short paragraphto justify the selection of specific BMPs for the site.

**d.** Operators must notify NMED when discharges of toxic or hazardous substances or oil from a spill or other release occurs - see Emergency Spill Notification Requirements, Part 2.3.6 of the permit. For emergencies, Operators can call 505-827-9329 at any time. For non-emergencies, Operators can call 866-428-6535 (voice mail 24-hours per day) or 505-476-6000 during business hours from 8am-5pm, Monday through Friday. Operators can also call the NMED Surface Water Quality Bureau directly at 505-827-0187.

**e.** Operators of small construction activities (i.e., 1-5 acres) are not eligible to qualify for a waiver in lieu of needing to obtain coverage under this general permit based on Item C.3 of Appendix C (Equivalent Analysis Waiver) in the State of New Mexico.

### 9.6.2 NMR10I000 Indian country within the State of New Mexico, except Navajo Reservation Lands that are covered under Arizona permit AZR10000I and Ute Mountain Reservation Lands that are covered under Colorado permit COR10000I.

**a. Nambe Pueblo**

**i.** The operator must provide a copy of the Notice of Intent (NOI) and Notice of Termination (NOT) to the Nambe Pueblo Governor's Office at the same time it is provided to the US Environmental Protection Agency. The NOI and NOT should be provided to the following address:

Office of the Governor Nambe Pueblo

!SA NPI02 WEST

Nambe Pueblo, New Mexico 87506

**ii.** The operator must provide a copy of the Storm Water Pollution Prevention Plan (SWPPP) to Nambe Pueblo at the same time it is submitted to the EPA, either by email to governor@nambepueblo.org or mailed to the above address.

**iii.** The operator must provide copies of inspection reports, a copy of the corrective action log, and modifications made to the SWPPP as a result of inspection findings, upon request by the Nambe Pueblo Department of Environmental and Natural Resources or Nam be Governor.

**b. Ohkay Owingeh Tribe**

**i.** All operators obtaining permit coverage under the EPA CGP, must submit a copy of the certified (signed) Notice of Intent (NOI) to the Ohkay Owingeh Office of Environmental Affairs, a copy of NOI modifications and the Notice of Termination (NOT), must be provided within three business days after EPA provides electronic confirmation that the submission has been received. The NOI and NOT must be provided to the following address:

Naomi L. Archuleta - Environmental Programs Manager Ohkay Owingeh Office of Environmental Affairs
P.O. Box 717
Ohkay Owingeh, NM 87566
naomi.archuleta@ohkay.org

Noah Kaniatobe - Environmental Specialist Ohkay Owingeh, Office of Environmental Affairs
P.O. Box 717
Ohkay Owingeh, NM 87566
noah.kaniatohe@ohkay.org

**ii.** All operators obtaining permit coverage under the EPA CGP, must submit an electronic copy of the Storm Water Pollution Prevention Plan (SWPPP) to Ohkay Owingeh Office of Environmental Affairsat the same time that the NOI is submitted to the tribe (see contact information listed above).

**iii.** Following each incident where the operator takes a corrective action the operator must provide thecorrective action log to the Ohkay Owingeh Office of Environmental Affairs.

**iv.** The operator must notify Ohkay Owingeh Office of Environmental Affairs within 24 hours, in the event of an emergency spill in addition to the notification requirements at Part 2.3.6 of the CGP. Please contact: Ohkay Owingeh Tribal Police Department at 505.852.2757.

*Please contact:*
*Ohkay Owingeh*
*Tribal Police Department*
*505.852.2757*

**c. Pueblo of Isleta**

**i.** All operators obtaining permit coverage under the EPA CGP must submit a copy of the certified Notice ofIntent (NOI) to the Pueblo of Isleta at the same time it is submitted to EPA for projects occurring within the exterior boundaries of the Pueblo of Isleta. Additionally, a copy of NOI modifications and the Notice of Termination (NOT), must be provided within three business days after EPA provides electronic confirmation that the submission has been received. The Notices must be provided to the following address:

Water Quality Control OfficerPueblo of Isleta
Environment DepartmentPO Box 1270
Isleta NM 87022
505-869-7565
WQCO@isletapueblo.com

**ii.** The operator must notify the Pueblo of Isleta's Dispatch at 505-869-3030 as soon as possible and thePueblo of Isleta Water Quality Control Officer within 10 hours, in the event of a spill of hazardous ortoxic substances or if health or the

environment become endangered in addition to the notification requirements at Part 2.3.6 and at I.12.6.1 of the CGP.

**iii.** All operators obtaining permit coverage under the EPA CGP must submit an electronic copy of the Stormwater Pollution Prevention Plan (SWPPP) to the Pueblo of Isleta Water Quality Control Officer atthe above address, 30 days prior to submitting the certified NOI to EPA. If the electronic file is too largeto send through e-mail, a zip file or flash drive may be submitted.

**iv.** All operators obtaining permit coverage under the EPA CGP must give 2 days advance notice to the Pueblo of Isleta Water Quality Control Officer of any planned changes in the permitted activity whichmay result in noncompliance with permit requirements.

**v.** All operators obtaining permit coverage under the EPA CGP must post a sign or other notice of permit coverage at a safe, publicly accessible location in close proximity to the construction site. The notice mustbe located so that it is visible from the public road or tribal road that is nearest to the active part of the construction site. The sign must be maintained on-site from the time construction activities begin until final stabilization is met.

**vi.** Erosion and sediment controls shall be designed to retain sediment on-site and project-generatedwaste materials that have the potential to discharge pollutants shall not be placed on open soil oron a surface that is not stabilized. Volumes of sediment over five (5) cubic yards must be removed from the active construction site; additionally, if sediment is placed for disposal withinthe exterior boundaries of the Pueblo of Isleta, disposal must be within a tribally approved sediment disposal site.

**d. Pueblo of Laguna**

**i.** All operators obtaining permit coverage under the EPA CGP must submit an electronic copy of the certified (signed) Notice of Intent (NOI) to the Pueblo of Laguna's Environmental & Natural Resources Department (ENRD) within three business days of submittal to the EPA. Additionally, a copy of NOI modifications and the Notice of Termination (NOT), must be provided within three business days after the EPA provides electronic confirmation that the submission has been received. The NOI and NOT must be electronically submitted to info.environmental@pol-nsn.gov.

**ii.** All operators obtaining permit coverage under the EPA CGP must submit an electronic copy of the Stormwater Pollution Prevention Plan (SWPPP) to the Pueblo of Laguna's ENRD 14 days prior to the submittal of the NOI (see contact information listed above).

**iii.** The operator must provide copies of corrective actions logs and modifications made to the SWPPP as a result of inspection findings to the Pueblo of Laguna ENRD (see contact information above).

**iv.** In addition to the notification requirements of Part 2.3.6 of the CPG ***[EPA interprets this intending to refer to the CGP]***, the operator must notify the Pueblo of Laguna ENRD at 505-552-7512 in the event of an emergency spill as soon as possible.

**e. Pueblo of Sandia. The following conditions apply only to discharges on the Pueblo of Sandia Reservation:**

**i.** All operators obtaining permit coverage under the EPA CGP, must submit a copy of the certified (signed) Notice of Intent (NOI) to the Pueblo of Sandia Environment Department concurrently with submittal to the EPA. Additionally, a copy of NOI modifications and the Notice of Termination (NOT), must be provided concurrently with submittal to the EPA. The NOI and NOT must be provided electronically to the following addresses:

Electronic Addresses:

Amy Rosebrough (Water Quality Manager): rosebrough@sanidapueblo.nsn.us
Greg Kaufman (Environment Director):gkaufman@sandiapueblo.nsn.us

**ii.** All operators obtaining permit coverage under the EPA CGP, must submit an electronic copy of the Stormwater Pollution Prevention Plan (SWPPP) to the Pueblo of Sandia Environment. Department at least 14 days prior to submittal of the NOI to the Pueblo (see contact information listed above).

**iii.** If requested by the Pueblo of Sandia Environment Department, the permittee must provide additional information necessary on a case-by-case basis to assure compliance with the Pueblo of Sandia Water Quality Standards and/or applicable Federal Standards.

**iv.** An "Authorization to Proceed Letter" with site specific mitigation requirements may be sent out to the permittee when a review of the NOI and SWPPP, on a case-by-case basis, is completed by the Pueblo of Sandia Environment Department. This approval will allow the application to proceed if all mitigation requirements are met.

**v.** The Pueblo of Sandia will not allow Small Construction Waivers (Appendix C) to be granted for any small construction activities.

**vi.** The operator must provide copies of inspection reports, a copy of the corrective action log, and modifications made to the SWPPP as a result of inspection findings to the Pueblo of Sandia Environment Department upon request. An inspection report and corrective action log must be submitted to the Pueblo within 3 days of any inspection that results in corrective action (see contact information listed above).

**vii.** The operator must notify the Pueblo of Sandia within 24 hours in the event of an emergency spill, in addition to the notification requirements at Part 2.3.6 of the COP (see contact information listed above).

**viii.** Before submitting a Notice of Termination (NOT) to the EPA, permittees must clearly demonstrate to the Pueblo of Sandia Environment Department through a site visit or documentation that requirements for site stabilization have been met and any temporary erosion control structures have been removed. A short letter stating that the NOT is acceptable and all requirements have been met will be sent to the permittee to add to the permittee's NOT submission to the EPA.

**f. Pueblo of Santa Ana. The following conditions apply only to discharges on the Pueblo of Santa Ana Reservation:**

**i.** All operators obtaining permit coverage under the EPA CGP, must submit a copy of the certified (signed) Notice of Intent (NOI) to the Pueblo's Department of Natural Resources within three business days of submittal to EPA. Additionally, a copy of NOI modifications and the Notice of Termination (NOT), must be

provided within three business days after EPA provides electronic confirmation that the submission has been received. The NOI and NOT must be provided to the following address:

Regular U.S. Delivery Mail:
Pueblo of Santa Ana
Department of Natural Resources Water Resources Division
Attn: Andrew Sweetman 02 Dove Rd
Santa Ana Pueblo, NM 87004

Electronically:
Andrew Sweetman
Water Resources Division Manager Andrew.Sweetman@santaana-nsn.gov
Tammy Montoya Hydrologist
Tammy.Montoya@santaana-nsn.gov

**ii.** All operators obtaining permit coverage under the EPA CGP, must submit an electronic copyof the Stormwater Pollution Prevention Plan (SWPPP) to the to the Pueblo's Department of Natural Resources at the same time that the NOI is submitted to the tribe (see contact information listed above).

**iii.** The operator must provide copies of inspection reports, a copy of the corrective action log, and modifications made to the SWPPP as a result of inspection findings, upon request by the Pueblo's Department of Natural Resources.

**iv.** The operator must notify the Pueblo's Department of Natural Resources within 24 hours in the event of an emergency spill, in addition to the notification requirements at Part 2.3.6 of the CGP.

**g. Pueblo of Taos**

**i.** All operators obtaining permit coverage under the EPA CGP, must submit a copy of the certified (signed) Notice of Intent (NOi) to the Taos Pueblo Environmental Office and Taos Pueblo Governor's Office within three business days of submittal to EPA. Additionally, a copy of NOi modifications and the Notice of Termination (NOT), must be provided within three business days after EPA provides electronic confirmation that the submission has been received. The NOi and NOTmust be provided to the following addresses:

Honorable Governor of Taos Pueblo PO Box 1846
Taos, New Mexico 87571

Taos Pueblo Environmental Office PO Box 1846
Taos, New Mexico 87571

**ii.** All operators obtaining permit coverage under the EPA CGP, must submit an electronic copy of theStormwater Pollution Prevention Plan (SWPPP) to the Taos Pueblo Environmental Office when the NOI is submitted to the tribe. Electronic copy of SWPPP downloaded on flash drive may be sent to the above address for the Taos Pueblo Environmental Office.

**iii.** The operator must provide a copy of the corrective action log following each corrective action undertaken and modifications made to the SWPPP as a result of

a corrective action to the Taos Pueblo Environmental Office at address listed above.

**h. Pueblo of Tesuque.**

**i.** All operators obtaining permit coverage under the EPA CGP, must submit a copy of the certified (signed) Notice of Intent (NOI) to the Pueblo of Tesuque Department of Environment and Natural Resources (DENR) and the Pueblo's Governor within three business days of submittal to EPA. Additionally, a copy of any NOi modifications and the Notice of Termination (NOT), must be provided within three business days after EPA provides electronic confirmation that the submission has been received. The NOI and NOT must be provided to the following address:

Governor Mark Mitchell Pueblo of Tesuque
20 TP 828
Santa Fe, NM 87506 governor@puebloftesuque.org

Sage Mountain.flower Pueblo of Tesuque
Department of Environment and Natural Resources Director
20 TP 828

**ii.** All operators obtaining permit coverage under the EPA CGP, must submit an electronic copyof the Stormwater Pollution Prevention Plan (SWPPP) to Pueblo of Tesuque DENR and the Pueblo's Governor at the same time that the NO! is submitted to the EPA (see contact information listed above).

**iii.** The operator must provide a copy of the corrective action log, and any modifications made tothe SWPPP as a result of inspection findings, or upon request by the Pueblo of Tesuque DENR.

**iv.** The operator must notify the Pueblo of Tesuque DENR within 24 hours in the event of an emergency spill, in addition to the notification requirements at Part 2.3.6 of the CGP (seecontact information listed above).

**i. Santa Clara Indian Pueblo.**

**i.** All operators obtaining permit coverage under the EPA CGP, must submit a copy of the certified (signed) Notice of Intent (NOI) to the Santa Clara Pueblo Office of Environmental Affairs at the same time the NOI is submitted to the U.S. EPA. Additionally, a copy of the NOI modifications and the Notice of Termination (NOT), must be provided at the same time after electronic confirmation is received from EPA that the NOT has been accepted. The NOI and NOT shall be provided to the following address in electronic format:

Dino Chavarria,
Santa Clara Pueblo
Office of Environmental Affairs
dinoc@santaclarapueblo.org

**ii.** All operators obtaining permit coverage under the EPA CGP, must submit an electronic copy of the Stormwater Pollution Prevention Plan to the Santa Clara Pueblo Office of Environmental Affairs at the same time the NOI is submitted to the U.S. EPA (see contact information listed above).

**iii.** The operator must notify the Santa Clara Pueblo Office of Environmental Affairs at the address above within 24 hours, in the event of an emergency spill, in addition to the notification requirements at Part 2.3.6 of the CGP

**9.6.3 OKR10I000 Indian country within the State of Oklahoma, except areas of Indian country covered by an extension of state program authority pursuant to Section 10211 of the Safe, Accountable, Flexible, Efficient Transportation Equity Act (SAFETEA).**

**a. Pawnee Nation. The following conditions apply only to discharges within Pawnee Indian country:**

**i.** Copies of the Notice of Intent (NOI) and Notice of Termination (NOT) must be provided to the Pawnee Nation at the same time it is submitted to the Environmental Protection Agency to the following address:

Pawnee Nation Department of Environmental Conservation and Safety
P.O. Box 470
Pawnee, OK 74058
Or email to dnrs@pawneenation.org

**ii.** An electronic copy of the Storm Water Pollution Prevention Plan (SWPPP) must be submitted to the Pawnee Nation Department of Environmental Conservation and Safety at the same time the NOI is submitted.

**iii.** The operator must provide access to the site for inspections and for copies of inspection reports, copy of the corrective action log and modifications, made to the SWPPP because of inspection findings, upon request by the Pawnee Nation DECS.

**iv.** The Pawnee Nation Department of Environmental Conservation and Safety must be notified at 918.762.3655 immediately upon discovery of any noncompliance with any provision of the permit conditions.

**9.6.4 OKR10F000 Discharges in the State of Oklahoma that are not under the authority of the Oklahoma Department of Environmental Quality, or the Oklahoma Department of Agriculture and Forestry including activities associated with oil and gas exploration, drilling, operations, and pipelines (includes SIC Groups 13 and 46, and SIC codes 492 and 5171), and point source discharges associated with agricultural production, services, and silviculture (includes SIC Groups 01, 02, 07, 08, 09).**

**a.** For activities located within the watershed of any Oklahoma Scenic River, including the Illinois River, Flint Creek, Barren Fork Creek, Upper Mountain Fork, Little Lee Creek, and Lee Creek or any water or watershed designated "ORW" in Oklahoma's Water Quality Standards, this permit may only be used to authorize discharges from temporary construction activities. Certification is denied for any on-going activities such as sand and gravel mining or any other mineral mining.

**b.** For activities located within the watershed of any Oklahoma Scenic River, including the Illinois River, Flint Creek, Barren Fork Creek, Upper Mountain Fork, Little Lee Creek, and Lee Creek or any water or watershed designated "ORW" in Oklahoma's Water Quality Standards, certification is denied for any discharges originating from support activities, including, but not limited to, concrete or asphalt batch plants, equipment staging yards, material storage areas, excavated material disposal areas, or borrow areas.

**c.** Dewatering discharges into sediment or nutrient-impaired waters, and waters identified as Tier 2, Tier 2.5, or Tier 3 (OAC 785:46-13) shall be controlled to meet water quality standards for turbidity in those waters as follows:

**i.** Cool Water Aquatic Community/Trout Fisheries: 10 NTUs (OAC 785: 45-5-12(f)(7)(A)(i)

**ii.** Lakes: 25 NTUs (OAC 785: 45-5-12(f)(7)(A)(ii)

**iii.** In waters where background turbidity exceeds these values, turbidity from dewatering discharges should be restricted to not exceed ambient levels (OAC 785: 45-5-12(f)(7)(B)

### 9.7 EPA REGION 7

No additional conditions.

### 9.8 EPA REGION 8

#### 9.8.1 MTR10I000 Indian country within the State of Montana

**a. Blackfeet Nation.**

**i.** The Applicant and applicants for projects authorized under the NWPs should obtain all other permits, licenses, and certifications that may be required by federal, state, or tribal authority. Primary relevant tribal permit will be ALPO (Ordinance 117). Others may apply. It is the applicant's responsibility to know the tribal and local ordinances and complete all necessary permissions before they can commence work.

**ii.** If a project is unable to meet the enclosed conditions, or if certification is denied for an applicable NWP, the Applicant may request an individual certification from Blackfeet. An individual certification request must follow the requirements outlined in 40 CFR 121.5 of EPA's CWA § 401 Certification Rule, effective September 11, 2020.

**iii.** Copies of this certification should be kept on the job site and readily available for reference.

**iv.** If the project is constructed and/or operated in a manner not consistent with the applicable NWP, general conditions, or regional conditions, the permittee may be in violation of this certification.

**v.** Blackfeet and EPA representatives may inspect the authorized activity and any mitigation areas to determine compliance with the terms and conditions of the NWP.

**vi.** This NWP Reissuance does not reduce Tribal authority under any other rule.

**vii.** The project, including any stream relocations and restoration, must be built as shown and as otherwise described in the application, the construction plans, cross sections, mitigation plans and other supporting documents submitted to this office. Impacts to aquatic systems and restoration efforts will be monitored by an appropriate aquatic resource professional to ensure that disturbed areas are restored to at least their original condition.

**viii.** All existing water uses will be fully maintained during and after the completion of the project. (If applicable)

**ix.** Where practicable, perform all in-channel and wetland work during periods of low flow or drawn—down or when dry

**x.** Equipment staging areas must be located out of all delineated wetlands

**xi.** Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during and immediately after construction, and all exposed soil and other fills, as well as any work below the ordinary high-water mark or in a wetland, must be permanently stabilized as soon as possible

**xii.** Materials such as piling, culverts, sandbags, fabric, mats, timbers used for temporary facilities in wetlands or below the high- water mark of Waters of the US must be free from oil, gas, excess dirt, loose paint and other pollutants.

**xiii.** Equipment staging areas in wetlands or in stream or river channels must be placed on mats, or other measures must be taken to minimize soil disturbance and compaction.

**xiv.** Clearing of riparian or wetland vegetation for the sole purpose of constructing work bridges, detours, staging areas or other temporary facilities must be limited to the absolute minimum necessary. When temporary impacts to native riparian or wetland vegetation are unavoidable, it must be mowed or cut above ground with the topsoil and root mass left intact.

**xv.** Remove all temporary fills and structures in the entirety when they are no longer needed. Restore affected areas to the appropriate original and planned contours where possible. Re-vegetate disturbed areas with appropriate native species when native species are impacted.

**xvi.** Construction methods and best management practices (BMPs) must minimize aquatic resource impacts to the maximum extent possible. Any BMPs described in the Joint Application must be followed. BMPs should include installation and maintenance of sediment control measures; separation, storage and reuse of any topsoil; and recovery of all disturbed areas where possible. All best management practices must in place prior to the onset of construction or as soon as practicable during the construction process.

**xvii.** Best available technology and/or best management practices must be utilized to protect existing water uses and maintain turbidity and sedimentation at the lowest practical level.

**xviii.** Applicant/contractor should manage disturbed streambank topsoil in a manner that optimizes plant establishment for the site.

**xix.** When operating equipment or otherwise undertaking construction in wetlands and water bodies the following conditions apply:

(a) Work should be done in dry conditions if possible.

(b) All equipment is to be inspected for oil, gas, diesel, anti-freeze, hydraulic fluid or other petroleum leaks. All such leaks will be properly repaired and equipment cleaned prior to being allowed on the project site. Leaks that occur after the equipment is moved to the project site will be fixed the same day or the next day or removed from the project area. The equipment is not allowed to continue operation once a leak is discovered.

(c) All equipment is to be inspected and cleaned before and after use to minimize the spread or introduction of invasive or undesirable species.

(d) Construction equipment shall not operate below the existing water surface except as follows:

- Impacts from construction should be minimized through the use of best management practices submitted in the permit application.
- Essential work below the waterline shall be done in a manner to minimize impacts to aquatic system and water quality.

(e) Containment booms and/or absorbent material must be available onsite. Any spills of petroleum products must be reported to the Army Corps, Blackfeet Nation BEO Office and the US EPA within 24 hours.

**xx.** Upland, riparian and in-stream vegetation should be protected except where its removal is necessary for completion of work. Revegetation should be completed as soon as possible. Applicant/contractor should revegetate disturbed soil in a manner that optimizes plant establishment for the site. Revegetation must include topsoil replacement, planting, seeding, fertilization, liming and weed-free mulching as necessary. Applicant must use native plant material and soils where appropriate and feasible. This certification does not allow for the introduction of non-native flora and fauna. All disturbed surface areas must be restored to pre-construction contours and elevation.

**xxi.** Spoils piles should not be placed or stored within the delineated wetlands or streams unless protected by a temporary structure designed to divert and handle high flows that can be anticipated during permit activity. Spoils piles should be placed on landscaping fabric or some other material to separate spoils material and allow retrieval of spoils material with minimal impact.

**xxii.** Impacts to wetlands shall not exceed 4.92 acres.

**xxiii.** Any unexpected and additional impacts to waters of the US should be reported to the

**xxiv.** Army Corps, Blackfeet Environmental Office Water Quality Coordinator and the US EPA.

**xxv.** All instream and stream channel reconstruction work must be completed before the stream is diverted into the new channel.

**xxvi.** Any temporary crossings, bridge supports, cofferdams, or other structures that are necessary during permit activity should be designed to handle high flows that can be anticipated during permit activity. All temporary structures should be completely removed from the water body at the conclusion of the permitted activity and the area restored to a natural function and appearance.

**xxvii.** The certification does not authorize any unconfined discharge of liquid cement into the waters of the United States. Grouting riprap must occur under dry conditions with no exposure of wet concrete to the water body.

**xxviii.** BMPs shall include application of certified weed-free straw or hay across all disturbed wetland areas that are temporarily impacted; installation and maintenance of sediment control measures during construction and if necessary, after construction is completed; use of heavy mud mats if necessary; separation,

storage and reuse of all streambank topsoil and wetland topsoil, as appropriate; and recovery of all disturbed wetland and streambank areas where possible. All conditions set by the Blackfeet Tribe and US Army Corps must be followed.

**xxix.** All applicants, including federal agencies, must notify EPA and the Blackfeet Environmental Office of the use of all NWPs for which certification has been granted prior to commencing work on the project. Notifications must include:

(a) project location (lat. Long., exact point on map);

(b) NWP that will be used and the specific activity that will be authorized under the NWP;

(c) amount of permanent and temporary fills;

(d) a short summary of the proposed activity, and all other federal, state, tribal or local permits or licenses required for the project;

(e) complete contact information of both the applicant and contractor (name, name of the company or property if applicable, telephone, mobile, and email); and,

(f) Summary of best management practices that will be used.

(g) A summary of communications with the affected Tribe's water quality staff regarding the project, including any concerns or issues.

(h) Notify Blackfeet and EPA at least 7 days before the completion of construction and operations begin.

**xxx.** Point source discharges may not occur: (1) in fens, bogs or other peatlands; (2) within 100 feet of the point of discharge of a known natural spring source; or (3) hanging gardens.

**xxxi.** Except as specified in the application, no debris, silt, sand, cement, concrete, oil or petroleum, organic material, or other construction related materials or wastes shall be allowed to enter into or be stored where it may enter into waters of the U.S.

**xxxii.** Silt fences, straw wattles, and other techniques shall be employed as appropriate to protect waters of the U.S. from sedimentation and other pollutants.

**xxxiii.** Water used in dust suppression shall not contain contaminants that could violate water quality standards.

**xxxiv.** Erosion control matting that is either biodegradable blankets or loose-weave mesh must be used to the maximum extent practicable.

**xxxv.** All equipment used in waters of the U.S. must be inspected for fluid leaks and invasive species prior to use on a project. All fluid leaks shall be repaired and cleaned prior to use or when discovered, or if the fluid leak can't be repaired, the equipment shall not be used on site. Equipment used in waters with the possibility of aquatic nuisance species infestation must be thoroughly cleaned and effectively decontaminated before they are used on the project.

**xxxvi.** Vegetation should be protected except where its removal is necessary for completion of the work. Locations disturbed by construction activities should be revegetated with appropriate native vegetation in a manner that optimizes plant establishment for the specific site.

**xxxvii.** Revegetation may include topsoil replacement, planting, seeding, fertilization, liming, and weed-free mulching, as necessary. Where practical, stockpile weed- seed-free topsoil and replace it on disturbed areas. All revegetation materials, including plants and plant seed shall be on site or scheduled for delivery prior to or upon completion of the earth moving activities.

**xxxviii.** Activities may not result in any unconfined discharge of liquid cement into waters of the U.S. Grouting riprap must occur under dry conditions with no exposure of wet concrete to the waterbody.

**xxxix.** Activities that may result in a point source discharge shall occur during seasonal low flow or no flow periods to the extent practicable.

**xl.** The placement of material (discharge) for the construction of new dams is not certified, except for stream restoration projects.

**xli.** Any decision-maker that is required under 7.0 of the CGP to prepare a Stormwater Pollution Prevention Plan (SWPPP), must submit an electronic copy of the SWPPP to the Blackfeet Environmental Office at least 30 days before construction starts for review and approval. Any modifications to the SWPPP should be submitted to the Blackfeet Environmental Office.

**xlii.** Any Decision-maker required under Part 1.4 of the CGP to submit a Notice of Intent (NOI) to EPA for coverage under the CGP, must submit a copy of the NOI to the Blackfeet Environmental Office within three business days of submittal to EPA. Additionally, a copy of the Notice of Termination (NOT) must be provided within three business days after electronic confirmation is received from EPA that the NOT has been accepted. The NOI and NOT must be provided to the following address Gerald Wagner, Blackfeet Environmental Office Director.

62 Hospital Drive, Browning, MT 59417

beo.director@gmail.com

**b. Fort Peck Tribes.**

**i.** Any Decision-maker required under Part 1.4 of the CGP to submit a Notice of Intent (NOI) to EPA for coverage under the CGP, must submit a copy of the NOI to the Fort Peck Tribes Office of Environmental Protection within three business days of submittal to EPA. Additionally, a copy of the Notice of Termination (NOT) must be provided within three business days after electronic confirmation is received from EPA that the NOT has been accepted. The NOI and NOT must be provided to the following address:

Martina Wilson, Office of Environmental Protection Director

501 Medicine Bear Rd Poplar, MT 59255

martinawilson@fortpecktribes.net

**ii.** Any Decision-maker that is required under Part 7.0 of the CGP to prepare a Stormwater Pollution Prevention Plan (SWPPP), must submit an electronic copy of the SWPPP to the Fort Peck Tribes Office of Environmental Protection at least 30 days before construction starts for review and approval. Any modifications to the

SWPPP should be submitted to the Fort Peck Tribes Office of Environmental Protection.

**iii.** Any Decision-maker that is required under Part 8.0 of the CGP to submit a weekly, bi-weekly, and/or annual report to EPA, must submit an electronic copy of the annual report to the Fort Peck Tribes Office of Environmental Protection within three business days after submittal to EPA.

## 9.9 EPA REGION 9

### 9.9.1 CAR10I000 Indian country within the State of California

**a. Morongo Band of Mission Indians**

**i.** A copy of the Stormwater Pollution Prevention Plan (SWPPP) must be submitted (either mailed or electronically) to the MEPD no less than thirty (30) days before commencing construction activities:

Morongo Band of Mission Indians
Environmental Protection Department
12700 Pumarra Road
Banning, CA 92220
Email: epd@morongo-nsn.gov

**ii.** Copies of the Notice of Intent (NOI) and the Notice of Termination (NOT) must be sent to the MEPD at the same time they are submitted to EPA.

**iii.** Operators of an "emergency-related project" must submit notice to the MEPD within twenty- four (24) hours after commencing construction activities.

**iv.** Spills, leaks, or unpermitted discharges must be reported to the MEPD within twenty-four (24) hours of the incident, in addition to the reporting requirements of the CGP.

**v.** Projects utilizing cationic treatment chemicals (as defined in Appendix A of the CGP) within the Morongo Reservation are not eligible for coverage under this certification of the CGP.

**vi.** Facilities covered under the CGP will be subject to compliance inspections by MEPD staff, including compliance with final site stabilization criteria prior to submitting an NOI ***[EPA assumes this intended to refer to an NOT]***.

### 9.9.2 GUR100000 Island of Guam

**a.** For purposes of this Order, the term "Project Proponent" shall mean U.S. Environmental Protection Agency, and its agents, assignees, and contractors.

**b.** For purposes of this Order, the permit "Operator" shall mean any party associated with a construction project that meets either of the following two criteria:

**i.** The party has operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications (e.g. in most cases this is the owner of the site); or

**ii.** The party has day-to-day operational control of those activities at a project that are necessary to ensure compliance with the permit conditions (e.g., they are authorized to direct workers at a site to carry out activities required by the permit; in most cases this is the general contractor of the project).

Subcontractors generally are not considered operators for the purposes of this permit.

**c.** The Project Proponent shall enforce the proposed 2022 CGP and ensure that the Operator complies with the conditions of the permit at all times.[107] (40 CFR §121.11(c))

**d.** All submittals required by this Order shall be sent to the Guam Environmental Protection Agency Attn: 401 Federal Permit Manager, Non-Point Source Program, EMAS Division, 3304 Mariner Avenue, Bldg. 17-3304, Barrigada, Guam 96913, AND via email to jesse.cruz@epa.guam.gov. The submittals shall be identified with WQC Order #2021- 04 and include the COP Permit Number, certifying representative's name, title, mailing address and phone number. (§51060)(4) 2017 GWQS)

**e.** A copy of the Operator's signed Stormwater Pollution Prevention Plan (SWPPP) and signed Notice of Intent (NOI) and Notice of Termination (NOT) submitted to EPA for review and approval, shall concurrently be submitted to Guam EPA, consistent with condition A4. Coordination with Guam EPA is encouraged when the receiving water(s) for the proposed discharge is/are being identified. (§10105.B.5.d.) GSESCR; (§51060)(4) 2017 GWQS)

**f.** The Operator must comply with the conditions and requirements set forth in 22 GAR 10, Guam Soil Erosion and Sediment Control Regulations (GSESCR).

**g.** Before submitting the NOT to EPA, Operators shall comply with GSESC regulations at §10105.B10. (Stabilization of Affected Areas) and §10107.B. {Final Inspection and Approval)

**h.** All operators/owners shall comply with the general design criteria for best management practices (BMPs) acceptable for meeting the Construction and Post-construction stormwater criteria in the 2006 CNMI and Guam Stormwater Management Manual. (E.O. 2012-02)

**i.** Operating reports and monitoring and analytical data (e.g. Discharge Monitoring Reports (DMRs), follow-up monitoring reports, Exceedance Reports for Numerical Effluent Limits, etc.) submitted to EPA shall be concurrently submitted to Guam EPA, consistent with condition A4. §51060)(4) 2017 GWQS

**j.** The Operators who install a sediment basin or similar impoundment shall maintain the storage capacity of five thousand cubic feet {5,000 cu. ft.) per acre of project area tributary to the basin. (§10105.B.5.i.) GSESCR

**k.** (1) This Order does not authorize EPA to qualify Rainfall Erosivity Waivers to stormwater discharges associated with small construction activities (i.e. 1-5 acres). Operators are required to apply for an NOI for those projects eligible for coverage under the proposed 2022 CGP. An Erosion and Sediment Control Plan is required for every site that would be covered by the proposed 2022 CGP. (22 GAR §10104) The average annual rainfall for Guam and the CNMI exceeds I00 inches per year in many locations. These climatic conditions combined with the region's unique limestone, volcanic geologic formations, sensitive water resources and significant land

[107] By incorporating this condition into the permit, EPA acknowledges receipt of Guam's certification conditions.

development forces make stormwater discharges a very significant environmental and economic issue. (2006 CNMJ/Guam Stormwater Management Manual) E.O. 2012-02

(2) This Order does not authorize EPA to approve a Sediment TMDL Waiver for the Ugum River. Operators of construction activities eligible for a TMDL Waiver in lieu of coverage under the proposed 2022 CGP, shall submit a complete and accurate waiver certification as described in C.2., Appendix C - (Small Construction Waivers) to Guam EPA per condition A4., prior to notifying EPA of its intention to obtain a waiver. §51060)(4) 2017 GWQS

**l.** The Project Proponent shall submit to Guam EPA a signed Statement of Understanding of Water Quality Certification Conditions.[108] (see Attachment A for an example) per condition A4. §51060)(4) 2017 GWQS

**m.** The Operator shall comply with applicable provisions of the Guam Pesticides Act of2007 (10 GCA Chapter 50) and implementing regulations at Title 22 GAR Chapter 15 for any use and application of pesticides.

**n.** Point source discharge(s) to waterbodies under the jurisdiction of Guam EPA must be consistent with the antidegradation policy in 22 GAR §510l(b).

**o.** The operator shall carry out construction activities in such a manner that will not violate Guam Water Quality Standards (GWQS). Proposed 2022 CGP discharges are prohibited as follows:

- **i.** In Marine Waters, Category M-1 Excellent 22 GAR Chapter 5 §5102(b)(I); and
- **ii.** In Surface Waters, Category S-1 High 22 GAR Chapter 5 §5102(c)(I)

**p.** In addition to complying with construction dewatering requirements in Part 2.4 and site inspection requirements for all areas where construction dewatering is taking place in Part 4 of the proposed 2022 CGP, Operators shall comply with all dewatering conditions and requirements set forth in 22 GAR 7, Water Resources Development and Operating Regulations, to include securing Guam EPA permits prior to any dewatering activities.

**q.** The Operator shall develop and implement a Spill Prevention and Containment Plan.

**r.** The Operator shall have adequate and appropriate spill response materials on hand to respond to emergency release of oil, petroleum or any other material into waters of the territory.

**s.** Any unpermitted discharge into territorial waters or onto land with a potential for entry into territorial waters, is prohibited. If this occurs, the Operator shall immediately take the following actions:

- **i.** Cease operations at the location of the violation or spill.
- **ii.** Assess the cause of the water quality problem and take appropriate measures to correct the problem and/or prevent further environmental damage.
- **iii.** Notify Guam EPA of the failure to comply. All petroleum spills shall be reported immediately to:

[108] By incorporating this condition into the permit, EPA acknowledges receipt of Guam's certification conditions.

(a) Guam's Emergency 911 system

(b) Guam EPA's 24-Hour Spill Response Team at (671) 888-6488 or during working hours (671) 300-4751

(c) US Coast Guard Sector Guam (671) 355-4824

(d) National Response Center 1-800-424-8802

**iv.** Submit a detailed written report to Guam EPA within five days of noncompliance that describes the nature of the event corrective action taken and/or planned, steps to be taken to prevent a recurrence, results of any samples taken, and any other pertinent information.

**t.** Compliance with this condition does not relieve the Operator from responsibility to maintain continuous compliance with the terms and conditions of this Order or the resulting liability from failure to comply.

**u.** Submittal or reporting of any of this information does not provide relief from any subsequent enforcement actions for unpermitted discharges to waters of the United States.

**v.** This Order is valid for five (5) Years from Date of Certification, unless otherwise approved by the Guam EPA Administrator.

**w.** The Operator shall be required to adhere to the current Guam Coral Spawning Moratorium dates for both hard and soft corals where in-water activities and/or construction activity in close proximity with marine waters may impair water quality. These dates can be obtained from the Guam Department of Agriculture, Division of Aquatic and Wildlife Resources, or the NOAA NMFS Pacific Islands Regional Office Habitat Conservation Division.

**x.** The Operator shall provide notice to Guam EPA consistent with Condition A4:

(a) Immediately upon discovery of noncompliance with the provisions of this Order.

**y.** A Notice of Violation/Work Stop Order will be issued if certification conditions are not adhered to or when significant or sustained water quality degradation occurs. Work or discharge shall be suspended or halted until the Operator addresses environmental problems/concerns to Guam EPA's satisfaction. Guam EPA may also levy penalties and fines (10 GCA §47111). Invalidity or enforceability of one or more provisions of this certification shall not affect any other provision of this certification.

## 9.10 EPA REGION 10

### 9.10.1 IDR10I000 Indian country within the State of Idaho, except Duck Valley Reservation lands (see Region 9)

#### a. Shoshone-Bannock Tribes

**i.** Copies of the following information must be sent to the SBT-WRD:

(a) Notice of Intents (NOI)

The Notice of Intent shall be forwarded to the SBT-WRD within thirty (30) days of receipt of submitting NOI to the USEPA.

Shoshone-Bannock Tribes Water Resources Department
PO Box 306 Pima Drive
Fort Hall, ID 83203 Phone: (208) 239-4582
Fax: (208) 239-4592
Or Email ctanaka@sbtribes.com

**b.** If requested by the SBT-WRD, the permittee must submit a copy of the SWPPP to SBT-WRD within fourteen (14) days of the request.

### 9.10.2 ORR10I000 Indian country within the State of Oregon, except Fort McDermitt Reservation lands (see Region 9)

**a. Confederated Tribes of Coos, Lower Umpqua, and Siuslaw**

**i.** No activities allowed under the CGP shall result in the degradation of any Tribal waters or affect resident aquatic communities or resident or migratory wildlife species at any life stage.

**ii.** The operator shall be responsible for achieving compliance with CTCLUSI Water Quality Standards and all other tribal codes, regulations, and laws as they exist at the time that the permit is submitted.

**iii.** The operator shall submit a copy of the Notice of Intent (NOI) to be covered by the general permit to the CTCLUSI Water Quality Program before, or at the same time as, it is submitted to EPA.

**iv.** The operator shall be responsible for submitting all Stormwater Pollution Prevention Plans (SWPPP) required under this general permit to the CTCLUSI Water Quality Program for review and determination that the SWPPP is sufficient to meet Tribal Water Quality Standards, prior to the beginning of any discharge activities taking place.

**v.** The operator shall be responsible for reporting an exceedance to Tribal Water Quality Standards to the CTCLUSI Water Quality Program at the same time it is reported to EPA.

**vi.** The THPO will be provided 30 days to comment on the APE as defined in the permit application.

**vii.** If the project is an undertaking, a cultural resource assessment must occur. All fieldwork must be permitted by the THPO (as appropriate), conducted by qualified personnel (as outlined by the Secretary of Interior's Standards and Guidelines; http://www.nps.gov/history/local-law/arch_stnds_O.htm) and documented according to Oregon Reporting Standards (Reporting_Guidelines.pdf) (oregon.gov). The resulting report must be submitted to the THPO and the THPO must concur with the finding of effect and recommendations before any ground disturbing work can occur. The THPO requires 30 days to review all reports.

**viii.** The operator must obtain THPO concurrence in writing. If historic properties are present, this written concurrence will outline measures to be taken to prevent or mitigate adverse effects to historic properties.

**b. Confederated Tribes of the Umatilla Indian Reservation**

**i.** The operator shall be responsible for achieving compliance with the

Confederated Tribes of the Umatilla Indian Reservation's (CTUIR) Water Quality Standards.

**ii.** The operator shall submit a copy of the Notice of Intent (NOI) to be covered by the general permit to the CTUIR Water Resources Program at the address below, at the same time it is submitted to EPA.

**iii.** The operator shall be responsible for submitting all Stormwater Pollution Prevention Plans (SWPPP) required under this general permit to the CTUIR Water Resources Program for review and determination that the SWPPP is sufficient to meet Tribal Water Quality Standards, prior to the beginning of any discharge activities taking place.

**iv.** The operator shall be responsible for reporting an exceedance to Tribal Water QualityStandards to the CTUIR Water Resources Program at the same time it is reported to EPA.

Confederated Tribes of the Umatilla Indian Reservation
Water Resources Program
46411 Timíne Way
Pendleton, OR 97801
(541) 429-7200

**v.** The THPO will be provided 30 days to comment on the APE as defined in the permit application.

**vi.** If the project is an undertaking, a cultural resource assessment must occur. All fieldwork must be permitted by the Tribal Historic Preservation Office (as appropriate), conducted by qualified personnel (as outlined by the Secretary of Interior's Standards and Guidelines; http://www.nps.gov/history/local-law/arch_stnds_0.htm) and documented according to Oregon Reporting Standards (Reporting_Guidelines.pdf (oregon.gov). The resulting report must be submitted to the THPO and the THPO must concur with the finding of effect and recommendations before any ground disturbing work can occur. The THPO requires 30 days to review all reports.

**vii.** The operator must obtain THPO concurrence in writing. If historic properties are present, this written concurrence will outline measures to be taken to prevent or mitigate adverse effects to historic properties.

### 9.10.3 WAR10F000 Areas in the State of Washington, except those located on Indian country, subject to construction activity by a Federal Operator

**a.** For purposes of this Order, the term "Project Proponent" shall mean those that are seeking coverage under this permit, and its agents, assignees and contractors.

**b.** The Federal Agency shall mean the US Environmental Protection Agency. The Federal Agency shall enforce the permit and ensure that the Project Proponent complies with the conditions of the permits at all times.

**c.** Failure of any person or entity to comply with this Certification may result in the issuance of civil penalties or other actions, whether administrative or judicial, to enforce the terms of this Certification.

**d.** The Certification conditions within this Order must be incorporated into EPA's final NPDES permit. Per 40 CFR 121.10(a), all certification conditions herein that satisfy the

requirements of 40 CFR 121.7(d) must be incorporated into the permit. Per 40 CFR 121.10(b), the permit must clearly identify all certification conditions.

**e.** This Certification does not authorize exceedances of water quality standards established in chapter 173-201A WAC.

**f.** Discharges from construction activity must not cause or contribute to violations of the Water Quality Standards for Surface Water of the State of Washington (chapter 173-201A WAC), Ground Water Quality Standards (chapter 173- 200 WAC), Sediment Management Standards (chapter 173-204 WAC), and standards in the EPA's Revision of certain Federal water quality criteria applicable to Washington (40 CFR 131.45). Discharges that do not comply with these standards are prohibited.

**g.** Prior to discharge of stormwater and non-stormwater to waters of the State, the Permittee must apply all known, available, and reasonable methods of prevention, control, and treatment (AKART). This includes the preparation and implementation of an adequate Stormwater Pollution Prevention Plan (SWPPP), with all appropriate Best Management Practices (BMPs) installed and maintained in accordance with the SWPPP and the terms and conditions of the permit.

**i.** BMPs must be consistent with:

(a) The Stormwater Management Manual for Western Washington (most current approved edition at the time this permit was issued), for sites west of the crest of the Cascade Mountains; or

(b) The Stormwater Management Manual for Eastern Washington (most current approved edition at the time this permit was issued), for sites east of the crest of the Cascade Mountains; or

(c) Revisions to either manual, or other stormwater management guidance documents or manuals which provide equivalent level of pollution prevention, that are approved by Ecology and incorporated into this permit in accordance with the permit modification requirements of WAC 173-226-230. (For purposes of this section, the stormwater manuals listed in Appendix 10 of the Phase I Municipal Stormwater Permit are approved by Ecology); or

(d) Documentation in the SWPPP that the BMPs selected provided an equivalent level of pollution prevention, compared to the applicable stormwater management manuals, including:

- The technical basis for the selection of all stormwater BMPs (scientific, technical studies, and/or modeling) that support the performance claims for the BMPs being selected.
- An assessment of how the selected BMP will satisfy AKART requirements and the applicable federal technology-based treatment requirements under 40 CFR part 125.3.

The Stormwater Management Manuals for Eastern and Western Washington can be found at: https://ecology.wa.gov/Regulations-Permits/Guidance-technical-assistance/Stormwater-permittee-guidance-resources/Stormwater-manuals.

**ii.** An adequate SWPPP must include a narrative and drawings. All BMPs must be clearly referenced in the narrative and marked on the drawings. The SWPPP

narrative must include documentation to explain and justify the pollution prevention decisions made for the project. Documentation must include:

(a) Information about existing site conditions (topography, drainage, soils, vegetation, etc.).

(b) Potential erosion problem areas.

(c) The 13 elements of a SWPPP, including BMPs used to address each element. Unless site conditions render the element unnecessary and the exemption is clearly justified in the SWPPP, the 13 elements are as follows:

- Preserve Vegetation/Mark Clearing Limits
- Establish Construction Access
- Control Flow Rates
- Install Sediment Controls
- Stabilize Soils
- Protect Slopes
- Protect Drain Inlets
- Stabilize Channels and Outlets
- Control Pollutants
- Control Dewatering
- Maintain BMPs
- Manage the Project
- Protect Low Impact Development (LID) BMPs

**h.** Discharges of stormwater and authorized non-stormwater must be monitored for turbidity (or transparency) and, in the event of significant concrete work or engineered soils, pH must also be monitored. As applicable based on project specifics, monitoring, benchmarks, and reporting requirements contained in Condition S.4. (pp.10-16) of the Washington State Construction Stormwater General Permit, effective January 1, 2021, shall apply.

**i.** Discharges to segments of waterbodies listed as impaired by the State of Washington under Section 303(d) of the Clean Water Act for turbidity, fine sediment, phosphorus, or pH must comply with the following numeric effluent limits:

| Parameter identified in 303(d) listing | Parameter Sampled | Unit | Analytical Method | Numeric Effluent Limit |
|---|---|---|---|---|
| • Turbidity<br>• Fine Sediment<br>• Phosphorus | Turbidity | NTU | SM2130 | 25 NTUs at the point where the stormwater is discharged from the site. |
| High pH | pH | su | pH meter | In the range of 6.5 – 8.5 |

All references and requirements associated with Section 303(d) of the Clean Water Act mean the most current EPA-approved listing of impaired waters that exists on the

effective date of the permit, or the date when the operator's complete permit application is received by EPA, whichever is later.

The EPA approved WQ Assessment can be found at: https://ecology.wa.gov/Water-Shorelines/Water-quality/Water-improvement/Assessment-of-state-waters-303d

**j.** Discharges to a waterbody that is subject to a Total Maximum Daily Load (TMDL) for turbidity, fine sediment, high pH, or phosphorus must be consistent with the TMDL.

- **i.** Where an applicable TMDL sets specific waste load allocations or requirements for discharges covered by this permit, discharges shall be consistent with any specific waste load allocations or requirements established by the applicable TMDL.
- **ii.** Where an applicable TMDL has established a general waste load allocation for construction stormwater discharges, but no specific requirements have been identified, compliance with this permit will be assumed to be consistent with the approved TMDL.
- **iii.** Where an applicable TMDL has not specified a waste load allocation for construction stormwater discharges, but has not excluded these discharges, compliance with this permit will be assumed to be consistent with the approved TMDL.
- **iv.** Where an applicable TMDL specifically precludes or prohibits discharges from construction activity, the operator is not eligible for coverage under this permit.

Applicable TMDL means a TMDL for turbidity, fine sediment, high pH, or phosphorus which has been completed and approved by EPA as of the effective date of the permit, or prior to the date of the operator's complete application for permit coverage is received by EPA, whichever is later.

**k.** Discharges to waters of the state from the following activities are prohibited:

- **i.** Concrete wastewater.
- **ii.** Wastewater from washout and clean-up of stucco, paint, form release oils, curing compounds and other construction materials.
- **iii.** Process wastewater as defined by 40 Code of Federal Regulations (CFR) 122.2.
- **iv.** Slurry materials and waste from shaft drilling, including process wastewater from shaft drilling for construction of building, road, and bridge foundations unless managed to prevent discharge to surface water.
- **v.** Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance.
- **vi.** Soaps or solvents used in vehicle and equipment washing.
- **vii.** Wheel wash wastewater, unless managed to prevent discharge to surface water.
- **viii.** Discharges from dewatering activities, including discharges from dewatering of trenches and excavations, unless managed according to appropriate controls described within the permit.

**l.** This Certification is valid until the expiration date including any administrative extension or termination date of the NPDES 2022 Construction General Permit. (40 CFR § 122.46)

**m.** The Federal Agency shall enforce and the Project Proponent must comply with all the reporting and notification conditions of the NPDES 2022 Construction General Permit in order to comply with this Order and the certification conditions herein (40 CFR § 121.11).

**n.** You have a right to appeal this Order to the Pollution Control Hearing Board (PCHB) within 30 days of the date of receipt of this Order. The appeal process is governed by chapter 43.21B RCW and chapter 371-08 WAC. "Date of receipt" is defined in RCW 43.21B.001(2).

To appeal you must do all of the following within 30 days of the date of receipt of this Order:

- File your appeal and a copy of this Order with the PCHB (see addresses below). Filing means actual receipt by the PCHB during regular business hours.
- Serve a copy of your appeal and this Order on Ecology in paper form - by mail or in person (see addresses below). E-mail is not accepted.

You must also comply with other applicable requirements in chapter 43.21B RCW and chapter 371-08 WAC.

**ADDRESS AND LOCATION INFORMATION**

| Street Addresses | Mailing Addresses |
|---|---|
| **Department of Ecology**<br>Attn: Appeals Processing Desk<br>300 Desmond Drive SE<br>Lacey, WA 98503<br><br>**Pollution Control Hearings Board**<br>1111 Israel RD SW<br>STE 301<br>Tumwater, WA 98501 | **Department of Ecology**<br>Attn: Appeals Processing Desk<br>PO Box 47608<br>Olympia, WA 98504-7608<br><br>**Pollution Control Hearings Board**<br>PO Box 40903<br>Olympia, WA 98504-0903 |

**CONTACT INFORMATION**

Please direct all questions about this Order to:

Noel Tamboer
Department of Ecology
P.O. Box 47600
Olympia, WA 98503-7600

(360) 701-6171
noel.tamboer@ecy.wa.gov

### 9.10.4 WAR10I000 Indian country within the State of Washington

**a. Lummi Nation**

**i.** This certification does not exempt and is provisional upon compliance with other applicable statutes and codes administered by federal and Lummi tribal agencies. Pursuant to Lummi Code of Laws (LCL) 17.05.020(a), the operator must also obtaina land use permit from the Lummi Planning Department as provided in Title 15 of theLummi Code of Laws and regulations adopted thereunder.

**ii.** Pursuant to LCL 17.05.020(a), each operator shall develop and submit a Storm WaterPollution Prevention Plan to the Lummi Water Resources Division for review and approval by the Water Resources Manager prior to beginning any discharge activities.

**iii.** Pursuant to LCL Title 17, each operator shall be responsible for achieving compliance with the Water Quality Standards for Surface Waters of the Lummi

**iv.** Indian Reservation (Lummi Administrative Regulations [LAR] 17 LAR 07.010 through 17 LAR 07.210 together with supplements and amendments thereto).

**v.** Each operator shall submit a signed copy of the Notice of Intent (NOI) to the Lummi Water Resources Division at the same time it is submitted electronically to the Environmental Protection Agency (EPA) and shall provide the Lummi Water Resources Division the acknowledgement of receipt of the NOI from the EPA and the associated NPDES tracking number provided by the EPA within 7 calendar days of receipt from the EPA.

**vi.** Each operator shall submit a signed copy of the Notice of Termination (NOT) to the Lummi Water Resources Division at the same time it is submitted electronically to the EPA and shall provide the Lummi Water Resources Division the EPA acknowledgement of receipt of the NOT.

**vii.** Storm Water Pollution Prevention Plans, Notice of Intent, Notice of Termination and associated correspondence with the EPA shall be submitted to:

Lummi Natural Resources Department
ATTN: Water Resources Manager 2665 Kwina Road
Bellingham, WA 98226-9298

**b. Port Gamble S'Klallam Tribe**

**i.** No discharge from the project site shall cause exceedances of Port Gamble S'KlallamSurface Water Quality Standards narrative or numeric criteria in Tribal waters. This includes activities outside of Tribal lands that occur upstream of Tribal waters.

(a) If any exceedance of these water quality standards occurred, the Natural Resources Department shall be notified immediately.

- The Department shall additionally be provided a complete draft of the proposed corrective action within a reasonable timeframe and its approval will be required before any corrective action may be taken.

ii. Operators performing activities under the CGP that may affect Tribal waters will requirea permit and shall submit their plans to the Port Gamble S'Klallam Natural Resources Department for review.

- The Department has the right to require conditions outside of this Water QualityCertification prior to permit approval.

**iii.** No activities allowed under the CGP shall result in the degradation of any Tribal watersor change in designated uses.

**iv.** No activities allowed under the CGP shall affect resident aquatic communities or resident/migratory wildlife species at any life stage.

- Biological assessment methods used to determine the effect of an activity allowedunder the CGP shall be approved by the PGST Natural Resources Department.

**v.** No activities allowed under the CGP shall be conducted within wetland and stream bufferzones, nor shall said activities affect in any way wetland or stream buffers, as defined by *PGST Law and Order Code 24.08.01(c)*.

**vi.** Concentrations for substances listed within the table in *Water Quality Standards for Surface Waters* sec. 7(7) shall not be exceeded by activities allowed under the CGP.

**c. Spokane Tribe of Indians**

**i.** Pursuant to Tribal Law and Order Code (TLOC) Chapter 30 each operator shall be responsible for achieving compliance with the Surface Water Quality Standards of the Spokane Tribe. The operator shall notify the Spokane Tribe, Water Control Board (WCB) of any spills of hazardous material and;

**ii.** Each operator shall submit a signed hard copy of the Notice of Intent (NOI) to the WCB at the same time it is submitted to EPA.

**iii.** The permittee shall allow the Tribal Water Control Board or its designee to inspect and sample at the construction site as needed.

**iv.** Each operator shall submit a signed copy of the Notice of Termination (NOT) to the WCB at the same time it is submitted to EPA

The correspondence address for the Spokane Tribe Water Control Board is:

Water Control Board c/o Brian Crossley PO Box480
Wellpinit WA 99040
(509)626-4409
crossley@spokanetribe.com

**d. Swinomish Tribe**

**i.** Owners and operators seeking coverage under this permit must submit a copy of the Notice of Intent (NOI) to the DEP at the same time the NOI is submitted to EPA.

**ii.** Owners and operators must also submit to the DEP changes in NOI and/or Notices of Termination at the same time they are submitted to EPA.

**iii.** Owners and operators seeking coverage under this permit must also submit a Stormwater Pollution Prevention Plan to the DEP for review and approval by DEP prior to beginning any discharge activities.

**e. Tulalip Tribes**

**i.** Submission of NOI: Copies of the Notice of Intent (NOI),) Certification shall be submitted to the Tribe's Natural Resources Department to notify the Tribes of the

pending project and in order for the Tribes to review the projects potential impacts to endangered or threatened species.

**ii.** Submission of SWPPP: A copy of the Stormwater Pollution Plans (SWPPPs) shall be submitted to the Tribe's Natural Resources Department along with the NOI during the 30 day waiting period.

**iii.** Submission of Monitoring Data and Reports: The results of any monitoring required by this permit and reports must be sent to the Tribe's Natural Resources Depa1tment,

**iv.** The Tulalip Tribes are federally recognized successors in the interest to the Snohomish, Snoqualmie, Skykomish, and other allied tribes and bands signatory to the Treaty of Point Elliott.

**v.** including a description of the corrective actions required and undertaken to meet effluent limits or benchmarks (as applicable).

**vi.** Authorization to Inspect: The Tribe's Natural Resources Department may conduct an inspection of any facility covered by this permit to ensure compliance with tribal water quality standards. The Department may enforce its certification conditions.

**vii.** Submission of Inspection Reports: Inspection reports must be sent to the Tribe's Natural Resources Department, including a description of the corrective actions required and undertaken to meet effluent limits or benchmarks (as applicable).

**viii.** Permits on-site: A copy of the pe1mit shall be kept on the job site and readily available for reference by the construction supervisor, construction managers and foreman, and Tribal inspectors.

**ix.** Project Management: The applicant shall ensure that project managers, construction managers and foreman, and other responsible parties have read and understand conditions of the permit, this certification, and other relevant documents, to avoid violations or noncompliance with this certification.

**x.** Emergency Spill Notification Requirements: In the event of a spill or the contractor shall immediately take action to stop the violation and correct the problem, and immediately repo1t spill to the Tulalip Tribes Police Department (425) 508-1565. Compliance with this condition does not relieve the applicant from responsibility to maintain continuous compliance with the tem1S and conditions of this certification or the resulting liability from failure to comply.

**xi.** Discharges to CERCLA Sites: This permit does not autho1ize direct stormwater discharges to certain sites undergoing remedial cleanup actions pursuant to the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) unless first approved by the appropriate EPA Regional office. In the case of the Tulalip Landfill site (WAD980639256), the Tulalip Tribes also requests notification by the facility and consultation with EPA prior to discharge. Contaminants at this site may include but are not limited to: dioxins, furans, arsenic, copper, lead, zinc, 4- methyl-phenol, Hex-CB, HPAHs, PCBs, PCE, cadmium, mercury, and LPAHs.

**xii.** Discharge-related Activities that have Potential to Cause an Adverse Effect on Historic Properties: Installation of stormwater controls that involve subsurface disturbances may potentially have an adverse impact on historic properties.

**xiii.** Procedures detailed in the permit shall be completed. Richard Young, of the Tulalip Tribe's Cultural Resources Department shall be contacted prior to initiating discharge- related activities that may have an impact on historic properties. His contact information is (360) 716-2652, ryoung@tulaliptribes-nsn.gov.

**xiv.** Invalidation: This certification will cease to be valid if the project is constructed and/or operated in a manner not consistent with the project description contained in

**xv.** the permit. This certification will also cease to be valid and the applicant must reapply with an updated application if info1mation contained in the permit is voided by subsequent submittals.

**xvi.** Modification: Nothing in this certification waives the Tulalip Tribes of Washington's authority to issue modifications to this ce1iification if additional impacts due to operational changes are identified, or if additional conditions are necessary to protect water quality or further protect the Tribal Communities interest.

**xvii.** incorporation by reference: TI1is certification does not exempt the applicant from compliance with other statues and codes administered by the Tribes, county, state and federal agencies.

**xviii.** Compliance with Tribe's I996 Water Quality Standards: Each permittee shall be responsible for controlling discharges and achieving compliance with the T1ibe's Water Quality Standards.

**xix.** Compliant with Tulalip Tribes Tidelands Management Policy: Permittee shall be responsible for achieving compliance with applicable sections of the Tulalip Tribe's Tidelands Management Policy. (Tulalip Tribal Code Title 8 Chapter 8.30).

**xx.** Compliant with Tulalip Tribes Environmental Infractions: Permittee shall be responsible for achieving compliance with applicable sections of the Tulalip Tribe's Environmental Infractions. (Tulalip Tribal Code Title 8 Chapter 8.20).

**xxi.** Where to Submit information and for further Coordination: All requested documents should be sent to the: Tulalip Tribes Natural Resources Environmental Department c/o Kurt Nelson and Valerie Streeter, 6704 Marine Drive, Tulalip, Washington 98271. For further 40 I Certification coordination with the Tulalip Tribes Natural Resources Department, please contact Mr. Kurt Nelson (360) 716-4617 knelson@tu1aliptribes- nsn.gov. 6406 Marine Dr., Tulalip WA 98271.

**f. Makah Tribe**

**i.** The permittee shall be responsible for meeting any additional permit requirements imposed by EPA necessary to comply with the Makah Tribe's Water Quality Standards if the discharge point is located within the Makah's U&A treaty reserved areas.

**ii.** Each permittee shall submit a copy of the Notice of Intent (NOI) to be covered by the general permit to Makah Fisheries Management, Water Quality Department at the address listed below at the same time it is submitted to the EPA.

Makah Water Quality
Makah Fisheries Management (MFM)
ray.colby@makah.com

PO Box 115
Neah bay, WA 98357

**iii.** All supporting documentation and certifications in the NOI related to coverage under the general permit for Endangered Species Act purposes shall be submitted to the Tribe's Habitat programs for their review.

**iv.** If EPA requires coverage under an individual or alternative permit, the permittee shall submit a copy of the permit to Assistant Fisheries Director, ray.colby@makah.com.

**v.** The permittee shall submit all Stormwater Pollution Prevention plan (SWPP) to MFM for review and approval prior to beginning any activities resulting in a discharge to Makah tribal waters.

**vi.** The permittee shall notify Ray Colby, ray.colby@makah.com (360) 645-3150 prior to conducting inspections at construction sites generating stormwater discharges to tribal waters.

**vii.** The operator shall treat dewatering discharges with controls necessary to minimize discharges of pollutants to surface waters, or ground waters, and from stormwater runoff onsite from excavations, trenches, foundations, or storage areas. To the extent feasible, at all points where dewatering is discharged, comply with the velocity dissipation using check dams, sediment traps, and grouted outlets.

**g. Puyallup Tribe of Indians**

**i.** The permittee shall be responsible for meeting any additional permit requirements imposed by EPA necessary to comply with the Puyallup Tribe's antidegradation procedures.

**ii.** Each permittee shall submit a copy of the Notice of Intent (NOI) to be covered by the general permit to Char Naylor, Tribal Water Quality Manager at the following e-mail address: (char.naylor@puyalluptribe-nsn.gov) at the same time it is submitted to EPA.

**iii.** All supporting documentation and certifications in the NOI related to coverage under the general permit for Endangered Species Act purposes shall be submitted to Char Naylor, Tribal Water Quality Manager/Assistant Fisheries Director (char.naylor@puyalluptribe-nsn.gov) for review.

**iv.** If EPA requires coverage under an individual or alternative permit, the permittee shall submit a copy of the permit to Char Naylor at the email address listed above.

**v.** The permittee shall submit all stormwater pollution prevention plans to Char Naylor for review and approval prior to beginning any activities resulting in a discharge to Puyallup tribal waters.

**vi.** The permittee shall contact Brandon Reynon (Brandon.reynon@puyalluptribe-nsn-gov), Tribe's Historic Preservation Officer or Jennifer Keating (Jennifer.keating@puyalluptribe-nsn.gov), Tribe's Assistant Historic Preservation Officer regarding historic properties and cultural resources.

**vii.** To minimize the discharge of pollutants to groundwater or surface waters from stormwater that is removed from excavations, trenches, foundations, vaults, or

other storage areas, treat dewatering discharges with controls necessary to minimize discharges of pollutants. Examples of appropriate controls include sediment basins or sediment traps, sediment socks, dewatering tanks, tube settlers, weir tanks, and filtration systems (e.g., bag or sand filters) that are designed to remove sediment.

To the extent feasible, utilize vegetated, upland areas of the site to infiltrate dewatering water before discharge. At all points where dewatering water is discharged, utilize velocity dissipation controls. Examples of velocity dissipation devices include check dams, sediment traps, riprap, and grouted riprap at outlets.

**viii.** The permittee shall provide and maintain natural buffers to the maximum extent possible (and/or equivalent erosion and sediment controls) when tribal waters are located within 100 feet of the boundaries. If infeasible to provide and maintain an undisturbed 100 foot natural buffer, erosion and sediment controls to achieve the sediment load reduction equivalent to a 100-foot undisturbed natural buffer shall be required.

# Appendix A - Definitions and Acronyms

## 1. Definitions

"Action Area" – all areas to be affected directly or indirectly by the Federal action and not merely the immediate area involved in the action. See 50 CFR 402. For the purposes of this permit and for application of the threatened and endangered species protection eligibility requirements, the following areas are included in the definition of action area:

- The areas on the construction site where stormwater discharges originate and flow toward the point of discharge into the receiving waters. This includes:
    - areas on the construction site where excavation, site development, or other ground disturbance activities occur, and
    - areas where stormwater controls will be constructed and operated, including any areas where stormwater flows to and from the stormwater controls.
- The areas in the vicinity of the construction site where stormwater discharges flow from the construction site to one or more points of discharge into receiving waters. (Example: Where stormwater flows into an off-site ditch, swale, or gully that leads to receiving waters.
- The extent of the receiving water potentially affected by stormwater discharges from your construction site through alteration of water chemistry, turbidity, temperature, or bank structure (i.e., erosive flow), regardless of whether the construction site is adjacent to the receiving water.

"Agricultural Land" - cropland, grassland, rangeland, pasture, and other agricultural land, on which agricultural and forest-related products or livestock are produced and resource concerns may be addressed. Agricultural lands include cropped woodland, marshes, incidental areas included in the agricultural operation, and other types of agricultural land used for the production of livestock.

"Antidegradation Policy" or "Antidegradation Requirements" - the water quality standards regulation that requires States and Tribes to establish a three-tiered antidegradation program:

1. Tier 1 maintains and protects existing uses and water quality conditions necessary to support such uses. An existing use can be established by demonstrating that fishing, swimming, or other uses have actually occurred since November 28, 1975, or that the water quality is suitable to allow such uses to occur. Where an existing use is established, it must be protected even if it is not listed in the water quality standards as a designated use. Tier 1 requirements are applicable to all surface waters.
2. Tier 2 maintains and protects "high quality" waters -- waterbodies where existing conditions are better than necessary to support CWA § 101(a)(2) "fishable/swimmable" uses. Water quality can be lowered in such waters. However, State and Tribal Tier 2 programs identify procedures that must be followed and questions that must be answered before a reduction in water quality can be allowed. In no case may water quality be lowered to a level which would interfere with existing or designated uses.
3. Tier 3 maintains and protects water quality in outstanding national resource waters (ONRWs). Except for certain temporary changes, water quality cannot be lowered in such waters. ONRWs generally include the highest quality waters of the United States. However, the ONRW classification also offers special protection for waters of exceptional ecological significance, i.e., those which are important, unique, or sensitive ecologically.

Decisions regarding which water bodies qualify to be ONRWs are made by States and authorized Indian Tribes.

"Arid Areas" – areas with an average annual rainfall of 0 to 10 inches. For assistance in determining average annual rainfall in specific locations, refer to the NOAA National Mapping webpage (https://www.ncdc.noaa.gov/cag/national/mapping), the PRISM Climate Group's Time Series Values for individual locations (https://prism.oregonstate.edu/explorer/), or EPA's US EPA EnviroAtlas (https://www.epa.gov/enviroatlas).

"Bank" (e.g., stream bank or river bank) – the rising ground bordering the channel of a water of the U.S.

"Biodegradable" – capable of decomposing under ambient soil conditions into naturally occurring materials over a period of time (e.g., one year).

"Bluff" – a steep headland, promontory, riverbank, or cliff.

"Borrow Areas" – the areas where materials are dug for use as fill, either onsite or off-site.

"Business day" – for the purposes of this permit, a business day is a calendar day on which construction activities will take place.

"Bypass" – the intentional diversion of waste streams from any portion of a treatment facility. See 40 CFR 122.41(m)(1)(i).

"Cationic Treatment Chemical" – polymers, flocculants, or other chemicals that contain an overall positive charge. Among other things, they are used to reduce turbidity in stormwater discharges by chemically bonding to the overall negative charge of suspended silts and other soil materials and causing them to bind together and settle out. Common examples of cationic treatment chemicals are chitosan and cationic PAM.

"Commencement of Construction Activities" – the initial disturbance of soils (or 'breaking ground') associated with clearing, grading, or excavating activities or other construction-related activities (e.g., grubbing; stockpiling of fill material; placement of raw materials at the site).

"Common Plan of Development or Sale" – A contiguous area where multiple separate and distinct construction activities may be taking place at different times on different schedules under one common plan. The "common plan" of development or sale is broadly defined as any announcement or piece of documentation (including a sign, public notice or hearing, sales pitch, advertisement, drawing, permit application, zoning request, computer design, etc.) or physical demarcation (including boundary signs, lot stakes, surveyor markings, etc.) indicating construction activities may occur on a specific plot.

"Construction Activities" – earth-disturbing activities, such as the clearing, grading, and excavation of land, and other construction-related activities (e.g., grubbing; stockpiling of fill material; placement of raw materials at the site) that could lead to the generation of pollutants. Some of the types of pollutants that are typically found at construction sites are:

- sediment;
- nutrients;
- heavy metals;
- pesticides and herbicides;
- oil and grease;
- bacteria and viruses;
- trash, debris, and solids;

- treatment polymers; and
- any other toxic chemicals.

"Construction and Development Effluent Limitations and New Source Performance Standards" (C&D Rule) – as published in 40 CFR § 450, the regulation requiring effluent limitations guidelines (ELGs) and new source performance standards (NSPS) for controlling the discharge of pollutants from construction sites.

"Construction Site" or "Site" – the land or water area where construction activities will occur and where stormwater controls will be installed and maintained. The construction site includes construction support activities, which may be located at a different part of the property from where the primary construction activity will take place, or on a different piece of property altogether.

"Construction Support Activity" – a construction-related activity that specifically supports the construction activity and involves earth disturbance or pollutant-generating activities of its own, and can include activities associated with concrete or asphalt batch plants, equipment staging yards, materials storage areas, excavated material disposal areas, and borrow areas.

"Construction Waste" – discarded material (such as packaging materials; scrap construction materials; masonry products; timber, steel, pipe, and electrical cuttings; plastics; and styrofoam).

"Conveyance Channel" – a temporary or permanent waterway designed and installed to safely convey stormwater flow within and out of a construction site.

"Critical Habitat" – as defined in the Endangered Species Act at 16 U.S.C. 1531 for a threatened or endangered species, (i) the specific areas within the geographical area occupied by the species, at the time it is listed in accordance with the provisions of section 4 of the Endangered Species Act, on which are found those physical or biological features essential to the conservation of the species and which may require special management considerations or protection; and (ii) specific areas outside the geographical area occupied by the species at the time it is listed in accordance with the provisions of section 4 of the Endangered Species Act, upon a determination by the Secretary that such areas are essential for the conservation of the species.

"CWA" – the Clean Water Act or the Federal Water Pollution Control Act, 33 U.S.C. section 1251 et seq.

"Dewatering" – the act of draining accumulated stormwater and/or ground water from building foundations, vaults, and trenches, or other similar points of accumulation. Examples can include, but are not limited to:

- Surface area dewatering: water pumped from disturbed surface areas (e.g., trenches, sumps, excavation pits, or other excavations associated with construction where sediment-laden ground water or surface water/storm inflow must be removed) or from sediment basins or similar impoundments for maintenance or decommissioning purposes.
- Ground water dewatering: water discharged from well development, well pump tests, or pumping of ground water from a construction area. Common methods of ground water dewatering from a construction area include sumps and wells, generally described as follows:
  - Sumps: lowers ground water levels near the construction area. Dewatering using sumps consists of pumping ground water out of a lower collection point(s) typically gravity-fed by local ground water.
  - Wells: drilled wells, including bored/augured, driven, or jetted, which use vacuum or pumping to lower the ground water at greater depths than sumps. The two most common types of wells used for dewatering ground water are:

- Wellpoints: small-diameter shallow wells which are connected via a header pipe. A pump creates a vacuum in the header pipe.
- Deep Wells: larger-diameter holes, drilled relatively deep (typically greater than 10 feet), pumped by submersible electric pumps.

"Dewatering Water" – as used in this permit, water discharged from dewatering operations.

"Discharge" – when used without qualification, means the "discharge of a pollutant."

"Discharge of a Pollutant" – any addition of any "pollutant" or combination of pollutants to "waters of the United States" from any "point source," or any addition of any pollutant or combination of pollutants to the waters of the "contiguous zone" or the ocean from any point source other than a vessel or other floating craft which is being used as a means of transportation. This includes additions of pollutants into waters of the United States from: surface runoff which is collected or channeled by man; discharges through pipes, sewers, or other conveyances, leading into privately owned treatment works. See 40 CFR 122.2.

"Discharge Point" – for the purposes of this permit, the location where collected and concentrated stormwater flows or dewatering water are discharged from the construction site.

"Discharge-Related Activity" – activities that cause, contribute to, or result in stormwater and allowable non-stormwater point source discharges, and measures such as the siting, construction, and operation of stormwater controls to control, reduce, or prevent pollutants from being discharged.

"Discharge to an Impaired Water" – for the purposes of this permit, a discharge to an impaired water occurs if the first water of the U.S. to which you discharge is identified by a State, Tribe, or EPA pursuant to Section 303(d) of the Clean Water Act as not meeting an applicable water quality standard and (1) requires development of a total maximum daily load (TMDL) (pursuant to section 303(d) of the CWA; or (2) is addressed by an EPA-approved or established TMDL; or (3) is not in either of the above categories but the waterbody is covered by a pollution control program that meets the requirements of 40 CFR 130.7(b)(1). For discharges that enter a storm sewer system prior to discharge, the water of the U.S. to which you discharge is the first water of the U.S. that receives the stormwater discharge from the storm sewer system.

"Domestic Waste" – for the purposes of this permit, typical household trash, garbage or rubbish items generated by construction activities.

"Drainageway" – an open linear depression, whether constructed or natural, that functions for the collection and drainage of surface water.

"Drought-Stricken Area" – for the purposes of this permit, an area in which the National Oceanic and Atmospheric Administration's U.S. Seasonal Drought Outlook indicates for the period during which the construction will occur that any of the following conditions are likely: (1) "Drought to persist or intensify", (2) "Drought ongoing, some improvement", (3) "Drought likely to improve, impacts ease", or (4) "Drought development likely". See http://www.cpc.ncep.noaa.gov/products/expert_assessment/sdo_summary.php.

"Earth-Disturbing Activity"– actions taken to alter the existing vegetation and/or underlying soil of a site, such as clearing, grading, site preparation (e.g., excavating, grubbing, cutting, and filling), soil compaction, and movement and stockpiling of top soils.

"Earth-Disturbing Activities Conducted Prior to Active Mining Activities" – Consists of two classes of earth-disturbing (i.e., clearing, grading and excavation) activities:

a. activities performed for purposes of mine site preparation, including: cutting new rights of way (except when related to access road construction); providing access to a mine site for vehicles and equipment (except when related to access road construction); other earth disturbances associated with site preparation activities on any areas where active mining

activities have not yet commenced (e.g., for heap leach pads, waste rock facilities, tailings impoundments, wastewater treatment plants); and

b. construction of staging areas to prepare for erecting structures such as to house project personnel and equipment, mill buildings, etc., and construction of access roads.

Note: only earth-disturbing activities associated with the construction of staging areas and the construction of access roads conducted prior to active mining (see (b) above) are considered to be "construction" and therefore stormwater discharges from these activities are eligible for coverage under this permit. See Part 1.2.1.b. The activities described in (a) above are not considered to be "construction" and therefore stormwater discharges associated with this activity are not eligible for coverage under this permit.

"Effective Operating Condition" – for the purposes of this permit, a stormwater control is kept in effective operating condition if it has been implemented and maintained in such a manner that it is working as designed to minimize pollutant discharges.

"Effluent Limitations" – for the purposes of this permit, any of the Part 2 or Part 3 requirements.

"Effluent Limitations Guideline" (ELG) – defined in 40 CFR § 122.2 as a regulation published by the Administrator under section 304(b) of the CWA to adopt or revise effluent limitations.

"Eligible" – for the purposes of this permit, refers to stormwater and allowable non-stormwater discharges that are authorized for coverage under this general permit.

"Emergency-Related Project" – a project initiated in response to a public emergency (e.g., mud slides, earthquake, extreme flooding conditions, disruption in essential public services), for which the related work requires immediate authorization to avoid imminent endangerment to human health or the environment, or to reestablish essential public services.

"Endangered Species" – defined in the Endangered Species Act at 16 U.S.C. 1531 as any species which is in danger of extinction throughout all or a significant portion of its range other than a species of the Class Insecta determined by the Secretary to constitute a pest whose protection under the provisions of this Act would present an overwhelming and overriding risk to man.

"Excursion" – a measured value that exceeds a specified limit.

"Existing Site" – a site where construction activities commenced prior to February 16, 2017.

"Exit Points" – any points of egress from the construction site to be used by vehicles and equipment during construction activities.

"Exposed Soils" – for the purposes of this permit, soils that as a result of earth-disturbing activities are left open to the elements.

"Federal Facility" – any buildings, installations, structures, land, public works, equipment, aircraft, vessels, and other vehicles and property, owned by, or constructed or manufactured for the purpose of leasing to, the Federal government.

"Federal Operator" – an entity that meets the definition of "Operator" in this permit and is either any department, agency or instrumentality of the executive, legislative, and judicial branches of the Federal government of the United States, or another entity, such as a private contractor, performing construction activity for any such department, agency, or instrumentality.

"Final Stabilization" – on areas not covered by permanent structures, either (1) uniform, perennial vegetation *(e.g., evenly distributed, without large bare areas)* has been established, or for arid or semi-arid areas, will be established that provides 70 percent or more of the cover that is provided by vegetation native to local undisturbed areas, and/or (2) permanent non-

vegetative stabilization measures (e.g., riprap, gravel, gabions, and geotextiles) have been implemented to provide effective cover for exposed portions of the site

"General Contractor" – for the purposes of this permit, the primary individual or company solely accountable to perform a contract. The general contractor typically supervises activities, coordinates the use of subcontractors, and is authorized to direct workers at a site to carry out activities required by the permit.

"Hazardous Substances" or "Hazardous or Toxic Waste" – for the purposes of this permit, any liquid, solid, or contained gas that contain properties that are dangerous or potentially harmful to human health or the environment. See also 40 CFR §261.2.

"Historic Property" – as defined in the National Historic Preservation Act regulations, means any prehistoric or historic district, site, building, structure, or object included in, or eligible for inclusion in, the National Register of Historic Places maintained by the Secretary of the Interior. This term includes artifacts, records, and remains that are related to and located within such properties. The term includes properties of traditional religious and cultural importance to an Indian Tribe or Native Hawaiian organization and that meet the National Register criteria.

"Impaired Water"– a water identified by the State, Tribe, or EPA as not meeting an applicable water quality standard and (1) requires development of a TMDL (pursuant to section 303(d) of the CWA; or (2) is addressed by an EPA-approved or established TMDL; or (3) is not in either of the above categories but the waterbody is covered by a pollution control program that meets the requirements of 40 CFR 130.7(b)(1).

"Impervious Surface" – for the purpose of this permit, any land surface with a low or no capacity for soil infiltration including, but not limited to, pavement, sidewalks, parking areas and driveways, packed gravel or soil, or rooftops.

"Indian Country" or "Indian Country Lands" – defined at 40 CFR §122.2 as:

1. All land within the limits of any Indian reservation under the jurisdiction of the United States Government, notwithstanding the issuance of any patent, and, including rights-of-way running through the reservation;
2. All dependent Indian communities with the borders of the United States whether within the originally or subsequently acquired territory thereof, and whether within or without the limits of a State; and
3. All Indian allotments, the Indian titles to which have not been extinguished, including rights-of-ways running through the same.

"Infeasible" – for the purpose of this permit, infeasible means not technologically possible or not economically practicable and achievable in light of best industry practices. EPA notes that it does not intend for any permit requirement to conflict with State water rights law.

"Install" or "Installation" – when used in connection with stormwater controls, to connect or set in position stormwater controls to make them operational.

"Jar test" – a test designed to simulate full-scale coagulation/flocculation/sedimentation water treatment processes by taking into account the possible conditions.

"Landward" – positioned or located away from a waterbody, and towards the land.

"Large Construction Activity" – defined at 40 CFR § 122.26(b)(14)(x) and incorporated here by reference. Large construction activity includes clearing, grading, and excavating resulting in a land disturbance that will disturb equal to or greater than five acres of land or will disturb less than five acres of total land area but is part of a larger common plan of development or sale that will ultimately disturb equal to or greater than five acres. Large construction activity does

not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the site.

"Linear Construction Site" – includes the construction of roads, bridges, conduits, substructures, pipelines, sewer lines, towers, poles, cables, wires, connectors, switching, regulating and transforming equipment and associated ancillary facilities in a long, narrow area.

"Minimize" – to reduce and/or eliminate to the extent achievable using stormwater controls that are technologically available and economically practicable and achievable in light of best industry practices.

"Mining Activity" – for the purposes of this permit, includes mining-related construction activities defined at 40 CFR 122.26(b)(14)(x) and 122.26(b)(15)(i), and active mining activities defined at 40 CFR 122.26(b)(14)(iii). Both of these sub categories of activities include earth-disturbing activities, with the latter also including such activities as: extraction, removal or recovery, and beneficiation of mined material from the earth; removal of overburden and waste rock to expose mineable material; and site reclamation and closure activities.

"Mining Operations" – for the purposes of this permit, mining operations are grouped into two distinct categories, with distinct effluent limits and requirements applicable to each: 1) earth-disturbing activities conducted prior to active mining activities; and 2) active mining activities, which includes reclamation.

"Municipal Separate Storm Sewer System" or "MS4" – defined at 40 CFR §122.26(b)(8) as a conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, manmade channels, or storm drains):

1. Owned and operated by a State, city, town, borough, county, parish, district, association, or other public body (created by or pursuant to State law) having jurisdiction over disposal of sewage, industrial wastes, stormwater, or other wastes, including special districts under State law such as a sewer district, flood control district or drainage district, or similar entity, or an Indian Tribe or an authorized Indian Tribal organization, or a designated and approved management agency under section 208 of the CWA that discharges to waters of the United States;
2. Designed or used for collecting or conveying stormwater;
3. Which is not a combined sewer; and
4. Which is not part of a Publicly Owned Treatment Works (POTW) as defined at 40 CFR §122.2.

"National Pollutant Discharge Elimination System" (NPDES) – defined at 40 CFR §122.2 as the national program for issuing, modifying, revoking and reissuing, terminating, monitoring and enforcing permits, and imposing and enforcing pretreatment requirements, under sections 307, 402, 318, and 405 of CWA. The term includes an 'approved program.'

"Native Topsoil" – the uppermost layer of naturally occurring soil for a particular area, and is often rich in organic matter, biological activity, and nutrients.

"Natural Buffer" – for the purposes of this permit, an area of undisturbed natural cover surrounding waters of the United States within which construction activities are restricted. Natural cover includes the vegetation, exposed rock, or barren ground that exists prior to commencement of earth-disturbing activities.

"Natural Vegetation" – vegetation that occurs spontaneously without regular management, maintenance, or species introductions or removals, and that generally has a strong component of native species..

"New Operator of a Permitted Site" – an operator that through transfer of ownership and/or operation replaces the operator of an already permitted construction site that is either a "new site" or an "existing site".

"New Site" – a site where construction activities commenced on or after February 16, 2017.

"New Source" – for the purposes of this permit, a construction project that commenced construction activities after February 1, 2010.

"New Source Performance Standards (NSPS)" – for the purposes of this permit, NSPS are technology-based standards that apply to construction sites that are new sources under 40 CFR 450.24.

"Non-Stormwater Discharges" – discharges that do not originate from storm events. They can include, but are not limited to, discharges of process water, air conditioner condensate, non-contact cooling water, vehicle wash water, sanitary wastes, concrete washout water, paint wash water, irrigation water, or pipe testing water.

"Non-Turbid" – a discharge that is free from visual turbidity.

"Notice of Intent" (NOI) – the form (electronic or paper) required for authorization of coverage under the Construction General Permit.

"Notice of Termination" (NOT) – the form (electronic or paper) required for terminating coverage under the Construction General Permit.

"NPDES eReporting Tool" (NeT) – EPA's online system for submitting electronic Construction General Permit forms.

"Operational" – for the purposes of this permit, stormwater controls are made "operational" when they have been installed and implemented, are functioning as designed, and are properly maintained.

"Operator" – for the purposes of this permit and in the context of stormwater discharges associated with construction activity, any party associated with a construction project that meets either of the following two criteria:

1. The party has operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications *(*e.g. *in most cases this is the owner of the site)*; or
2. The party has day-to-day operational control of those activities at a project that are necessary to ensure compliance with the permit conditions (e.g.*, they are authorized to direct workers at a site to carry out activities required by the permit; in most cases this is the general contractor of the project)*.

This definition is provided to inform permittees of EPA's interpretation of how the regulatory definitions of "owner or operator" and "facility or activity" are applied to discharges of stormwater associated with construction activity. Subcontractors generally are not considered operators for the purposes of this permit.

"Ordinary High Water Mark" – the line on the shore established by fluctuations of water and indicated by physical characteristics such as a clear, natural line impressed on the bank, shelving, changes in the character of soil, destruction of terrestrial vegetation, and/or the presence of litter and debris.

"Permitting Authority" – for the purposes of this permit, EPA, a Regional Administrator of EPA, or an authorized representative.

"Point(s) of Discharge" – see "Discharge Point."

"Point Source" – any discernible, confined, and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock concentrated animal feeding operation, landfill leachate collection system, vessel or other floating craft from which pollutants are or may be discharged. This term does not include return flows from irrigated agriculture or agricultural stormwater runoff.

"Pollutant" – defined at 40 CFR §122.2. A partial listing from this definition includes: dredged spoil, solid waste, sewage, garbage, sewage sludge, chemical wastes, biological materials, heat, wrecked or discarded equipment, rock, sand, cellar dirt, and industrial or municipal waste.

"Pollution Prevention Controls" – stormwater controls designed to reduce or eliminate the addition of pollutants to construction site discharges through analysis of pollutant sources, implementation of proper handling/disposal practices, employee education, and other actions.

"Polymers" – for the purposes of this permit, coagulants and flocculants used to control erosion on soil or to enhance the sediment removal capabilities of sediment traps or basins. Common construction site polymers include polyacrylamide (PAM), chitosan, alum, polyaluminum chloride, and gypsum.

"Prohibited Discharges" – discharges that are not allowed under this permit, including:

1. Wastewater from washout of concrete;
2. Wastewater from washout and cleanout of stucco, paint, form release oils, curing compounds and other construction materials;
3. Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance;
4. Soaps or solvents used in vehicle and equipment washing;
5. Toxic or hazardous substances from a spill or other release; and
6. Waste, garbage, floatable debris, construction debris, and sanitary waste.

"Provisionally Covered Under this Permit" – for the purposes of this permit, EPA provides temporary coverage under this permit for emergency-related projects prior to receipt of a complete and accurate NOI. Discharges from earth-disturbing activities associated with the emergency-related projects are subject to the terms and conditions of the permit during the period of temporary coverage.

"Qualified Person" – a person knowledgeable in the principles and practice of erosion and sediment controls and pollution prevention, who possesses the appropriate skills and training to assess conditions at the construction site that could impact stormwater quality, and the appropriate skills and training to assess the effectiveness of any stormwater controls selected and installed to meet the requirements of this permit.

"Receiving Water" – a "Water of the United States" as defined in 40 CFR §122.2 into which the regulated stormwater discharges.

"Run-On" – sources of stormwater that drain from land located upslope or upstream from the regulated site in question.

"Seasonally Dry Period" – a month in which the long-term average total precipitation is less than or equal to 0.5 inches. Refer to EPA's Seasonally Dry Period Locator and supporting maps for assistance in determining whether a site is operating during a seasonally dry period for the area, located at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates.

"Sediment-Related parameter" – for the purposes of this permit, a pollutant parameter that is closely related to sediment such as turbidity, total suspended solids (TSS), total suspended sediment, transparency, sedimentation, and siltation.

"Semi-Arid Areas" – areas with an average annual rainfall of 10 to 20 inches. For assistance in determining average annual rainfall in specific locations, refer to the NOAA National Mapping webpage (https://www.ncdc.noaa.gov/cag/national/mapping), the PRISM Climate Group's Time Series Values for individual locations (https://prism.oregonstate.edu/explorer/), or EPA's US EPA EnviroAtlas (https://www.epa.gov/enviroatlas).

"Shared Control" - for the purposes of this permit, a stormwater control, such as a sediment basin or pond, used by two or more operators that is installed and maintained for the purpose of minimizing and controlling pollutant discharges from a construction site with multiple operators associated with a common plan of development or sale. Any operators that are contributing stormwater from their construction activities to a shared control are considered to rely upon a shared control.

"Small Construction Activity" – defined at 40 CFR §122.26(b)(15) and incorporated here by reference. A small construction activity includes clearing, grading, and excavating resulting in a land disturbance that will disturb equal to or greater than one (1) acre and less than five (5) acres of land or will disturb less than one (1) acre of total land area but is part of a larger common plan of development or sale that will ultimately disturb equal to or greater than one (1) acre and less than five (5) acres. Small construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the site.

"Small Residential Lot" – for the purpose of this permit, a lot being developed for residential purposes that will disturb less than 1 acre of land, but is part of a larger residential project that will ultimately disturb greater than or equal to 1 acre.

"Snowmelt" – the conversion of snow into overland stormwater and ground water flow as a result of warmer temperatures.

"Spill" – for the purpose of this permit, the release of a hazardous or toxic substance from its container or containment.

"Stabilization" – the use of vegetative and/or non-vegetative cover to prevent erosion and sediment loss in areas exposed through the construction process.

"Steep Slopes" – where a State, Tribe, local government, or industry technical manual (e.g., stormwater BMP manual) has defined what is to be considered a "steep slope", this permit's definition automatically adopts that definition. Where no such definition exists, steep slopes are automatically defined as those that are 15 percent or greater in grade.

"Storm Sewer System" – a conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, manmade channels, or storm drains) designed or used for collecting or conveying stormwater.

"Stormwater" – stormwater runoff, snowmelt runoff, and surface runoff and drainage.

"Stormwater Control" - refers to any best management practice or other method (including narrative effluent limitations) used to prevent or reduce the discharge of pollutants to waters of the United States.

"Stormwater Discharge Associated with Construction Activity" – as used in this permit, a discharge of pollutants in stormwater to waters of the United States from areas where earth-disturbing activities (e.g., clearing, grubbing, grading, or excavation) occur, or where construction materials or equipment storage or maintenance (e.g., fill piles, borrow area,

concrete truck chute washdown, fueling), or other industrial stormwater directly related to the construction process (e.g., concrete or asphalt batch plants), are located.

"Stormwater Inlet" – a structure placed below grade to conduct water used to collect stormwater runoff for conveyance purposes.

"Stormwater Team" – the group of individuals responsible for oversight of the development and modifications of the SWPPP, and oversight of compliance with the permit requirements. The individuals on the "Stormwater Team" must be identified in the SWPPP.

"Storm Event" – a precipitation event that results in a measurable amount of precipitation.

"Storm Sewer" – a system of pipes (separate from sanitary sewers) that carries stormwater runoff from buildings and land surfaces.

"Subcontractor" – for the purposes of this permit, an individual or company that takes a portion of a contract from the general contractor or from another subcontractor.

"SWPPP" (Stormwater Pollution Prevention Plan) – a site-specific, written document that, among other things: (1) identifies potential sources of stormwater pollution at the construction site; (2) describes stormwater controls to reduce or eliminate pollutants in stormwater discharges from the construction site; and (3) identifies procedures the operator will implement to comply with the terms and conditions of this general permit.

"Temporary Stabilization" – a condition where exposed soils or disturbed areas are provided temporary vegetative and/or non-vegetative protective cover to prevent erosion and sediment loss. Temporary stabilization may include temporary seeding, geotextiles, mulches, and other techniques to reduce or eliminate erosion until either final stabilization can be achieved or until further construction activities take place to re-disturb this area.

"Thawing Conditions" – for the purposes of this permit, thawing conditions are expected based on the historical likelihood of two or more days with daytime temperatures greater than 32˚F. This date can be determined by looking at historical weather data. Note: the estimation of thawing conditions is for planning purposes only. During construction the permittee will be required to conduct site inspections based upon actual conditions (i.e., if thawing conditions occur sooner than expected, the permittee will be required to conduct inspections at the regular frequency).

"Threatened Species" – defined in the Endangered Species Act at 16 U.S.C. 1531 as any species which is likely to become an endangered species within the foreseeable future throughout all or a significant portion of its range.

"Tier 2 Waters" – for antidegradation purposes, pursuant to 40 CFR 131.12(a)(2), those waters that are characterized as having water quality that exceeds the levels necessary to support propagation of fish, shellfish, and wildlife and recreation in and on the water.

"Tier 2.5 Waters" – for antidegradation purposes, those waters designated by States or Tribes as requiring a level of protection equal to and above that given to Tier 2 waters, but less than that given Tier 3 waters. Some States have special requirements for these waters.

"Tier 3 Waters" – for antidegradation purposes, pursuant to 40 CFR 131.12(a)(3), Tier 3 waters are identified by States as having high quality waters constituting an Outstanding National Resource Water (ONRW), such as waters of National Parks and State Parks, wildlife refuges, and waters of exceptional recreational or ecological significance.

"Total Maximum Daily Load" or "TMDL" – the sum of the individual wasteload allocations (WLAs) for point sources and load allocations (LAs) for nonpoint sources and natural background. If receiving water has only one point source discharger, the TMDL is the sum of that point source WLA plus the LAs for any nonpoint sources of pollution and natural background sources,

tributaries, or adjacent segments. TMDLs can be expressed in terms of mass per time, toxicity, or other appropriate measure.

"Toxic Waste" – see "Hazardous Substances."

"Treatment Chemicals" – polymers, flocculants, or other chemicals used to reduce turbidity in stormwater.

"Turbidity" – a condition of water quality characterized by the presence of suspended solids and/or organic material.

"Uncontaminated Discharge" – in the context of authorized non-stormwater discharges, a discharge that meets applicable water quality standards.

"Upland" – the dry land area above and 'landward' of the ordinary high water mark.

"Upset" – Upset means an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond your reasonable control. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation. See 40 CFR 122.41(n)(1).

"Visual Turbidity" – for the purposes of this permit, visual turbidity is present when there is a sediment plume in the discharge or the discharge appears cloudy, opaque, or has a visible contrast that can be visually identified by an observer.

"Water-Dependent Structures" – structures or facilities that are required to be located directly adjacent to a waterbody or wetland, such as a marina, pier, boat ramp, etc.

"Water Quality Standards" – defined in 40 CFR § 131.3, and are provisions of State (including Tribal) or Federal law which consist of a designated use or uses for the waters of the United States, water quality criteria for such waters based upon such uses, and an antidegradation policy to protect high-quality waters. Water quality standards protect the public health or welfare, enhance the quality of water and serve the purposes of the Act.

"Waters of the United States" – see definition at 40 CFR 122.2.

"Wetland" – those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, bogs, and similar areas. On-site evaluations are typically required to confirm the presence and boundaries of wetlands.

### 2. Acronyms

ACHP – Advisory Council on Historic Preservation

BMP – Best Management Practice

CBI – Confidential Business Information

CGP – Construction General Permit

CFR – Code of Federal Regulations

CWA – Clean Water Act

CZMA – Coastal Zone Management Act

ECHO – EPA Enforcement and Compliance History Online

ELG – Effluent Limitations Guideline

EPA – United States Environmental Protection Agency
ESA – Endangered Species Act
FR – Federal Register
MS4 – Municipal Separate Storm Sewer System
MSGP – Multi-Sector General Permit
NEPA – National Environmental Policy Act
NeT – NPDES eReporting Tool
NTU - Nephelometric turbidity units
NHPA – National Historic Preservation Act
NMFS – United States National Marine Fisheries Service
NPDES – National Pollutant Discharge Elimination System
NOI – Notice of Intent
NOT – Notice of Termination
NPDES – National Pollutant Discharge Elimination System
NRC – National Response Center
NRCS – National Resources Conservation Service
NSPS – New Source Performance Standards
ONRW – Outstanding National Resource Water
PAM – Polyacrylamide
POTW – Publicly Owned Treatment Works
RUSLE – Revised Universal Soil Loss Equation
SDS – Safety Data Sheet
SHPO – State Historic Preservation Office
SPCC – Spill Prevention Control and Countermeasure
SWPPP – Stormwater Pollution Prevention Plan
THPO – Tribal Historic Preservation Office
TMDL – Total Maximum Daily Load
TSS – Total Suspended Solids
UIC – Underground Injection Control
USDA – United States Department of Agriculture
USFWS – United States Fish and Wildlife Service
USGS – United States Geological Survey
WQS – Water Quality Standard

## Appendix B - Permit Areas Eligible for Coverage and EPA Regional Addresses

Permit coverage for stormwater discharges from construction activity occurring within the following areas is provided by legally separate and distinctly numbered permits. For assistance in determining whether your construction activities are located within Indian country, refer to the Bureau of Indian Affairs' digital map of the land areas of Federally-recognized Tribes at https://biamaps.doi.gov/indianlands/#.

### B.1 EPA Region 1

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 1:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **CTR10I000** | Indian country within the State of Connecticut |
| **MAR100000** | Commonwealth of Massachusetts (except Indian country) |
| **MAR10I000** | Indian country within the State of Massachusetts |
| **NHR100000** | State of New Hampshire |
| **RIR10I000** | Indian country within the State of Rhode Island |
| **VTR10F000** | Areas in the State of Vermont located at a Federal Facility (as defined in Appendix A) |
| **1R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 1 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 1 Address:**
U.S. EPA Region 1
Office of Ecosystem Protection
Stormwater and Construction Permits Section
5 Post Office Square, Suite 100
(OEP 06-1)
Boston, MA 02109-3912

### B.2 EPA Region 2

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 2:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **NYR10I000** | Indian country within the State of New York |
| **PRR100000** | Commonwealth of Puerto Rico |
| **02R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 2 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 2 Address:**
*For Puerto Rico:*
U.S. EPA Region 2
Caribbean Environmental Protection Division
NPDES Stormwater Program
City View Plaza II – Suite 7000
48 Rd. 165 Km 1.2
Guaynabo, PR 00968-8069

*For New York:*
U.S. EPA Region 2
NPDES Stormwater Program
290 Broadway, 24th Floor
New York, NY 10007-1866

### B.3 EPA Region 3

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 3:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **DCR100000** | District of Columbia |
| **DER10F000** | Areas in the State of Delaware located at a Federal Facility (as defined in Appendix A) |
| **VAR10I000** | Indian country within the State of Virginia |
| **03R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 3 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 3 Address:**
U.S. EPA Region 3
Office of NPDES Permits and Enforcement
NPDES Permits Branch, Mailcode 3WP41
1650 Arch Street
Philadelphia, PA 19103

### B.4 EPA Region 4

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 4:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **ALR10I000** | Indian country within the State of Alabama |
| **FLR10I00E** | Indian country within the State of Florida |
| **MSR10I000** | Indian country within the State of Mississippi |
| **NCR10I000** | Indian country within the State of North Carolina |
| **04R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country (except Catawba lands in South Carolina) |

For stormwater discharges in EPA Region 4 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 4 Address:**
U.S. EPA Region 4
Water Protection Division
NPDES Stormwater Program
Atlanta Federal Center
61 Forsyth Street SW
Atlanta, GA 30303-3104

### B.5 EPA Region 5

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 5:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **MIR10I000** | Indian country within the State of Michigan, except the L'Anse Reservation of the Keweenaw Bay Indian Community |
| **MNR10I000** | Indian country within the State of Minnesota, except sites located in the Fond du Lac Reservation discharging to Outstanding Reservation Resources Waters (ORRWs)[1] |
| **WIR10I000** | Indian country within the State of Wisconsin, except sites located in the Bad River Band of Lake Superior Tribe of Chippewa Indians discharging to Outstanding Tribal Resource Waters (OTRWs) or Tier 3 waters[2] |
| **05R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

[1] The Tribe has identified Perch Lake, Rice Portage Lake, Miller Lake, Deadfish Lake, and Jaskari Lake as ORRWs.
[2] The Tribe has identified the following as OTRWs or Tier 3 waters: Kakagon Slough and the lower wetland reaches of its tributaries that support wild rice, Kakagon River, Bad River Slough, Honest John Lake, Bog Lake, a portion of Bad River, from where it enters the Reservation through the confluence with the White River, and Potato River.

For stormwater discharges in EPA Region 5 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 5 Address:**
U.S. EPA Region 5
NPDES Program Branch
77 W. Jackson Blvd.
Mail Code WN16J
Chicago, IL 60604-3507

### B.6 EPA Region 6

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 6:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **LAR10I000** | Indian country within the State of Louisiana |
| **NMR100000** | State of New Mexico, except Indian country |
| **NMR10I000** | Indian country within the State of New Mexico, except Navajo Reservation Lands that are covered under Arizona permit AZR10000I and Ute Mountain Reservation Lands that are covered under Colorado permit COR10000I. |
| **OKR10I000** | Indian country within the State of Oklahoma, except areas of Indian country covered by an extension of state program authority pursuant to Section 10211 of the Safe, Accountable, Flexible, Efficient Transportation Equity Act (SAFETEA). |
| **OKR10F000** | Discharges in the State of Oklahoma that are not under the authority of the Oklahoma Department of Environmental Quality, or the Oklahoma Department of Agriculture and Forestry including activities associated with oil and gas exploration, drilling, operations, and pipelines (includes SIC Groups 13 and 46, and SIC codes 492 and 5171), and point source discharges associated with agricultural production, services, and silviculture (includes SIC Groups 01, 02, 07, 08, 09). |
| **TXR10I000** | Indian country within the State of Texas |
| **06R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 6 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 6 Address:**
U.S. EPA Region 6
NPDES Stormwater Program (WQ-PP)
1445 Ross Avenue, Suite 1200
Dallas, TX 75202-2733

### B.7 EPA Region 7

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 7:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **IAR10I000** | Indian country within the State of Iowa |
| **KSR10I000** | Indian country within the State of Kansas |
| **NER10I000** | Indian country within the State of Nebraska, except Pine Ridge Reservation lands (see Region 8) |
| **07R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 7 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 7 Address:**
U.S. EPA Region 7
NPDES Stormwater Program
11201 Renner Blvd
Lenexa, KS 66219

### B.8 EPA Region 8

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 8:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **COR10F000** | Areas in the State of Colorado located at a Federal Facility (as defined in Appendix A), except those located on Indian country |
| **COR10I000** | Indian country within the State of Colorado, as well as the portion of the Ute Mountain Reservation located in New Mexico |
| **MTR10I000** | Indian country within the State of Montana |
| **NDR10I000** | Indian country within the State of North Dakota, as well as that portion of the Standing Rock Reservation located in South Dakota (except for the portion of the lands within the former boundaries of the Lake Traverse Reservation which is covered under South Dakota permit SDR10000I listed below) |
| **SDR10I000** | Indian country within the State of South Dakota, as well as the portion of the Pine Ridge Reservation located in Nebraska and the portion of the lands within the former boundaries of the Lake Traverse Reservation located in North Dakota (except for the Standing Rock Reservation which is covered under North Dakota permit NDR10000I listed above) |
| **UTR10I000** | Indian country within the State of Utah, except Goshute and Navajo Reservation lands (see Region 9) |
| **WYR10I000** | Indian country within the State of Wyoming |
| **08R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 8 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 8 Address:**
EPA Region 8 Storm Water Program
Mailcode: 8P-W-WW
1595 Wynkoop Street
Denver, CO 80202-1129

### B.9 EPA Region 9

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 9:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **ASR100000** | Island of American Samoa |
| **AZR10I000** | Indian country within the State of Arizona, as well as Navajo Reservation lands in New Mexico and Utah |
| **CAR10I000** | Indian country within the State of California |
| **GUR100000** | Island of Guam |
| **JAR100000** | Johnston Atoll |
| **MPR100000** | Commonwealth of the Northern Mariana Islands |
| **MWR100000** | Midway Island and Wake Island |
| **NVR10000I** | Indian country within the State of Nevada, as well as the Duck Valley Reservation in Idaho, the Fort McDermitt Reservation in Oregon and the Goshute Reservation in Utah |
| **09R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 9 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 9 Address:**
U.S. EPA Region 9
Water Division
NPDES Stormwater Program (WTR-2-3)
75 Hawthorne Street
San Francisco, CA 94105-3901

### B.10 EPA Region 10

The permit offers coverage for stormwater discharges from construction activity from the following areas in EPA Region 10:

| Permit No. | Areas of Coverage/Where EPA is Permitting Authority |
|---|---|
| **AKR10I000** | Indian country lands as defined in 18 U.S.C. 1151 within the State of Alaska |
| **AKR10F000** | Denali National Park and Preserve |
| **IDR10I000** | Indian country within the State of Idaho, except Duck Valley Reservation lands (see Region 9) |
| **ORR10I000** | Indian country within the State of Oregon, except Fort McDermitt Reservation lands (see Region 9) |
| **WAR10F000** | Areas in the State of Washington, except those located on Indian country, subject to construction activity by a Federal Operator |
| **WAR10I000** | Indian country within the State of Washington |
| **010R10I000** | All areas of Indian country not identified above that are not already covered by an EPA-approved permitting program with authorization to issue permits in Indian country |

For stormwater discharges in EPA Region 10 outside the areas of coverage identified above, please contact your State NPDES permitting authority to obtain coverage under a State-issued NPDES permit.

**EPA Region 10 Address:**
U.S. EPA Region 10
NPDES Stormwater Program
1200 6th Avenue (OWW-191)
Seattle, WA 98101-3140

# Appendix C - Small Construction Waivers and Instructions

These waivers are only available to stormwater discharges associated with small construction activities (i.e., 1-5 acres). As the operator of a small construction activity, you may be able to qualify for a waiver in lieu of needing to obtain coverage under this general permit based on: (A) a low rainfall erosivity factor, (B) a TMDL analysis, or (C) an equivalent analysis that determines allocations for small construction sites are not needed. Each operator, otherwise needing permit coverage, must notify EPA of its intention for a waiver. It is the responsibility of those individuals wishing to obtain a waiver from coverage under this general permit to submit a complete and accurate waiver certification as described below. Where the operator changes or another is added during the construction project, the new operator must also submit a waiver certification to be waived.

## C.1 Rainfall Erosivity Waiver

Under this scenario the small construction project's rainfall erosivity factor calculation ("R" in the Revised Universal Soil Loss Equation) is less than five during the period of construction activity. The operator must certify to EPA that construction activity will occur only when the rainfall erosivity factor is less than five. The period of construction activity begins at initial earth disturbance and ends with final stabilization. Where vegetation will be used for final stabilization, the date of installation of a stabilization practice that will provide interim non-vegetative stabilization can be used for the end of the construction period, provided the operator commits (as a condition of waiver eligibility) to periodically inspect and properly maintain the area until the criteria for final stabilization as defined in the CGP have been met. If use of this interim stabilization eligibility condition was relied on to qualify for the waiver, signature on the waiver with its certification statement constitutes acceptance of and commitment to complete the final stabilization process. The operator must submit a waiver certification to EPA prior to commencing construction activities.

> *Note: The rainfall erosivity factor "R" is determined in accordance with Chapter 2 of Agriculture Handbook Number 703, Predicting Soil Erosion by Water: A Guide to Conservation Planning With the Revised Universal Soil Loss Equation (RUSLE), pages 21–64, dated January 1997; United States Department of Agriculture (USDA), Agricultural Research Service.*

EPA has developed an online rainfall erosivity calculator to help small construction sites determine potential eligibility for the rainfall erosivity waiver. You can access the calculator from EPA's website at: https://www.epa.gov/npdes/rainfall-erosivity-factor-calculator-small-construction-sites. The R factor can easily be calculated by using the construction site latitude/longitude or address and estimated start and end dates of construction. This calculator may also be useful in determining the time periods during which construction activity could be waived from permit coverage. You may find that moving your construction activity by a few weeks or expediting site stabilization will allow you to qualify for the waiver. Use this online calculator or the Construction Rainfall Erosivity Waiver Fact Sheet (https://www.epa.gov/sites/production/files/2015-10/documents/fact3-1.pdf) to assist in determining the R Factor for your small construction site.

If you are the operator of the construction activity and eligible for a waiver based on low erosivity potential, you can submit a rainfall erosivity waiver electronically via EPA's NPDES eReporting Tool (NeT) (https://www.epa.gov/npdes/stormwater-discharges-construction-activities#ereporting), unless you received a waiver from your EPA Regional Office (see Part 1.4.1 of the CGP for information about receiving a waiver from electronic reporting).

*Note: If the R factor is five or greater, you do not qualify for the rainfall erosivity waiver, and must obtain coverage under an NPDES permit (e.g., the CGP), unless you qualify for the Water Quality Waiver as described in section B below.*

If your small construction project continues beyond the projected completion date given on the waiver certification, you must recalculate the rainfall erosivity factor for the new project duration. If the R factor is below five, you must update all applicable information on the waiver certification and retain a copy of the revised waiver as part of your records. The new waiver certification must be submitted prior to the projected completion date listed on the original waiver form to assure your exemption from permitting requirements is uninterrupted. If the new R factor is five or above, you must obtain NPDES permit coverage.

### C.2 TMDL Waiver

This waiver is available if EPA has established or approved a TMDL that addresses the pollutant(s) of concern for the impaired water and has determined that controls on stormwater discharges from small construction activity are not needed to protect water quality. The pollutant(s) of concern include sediment (such as total suspended solids, turbidity or siltation) and any other pollutant that has been identified as a cause of impairment of any waterbody that will receive a discharge from the construction activity. Information on TMDLs that have been established or approved by EPA is available from EPA online at https://www.epa.gov/tmdl and from State and Tribal water quality agencies.

If you are the operator of the construction activity and eligible for a waiver based on compliance with an EPA-established or approved TMDL, you must provide the following information in order to be waived from permitting requirements:

1. Name, address and telephone number of the construction site operator(s);
2. Name (or other identifier), address, county or similar governmental subdivision, and latitude/longitude of the construction project or site;
3. Estimated construction start and completion (i.e., final stabilization) dates, and total acreage (to the nearest quarter acre) to be disturbed;
4. The name of the waterbody(s) that would be receiving stormwater discharges from your construction project;
5. The name and approval date of the TMDL;
6. A statement, signed and dated by an authorized representative as provided in Appendix G, Subsection G.11, that certifies that the construction activity will take place and that the stormwater discharges will occur, within the drainage area addressed by the TMDL.

### C.3 Equivalent Analysis Waiver

This waiver is available for discharges to non-impaired waters only. The operator can develop an equivalent analysis that determines allocations for his/her small construction site for the pollutant(s) of concern or determines that such allocations are not needed to protect water quality. This waiver requires a small construction operator to develop an equivalent analysis based on existing in-stream concentrations, expected growth in pollutant concentrations from all sources, and a margin of safety.

If you are a construction operator who wants to use this waiver, you must develop your equivalent analysis and provide the following information to be waived from permitting requirements:

1. Name, address and telephone number of the construction site operator(s);

2. Name (or other identifier), address, county or similar governmental subdivision, and latitude/longitude of the construction project or site;
3. Estimated construction start and completion (i.e., final stabilization) dates, and total acreage (to the nearest quarter acre) to be disturbed;
4. The name of the waterbody(s) that would be receiving stormwater discharges from your construction project;
5. Your equivalent analysis;
6. A statement, signed and dated by an authorized representative as provided in Appendix G, Subsection G.11, that certifies that the construction activity will take place and that the stormwater discharges will occur, within the drainage area addressed by the equivalent analysis.

### C.4 Waiver Deadlines and Submissions

1. Waiver certifications must be submitted prior to commencement of construction activities.
2. If you submit a TMDL or equivalent analysis waiver request, you are not waived until EPA approves your request. As such, you may not commence construction activities until receipt of approval from EPA.
3. Late Notifications: Operators are not prohibited from submitting waiver certifications after initiating clearing, grading, excavation activities, or other construction activities. The Agency reserves the right to take enforcement for any unpermitted discharges that occur between the time construction commenced and waiver authorization is granted.

Submittal of a waiver certification is an optional alternative to obtaining permit coverage for discharges of stormwater associated with small construction activity, provided you qualify for the waiver. Any discharge of stormwater associated with small construction activity not covered by either a permit or a waiver may be considered an unpermitted discharge under the Clean Water Act. As mentioned above, EPA reserves the right to take enforcement for any unpermitted discharges that occur between the time construction commenced and either discharge authorization is granted or a complete and accurate waiver certification is submitted. EPA may notify any operator covered by a waiver that they must obtain NPDES permit coverage. EPA may notify any operator who has been in non-compliance with a waiver that they may no longer use the waiver for future projects. Any member of the public may petition EPA to take action under this provision by submitting written notice along with supporting justification.

Complete and accurate TMDL or equivalent analysis waiver requests must be sent to the applicable EPA Regional Office address specified in Appendix B.

# Appendix D - Eligibility Worksheet Relating to Threatened and Endangered Species Protection

## D.1 Introduction

This appendix provides a printable worksheet that can be helpful in selecting and documenting your eligibility criteria with respect to the protection of Federally listed threatened or endangered species and Federally designated "critical habitat" under the Endangered Species Act (ESA) [hereinafter "ESA-listed species and designated critical habitat(s)"] from discharges and discharge-related activities authorized under this permit. This is important because Section 9 of the ESA prohibits all persons and agencies from "taking" threatened and endangered species (16 U.S.C. § 1532(19)).

While coordination between you and the U.S. Fish and Wildlife Service (USFWS) and/or the National Marine Fisheries Service (NMFS) (together, referred to as the "Services") may not be required in all cases, EPA encourages you to coordinate with the Services, to document that coordination, and to do so early in the planning process prior to submitting your NOI.

## D.2 Certifying ESA Eligibility Criterion for the CGP

To be eligible for coverage under the CGP, you must certify that you meet one of the criteria listed in this worksheet (Section D.5), which is then submitted with your NOI for coverage under this permit. If you do not meet one of the ESA eligibility criteria outlined in the worksheet below, you are not eligible for coverage under this permit. These criteria ensure that coverage is available only for discharges and discharge-related activities that (1) avoid or eliminate any short- or long-term adverse effects to ESA-listed species and designated critical habitat(s), or (2) may result in any short- or long-term adverse effects that result in incidental take addressed under the incidental take statement of a biological opinion or permit for take issued under Section 10 of the ESA.

As part of your determination of eligibility, EPA has developed a worksheet that assists operators in arriving at the correct criterion. The following requirements apply to the completion of the worksheet depending on how you are submitting your NOI for permit coverage:

1. If the EPA Regional Office grants you a waiver from electronic reporting, in accordance with Part 1.1.5 of the CGP, you must complete the worksheet in section D.4 of this appendix to provide all information as required on your NOI that supports the eligibility criterion you qualify under per Part 1.1.5 of the permit. **You must submit the worksheet with your NOI. If you do not submit the worksheet with your NOI, your NOI will be considered incomplete.**
2. If you do not have a waiver from electronic reporting, you must **complete your eligibility criteria selection outlined in the Endangered Species Protection section of the NOI in the NPDES eReporting Tool (NeT-CGP)** and provide all information as required on your NOI that supports the eligibility criterion you qualify under per Part 1.1.5 of the permit. The printable worksheet in this appendix may be helpful to you in preparing to submit your NOI, but you do not have to use it.

## D.3 What to Expect Once you Submit your NOI

After you submit your NOI and before your NOI is authorized, EPA may notify you if any additional controls are necessary to ensure your discharges are not likely to result in any short- or long-term adverse effects on ESA-listed species and critical habitat.

The Services have the opportunity, within 14 days of submission of the NOI, to advise EPA whether either agency believes the planned discharges meet the selected eligibility criterion; whether the eligibility criterion could be met with additional conditions; or whether the eligibility criterion is not met. With respect to ESA issues, EPA recognizes the Services' expertise and will carefully consider their conclusion(s) in identifying eligibility for authorization, either with or without additional conditions. In the event EPA has placed a hold on your NOI based on NMFS or USFWS' recommendation, EPA will notify you as to whether your discharges are authorized or whether an individual permit will be required. If you do not hear from EPA within 14 days, you may assume that your discharge is authorized without further conditions.

### D.4 Worksheet Instructions

Follow the instructions within the worksheet below to determine which criterion you are eligible for coverage under this permit. Check only 1 criterion, answer the required questions, and include the required information.

Please keep the following in mind as you complete the worksheet:

- The worksheet requires that you answer questions in a sequential order so that you can select the correct eligibility criterion. The worksheet does not go through each criterion alphabetically, but rather is organized in a way that allows you to eliminate those criteria that do not apply to your site. For instance, Step 1 of the worksheet requires you to determine whether criterion B, E, or F applies first, in that order, before proceeding to determining whether criterion A applies in Step 2.
- You must consider ESA-listed species and/or designated critical habitat(s) under the jurisdiction of both the U.S. Fish and Wildlife Service (USFWS) and National Marine Fisheries Service (NMFS) and select the criterion that best applies to your site. You must comply with any applicable terms, conditions, or other requirements developed in theprocess of meeting one of the eligibility criteria in this section to remain eligible for coverage under this permit.
- When evaluating the potential effects of your activities, you must consider effects to listed species or critical habitats within the "action area" of your construction activity, as identified by the USFWS IPaC and/or the NOAA website resources on page D-10 through D-11 of this appendix. Please Note: *NMFS' jurisdiction includes ESA-listed marine and estuarine species that spawn in inland rivers.* The definition of "action area," which is contained in Appendix A, is repeated below forconvenience.

"Action Area" – all areas to be affected directly or indirectly by the federal action and not merely theimmediate area involved in the action. See 50 CFR part 402. For the purposes of this permit and for application of the Endangered Species Act requirements, the following areas are included in the definition of action area:

- The **areas on the construction site** where stormwater discharges originate and flow toward the point of discharge into the receiving waters. This includes:
  - areas on the construction site where excavation, site development, or other ground disturbance activities occur, and
  - areas where stormwater controls will be constructed and operated, including any areas where stormwater flows to and from the stormwater controls.
- The areas **in the vicinity of the construction site** where stormwater discharges flow from the construction site to one or more points of discharge into receiving waters. (Example: Where stormwater flows into an off-site ditch, swale, or gully that leads to receiving waters.)
- **The extent of the receiving water** potentially affected by stormwater discharges from your construction site through alteration of water chemistry, turbidity, temperature, or bank structure (i.e., erosive flow), regardless of whether the construction site is adjacent to the receiving water.

**D.5 Worksheet**

## Step 1 – Determine if You Meet the Eligibility Requirements of Criterion B, E, or F

***Instructions***

- First determine whether you are eligible under Criterion B by reviewing the eligibility requirements below.
- If you determine that your facility does not meet Criterion B (e.g., due to difference in action area described, lack of analysis of appropriate effects, new listings or designation of critical habitat), proceed to check if you meet the requirements for Criterion E or F.

### Criterion B Eligibility Requirements

**If your discharges and discharge-related activities were already addressed in another operator's valid certification of eligibility under the current 2022 CGP that included your action area** (e.g., a general contractor or developer may have completed and filed an NOI for the entire action area with the necessary ESA certifications (Criterion A, C, D, E, or F)), you may be eligible under Criterion B. In order to be eligible for coverage, you must confirm that **all** three of the following are true (**check all that apply**):

☐ I have confirmed that the other operator's certification of eligibility accounted for my action area and that the eligibility certification was valid.

☐ There has been no lapse of NPDES permit coverage in the other operator's certification.

☐ I will comply with all measures that formed the basis of the other operator's valid certification of eligibility.

***Instructions***

- **If all three of the above are true, you may check Criterion B below and answer questions B1-B5, and if applicable, B6-B7.**
- **If any of the above are not true** (for example, if there are any listed species in your action area that were not addressed in the other operator's certification, you are not eligible under Criterion B), **you may not select Criterion B and must proceed to check if you meet the requirements for Criterion E or F.**

☐ **B Eligibility requirements met by another operator under the 2022 CGP.** The construction site's discharges and discharge-related activities were already addressed in another operator's valid certification of eligibility for your "action area" under eligibility Criterion A, C, D, E, or F of the 2022 CGP and you have confirmed that no additional ESA-listed species and/or designated critical habitat under the jurisdiction of USFWS and/or NMFS not considered in the

that certification may be present or located in the "action area." To certify your eligibility under this criterion, there must be no lapse of NPDES permit coverage in the other CGP operator's certification. By certifying eligibility under this criterion, you agree to comply with any conditions upon which the other CGP operator's certification was based. You must include below the NPDES ID from the other 2022 CGP operator's notification of authorization under this permit and list any measures that you must comply with). If your certification is based on another 2022 CGP operator's certification under Criterion C, you must provide EPA with the relevant supporting information required of existing dischargers in Criterion C.

**B1.** Provide the NPDES ID from the other CGP operator's NOI authorized under this permit:

_ _ _ _ _ _ _ _ _ _

**B2.** Identify the eligibility criterion of the other CGP operator's NOI? (check only one)

☐ A ☐ C ☐ D ☐ E ☐ F

**B3.** Provide the authorization date of the other CGP operator's NOI (MM/DD/YYYY):

_ _ / _ _ / _ _ _ _

By certifying eligibility under Criterion B, you must comply with any terms and conditions imposed under the eligibility requirements of the criterion for which the other operator has established eligibility (either Criterion A, C, D, E, or F) to ensure that your discharges and discharge-related activities are protective of listed species and/or critical habitat. *Note: If you are unable to meet these eligibility requirements, then you may either establish eligibility under one of the other criteria, or you may consider applying to EPA for an individual permit.*

**B4.** List any measures that formed the basis of the other operator's valid certification of eligibility that you will comply with (or enter "N/A" if none exist):

**B5.** Check to confirm you have provided documentation in your SWPPP supporting your eligibility under Criterion B, including any of the terms and conditions, as well as the other operator's basis for establishing eligibility. Yes ☐

**If your certification is based on another operator's certification under Criterion C, you must provide the following:**

**B6.** What Federally listed species and/or designated habitat are located in your "action area"? (attached separate sheet if necessary)

**B7.** What is the distance between your site and the listed species or designated critical habitat (in miles)? _____

***Instructions***

- **If you selected Criterion B above and answered questions B1-B5, and if applicable, B6-B7, you are done with this worksheet. If you are *not* filing electronically, you must submit this worksheet with your NOI.**
- If you are not eligible under Criterion B, proceed to check if you meet the requirements for Criterion E or F.






## Criterion E Eligibility Requirements

If consultation under ESA section 7 has concluded, you may be eligible for coverage under Criterion E. In order to be eligible for coverage under Criterion E, **you must confirm that both of the following are true (check all that apply)**:

☐ A consultation between a Federal agency and USFWS and/or the NMFS under section 7 of the ESA has concluded**.** Consultations can be either formal or informal, and would have occurred only as a result of a separate Federal action (e.g., during application for an individual wastewater discharge permit or the issuance of a wetlands dredge and fill permit), and the consultation must have addressed the effects of your construction activity's discharges and discharge-related activities on all ESA-listed threatened or endangered species and all designated critical habitat under the jurisdiction of each Service, as appropriate, in your action area. The result of this consultation must be either:

i. A biological opinion currently in effect that determined that the action in question (taking into account the effects of your facility's discharges and discharge-related activities) is likely to adversely affect, but is not likely to jeopardize the continued existence of listed species or result in the destruction or adverse modification of critical habitat. The biological opinion must have included the effects of your facility's discharges[1] and discharge-related activities on all the listed species and designated

[1] Effects of discharge include, but are not limited to, the analysis of the hydrological, chemical, and biological effects of the discharge on listed species, their prey, and their habitat, as well as critical habitat, where designated. For example, the

critical habitat in your action area under the jurisdiction of each Service, as appropriate. To be eligible under (i), any reasonable and prudent measures specified in the incidental take statement must be implemented;

ii. Written concurrence (e.g., letter of concurrence) from the applicable Service(s) with a determination that your facility's discharges and discharge-related activities are not likely to adversely affect ESA-listed species and/or designated critical habitat. The concurrence letter must have included the effects of your facility's discharges and discharge-related activities on all the ESA-listed species and/or designated critical habitat on your species list(s) acquired from USFWS and/or NMFS as part of this worksheet.

☐ The consultation does not warrant reinitiation under 50 CFR §402.16; or, if reinitiation of consultation is required (e.g., due to a new species listing, critical habitat designation, or new information), the Federal action agency has reinitiated the consultation and the result of the consultation is consistent with the statements above. Include any reinitiation documentation from the Services or consulting Federal agency with your NOI.

***Instructions***

- **If both of the above are true, you may check Criterion E below and answer questions E1-E6.**
  - For more information on section 7 consultation, see 50 CFR part 402. If you receive a "jeopardy opinion," you may continue to work with USFWS and/or NMFS and your permitting authority to modify your project so that it will not jeopardize listed species or designated critical habitat.
  - Note that most consultations are accomplished through informal consultation. When conducting informal ESA section 7 consultation as a non-Federal representative, you must follow the procedures found in 50 CFR Part 402 of the ESA regulations. You must notify the Services of your intention and agreement to conduct consultation as a non-Federal representative.
  - Consultation may also occur in the context of another Federal action at the construction site (e.g., where ESA section 7 consultation was performed for issuance of a wetlands dredge and fill permit for the project or where a NEPA review is performed for the project that incorporates a section 7 consultation).
  - Any terms and conditions developed through consultations to protect listed species and critical habitat must be incorporated into the SWPPP. As noted above, a Federal operator may, if they wish, initiate consultation with the Services at Step Four. Non-Federal operators may seek technical assistance from the Services at Step 5.
  - Whether ESA section 7 consultation must be performed with either USFWS, NMFS, or both Services depends on the listed species that may be affected by the operator's stormwater discharges. In general, NMFS has jurisdiction over marine, estuarine, and anadromous species. Operators should also be aware that while formal section 7 consultation provides protection from incidental takings liability, informal consultation does not.

- **If not, proceed to check if you meet the requirements for Criterion F.**

effects analysis would have evaluated whether the various pollutants in the discharge (e.g., TSS, metals) would adversely affect listed species through exposure to the pollutants, or to their prey or habitat. Effects that look only at short-term effects unrelated to the stormwater discharge effects to listed species are not sufficient for these purposes.

☐ **E** **ESA Section 7 consultation has successfully concluded.** Consultation between a Federal Agency and the USFWS and/or NMFS under section 7 of the ESA has concluded. The consultation must have addressed the effects of the construction site's discharges and discharge-related activities on ESA-listed species and/or designated critical habitat under the jurisdiction of USFWS and/or NMFS. To certify eligibility under this criterion, **Indicate the result of the consultation**:

☐ Biological opinion and/or conference opinion and incidental take statement currently in effect currently in effect from USFWS and/or NMFS that concludes that the action in question (taking into account the effects of your site's discharges and discharge-related activities) is not likely to jeopardize the continued existence of ESA-listed species, nor the destruction or adverse modification of critical habitat;

**Or**

☐ Written concurrence from USFWS and/or NMFS with a finding that the site's discharges and discharge-related activities are not likely to adversely affect ESA-listed species and/or designated critical habitat.

**E1.** Identify the federal action agency or agencies involved:

**E2.** Identify the Service(s) field or regional offices providing the consultation:

**E3.** Identify any tracking numbers associated with the consultation (e.g., IPaC number, ECO number):

**E4.** What is the date the consultation was completed? (MM/DD/YYYY) __ __ / __ __ / __ __ __ __

**E5.** Check to confirm that correspondence with USFWS and/or NMFS documenting the Biological Opinion, conference opinion (IPaC or ECO tracking number) or concurrence is attached. Yes ☐

**E6.** Check to confirm you have provided documentation in your SWPPP supporting your eligibility under Criterion E, including copies of the correspondence between yourself and the Services. Yes ☐

***Instructions***

- **If you selected Criterion E above and answered questions E1-E6, you are done with this worksheet. If you are not filing electronically, you must submit this worksheet with your NOI.**
- If you are not eligible under Criterion E, proceed to check if you meet the requirements for Criterion F.

## Criterion F Eligibility Requirements

If your construction activities are the subject of a permit under ESA section 10, and this authorization addresses the effects of your site's discharges and discharge-related activities on ESA-listed species and designated critical habitat in your action area, you may be eligible for coverage under Criterion F. In order to be eligible or coverage under Criterion F, **you must confirm that the following is true:**

☐ A permit or permits issued under section 10 of the ESA specifically address the effects of your facility's discharges and discharge-related activities (if applicable) on all federally-listed species and designated critical habitat in your action area.

Note: You must follow USFWS and/or NMFS procedures when applying for an ESA section 10 permit (see 50 CFR §17.22(b)(1) for USFWS and §222.22 for NMFS). Application instructions for section 10 permits can be obtained from http://www.fws.gov and http://www.nmfs.noaa.gov or by contacting the appropriate Service office.

***Instructions***

- **If the above is true, you may check Criterion F below and answer questions F1-F6.**
- If you are not eligible under criterion F, proceed to Step 2.

☐ **F** **Issuance of section 10 permit**. Potential take is authorized through the issuance of a permit under section 10 of the ESA by the USFWS and/or NMFS, and this authorization addresses the effects of the site's discharges and discharge-related activities on ESA-listed species and designated critical habitat. You must include copies of the correspondence between yourself and the participating agencies in your SWPPP and your NOI.

**F1.** Which Service provided the section 10 permit? (check all that apply)

USFWS ☐ NMFS ☐

**F2.** Identify the field or regional offices providing the permit(s):

**F3.** Identify any tracking numbers associated with the consultation (e.g., IPaC number, ECO number):

**F4.** What is the date the permit(s) was granted? (MM/DD/YYY) __ __ / __ __ / __ __ __ __
(2nd permit date, if applicable: __ __ / __ __ / __ __ __ __ )

**F5.** Check to confirm that correspondence with USFWS and/or NMFS and a copy of the section 10 permit or relevant tracking number(s) (IPaC and/or ECO number) is attached. Yes ☐

**F6.** Check to confirm you have provided documentation in your SWPPP supporting your eligibility under Criterion F, including a copy of the section 10 permit and copies of the correspondence between yourself and the Services. Yes ☐

***Instructions***

- **If you selected Criterion F above and answered questions F1-F6, you are done with this worksheet. If you are not filing electronically, you must submit this worksheet with your NOI.**
- If you are not eligible under Criterion F, proceed to Step 2.

## Step 2 – Determine if Listed Threatened or Endangered Species or their Designated Critical Habitat(s) are Likely to Occur in your Site's Action Area

***Instructions***

- **First, determine the extent of your action area.** You must determine whether species listed as either threatened or endangered, or their critical habitat(s) are located in your site's action area (i.e., all areas to be affected directly or indirectly by the Federal action and not merely the immediate area involved in the action, including areas beyond the footprint of the site that are likely to be affected by stormwater discharges, discharge-related activities, and authorized non-stormwater discharges).

You must consider the following in determining the action area for your site, and **confirm that all the following are true**:

☐ In determining my "action area", I have considered that discharges of pollutants from the project site can expand the action area well beyond the footprint of my site and the discharge point(s). I have taken into account the controls I will be implementing to minimize pollutants and the receiving waterbody characteristics (e.g., perennial, intermittent, ephemeral) in determining the extent of physical, chemical, and/or biotic effects of the

discharges. I confirm that all receiving waterbodies that could receive pollutants from my site are included in my action area.

☐ In determining my "action area", I have considered that discharge-related activities must also be accounted for in determining my action area. I understand that discharge-related activities are any activities that cause, contribute to, or result in stormwater and authorized non-stormwater point source discharges, and measures such as the siting, construction, timing,[2] and operation of stormwater controls to control, reduce, or prevent pollutants from being discharged. I understand that any new or modified stormwater controls that will have noise or other similar effects, and any disturbances associated with construction of controls, are part of my action area.

If you have any questions about determining the extent of your action area, you may contact EPA or the Services for assistance. https://www.epa.gov/npdes/contact-us-stormwater#regional

***Instructions***

- **Next, you must identify, to the best of your ability, any species listed as either threatened or endangered, or their critical habitat(s), that are located in your site's action area (see definitions of these terms in Appendix A).** You must follow the instructions on the https://www.epa.gov/npdes/construction-general-permit-threatened-and-endangered-species to obtain lists of any ESA-protected species and/or critical habitat that are expected to exist in your county, township, or the receiving water for your discharge.
- If ESA-protected resources occur within your action area, keep a copy of the species and critical habitat list(s) from the Service(s) with your SWPPP and use the list(s) to complete your NOI. For USFWS species, attach to this worksheet the full printout from your IPaC query/Official Species List. You can include the map from your IPaC query. For NMFS species, attach to this worksheet the full printout of the report from your query of the mapping resource you used (either the National or Greater Atlantic Region Mapper). The printed report from NMFS mappers will include a map of your query.

[2] Timing considerations could be related to, for example, a time of the year where a migratory bird species is present in the action area and the operator might want to consider that in terms of their construction sequencing; there are other times of the year where this consideration might not be relevant.

***Instructions***

- **After completing Step 2 above, if there are <u>no</u> listed species and <u>no</u> critical habitat areas in your action area,** you may be eligible for criterion A.

## Criterion A Eligibility Requirements

In order to be eligible for coverage under criterion A, you must confirm that all the following are true (**check all that apply**):

☐ I confirm that I have used the species location resources of **BOTH** NMFS and USFWS to identify any ESA-listed species within my action area.

☐ I have confirmed there to be no ESA-listed species and no critical habitat in my action area.

***Instructions***

- **If all of the above are true, you may check criterion A below and answer questions A1-A5.** 
- **If any of the above is not true, you may not select criterion A and must proceed to Step 3** to determine if you can become eligible under criterion C.

Note: For existing dischargers that have previously obtained coverage under criterion A, you must verify whether ESA-protected species and/or critical habitat are expected to exist in your action area, as described above. Please note that if you now find that your action area overlaps with ESA-protected species or critical habitat, you must proceed to Step 3.

☐ **A <u>No ESA-listed species and/or designated critical habitat present in action area</u>**. You certify that ESA-listed species and designated critical habitat(s) under the jurisdiction of the USFWS or NMFS are not likely to occur in your site's "action area" as defined in Appendix A of this permit.. *Please Note: NMFS' jurisdiction includes ESA-listed marine and estuarine species that spawn in inland rivers.*

**A1.** USFWS information sources used (reliance on State resources is not acceptable):

Note: If your Official Species List from USFWS indicated no species or critical habitat were present in your action area, include the full consultation tracking code at the top of your Official Species List in your NOI in the basis statement for Criterion A. If an Official Species List was not available on IPaC, list the contact date and name of the Service staff with whom you corresponded to verify no USFWS species or critical habitat were present in your action area.

**A2.** NMFS information sources used (reliance on State resources is not acceptable):

**A3.** I confirm that aerial image(s) of the site is attached. Yes ☐

**A4.** I confirm that a printout of the species' list(s) showing no ESA-listed species or critical habitat in my action area is attached. Yes ☐

**A5.** Check to confirm you have provided documentation in your SWPPP supporting your eligibility under Criterion A. For USFWS species, include the full printout from your IPaC query/Official Species List. You can include the map from your IPaC query. For NMFS species, include the full printout from the appropriate NMFS website resources on page X with the correct Region selected. Yes ☐

***Instructions***

- **If you selected Criterion A above and answered questions A1-A5, you are done with this worksheet. If you are not filing electronically, you must submit this worksheet with your NOI.**




- **If listed species and/or critical habitat may exist in your action area, you must do one or more of the following**:



  - **Conduct visual inspections.** This method may be particularly suitable for construction sites that are smaller in size or located in non-natural settings such as highly urbanized areas or industrial parks where there is little or no natural habitat, or for construction activities that discharge directly into municipal stormwater collection systems.
  - **Conduct a formal biological survey**. In some cases, particularly for larger construction sites with extensive stormwater discharges, biological surveys may be an appropriate way to assess whether species are located in the action area and whether there are likely to be short- or long-term adverse effects to such species. Biological surveys are frequently performed by environmental consulting firms.
  - **If required, conduct an environmental assessment under the National Environmental Policy Act (NEPA).** Some construction activities might require review under NEPA for specific reasons, such as Federal funding or other Federal involvement in the project. Note: Coverage under the CGP does not trigger such a review for individual projects/sites. EPA has complied with NEPA in the issuance of the CGP.

    **and**

  - **Follow the instructions in Steps 3 – 5 below, as applicable.** Note that many but not all measures imposed to protect listed species under these steps will also protect critical habitat. Thus, meeting the eligibility requirements of this CGP may require measures to protect critical habitat that are separate from those to protect listed species.

## Step 3 – Assess if the Construction Activity's Discharges or Discharge-Related Activities Are Likely to Result in Short- or Long-Term Adverse Effects to Listed Threatened or Endangered Species or Designated Critical Habitat

***Instructions***

- If in Step 2 you identified that listed species and/or designated critical habitat could exist in your action area, **you must next assess whether your discharges or discharge-related activities are likely to result in short- or long-term adverse effects to ESA-listed threatened or endangered species or designated critical habitat**.

Potential short- or long-term adverse effects from discharges and discharge-related activities include:

- **Hydrological**. Stormwater discharges may cause siltation, sedimentation, or induce other changes in receiving waters such as temperature, salinity, or pH. These effects will vary with the amount of stormwater discharged and the volume and condition of the receiving water. Where a stormwater discharge constitutes a minute portion of the total volume of the receiving water, adverse hydrological effects are less likely. Construction activity itself may also alter drainage patterns on a site where construction occurs that can impact listed species or critical habitat.
- **Habitat**. Excavation, site development, grading, and other surface disturbance activities from construction activities, including the installation or placement of stormwater controls, may result in adverse effects to listed species or their habitat. Stormwater may drain or inundate listed species habitat.
- **Toxicity**. In some cases, pollutants in construction stormwater may have toxic effects on listed species. For example: Stormwater discharges from construction on or adjacent to agricultural property may contain pesticides. Stormwater discharges from projects involving pavement and roofing could include tar and asphalt.

The scope of effects to consider will vary with each site. If you are having difficulty determining whether your project is likely to result in short- or long-term adverse effects to listed species or critical habitat, or one of the Services has already raised concerns to you, you should contact the appropriate Services office for assistance.

***Instructions***

- **If any short- or long-term adverse effects to listed threatened or endangered species or their critical habitat <u>are not</u> likely, then you may check Criterion C below and answer questions C1-C8.**
- **If any short- or long-term adverse effects to listed threatened or endangered species or their critical habitat <u>are</u> likely, you must follow Step 4 below.** You may still be eligible for Criterion C if you are able to install and implement appropriate measures to avoid the likelihood of adverse effects.

**Criterion C Eligibility Requirements**

☐ **C** **Discharges not likely to result in any short- or long-term adverse effects to ESA-listed species and/or designated critical habitat.** ESA-listed species and/or designated critical habitat(s) under the jurisdiction of the USFWS and/or NMFS are likely to occur in or near your site's "action area," and you certify to EPA that your site's discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects to ESA-listed threatened or endangered species and/or designated critical habitat. This certification may include consideration of any stormwater controls and/or management practices you will adopt to ensure that your discharges and discharge-related activities are not likely to result in any short- or long-term adverse effects to ESA-listed species and/or designated critical habitat. To certify your eligibility under this criterion, you must indicate below1) the ESA-listed species and/or designated habitat located in your "action area" using the process outlined in this Appendix; 2) the distance between the site and the listed species and/or designated critical habitat in the action area (in miles); and 3) a rationale describing specifically how short- or long-term adverse effects to ESA-listed species will be avoided from the discharges and discharge-related activities. You must also include a copy of your site map from your SWPPP showing the upland and in-water extent of your "action area" with your NOI.

**C1.** I confirm that both ESA-listed species and designated critical habitat under the jurisdiction of the USFWS and/or NMFS were considered in my evaluation. Yes ☐

**C2.** Provide the USFWS information resources and expertise used to arrive at this criterion selection:

**C3.** Provide the NMFS information resources and expertise used to arrive at this criterion selection:

**C4.** What ESA-listed species and/or designated critical habitat are located in your "action area?" (or attach a printout of the species' list(s))

**C5.** What is the distance between your site and the ESA-listed species and/or designated critical habitat within the action area (in miles, state "on site" if the ESA-listed species and/or designated critical habitat is within the area to be disturbed)? _____

**C6.** Provide the rationale describing specifically how any short- or long-term adverse effects to ESA-listed species will be avoided from the discharge and discharge-related activities.

**C7.** I confirm that a site map from my SWPPP showing the upland and in-water extent of my "action area" is attached. Yes ☐

**C8.** Check to confirm you have provided documentation in your SWPPP supporting your eligibility under Criterion C. Yes ☐

***Instructions***

- **If you selected Criterion C above and answered questions C1-C8, you are done with this worksheet. If you are not filing electronically, you must submit this worksheet with your NOI.** 

- If not, please proceed to step 4. 

## Step 4 - Determine if Measures Can Be Implemented to Avoid Adverse Effects

***Instructions***

If you make a preliminary decision in Step 3 that short- or long-term adverse effects from your construction activity's discharges or discharge-related activities are likely to occur, you can still receive coverage under eligibility Criterion C of the CGP if appropriate measures are undertaken to avoid or eliminate the likelihood of short- or long-term adverse effects prior to applying for CGP coverage.

These measures may involve relatively simple changes to construction activities such as re-routing a stormwater discharge to bypass an area where species are located, relocating stormwater controls, or by modifying the "footprint" of the construction activity. If you are unable to ascertain which measures to implement to avoid the likelihood of short- or long-term adverse effects, you must coordinate with USFWS and/or NMFS, in which case you would not be eligible for coverage under eligibility Criterion C, but may instead be eligible for coverage under eligibility criterion D (described in more detail in Step 5).

- **If you are able to install and implement appropriate measures to avoid the likelihood of short- or long-term adverse effects, then <u>you</u> <u>may go back</u> and check eligibility Criterion C above and answer questions C1-C8 above, <u>and</u> C9-C10 below.** The measures you adopt to avoid or eliminate short- or long-term adverse effects must be implemented for the duration of the construction project and your coverage under the CGP.
- **If you cannot ascertain which measures to implement to avoid the likelihood of adverse effects,** you must follow the procedures in Step 5.

**C9.** I confirm that I have or will install and implement appropriate measures to avoid the likelihood of any short- or long-term adverse effects to ESA-listed threatened or endangered species or their critical habitat. Yes ☐

**C10.** Provide a description of the measures installed/to be installed and implemented to avoid likelihood of any short- or long-term adverse effects.

***Instructions***

- **If you selected Criterion C above and answered questions C1-C10, you are done with this worksheet. If you are not filing you NOI electronically, you must submit this worksheet with your NOI.**
- If you are not eligible for Criterion C, please proceed to step 5.

## Step 5 - Determine if the Eligibility Requirements of Criterion D Can Be Met

***Instructions***

- If in Step 4 you cannot ascertain which measures to implement to avoid the likelihood of short- or long-term adverse effects, you must contact USFWS and/or NMFS. You may still be eligible for CGP coverage if likely adverse effects can be addressed through meeting criterion D.
- If you meet the requirements of criterion D, **then you may check criterion D below and answer questions D1-D5.**

### Criterion D Eligibility Requirements

☐ **D** **Coordination with USFWS and/or NMFS has successfully concluded.** Coordination between you and the USFWS and/or NMFS has concluded. The coordination must have addressed the effects of your site's discharges and discharge-related activities on ESA-listed species and/or designated critical habitat under the jurisdiction of USFWS and/or NMFS, and resulted in a written confirmation from USFWS and/or NMFS that the effects of your site's discharges and discharge-related activities are not likely to result in short- or long-term adverse effects for ESA-listed species and/or designated critical habitat in your action area. By certifying eligibility under this criterion, you agree to comply with any conditions you must meet for your site's discharges and discharge-related activities to not likely result in any short- or long-term adverse effects. You must include copies of the correspondence with the participating agencies in your SWPPP and your NOI.

**D1.** Which Service participated in coordination? (check all that apply) USFWS ☐ NMFS ☐

**D2.** Identify the field and/or regional office(s) that provided the coordination?

**D3.** What is the date the coordination concluded? (MM/DD/YYY) __ __ / __ __ / __ __ __ __

**D4.** Check to confirm that correspondence with USFWS and/or NMFS documenting concurrence is attached. Yes ☐

**D5.** Check to confirm you have provided documentation in your SWPPP supporting your eligibility under Criterion D, including copies of the correspondence between yourself and the Services. Yes ☐

***Instructions***

- **If you selected Criterion D above and answered questions D1-D5, you are done with this worksheet. If you are not filing electronically, you must submit this worksheet with your NOI.**




**Paperwork Reduction Act Notice**

This collection of information is approved by OMB under the Paperwork Reduction Act, 44 U.S.C. 3501 et seq. (OMB Control No. 2040-0305). Responses to this collection of information are mandatory (40 CFR 122.26). An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. The public reporting and recordkeeping burden for this collection of information is estimated to be 3.3 hours per response. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates and any suggested methods for minimizing respondent burden to the Regulatory Support Division Director, U.S. Environmental Protection Agency (2821T), 1200 Pennsylvania Ave., NW, Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed form to this address.

## Appendix E – Historic Property Screening Process

### Background

Section 106 of the National Historic Preservation Act (NHPA) requires Federal agencies to take into account the effects of Federal "undertakings", such as the issuance of this permit, on historic properties that are either listed on, or eligible for listing on, the National Register of Historic Places. To address any issues relating to historic properties in connection with the issuance of this permit, EPA developed the screening process in this appendix that enables construction operators to appropriately consider the potential impacts, if any, of their installation of stormwater controls on historic properties and to determine whether actions can be taken, if applicable, to mitigate any such impacts. Although the coverages of individual construction sites under this permit do not constitute separate Federal undertakings, the screening process in this appendix provides an appropriate site-specific means of addressing historic property issues in connection with EPA's issuance of the permit.

***Key Terms***

***Historic property***- prehistoric or historic districts, sites, buildings, structures, or objects that are included in or eligible for inclusion in the National Register of Historic Places, including artifacts, records, and remains that are related to and located within such properties

***SHPO*** – The State Historic Preservation Officer for a particular State

***THPO or Tribal representative*** – The Tribal Historic Preservation Officer for a particular Tribe or, if there is no THPO, the representative designated by such Tribe for NHPA purposes

### Instructions for All Construction Operators

You are required to follow the screening process in this appendix to determine if your installation of stormwater controls on your site has the potential to cause effects to historic properties, and whether or not you need to contact your SHPO, THPO, or other Tribal representative for further information. **You may not submit your NOI until you have completed this screening process.** The following four steps describe how applicants can meet the historic property requirements under this permit:

Step 1 *Are you installing any stormwater controls that require subsurface earth disturbance?*[1]

The first step of the screening process is to determine if you will install stormwater controls that cause subsurface earth disturbance. The installation of the following types of stormwater controls require subsurface earth disturbance:[2]

- Dikes
- Berms
- Catch Basins
- Ponds
- Ditches
- Trenches
- Culverts
- Channels

[1] You are only required to consider earth-disturbing activities related to the installation of stormwater controls in the NHPA screening process. You are not reqired to consider other earth-disturbing activities at the site. If you are installing one of the above stormwater controls or another type of control that requires subsurface earth disturbance, your stormwater controls have the potential to have an effect on historic properties. If this is the case, then you must proceed to Step 2.

[2] This list is not intended to be exhaustive. Other stormwater controls that are not on this list may involve earth-disturbing activities and must also be examined for the potential to affect historic properties.

- Perimeter Drains
- Swales

If you are not installing one of the above stormwater controls or another type of control that requires subsurface earth disturbance, then you may indicate this on your NOI, and no further screening is necessary. During the 14-day waiting period after submitting your NOI, the SHPO, THPO, or other Tribal representative may request that EPA hold up authorization based on concerns about potential adverse effects to historic properties. EPA will evaluate any such request and notify you if any additional controls to address adverse effects to historic properties are necessary.

Step 2 *Have prior professional cultural resource surveys or other evaluations determined that historic properties do not exist, or have prior disturbances precluded the existence of historic properties?*

If you are installing a stormwater control that requires subsurface earth disturbance, you must next determine if no historic properties exist on your site based on prior professional cultural resource surveys or other evaluations, or if the existence of historic properties has been precluded because of prior earth disturbances.

If prior to your project it has already been determined that no historic properties exist at your site based on available information, including information that may be provided by your applicable SHPO, THPO, or other Tribal representative, then you may indicate this on your NOI, and no further screening steps are necessary. Similarly, if prior earth disturbances have eliminated the possibility that historic properties exist on your site, you may indicate this on your NOI, and no further screening steps are necessary. After submitting your NOI, and during the 14-day waiting period, the SHPO, THPO, or other Tribal representative may request that EPA hold up authorization based on concerns about potential adverse effects to historic properties. EPA will evaluate any such request and notify you if any additional measures to address adverse effects to historic properties are necessary.

If neither of these circumstances exists for your project, you must proceed to Step 3.

Step 3 *If you are installing any stormwater controls that require subsurface earth disturbance, you must determine if these activities will have an effect on historic properties.*

If your answer to the question in Step 2 is "no", then you must assess whether your earth-disturbing activities related to the installation of stormwater controls will have an effect on historic properties. This assessment may be based on historical sources, knowledge of the area, an assessment of the types of earth-disturbing activities you are engaging in, considerations of any controls and/or management practices you will adopt to ensure that your stormwater control-related earth-disturbing activities will not have an effect on historic properties, and any other relevant factors. If you determine based on this assessment that earth disturbances related to the installation of your stormwater controls will have no effect on historic properties, you may indicate this on your NOI, and document the basis for your determination in your SWPPP, and no further screening steps are necessary. After submitting your NOI, and during the 14-day waiting period, the SHPO, THPO, or other Tribal representative may request that EPA hold up authorization based on concerns about potential adverse effects to historic properties. EPA will evaluate any such request and notify you if any further processes are necessary including any additional measures to address adverse effects to historic properties are necessary.

If none of the circumstances in Steps 1 - 3 exist for your project, you must proceed to Step 4.

Step 4: *If you are installing any stormwater controls that require subsurface earth disturbance and you have not satisfied the conditions in Steps 1 - 3, you must contact and consult with the appropriate historic preservation authorities.*

Where you are installing stormwater controls that require subsurface earth disturbance, and you cannot determine in Step 3 that these activities will have no effect on historic properties, then you must contact the relevant SHPO, THPO, or other Tribal representative to request their views as to the likelihood that historic properties are potentially present on your site and may be impacted by the installation of these controls.

> *Note: Addresses for SHPOs may be found at https://ncshpo.org/directory/, and addresses for THPOs may be found at https://grantsdev.cr.nps.gov/THPO_Review/index.cfm. If a Tribe does not have a THPO, you should contact the appropriate Tribal government office designated by the Tribe for this purpose.*

You must submit the following minimum information in order to properly initiate your request for information:

1. Project name (*i.e.*, the name or title most commonly associated with your project);
2. A narrative description of the project;
3. Name, address, phone and fax number, and email address (if available) of the operator;
4. Most recent U.S. Geological Survey (USGS) map section (7.5 minute quadrangle) showing actual project location and boundaries clearly indicated; and
5. Sections of the SWPPP site map (see Part 7.2.4) that show locations where stormwater controls that will cause subsurface earth disturbance will be installed (see Step 1).

Without submitting this minimum information, you will not have been considered to have properly initiated your request. You will need to provide the SHPO, THPO, or other Tribal representative **a minimum of 15 calendar days** after they receive these materials to respond to your request for information about your project.

If you do not receive a response within 15 calendar days after receipt by the SHPO, THPO, or other Tribal representative of your request, then you may indicate this on your NOI, and no further screening steps are necessary. Or, if the applicable SHPO, THPO, or other Tribal representative responds to your request with an indication that no historic properties will be affected by the installation of stormwater controls at your site, then you may indicate this on your NOI, and no further screening steps are necessary. After submitting your NOI, and during the 14-day waiting period, the SHPO, THPO, or other Tribal representative may request that EPA hold up authorization based on concerns about potential adverse effects to historic properties. EPA will evaluate any such request and notify you if any further processes are necessary including any additional measures to address adverse effects to historic properties are necessary.

If within 15 calendar days of receipt of your request the applicable SHPO, THPO, or other Tribal representative responds with a request for additional information or for further consultation regarding appropriate measures for treatment or mitigation of effects on historic properties caused by the installation of stormwater controls on your site, you must comply with this request and proceed to Step 5.

Step 5: *Consultation with applicable consulting parties.*

If, following your discussions with the appropriate historic preservation authorities in Step 4, the applicable SHPO, THPO, Tribal representative, or any other consulting party requests additional information or further consultation, you must respond with such information or consult to determine impacts to historic properties that may be caused by the installation of stormwater controls on your site and appropriate measures for treatment or mitigation of such impacts. If as a result of your discussions with the applicable SHPO, THPO, Tribal representative, or any other

consulting party, you enter into, and comply with, a written agreement regarding treatment and/or mitigation of impacts on your site, then you may indicate this on your NOI, and no further screening steps are necessary.

If, however, agreement on an appropriate treatment or mitigation plan cannot be reached between you and the SHPO, THPO, Tribal representative, or any other consulting party within 30 days of your response to the SHPO, THPO, Tribal representative, or any other consulting party's request for additional information or further consultation, you may submit your NOI, but you must indicate that you have not negotiated measures to avoid or mitigate such effects. You must also include in your SWPPP the following documentation:

1. Copies of any written correspondence between you and the SHPO, THPO, Tribal representative, or any other consulting party; and
2. A description of any significant remaining disagreements as to mitigation measures between you and the SHPO, THPO, Tribal representative, or any other consulting party.

After submitting your NOI, and during the 14-day waiting period, the SHPO, THPO, ACHP, Tribal representative, or any other consulting party may request that EPA place a hold on authorization based upon concerns regarding potential adverse effects to historic properties. EPA, in coordination with the ACHP, will evaluate any such request and notify you if any further processes are necessary including any additional measures to address adverse effects to historic properties are necessary.

## Appendix F – Buffer Requirements.

The purpose of this appendix is to assist you in complying with the requirements in Part 2.2.1 of the permit regarding the establishment of natural buffers and/or equivalent sediment controls. This appendix is organized as follows:

F.1 SITES THAT ARE REQUIRED TO PROVIDE AND MAINTAIN NATURAL BUFFERS AND/OR EQUIVALENT EROSION AND SEDIMENT CONTROLS ..... 2
F.2 COMPLIANCE ALTERNATIVES AND EXCEPTIONS ..... 3
F.2.1 Compliance Alternatives ..... 3
F.2.2 Exceptions to the Compliance Alternatives ..... 3
F.2.3 Requirements for Providing and Maintaining Natural Buffers ..... 4
F.2.4 Guidance for Providing the Equivalent Sediment Reduction as a 50-foot Buffer ..... 7
F.3 SMALL RESIDENTIAL LOT COMPLIANCE ALTERNATIVES ..... 12
F.3.1 Small Residential Lot Compliance Alternative Eligibility ..... 12
F.3.2 Small Residential Lot Compliance Alternatives ..... 12

## F.1 SITES THAT ARE REQUIRED TO PROVIDE AND MAINTAIN NATURAL BUFFERS AND/OR EQUIVALENT EROSION AND SEDIMENT CONTROLS

The requirement in Part 2.2.1 to provide and maintain natural buffers and/or equivalent erosion and sediment controls applies for any discharges to waters of the U.S. located within 50 feet of your site's earth disturbances. If the receiving water is not located within 50 feet of earth-disturbing activities, Part 2.2.1 does not apply. See Figure F – 1.





**Figure F-1 Example of earth-disturbing activities within 50 feet of a water of the U.S.**

## F.2 COMPLIANCE ALTERNATIVES AND EXCEPTIONS

### F.2.1 Compliance Alternatives

If Part 2.2.1 applies to your site, you have three compliance alternatives from which you can choose, unless you qualify for any of the exceptions (see below and Part 2.2.1.a):

1. Provide and maintain a 50-foot undisturbed natural buffer; or
2. Provide and maintain an undisturbed natural buffer that is less than 50 feet and is supplemented by erosion and sediment controls that achieve the sediment load reduction equivalent to a 50-foot undisturbed natural buffer; or
3. If infeasible to provide and maintain an undisturbed natural buffer of any size, implement erosion and sediment controls to achieve the sediment load reduction equivalent to a 50-foot undisturbed natural buffer.

The compliance alternative selected must be maintained throughout the duration of permit coverage.

See Part F.2.2 below for exceptions to the compliance alternatives.

See Part F.2.3 for requirements applicable to providing and maintaining natural buffers under compliance alternatives 1 and 2 above.

See Part F.2.4 for requirements applicable to providing erosion and sediment controls that achieve the sediment load reduction equivalent to a 50-foot undisturbed natural buffer under compliance alternatives 2 and 3 above.

### F.2.2 Exceptions to the Compliance Alternatives

The following exceptions apply to the requirement to implement one of the Part 2.2.1.a compliance alternatives (see also Part 2.2.1.b):

- The following disturbances are exempt from the requirements Part 2.2.1 and this Appendix[1]:
  - Construction approved under a CWA Section 404 permit; or
  - Construction of a water-dependent structure or water access areas *(e.g., pier, boat ramp, trail)*.
- If there is no discharge of stormwater to waters of the U.S. through the area between the disturbed portions of the site and any waters of the U.S. located within 50 feet of your site, you are not required to comply with the requirements in Part 2.2.1 and this Appendix. This includes situations where you have implemented controls measures, such as a berm or other barrier, that will prevent such discharges.
- Where no natural buffer exists due to preexisting development disturbances *(e.g., structures, impervious surfaces)* that occurred prior to the initiation of planning for the current development of the site, you are not required to comply with the requirements in Part 2.2.1 and this Appendix.
  Where some natural buffer exists but portions of the area within 50 feet of the receiving water are occupied by preexisting development disturbances, you are

[1] This exemption does not apply, however, to disturbances within 50 feet of a receiving water that are adjacent to the disturbances listed here (i.e., construction permitted under CWA Section 404, or construction of a water-dependent structure or water access area) and that are covered by this permit.

required to comply with the requirements in Part 2.2.1 and this Appendix. For the purposes of calculating the sediment load reduction for either compliance alternative 2 or 3, you are not expected to compensate for the reduction in buffer function that would have resulted from the area covered by these preexisting disturbances. Clarity about how to implement the compliance alternatives for these situations is provided in F.2.3 and F.2.4 below.

If during your project, you will disturb any portion of these preexisting disturbances, the area removed will be deducted from the area treated as a "natural buffer."

- For "linear construction sites" (see Appendix A), you are not required to comply with this requirement if site constraints *(e.g., limited right-of-way)* make it infeasible to implement one of the Part 2.2.1.a compliance alternatives, provided that, to the extent feasible, you limit disturbances within 50 feet of any waters of the U.S. and/or you provide supplemental erosion and sediment controls to treat stormwater discharges from earth disturbances within 50 feet of the receiving water You must also document in your SWPPP your rationale for why it is infeasible for you to implement one of the Part 2.2.1.a compliance alternatives, and describe any buffer width retained and supplemental erosion and sediment controls installed.
- For "small residential lot" construction *(i.e., a lot being developed for residential purposes that will disturb less than 1 acre of land, but is part of a larger residential project that will ultimately disturb greater than or equal to 1 acre),* you have the option of complying with one of the "small residential lot" compliance alternatives in Part F.3 of this appendix.

Note that you must document in your SWPPP if any disturbances related to any of the above exceptions occurs within the buffer area on your site.

### F.2.3 Requirements for Providing and Maintaining Natural Buffers

This part of the appendix applies to you if you choose compliance alternative 1 (50-foot buffer), compliance alternative 2 (a buffer of < 50 feet supplemented by additional erosion and sediment controls that achieve the equivalent sediment load reduction as the 50-foot buffer), or if you are providing a buffer in compliance with one of the "small residential lot" compliance alternatives in Part F.3.

**Buffer Width Measurement**

Where you are retaining a buffer of any size, the buffer should be measured perpendicularly from any of the following points, whichever is further landward from the water:

1. The ordinary high water mark of the water body, defined as the line on the shore established by fluctuations of water and indicated by physical characteristics such as a clear, natural line impressed on the bank, shelving, changes in the character of soil, destruction of terrestrial vegetation, and/or the presence of litter and debris; or
2. The edge of the stream or river bank, bluff, or cliff, whichever is applicable.

Refer to Figures F – 2 and F - 3. You may find that specifically measuring these points is challenging if the flow path of the receiving water changes frequently, thereby causing the measurement line for the buffer to fluctuate continuously along the path of the waterbody. Where this is the case, EPA suggests that rather than measuring each change or deviation along the water's edge, it may be easier to select regular intervals

from which to conduct your measurement. For instance, you may elect to conduct your buffer measurement every 5 to 10 feet along the length of the water.

Additionally, note that if earth-disturbing activities will take place on both sides of a receiving water that flows through your site, to the extent that you are establishing a buffer around this water, it must be established on both sides. For example, if you choose compliance alternative 1, and your project calls for disturbances on both sides of a small stream, you would need to retain the full 50 feet of buffer on both sides of the water. However, if your construction activities will only occur on one side of the stream, you would only need to retain the 50-foot buffer on the side of the stream where the earth-disturbance will occur.





**Figure F-2 Buffer measurement from the ordinary high water mark of the water body, as indicated by a clear natural line impressed on the bank, shelving, changes in the character of the soil, destruction of terrestrial vegetation, and/or the presence of litter/debris.**





**Figure F-3 Buffer measurement from the edge of the bank, bluff, or cliff, whichever is applicable.**

**Limits to Disturbance Within the Buffer**

You are considered to be in compliance with the requirement to provide and maintain a natural buffer if you retain and protect from construction activities the natural buffer that existed prior to the commencement of construction. If the buffer area contains no vegetation prior to the commencement of construction (e.g., sand or rocky surface), you are not required to plant vegetation. As noted above, any preexisting structures or impervious surfaces may occur in the natural buffer provided you retain and protect from disturbance the buffer areas outside of the preexisting disturbance.

To ensure that the water quality protection benefits of the buffer are retained during construction, you are prohibited from conducting any earth-disturbing activities within the buffer during permit coverage. In furtherance of this requirement, **prior to commencing earth-disturbing activities on your site, you must delineate, and clearly mark off, with flags, tape, or a similar marking device, the buffer area on your site.** The purpose of this requirement is to make the buffer area clearly visible to the people working on your site so that unintended disturbances are avoided.

While you are not required to enhance the quality of the vegetation that already exists within the buffer, you are encouraged to do so where such improvements will enhance the water quality protection benefits of the buffer. (Note that any disturbances within the buffer related to buffer enhancement are permitted and do not constitute construction disturbances.) For instance, you may want to target plantings where limited vegetation exists, or replace existing vegetation where invasive or noxious plant species (see http://plants.usda.gov/java/noxiousDriver) have taken over. In the case of invasive or noxious species, you may want to remove and replace them with a diversity of native trees, shrubs, and herbaceous plants that are well-adapted to the climatic, soil, and hydrologic conditions on the site. You are also encouraged to limit the removal of naturally deposited leaf litter, woody debris, and other biomass, as this material contributes to the ability of the buffer to retain water and filter pollutants.

If a portion of the buffer area adjacent to the receiving water is owned by another party and is not under your control, you are only required to retain and protect from construction activities the portion of the buffer area that is under your control. For example, if you comply with compliance alternative 1 (provide and maintain a 50-foot buffer), but 10 feet of land immediately adjacent to the receiving water is owned by a different party than the land on which your construction activities are taking place and you do not have control over that land, you must only retain and protect from construction activities the 40-foot buffer area that occurs adjacent to the property on which your construction activities are taking place. EPA would consider you to be in compliance with this requirement regardless of the activities that are taking place in the 10-foot area that is owned by a different party than the land on which your construction activities are taking place that you have no control over.

**Discharges to the Buffer**

**You must ensure that all discharges from the area of earth disturbance to the natural buffer are first treated by the site's erosion and sediment controls** (*for example, you must comply with the Part 2.2.3 requirement to install sediment controls along any perimeter areas of the site that will receive pollutant discharges*), **and if necessary to prevent erosion caused by stormwater flows within the buffer, you must use velocity dissipation devices**. The purpose of this requirement is to decrease the rate of stormwater flow and encourage infiltration so that the pollutant filtering functions of the buffer will be achieved. To comply with this requirement, construction operators typically will use devices that physically dissipate stormwater flows so that the discharge entering the buffer is spread out and slowed down.

**SWPPP Documentation**

You are required to document in your SWPPP the natural buffer width that is retained. For example, if you are complying with alternative 1, you must specify in your SWPPP that you are providing a 50-foot buffer. Or, if you will be complying with alternative 2, you must document the reduced width of the buffer you will be retaining (and you must also describe the erosion and sediment controls you will use to achieve an equivalent sediment reduction, as required in Part F.2.4 below). Note that you must also show any buffers on your site map in your SWPPP consistent with Part 7.2.4.j. Additionally, if any disturbances related to the exceptions in Part F.2.2 occur within the buffer area, you must document this in the SWPPP.

### F.2.4 Guidance for Providing the Equivalent Sediment Reduction as a 50-foot Buffer

This part of the appendix applies to you if you choose compliance alternative 2 (provide and maintain a buffer that is less than 50 feet that is supplemented by erosion and sediment controls that achieve the sediment load reduction equivalent to a 50-foot buffer) or compliance alternative 3 (implement erosion and sediment controls to achieve the sediment load reduction equivalent to a 50-foot buffer).

**Determine Whether it is Feasible to Provide a Reduced Buffer**

EPA recognizes that there will be a number of situations in which it will be infeasible to provide and maintain a buffer of any width. While some of these situations may exempt you from the buffer requirement entirely (see F.2.2), if you do not qualify for one of these exemptions, there still may be conditions or circumstances at your site that make it infeasible to provide a natural buffer. For example, there may be sites where a significant portion of the property on which the earth-disturbing activities will occur is located within the buffer area, thereby precluding the retention of natural buffer areas.

Therefore, you should choose compliance alternative 2 if it is feasible for you to retain some natural buffer on your site. (Note: For any buffer width retained, you are required to comply with the requirements in Part F.2.3, above, concerning the retention of vegetation and restricting earth disturbances.) Similarly, if you determine that it is infeasible to provide a natural buffer of any size during construction, you should choose alternative 3.

**Design Controls That Provide Equivalent Sediment Reduction as 50-foot Buffer**

You must next determine what additional controls must be implemented on your site that, alone or in combination with any retained natural buffer, achieve a reduction in sediment equivalent to that achieved by a 50-foot buffer.

Note that if only a portion of the natural buffer is less than 50 feet, you are only required to implement erosion and sediment controls that achieve the sediment load reduction equivalent to the 50-foot buffer for discharges through that area. You would not be required to provide additional treatment of stormwater discharges that flow through 50 feet or more of natural buffer. See Figure F-4.





**Figure F-4 Example of how to comply with the requirement to provide the equivalent sediment reduction when only a portion of your earth-disturbances discharge to a buffer of less than 50-feet.**

Steps to help you meet compliance alternative 2 and 3 requirements are provided below.

**Step 1 - Estimate the Sediment Reduction from the 50-foot Buffer**

In order to design controls that match the sediment removal efficiency of a 50-foot buffer, you first need to know what this efficiency is for your site. The sediment removal efficiencies of natural buffers vary according to a number of site-specific factors, including precipitation, soil type, land cover, slope length, width, steepness, and the types of erosion and sediment controls used to reduce the discharge of sediment prior to the buffer. EPA has simplified this calculation by developing buffer performance tables covering a range of vegetation and soil types for the areas covered by the CGP. See

Attachment 1 of this Appendix, Tables F-8 through F-15. Note: buffer performance values in Tables F-8 through F-15 represent the percent of sediment captured through the use of perimeter controls (e.g., silt fences) and 50-foot buffers at disturbed sites of fixed proportions and slopes.[2]

Using Tables F-8 through F-15 (see Attachment 1 of this Appendix), you can determine the sediment removal efficiency of a 50-foot buffer for your geographic area by matching the vegetative cover type that best describes your buffer area and the type of soils that predominate at your site. For example, if your site is located in Massachusetts (Table F-9), and your buffer vegetation corresponds most closely with that of tall fescue grass, and the soil type at your site is best typified as sand, your site's sediment removal efficiency would be 81 percent.

In this step, you should choose the vegetation type in the tables that most closely matches the vegetation that would exist naturally in the buffer area on your site regardless of the condition of the buffer. However, because you are not required to plant any additional vegetation in the buffer area, in determining what controls are necessary to meet this sediment removal equivalency in Step 2 below, you will be able to take credit for this area as a fully vegetated "natural buffer."

Similarly, if a portion of the buffer area adjacent to the receiving water is owned by another party and is not under your control, you can treat the area of land not under your control as having the equivalent vegetative cover and soil type that predominates on the portion of the property on which your construction activities are occurring.

*For example, if your earth-disturbances occur within 50 feet of a receiving water, but the 10 feet of land immediately adjacent to the receiving water is owned by a different party than the land on which your construction activities are taking place and you do not have control over that land, you can treat the 10 foot area adjacent to the stream as having the equivalent soil and vegetation type that predominates in*

[2] EPA used the following when developing the buffer performance tables:

- The sediment removal efficiencies are based on the U.S. Department of Agriculture's RUSLE2 ("Revised Universal Soil Loss Equation 2") model for slope profiles using a 100-foot long denuded slopes.
- Sediment removal was defined as the annual sediment delivered at the downstream end of the 50-foot natural buffer (tons/yr/acre) divided by the annual yield from denuded area (tons/yr/acre).
- As perimeter controls are also required by the CGP, sediment removal is in part a function of the reduction due to a perimeter control (i.e., silt fence) located between the disturbed portion of the site and the upstream edge of the natural buffer and flow traveling through a 50-foot buffer of undisturbed natural vegetation.
- It was assumed that construction sites have a relatively uniform slope without topographic features that accelerate the concentration for erosive flows.
- It was assumed that vegetation has been removed from the disturbed portion of the site and a combination of cuts and fills have resulted in a smooth soil surface with limited retention of near-surface root mass.

To represent the influence of soil, EPA analyzed 11 general soil texture classifications in its evaluation of buffer performance. To represent different types of buffer vegetation, EPA evaluated 4 or more common vegetative types for each State/Territory covered under the permit. For each vegetation type evaluated, EPA considered only permanent, non-grazed, and non-harvested vegetation, on the assumption that a natural buffer adjacent to the receiving water will typically be undisturbed. EPA also evaluated slope steepness and found that sediment removal efficiencies present in Tables G-8 through G-15 are achievable for slopes that are less than nine percent.

*the 40 foot area under your control. You would then make the same assumption in Step 2 for purposes of determining the equivalent sediment removal.*

Alternatively, you may do your own calculation of the effectiveness of the 50-foot buffer based upon your site-specific conditions, and may use this number as your sediment removal equivalency standard to meet instead of using Tables F-8 through F-15. This calculation must be documented in your SWPPP.

**Step 2 - Design Controls That Match the Sediment Removal Efficiency of the 50-foot Buffer**

Once you determine the estimated sediment removal efficiency of a 50-foot buffer for your site in Step 1, you must next select stormwater controls that will provide an equivalent sediment load reduction. These controls can include the installation of a single control, such as a sediment pond or additional perimeter controls, or a combination of stormwater controls. Whichever control(s) you select, you must demonstrate in your SWPPP that the controls will provide at a minimum the same sediment removal capabilities as a 50-foot natural buffer (Step 1). You may take credit for the removal efficiencies of your required perimeter controls in your calculation of equivalency, because these were included in calculating the buffer removal efficiencies in Tables F-8 through F-15. (Note: You are reminded that the controls must be kept in effective operating condition until you complete final stabilization on the disturbed portions of the site discharging to the receiving water)

To make the determination that your controls and/or buffer area achieve an equivalent sediment load reduction as a 50-foot buffer, you should use a model or other type of calculation. As mentioned above, there are a variety of models available that can be used to support your calculation, including USDA's RUSLE-series programs and the WEPP erosion model, SEDCAD, SEDIMOT, or other models. A couple of examples are provided in Attachment 3 to help illustrate how this determination could be made.

If you retain a buffer of less than 50 feet, you may take credit for the removal that will occur from the reduced buffer and only need to provide additional controls to make up the difference between the removal efficiency of a 50 foot buffer and the removal efficiency of the narrower buffer. For example, if you retain a 30 foot buffer, you can account for the sediment removal provided by the 30 foot buffer retained, and you will only need to design controls to make up for the additional removal provided by the 20 feet of buffer that is not being provided. To do this, you would plug the width of the buffer that is retained into RUSLE or another model, along with other stormwater controls that will together achieve a sediment reduction equivalent to a natural 50-foot buffer.

As described in Step 1 above, you can take credit for the area you retained as a "natural buffer" as being fully vegetated, regardless of the condition of the buffer area.

*For example, if your earth-disturbances occur 30 feet from a receiving water, but the 10 feet of land immediately adjacent to the receiving water is owned by a different party than the land on which your construction activities are taking place and you do not have control over that land, you can treat the 10-foot area as a natural buffer, regardless of the activities that are taking place in the area. Therefore, you can assume (for purposes of your equivalency calculation) that your site is providing the sediment removal equivalent of a 30-foot buffer, and you will only need to design controls to make up for the additional removal provided by the 20-foot of buffer that is not being provided.*

**Step 3 - Document How Site-Specific Controls Will Achieve the Sediment Removal Efficiency of the 50-foot Buffer**

In Steps 1 and 2, you determined both the expected sediment removal efficiency of a 50-foot buffer at your site, and you used this number as a performance standard to design controls to be installed at your site, which alone or in combination with any retained natural buffer, achieves the expected sediment removal efficiency of a 50-foot buffer at your site. The final step is to document in your SWPPP the information you relied on to calculate the equivalent sediment reduction as an undisturbed natural buffer.

EPA will consider your documentation to be sufficient if it generally meets the following:

- For Step 1, refer to the table in Attachment 1 that you used to derive your estimated 50-foot buffer sediment removal efficiency performance. Include information about the buffer vegetation and soil type that predominate at your site, which you used to select the sediment load reduction value in Tables F-8 through F-15. Or, if you conducted a site-specific calculation for sediment removal efficiency, provide the specific removal efficiency, and the information you relied on to make your site-specific calculation.
- For Step 2, (1) Specify the model you used to estimate sediment load reductions from your site; and (2) the results of calculations showing how your controls will meet or exceed the sediment removal efficiency from Step 1.

If you choose compliance alternative 3, you must also include in your SWPPP a description of why it is infeasible for you to provide and maintain an undisturbed natural buffer of any size.

## F.3 SMALL RESIDENTIAL LOT COMPLIANCE ALTERNATIVES

EPA has developed two additional compliance alternatives applicable only to "small residential lots" that are unable to provide and maintain a 50 foot buffer.

A **small residential lot** is a lot or grouping of lots being developed for residential purposes that will disturb less than 1 acre of land, but that is part of a larger residential project that will ultimately disturb greater than or equal to 1 acre.

The following steps describe how a small residential lot operator would achieve compliance with one these 2 alternatives.

### F.3.1 Small Residential Lot Compliance Alternative Eligibility

In order to be eligible for the small residential lot compliance alternatives, the following conditions must be met:

**a.** The lot or grouping of lots meets the definition of "small residential lot"; and

**b.** The operator must follow the guidance for providing and maintaining a natural buffer in Part F.2.3 of this Appendix, including:

**i.** Ensure that all discharges from the area of earth disturbance to the natural buffer are first treated by the site's erosion and sediment controls, and use velocity dissipation devices if necessary to prevent erosion caused by stormwater within the buffer;

**ii.** Document in the SWPPP the natural buffer width retained on the property, and show the buffer boundary on your site plan; and

**iii.** Delineate, and clearly mark off, with flags, tape, or other similar marking device, all natural buffer areas.

### F.3.2 Small Residential Lot Compliance Alternatives

You must next choose from one of two small residential lot compliance alternatives and implement the stormwater control practices associated with that alternative.

*Note: The compliance alternatives provided below are not mandatory. Operators of small residential lots can alternatively choose to comply with the any of the options that are available to other sites in Part 2.2.1.a and F.2.1 of this Appendix.*

**Small Residential Lot Compliance Alternative 1**

Alternative 1 is a straightforward tiered-technology approach that specifies the controls that a small residential lot must implement based on the buffer width retained. To meet the requirements of small residential lot compliance alternative 1, you must implement the controls specified in Table F–1 based on the buffer width to be retained. See footnote 3, below, for a description of the controls you must implement.

*For example, if you are an operator of a small residential lot that will be retaining a 35-foot buffer and you choose Small Residential Lot Compliance Alternative 1, you must implement double perimeter controls between earth disturbances and the receiving water*

In addition to implementing the applicable control, you must also document in your SWPPP how you will comply with small residential lot compliance alternative 1.

**Table F-1 Alternative 1 Requirements[3]**

| Retain 50-foot Buffer | Retain <50 and >30 foot Buffer | Retain ≤ 30 foot Buffer |
|---|---|---|
| No Additional Requirements | Double Perimeter Controls | Double Perimeter Controls and 7-Day Site Stabilization |

**Small Residential Lot Compliance Alternative 2**

Alternative 2 specifies the controls that a builder of a small residential lot must implement based on both the buffer width retained and the site's sediment discharge risk. By incorporating the sediment risk, this approach may result in the implementation of controls that are more appropriate for the site's specific conditions.

**Step 1 – Determine Your Site's Sediment Risk Level**

To meet the requirements of Alternative 2, you must first determine your site's sediment discharge "risk level" based on the site's slope, location, and soil type. To help you to determine your site's sediment risk level, EPA developed five different tables for different slope conditions. You should select the table that most closely corresponds to your site's average slope.

*For example, if your site's average slope is 7 percent, you should use Table G–4 to determine your site's sediment risk.*

After you determine which table applies to your site, you must then use the table to determine the "risk level" (e.g., "low", "moderate", or "high") that corresponds to your site's location and predominant soil type.[4]

*For example, based on Table F-3, a site located in New Hampshire with a 4 percent average slope and with predominately sandy clay loam soils would fall into the "moderate" risk level.*

[3] **Description of Additional Controls Applicable to Small Residential Lot Compliance Alternatives 1 and 2:**

- **No Additional Requirements:** If you implement a buffer of 50 feet or greater, then you are not subject to any additional requirements. Note that you are required to install perimeter controls between the disturbed portions of your site and the buffer in accordance with Part 2.2.3.
- **Double Perimeter Control:** In addition to the reduced buffer width retained on your site, you must provide a double row of perimeter controls between the disturbed portion of your site and the receiving water spaced a minimum of 5 feet apart.
- **Double Perimeter Control and 7-Day Site Stabilization:** In addition to the reduced buffer width retained on your site and the perimeter control implemented in accordance with Part 2.2.3, you must provide a double row of perimeter controls between the disturbed portion of your site and the receiving water spaced a minimum of 5 feet apart, and you are required to complete the stabilization activities specified in Parts 2.2.14 within 7 calendar days of the temporary or permanent cessation of earth-disturbing activities.

[4] One source for determining your site's predominant soil type is the USDA's Web Soil Survey located at http://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx.

**Table F-2 Risk Levels for Sites with Average Slopes of ≤ 3 Percent**

| Soil Type / Location | Clay | Silty Clay Loam or Clay-Loam | Sand | Sandy Clay Loam, Loamy Sand or Silty Clay | Loam, Silt, Sandy Loam or Silt Loam |
|---|---|---|---|---|---|
| **CNMI / Guam** | Moderate | Moderate | Moderate | Moderate | High |
| **Puerto Rico** | Moderate | Moderate | Moderate | Moderate | High |
| **Virgin Islands** | Low | Moderate | Low | Moderate | Moderate |
| **American Samoa** | Moderate | Moderate | Moderate | Moderate | High |
| **Massachusetts and New Hampshire** | Low | Moderate | Low | Low | Moderate |
| **Idaho** | Low | Low | Low | Low | Low |
| **New Mexico** | Low | Low | Low | Low | Low |
| **Washington D.C.** | Low | Moderate | Low | Low | Moderate |

**Table F-3 Risk Levels for Sites with Average Slopes of > 3 Percent and ≤ 6 Percent**

| Soil Type / Location | Clay | Silty Clay Loam or Clay-Loam | Sand | Sandy Clay Loam, Loamy Sand or Silty Clay | Loam, Silt, Sandy Loam or Silt Loam |
|---|---|---|---|---|---|
| **CNMI / Guam** | Moderate | Moderate | Moderate | Moderate | High |
| **Puerto Rico** | Moderate | Moderate | Moderate | Moderate | High |
| **Virgin Islands** | Moderate | Moderate | Moderate | Moderate | High |
| **American Samoa** | High | High | Moderate | High | High |
| **Massachusetts and New Hampshire** | Moderate | Moderate | Low | Moderate | High |
| **Idaho** | Low | Low | Low | Low | Low |
| **New Mexico** | Low | Low | Low | Low | Moderate |
| **Washington D.C.** | Moderate | Moderate | Moderate | Moderate | High |

**Table F-4 Risk Levels for Sites with Average Slopes of > 6 Percent and ≤ 9 Percent**

| Soil Type / Location | Clay | Silty Clay Loam or Clay-Loam | Sand | Sandy Clay Loam, Loamy Sand or Silty Clay | Loam, Silt, Sandy Loam or Silt Loam |
|---|---|---|---|---|---|
| **CNMI / Guam** | Moderate | High | Moderate | High | High |
| **Puerto Rico** | Moderate | High | Moderate | Moderate | High |
| **Virgin Islands** | Moderate | Moderate | Moderate | Moderate | High |
| **American Samoa** | High | High | High | High | High |
| **Massachusetts and New Hampshire** | Moderate | Moderate | Moderate | Moderate | High |
| **Idaho** | Low | Low | Low | Low | Low |
| **New Mexico** | Low | Low | Low | Low | Moderate |
| **Washington D.C.** | Moderate | Moderate | Moderate | Moderate | High |

**Table F-5 Risk Levels for Sites with Average Slopes of > 9 Percent and ≤ 15 Percent**

| Soil Type / Location | Clay | Silty Clay Loam or Clay-Loam | Sand | Sandy Clay Loam, Loamy Sand or Silty Clay | Loam, Silt, Sandy Loam or Silt Loam |
|---|---|---|---|---|---|
| **CNMI / Guam** | High | High | High | High | High |
| **Puerto Rico** | High | High | High | High | High |
| **Virgin Islands** | Moderate | High | Moderate | High | High |
| **American Samoa** | High | High | High | High | High |
| **Massachusetts and New Hampshire** | Moderate | Moderate | Moderate | Moderate | High |
| **Idaho** | Low | Low | Low | Low | Low |
| **New Mexico** | Low | Moderate | Low | Moderate | Moderate |
| **Washington D.C.** | Moderate | High | Moderate | Moderate | High |

**Table F-6 Risk Levels for Sites with Average Slopes of > 15 Percent**

| Soil Type / Location | Clay | Silty Clay Loam or Clay-Loam | Sand | Sandy Clay Loam, Loamy Sand or Silty Clay | Loam, Silt, Sandy Loam or Silt Loam |
|---|---|---|---|---|---|
| **CNMI / Guam** | High | High | High | High | High |
| **Puerto Rico** | High | High | High | High | High |
| **Virgin Islands** | High | High | High | High | High |
| **American Samoa** | High | High | High | High | High |
| **Massachusetts and New Hampshire** | High | High | Moderate | High | High |
| **Idaho** | Low | Low | Low | Low | Moderate |
| **New Mexico** | Moderate | Moderate | Moderate | Moderate | High |
| **Washington D.C.** | High | High | Moderate | High | High |

**Step 2 – Determine Which Additional Controls Apply**

Once you determine your site's "risk level", you must next determine the additional controls you need to implement on your site, based on the width of buffer you plan to retain. Table F-7 specifies the requirements that apply based on the "risk level" and buffer width retained. See footnote 3, above, for a description of the additional controls that are required.

*For example, if you are the operator of a small residential lot that falls into the "moderate" risk level, and you decide to retain a 20-foot buffer, using Table F-7 you would determine that you need to implement double perimeter controls to achieve compliance with small residential lot compliance alternative 2.*

You must also document in your SWPPP your compliance with small residential lot compliance alternative 2.

**Table F-7. Alternative 2 Requirements[2]**

| Risk Level Based on Estimated Soil Erosion | Retain ≥ 50' Buffer | Retain <50' and >30' Buffer | Retain ≤30' and >10' Buffer | Retain ≤ 10' Buffer |
|---|---|---|---|---|
| **Low Risk** | No Additional Requirements | No Additional Requirements | Double Perimeter Control | Double Perimeter Control |
| **Moderate Risk** | No Additional Requirements | Double Perimeter Control | Double Perimeter Control | Double Perimeter Control and 7-Day Site Stabilization |
| **High Risk** | No Additional Requirements | Double Perimeter Control | Double Perimeter Control and 7-Day Site Stabilization | Double Perimeter Control and 7-Day Site Stabilization |

**ATTACHMENT 1**

Sediment Removal Efficiency Tables[5]

EPA recognizes that very high removal efficiencies, even where theoretically achievable by a 50-foot buffer, may be very difficult to achieve in practice using alternative controls. Therefore in the tables below, EPA has limited the removal efficiencies to a maximum of 90%. Efficiencies that were calculated at greater than 90% are shown as 90%, and this is the minimum percent removal that must be achieved by alternative controls.

**Table F-8 Estimated 50-foot Buffer Performance in Idaho***

| | Estimated % Sediment Removal | | | | |
|---|---|---|---|---|---|
| **Type of Buffer Vegetation**** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
| **Tall Fescue Grass** | 42 | 52 | 44 | 48 | 85 |
| **Medium-density Weeds** | 28 | 30 | 28 | 26 | 60 |
| **Low-density Warm-season Native Bunchgrass (i.e., Grama Grass)** | 25 | 26 | 24 | 24 | 55 |
| **Northern Mixed Prairie Grass** | 28 | 30 | 28 | 26 | 50 |
| **Northern Range Cold Desert Shrubs** | 28 | 28 | 24 | 26 | 50 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

**Table F-9 Estimated 50-foot Buffer Performance in Massachusetts and New Hampshire***

| | Estimated % Sediment Removal | | | | |
|---|---|---|---|---|---|
| **Type of Buffer Vegetation**** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
| **Warm-season Grass (i.e., Switchgrass, Lemongrass)** | 79 | 90 | 90 | 90 | 90 |
| **Cool-season Dense Grass (Kentucky Bluegrass, Smooth Bromegrass, Timothy)** | 78 | 90 | 90 | 90 | 90 |
| **Tall Fescue Grass** | 76 | 90 | 81 | 89 | 90 |
| **Medium-density Weeds** | 66 | 76 | 60 | 72 | 66 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

[5] The buffer performances were calculated based on a denuded slope upgradient of a 50-foot buffer and a perimeter controls, as perimeter controls are a standard requirement (see Part 2.2.3).

**Table F-10 Estimated 50-foot Buffer Performance in New Mexico***

| | Estimated % Sediment Removal | | | | |
|---|---|---|---|---|---|
| **Type of Buffer Vegetation **** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
| **Tall Fescue grass** | 71 | 85 | 80 | 86 | 90 |
| **Medium-density Weeds** | 56 | 73 | 55 | 66 | 78 |
| **Low-density Warm-season Native Bunchgrass (i.e., Grama Grass)** | 53 | 70 | 51 | 62 | 67 |
| **Southern Mixed Prairie Grass** | 53 | 71 | 52 | 63 | 50 |
| **Southern Range Cold Desert Shrubs** | 56 | 73 | 55 | 65 | 53 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

**Table F-11 Estimated 50-foot Buffer Performance in Washington, DC***

| | Estimated % Sediment Removal | | | | |
|---|---|---|---|---|---|
| **Type of Buffer Vegetation **** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
| **Warm-season Grass (i.e., Switchgrass, Lemongrass)** | 82 | 90 | 90 | 90 | 90 |
| **Cool-season Dense Grass (Kentucky Bluegrass, Smooth Bromegrass, Timothy)** | 81 | 90 | 90 | 90 | 90 |
| **Tall Fescue Grass** | 79 | 90 | 83 | 89 | 90 |
| **Medium-density Weeds** | 71 | 79 | 66 | 75 | 74 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

**Table F-12 Estimated 50-foot Buffer Performance in American Samoa***

| | Estimated % Sediment Removal | | | | |
|---|---|---|---|---|---|
| **Type of Buffer Vegetation **** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
| **Bahiagrass (Permanent cover)** | 82 | 90 | 90 | 90 | 83 |
| **Warm-season Grass (i.e., Switchgrass, Lemongrass)** | 82 | 90 | 90 | 90 | 85 |
| **Dense Grass** | 82 | 90 | 90 | 90 | 83 |
| **Tall Fescue Grass** | 82 | 89 | 82 | 89 | 79 |
| **Medium-density Weeds** | 70 | 73 | 62 | 75 | 59 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

**Table F-13 Estimated 50-foot Buffer Performance in CNMI and Guam***

| | Estimated % Sediment Removal | | | | |
|---|---|---|---|---|---|
| **Type of Buffer Vegetation **** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
| **Bahiagrass (Permanent cover)** | 80 | 90 | 90 | 90 | 89 |
| **Warm-season Grass (i.e., Switchgrass, Lemongrass)** | 80 | 90 | 90 | 90 | 90 |
| **Dense Grass** | 79 | 90 | 90 | 90 | 89 |
| **Tall Fescue Grass** | 76 | 90 | 80 | 88 | 87 |
| **Medium-density Weeds** | 63 | 73 | 53 | 68 | 61 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

**Table F-14 Estimated 50-foot Buffer Performance in Puerto Rico***

| | Estimated % Sediment Removal | | | | |
|---|---|---|---|---|---|
| **Type of Buffer Vegetation**** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
| **Bahiagrass (Permanent cover)** | 83 | 90 | 90 | 90 | 90 |
| **Warm-season Grass (i.e., Switchgrass, Lemongrass)** | 83 | 90 | 90 | 90 | 90 |
| **Dense Grass** | 83 | 90 | 90 | 90 | 90 |
| **Tall Fescue Grass** | 82 | 90 | 84 | 90 | 89 |
| **Medium-density Weeds** | 72 | 78 | 65 | 76 | 64 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

**Table F-15 Estimated 50-foot Buffer Performance in Virgin Islands***

| **Type of Buffer Vegetation**** | **Clay** | **Silty Clay Loam or Clay-Loam** | **Sand** | **Sandy Clay Loam, Loamy Sand or Silty Clay** | **Loam, Silt, Sandy Loam or Silt Loam** |
|---|---|---|---|---|---|
| **Bahiagrass (Permanent cover)** | 85 | 90 | 90 | 90 | 90 |
| **Warm-season Grass (i.e., Switchgrass, Lemongrass)** | 86 | 90 | 90 | 90 | 90 |
| **Dense Grass** | 85 | 90 | 90 | 90 | 90 |
| **Tall Fescue Grass** | 85 | 90 | 88 | 90 | 89 |
| **Medium-density Weeds** | 75 | 77 | 71 | 78 | 63 |

* Applicable for sites with less than nine percent slope
** Characterization focuses on the under-story vegetation

**ATTACHMENT 2**

Using the Sediment Removal Efficiency Tables – Questions and Answers

- *What if my specific buffer vegetation is not represented in Tables F-8 through F-15?* Tables F-8 through F-15 provide a wide range of factors affecting buffer performance; however, there are likely instances where the specific buffer vegetation type on your site is not listed. If you do not see a description of the type of vegetation present at your site, you should choose the vegetation type that most closely matches the vegetation type on your site. You can contact your local Cooperative Extension Service Office (http://nifa.usda.gov/partners-and-extension-map) for assistance in determining the vegetation type in Tables F-8 through F-15 that most closely matches your site-specific vegetation.
- *What if there is high variability in local soils?* EPA recognizes that there may be a number of different soil type(s) on any given construction site. General soil information can be obtained from USDA soil survey reports (http://websoilsurvey.nrcs.usda.gov) or from individual site assessments performed by a certified soil expert. Tables F-8 through F-15 present eleven generic soil texture classes, grouping individual textures where EPA has determined that performance is similar. If your site contains different soil texture classes, you should use the soil type that best approximates the predominant soil type at your site.
- *What if my site slope is greater than 9 percent after final grade is reached?* As indicated in the buffer performance tables, the estimated sediment removal efficiencies are associated with disturbed slopes of up to 9 percent grade. Where your graded site has an average slope of greater than 9 percent, you should calculate a site-specific buffer performance.
- *How do I calculate my own estimates for sediment reduction at my specific site?* If you determine that it is necessary to calculate your own sediment removal efficiency using site-specific conditions (e.g., slopes at your site are greater than 9 percent), you can use a range of available models that are available to facilitate this calculation, including USDA's RUSLE-series programs and the WEPP erosion model, SEDCAD, SEDIMOT, or other equivalent models.
- *What is my estimated buffer performance if my site location is not represented by Tables F-8 through F-15?* If your site is located in an area not represented by Tables F-8 through F-15, you should use the table that most closely approximates conditions at your site. You may instead choose to conduct a site-specific calculation of the buffer performance.
- *What if only a portion of my site drains to the buffer area?* If only a portion of your site drains to a receiving water, where that water is within 50 feet of your earth disturbances, you are only required to meet the equivalency requirement for the stormwater flows corresponding to those portions of the site. See Example 2 below for an example of how this is expected to work.

**ATTACHMENT 3**

Examples of How to Use the Sediment Removal Efficiency Tables

*Example 1. Comparatively Wet Location (7.5 acre site located in Massachusetts)*

The operator of a 7.5-acre construction site in Massachusetts has determined that it is infeasible to establish a buffer of any size on the site, and is now required to select and install controls that will achieve an equivalent sediment load reduction as that estimated in F-9 for their site conditions. The first step is to identify what percentage of eroded sediment is estimated to be retained from a 50-foot buffer. For this example, it is assumed that the site has a relatively uniform gentle slope (3 percent), so Table F-9 can be used to estimate the 50-foot buffer sediment load reduction. If the site's buffer vegetation is best typified by cool-season dense grass and the underlying soil is of a type best described as loamy sand, the 50-foot buffer is projected to capture 90 percent of eroded sediment from the construction site.

The second step is to determine what sediment controls can be selected and installed in combination with the perimeter controls already required to be implemented at the site (see Part 2.2.3), which will achieve the 90 percent sediment removal efficiency from Table F-9. For this example, using the RUSLE2 profile model, it was determined that installing a pair of shallow-sloped diversion ditches to convey runoff to a well-designed and maintained sediment basin provides 99 percent sediment removal. Because the estimated sediment reduction is greater than the required 90 percent that a 50-foot buffer provides, the operator will have met the buffer requirements. See Figure F-5. The operator could also choose a different set of controls, as long as they achieve at least a 90 percent sediment removal efficiency.





**Figure F-5 Example 1 – Equivalent Sediment Load Reductions at a 7.5 ac Site in MA.**

*Example 2. Arid Location With Pre-existing Disturbances in the Natural Buffer (6.5 acre site located in New Mexico)*

An operator of a site in New Mexico determines that it is not feasible to provide a 50-foot buffer, but a 28-foot buffer can be provided. Because the operator will provide a buffer that is less than 50 feet, the operator must determine which controls, in combination with the 28-foot buffer, achieve a sediment load reduction equivalent to the 50-foot buffer. In this example, the project will disturb 6.5 acres of land, but only 1.5 acres of the total disturbed area drains to the buffer area. Within the 28-foot buffer area is a preexisting concrete walkway. Similar to Example 1, the equivalence analysis starts with Step 1 in Part F.2.4 of this Appendix with a review of the New Mexico buffer performance (Table F-10). The operator determines that the predominate vegetation type in the buffer area is prairie grass, the soil type is similar to silt, and the site is of a uniform, shallow slope (e.g., 3 percent grade). Although the operator will take credit for the disturbance caused by the concrete walkway as a natural buffer in Step 2, here the operator can treat the entire buffer area as being naturally vegetated with prairie grass. Based on this information, the operator refers to Table F-10 to estimate that the 50-foot buffer would retain 50 percent of eroded soil.

The second step is to determine, based on the 50 percent sediment removal efficiency found in Table F-10, what sediment controls, in combination with the 28-foot buffer area, can be implemented to reduce sediment loads by 50 percent or more. The operator does not have to account the reduction in buffer function caused by the preexisting walkway, and can take credit for the entire 28-foot buffer being fully vegetated in the analysis. For this example, using the RUSLE2 profile model, the operator determined that installing a fiber roll barrier between the

silt fence (already required by Part 2.2.3) and the 28-foot buffer will achieve an estimated 84 percent sediment removal efficiency. See Figure F-6. Note that this operator is subject to the requirement in Part F.2.3 of this Appendix to ensure that discharges through the silt fence, fiber roll barrier, and 28-foot buffer do not cause erosion within the buffer. The estimated sediment reduction is greater than the required 50 percent; therefore the operator will have met the buffer alternative requirement.





**Figure F-6 Example 2 – Equivalent Sediment Load Reductions at a 6.5 ac Site in NM.**

# Appendix G - Standard Permit Conditions

Standard permit conditions in Appendix G are consistent with the general permit provisions required under 40 CFR 122.41.

## G.1 Duty To Comply.

You must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application.

**G.1.1** You must comply with effluent standards or prohibitions established under section 307(a) of the Clean Water Act for toxic pollutants within the time provided in the regulations that establish these standards, even if the permit has not yet been modified to incorporate the requirement.

**G.1.2** Penalties for Violations of Permit Conditions: EPA and other federal agencies are required to adjust their maximum and minimum statutory civil penalty amounts through rulemaking by January 15 each year to account for inflation. EPA's annual rulemaking adjustments, codified in 40 C.F.R. § 19.4, are mandated by the Federal Civil Penalties Inflation Adjustment Act of 1990, as amended through the Federal Civil Penalties Inflation Adjustment Act Improvements Act of 2015 (28 U.S.C. § 2461 note). As such, the civil penalty amounts below may change in the future due to inflation. See 40 C.F.R. § 19.4 for the most up-to-date civil penalty amounts.

G.1.2.1 *Criminal Penalties.*

a. *Negligent Violations*. The CWA provides that any person who negligently violates permit conditions implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the Act is subject to criminal penalties of not less than $2,500 nor more than $25,000 per day of violation, or imprisonment of not more than one year, or both. In the case of a second or subsequent conviction for a negligent violation, a person shall be subject to criminal penalties of not more than $50,000 per day of violation or by imprisonment of not more than two years, or both.

b. *Knowing Violations.* The CWA provides that any person who knowingly violates permit conditions implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the Act is subject to a fine of not less than $5,000 nor morethan $50,000 per day of violation, or by imprisonment for not more than 3 years, or both. In the case of a second or subsequent conviction for a knowing violation, a person shall be subject to criminal penalties of not more than $100,000 per day of violation, or imprisonment of not more than 6 years, or both.

c. *Knowing Endangerment.* The CWA provides that any person who knowingly violates permit conditions implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the Act and who knows at that time that he or she is placing another person in imminent danger of death or serious bodily injury shall upon conviction be subject to a fine of not more than $250,000 or by imprisonment of not more than 15 years, or both. In the case of a second or subsequent conviction for a knowing endangerment violation, aperson shall be subject to a fine of not more than $500,000 or by imprisonment of not more than 30 years, or both. An organization, as defined in section 309(c)(3)(B)(iii) of the Act, shall, upon conviction of violating the imminent danger provision be subject to a fine of not more than $1,000,000 and can fined up to $2,000,000 for second or subsequent convictions.

d. *False Statement.* The CWA provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under this permit shall, upon conviction, be punished by a fine of not more than $10,000, or by imprisonment for not more than 2 years, or both. If a conviction of a person is for a violation committed after a first conviction of such person under this paragraph, punishment is a fine of not more than $20,000 per day of violation, or by imprisonment of not more than 4 years, or both. The Act further provides that any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance shall, upon conviction, be punished by a fine of not more than $10,000 per violation, or by imprisonment for not more than 6 months per violation, or by both.

G.1.2.2 *Civil Penalties.* The CWA provides that any person who violates a permit condition implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the Act is subject to a civil penalty not to exceed the maximum amount authorized by Section 309(d) of the Act, as adjusted pursuant to the Federal Civil Penalties Inflation Adjustment Act of 1990 (28 U.S.C. § 2461 note), and codified at 40 CFR § 19.4.

G.1.2.3 *Administrative Penalties.* The CWA provides that any person who violates a permit condition implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the Act is subject to an administrative penalty, as follows:

a. *Class I Penalty*. Not to exceed the maximum amounts authorized by Section 309(g)(2)(A) of the Act and the Federal Civil Penalties Inflation Adjustment Act of 1990 as amended by the Federal Civil Penalties Inflation Adjustment Act Improvements Act of 2015 (28 U.S.C. § 2461 note), and codified at 40 CFR § 19.4.

b. *Class II Penalty*. Not to exceed the maximum amounts authorized by Section 309(g)(2)(B) of the Act and the Federal Civil Penalties Inflation Adjustment Act of 1990, as amended by the Federal Civil Penalties Inflation Adjustment Act Improvements Act of 2015 (28 U.S.C. § 2461 note), and codified at 40 CFR § 19.4.

### G.2 Duty to Reapply.

If you wish to continue an activity regulated by this permit after the expiration date of this permit, you must apply for and obtain authorization as required by the new permit once EPA issues it.

### G.3 Need to Halt or Reduce Activity Not a Defense.

It shall not be a defense for you in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.

### G.4 Duty to Mitigate.

You must take all reasonable steps to minimize or prevent any discharge in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment.

### G.5 Proper Operation and Maintenance.

You must at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) that are installed or used by you to achieve compliance with the conditions of this permit. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the

operation of backup or auxiliary facilities or similar systems which are installed by you only when the operation is necessary to achieve compliance with the conditions of this permit.

### G.6 Permit Actions.

This permit may be modified, revoked and reissued, or terminated for cause. Your filing of a request for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any permit condition.

### G.7 Property Rights.

This permit does not convey any property rights of any sort, or any exclusive privileges.

### G.8 Duty to Provide Information.

You must furnish to EPA or an authorized representative (including an authorized contractor acting as a representative of EPA), within a reasonable time, any information that EPA may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit or to determine compliance with this permit. You must also furnish to EPA or an authorized representative upon request, copies of records required to be kept by this permit.

### G.9 Inspection and Entry.

You must allow EPA or an authorized representative (including an authorized contractor acting as a representative of EPA), upon presentation of credentials and other documents as may be required by law, to:

**G.9.1** Enter upon your premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this permit;

**G.9.2** Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;

**G.9.3** Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit; and

**G.9.4** Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the Clean Water Act, any substances or parameters at any location.

### G.10 Monitoring and Records.

**G.10.1** Samples and measurements taken for the purpose of monitoring must be representative of the volume and nature of the monitored activity.

**G.10.2** You must retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this permit, and records of all data used to complete the application for this permit, for a period of at least three years from the date the permit expires or the date the permittee's authorization is terminated. This period may be extended by request of EPA at any time.

**G.10.3** Records of monitoring information must include:

G.10.3.1 The date, exact place, and time of sampling or measurements;

G.10.3.2 The individual(s) who performed the sampling or measurements;

G.10.3.3 The date(s) analyses were performed

G.10.3.4 The individual(s) who performed the analyses;

G.10.3.5 The analytical techniques or methods used; and

G.10.3.6 The results of such analyses.

**G.10.4** Monitoring must be conducted according to test procedures approved under 40 CFR Part 136, unless other test procedures have been specified in the permit.

**G.10.5** The Clean Water Act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under this permit shall, upon conviction, be punished by a fine of not more than $10,000, or by imprisonment for not more than 2 years, or both. If a conviction of a person is for a violation committed after a first conviction of such person under this paragraph, punishment is a fine of not more than $20,000 per day of violation, or by imprisonment of not more than 4 years, or both.

**G.11 Signatory Requirements.**

**G.11.1** All applications, including NOIs and NOTs, must be signed as follows:

G.11.1.1 For a corporation: By a responsible corporate officer. For the purpose of this subsection, a responsible corporate officer means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

G.11.1.2 For a partnership or sole proprietorship: By a general partner or the proprietor, respectively; or

G.11.1.3 For a municipality, state, federal, or other public agency: By either a principal executive officer or ranking elected official. For purposes of this subsection, a principal executive officer of a federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of EPA).

**G.11.2** Your SWPPP (including changes to your SWPPP inspection reports), corrective action log, turbidity monitoring report, site inspection and dewatering inspection reports, and any other compliance documentation required under this permit, must be signed by a person described in Appendix G, Subsection G.11.1 above or by a duly authorized representative of that person. A person is a duly authorized representative only if:

G.11.2.1 The authorization is made in writing by a person described in Appendix G, Subsection G.11.1;

G.11.2.2 The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental

matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position); and

G.11.2.3 The signed and dated written authorization is included in the SWPPP. A copy must be submitted to EPA, if requested.

**G.11.3** Changes to Authorization. If an authorization under this permit is no longer accurate because a different operator has responsibility for the overall operation of the construction site, a new NOI must be submitted to EPA. See Table 1 in Part 1.4.3 of the permit. However, if the only change that is occurring is a change in contact information or a change in the facility's address, the operator need only make a modification to the existing NOI submitted for authorization.

**G.11.4** Any person signing documents in accordance with Appendix G, Subsections G.11.1 or G.11.2 above must include the following certification:

> "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information contained therein. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information contained is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

**G.11.5** For persons signing NOIs electronically, in addition to meeting other applicable requirements in Appendix G, Subsection G.11, such signatures must meet the same signature, authentication, and identity-proofing standards set forth at 40 CFR § 3.2000(b) for electronic reports (including robust second-factor authentication).

**G.11.6** The CWA provides that any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or non-compliance shall, upon conviction, be punished by a fine of not more than $10,000 per violation, or by imprisonment for not more than 6 months per violation, or by both.

**G.12 Reporting Requirements.**

**G.12.1** Planned changes. You must give notice to EPA as soon as possible of any planned physical alterations or additions to the permitted facility. Notice is required only when:

G.12.1.1 The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in 40 CFR 122.29(b); or

G.12.1.2 The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants which are subject neither to effluent limitations in the permit, nor to notification requirements under 40 CFR 122.42(a)(1).

**G.12.2** Anticipated noncompliance. You must give advance notice to EPA of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.

**G.12.3** Transfers. This permit is not transferable to any person except after notice to EPA. Where a facility wants to change the name of the permittee, the original permittee (the first owner or operators) must submit a Notice of Termination pursuant to Part 8. The new

owner or operator must submit a Notice of Intent in accordance with Part 1.4 and Table 1. See also requirements in Appendix G, Subsections G.11.1 and G.11.2.

**G.12.4** Monitoring reports. Monitoring results must be reported at the intervals specified elsewhere in this permit.

G.12.4.1 Monitoring results must be reported on a Discharge Monitoring Report (DMR) or forms provided or specified by EPA for reporting results of monitoring of sludge use or disposal practices.

G.12.4.2 If you monitor any pollutant more frequently than required by the permit using test procedures approved under 40 CFR Part 136 or, in the case of sludge use or disposal, approved under 40 CFR 136 unless otherwise specified in 40 CFR Part 503, or as specified in the permit, the results of this monitoring must be included in the calculation and reporting of the data submitted in the DMR or sludge reporting form specified by EPA.

**G.12.5** Compliance schedules. Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this permit must be submitted no later than 14 days following each schedule date.

**G.12.6** Twenty-four hour reporting. In addition to reports required elsewhere in this permit:

G.12.6.1 You must report any noncompliance which may endanger health or the environment directly to the EPA Regional Office (see contacts at https://www2.epa.gov/national-pollutant-discharge-elimination-system-npdes/contact-us-stormwater#regional). Any information must be provided orally within 24 hours from the time you become aware of the circumstances. A written submission must also be provided within five days of the time you become aware of the circumstances. The written submission must contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.

G.12.6.2 The following shall be included as information which must be reported within 24 hours under this paragraph.

a. Any unanticipated bypass which exceeds any effluent limitation in the permit. (See 40 CFR 122.41(m)(3)(ii))

b. Any upset which exceeds any effluent limitation in the permit

c. Violation of a maximum daily discharge limit for any numeric effluent limitation. (See 40 CFR 122.44(g).)

G.12.6.3 EPA may waive the written report on a case-by-case basis for reports under Appendix G, Subsection G.12.6.2 if the oral report has been received within 24 hours.

**G.12.7** Other noncompliance. You must report all instances of noncompliance not reported under Appendix G, Subsections G.12.4, G.12.5, and G.12.6, at the time monitoring reports are submitted. The reports must contain the information listed in Appendix G, Subsection G.12.6.

**G.12.8** Other information. Where you become aware that you failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Permitting Authority, you must promptly submit such facts or information.

**G.13 Bypass.**

**G.13.1** Definitions.

G.13.1.1 Bypass means the intentional diversion of waste streams from any portion of a treatment facility See 40 CFR 122.41(m)(1)(i).

G.13.1.2 Severe property damage means substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production. See 40 CFR 122.41(m)(1)(ii).

**G.13.2** Bypass not exceeding limitations. You may allow any bypass to occur which does not cause effluent limitations to be exceeded, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions of Appendix G, Subsections G.13.3 and G.13.4. See 40 CFR 122.41(m)(2).

**G.13.3** Notice.

G.13.3.1 Anticipated bypass. If you know in advance of the need for a bypass, you must submit prior notice, if possible at least ten days before the date of the bypass. See 40 CFR 122.41(m)(3)(i).

G.13.3.2 Unanticipated bypass. You must submit notice of an unanticipated bypass as required in Appendix G, Subsection G.12.6 (24-hour notice). See 40 CFR 122.41(m)(3)(ii).

**G.13.4** Prohibition of bypass. See 40 CFR 122.41(m)(4).

G.13.4.1 Bypass is prohibited, and EPA may take enforcement action against you for bypass, unless:

a. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;

b. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance; and

c. You submitted notices as required under Appendix G, Subsection G.13.3.

G.13.4.2 EPA may approve an anticipated bypass, after considering its adverse effects, if EPA determines that it will meet the three conditions listed above in Appendix G, Subsection G.13.4.1.

**G.14 Upset.**

**G.14.1** Definition. Upset means an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond your reasonable control. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation. See 40 CFR 122.41(n)(1).

**G.14.2** Effect of an upset. An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of Appendix G, Subsection G.14.3 are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review. See 40 CFR 122.41(n)(2).

**G.14.3** Conditions necessary for a demonstration of upset. See 40 CFR 122.41(n)(3). A permittee who wishes to establish the affirmative defense of upset must demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:

G.14.3.1 An upset occurred and that you can identify the cause(s) of the upset;

G.14.3.2 The permitted facility was at the time being properly operated; and

G.14.3.3 You submitted notice of the upset as required in Appendix G, Subsection G.12.6.2.b (24 hour notice).

G.14.3.4 You complied with any remedial measures required under Appendix G, Subsection G.4.

**G.14.4** Burden of proof. In any enforcement proceeding, you, as the one seeking to establish the occurrence of an upset, have the burden of proof. See 40 CFR 122.41(n)(4).

### G.15 Retention of Records.

Copies of the SWPPP and all documentation required by this permit, including records of all data used to complete the NOI to be covered by this permit, must be retained for at least three years from the date that permit coverage expires or is terminated. This period may be extended by request of EPA at any time.

### G.16 Reopener Clause.

**G.16.1** Procedures for modification or revocation. Permit modification or revocation will be conducted according to 40 CFR §122.62, §122.63, §122.64 and §124.5.

**G.16.2** Water quality protection. If there is evidence indicating that the stormwater discharges authorized by this permit cause, have the reasonable potential to cause or contribute to an excursion above any applicable water quality standard, you may be required to obtain an individual permit, or the permit may be modified to include different limitations and/or requirements.

**G.16.3** Timing of permit modification. EPA may elect to modify the permit prior to its expiration (rather than waiting for the new permit cycle) to comply with any new statutory or regulatory requirements, such as for effluent limitation guidelines that may be promulgated in the course of the current permit cycle.

### G.17 Severability.

Invalidation of a portion of this permit does not necessarily render the whole permit invalid. EPA's intent is that the permit is to remain in effect to the extent possible; in the event that any part of this permit is invalidated, EPA will advise the regulated community as to the effect of such invalidation.

## Appendix H - Notice of Intent (NOI) Form and Instructions

Part 1.4.1 requires you to use the NPDES eReporting Tool, or "NeT" system, to prepare and submit your NOI electronically. However, if the EPA Regional Office grants you a waiver to use a paper NOI form, and you elect to use it, you must complete and submit the following form.

| NPDES Form 3510-9 | EPA | U.S. Environmental Protection Agency<br>Washington, DC 20460<br>Notice of Intent for the 2022 NPDES Construction General Permit | OMB No. 2040-0305<br>Exp. Date 01/31/2025 |
|---|---|---|---|

Submission of this Notice of Intent (NOI) constitutes notice that the operator identified in Section III of this form requests authorization to discharge pursuant to the NPDES Construction General Permit (CGP) permit number identified in Section II of this form. Submission of this NOI also constitutes notice that the operator identified in Section III of this form meets the eligibility requirements of Part 1.1 CGP for the project identified in Section IV of this form. Permit coverage is required prior to commencement of construction activity until you are eligible to terminate coverage as detailed in Part 8 of the CGP. To obtain authorization, you must submit a complete and accurate NOI form. Discharges are not authorized if your NOI is incomplete or inaccurate or if you were never eligible for permit coverage. Refer to the instructions at the end of this form.

## SECTION I. APPROVAL TO USE PAPER NOI FORM

**Paper NOI Form**

Have you been granted a waiver from electronic reporting from the Regional Office*? ☐ Yes ☐ No

If yes, check which waiver you have been granted, the name of the EPA Regional Office staff person who granted the waiver, and the date of approval:

Waiver granted:

☐ The owner/operator's headquarters is physically located in a geographic area (i.e., ZIP code or census tract) that is identified as under-served for broadband Internet access in the most recent report from the Federal Communications Commission.

☐ The owner/operator has issues regarding available computer access or computer capability.

| Name of EPA staff person that granted the waiver | Date approval obtained (MM/DD/YYYY) |
|---|---|
| | |

*** Note: You are required to obtain approval from the applicable Regional Office prior to using this paper NOI form. If you have not obtained a waiver, you must file this form electronically using the NPDES eReporting Tool (NeT).**

## SECTION II. PERMIT INFORMATION

**Permit**

| **NPDES ID** (EPA Use Only) | Master Permit Number (see Appendix B of the CGP for the list of eligible permit numbers) |
|---|---|
| | |

## SECTION III. OPERATOR INFORMATION

**Operator Information**

Operator Name

Are you requesting coverage under this NOI as a "Federal Operator" or for a "Federal Facility" as defined in Appendix A? ☐ Yes ☐ No

Mailing Address

Street

| City | State | ZIP Code |
|---|---|---|
| | | |

County or Similar Government Division

Operator Point of Contact Information:

| First Name | Middle Initial | Last Name |
|---|---|---|
| | | |

Title

| Phone Number | Email Address |
|---|---|
| | |

**NOI Preparer**

Complete if NOI was prepared by someone other than the certifier:

| First Name | Middle Initial | Last Name |
|---|---|---|
| | | |

Organization

| Phone number | Email address |
|---|---|
| | |

## SECTION IV. PROJECT/SITE INFORMATION

**Project/Site Address**

Project/Site Name

Street/Location

| City | State | ZIP Code |
|---|---|---|
| | | |

County or Similar Government Division:

For the project/site you are seeking permit coverage, provide the following information:

| Latitude (in decimal degrees to four decimal places): | Longitude (in decimal degrees to four decimal places): |
|---|---|
| ° N | ° W |

Latitude/Longitude Data Source: ☐ Map ☐ GPS ☐ Other (Specify):

Horizontal Reference Datum: ☐ NAD 27 ☐ NAD 83 ☐ WGS 84

**Site Information**

Is your site located in Indian country lands, or on a property of religious or cultural significance to an Indian Tribe? ☐ Yes ☐ No

If yes, provide the name of the Indian Tribe associated with the area of Indian country (including name of Indian reservation, if applicable), or if not in Indian country, provide the name of the Indian Tribe associated with the property:

**Project Information**

| Estimated Project Start Date (MM/DD/YYYY) | Estimated Project Completion Date (MM/DD/YYYY) |
|---|---|
| | |

Estimated Area to be Disturbed (to the nearest quarter acre):

Type of Construction Site (check all that apply):

☐ Single-Family Residential ☐ Multi-Family Residential ☐ Commercial

☐ Industrial ☐ Institutional ☐ Highway or Road

☐ Utility ☐ Other (Specify):

Was the pre-development land use used for agriculture (see Appendix A for definition of "agricultural land")? ☐ Yes ☐ No

Have earth-disturbing activities commenced on your project/site? ☐ Yes ☒ No

If yes, is your project an "emergency-related project" (see Appendix A)? ☒ Yes ☐ No

**Project Information**

| | | |
|---|---|---|
| Have stormwater discharges from your project/site been covered previously under an NPDES permit? | ☐ Yes | ☐ No |
| If yes, provide the NPDES ID (if you had coverage under EPA's 2017 CGP) or the NPDES permit number (if you had coverage under an EPA individual permit): _____ | | |
| Are there other operators that are covered under this permit for the same project site? | ☐ Yes | ☐ No |
| If yes, provide the NPDES ID number for all other operators at the site who have coverage under this permit: _____ | | |
| Will there be demolition of any structure built or renovated before January 1, 1980? | ☐ Yes | ☐ No |
| If yes, do any of the structures being demolished have at least 10,000 square feet of floor space? | ☐ Yes | ☐ No |
| Will you be discharging dewatering water from your site? | ☐ Yes | ☐ No |
| If yes, will you be discharging dewatering water from a current or former Federal or State remediation site? | ☐ Yes | ☐ No |

## SECTION V. DISCHARGE INFORMATION

**Project Information**

| | | |
|---|---|---|
| By indicating "Yes," I confirm that I understand that the CGP only authorizes the allowable stormwater discharges in Part 1.2.1 and the allowable non-stormwater discharges listed in Part 1.2.2. Any discharges not expressly authorized in this permit cannot become authorized or shielded from liability under CWA section 402(k) by disclosure to EPA, State, or local authorities after issuance of this permit via any means, including the Notice of Intent (NOI) to be covered by the permit, the Stormwater Pollution Prevention Plan (SWPPP), during an inspection, etc. If any discharges requiring NPDES permit coverage other than the allowable stormwater and non-stormwater discharges listed in Parts 1.2.1 and 1.2.2 will be discharged, they must be covered under another NPDES permit. | ☐ Yes | |
| Does your project/site discharge stormwater into a Municipal Separate Storm Sewer System (MS4)? | ☐ Yes | ☐ No |
| Are there any waters of the U.S. within 50 feet of your project's earth disturbances? | ☐ Yes | ☐ No |

**Receiving Waters Information**

**For each point of discharge, provide the following receiving water information. (Attach a separate list if necessary)**

| Point of Discharge ID | Provide the name of the first water of the U.S. that receives stormwater directly from the point of discharge and/or from the MS4 that the point of discharge discharges to: | If the receiving water is impaired (on the CWA 303(d) list), list the pollutants that are causing the impairment: | If a TMDL been completed for this receiving waterbody, providing the following information: |
|---|---|---|---|
| | | | **TMDL Name and ID:** |
| | | | **Pollutant(s) for which there is a TMDL:** |
| | | | **TMDL Name and ID:** |
| | | | **Pollutant(s) for which there is a TMDL:** |

**Receiving Waters Information**

| For each point of discharge, provide the following receiving water information. (Attach a separate list if necessary) | | | |
|---|---|---|---|
| **Point of Discharge ID** | **Provide the name of the first water of the U.S. that receives stormwater directly from the point of discharge and/or from the MS4 that the point of discharge discharges to:** | **If the receiving water is impaired (on the CWA 303(d) list), list the pollutants that are causing the impairment:** | **If a TMDL been completed for this receiving waterbody, providing the following information:** |
| | | | **TMDL Name and ID:**<br>**Pollutant(s) for which there is a TMDL:** |
| | | | **TMDL Name and ID:**<br>**Pollutant(s) for which there is a TMDL:** |
| | | | **TMDL Name and ID:**<br>**Pollutant(s) for which there is a TMDL:** |
| | | | **TMDL Name and ID:**<br>**Pollutant(s) for which there is a TMDL:** |
| | | | **TMDL Name and ID:**<br>**Pollutant(s) for which there is a TMDL:** |

Are any of the waters of the U.S. to which you discharge designated by the State or Tribal authority under its antidegradation policy as a Tier 2 (or Tier 2.5) water (water quality exceeds levels necessary to support propagation of fish, shellfish, and wildlife and recreation in and on the water) or as a Tier 3 water (Outstanding National Resource Water)? (See Appendix F). ☐ Yes ☐ No

If yes, name(s) of receiving water(s) and its designation (Tier 2, Tier 2.5 or Tier 3):

## SECTION VI. CHEMICAL TREATMENT INFORMATION

**Chemical Treatment**

Will you use polymers, flocculants, or other treatment chemicals at your construction site? ☐ Yes ☐ No

If yes, will you use cationic treatment chemicals at your construction site*? ☐ Yes ☐ No

If yes, have you been authorized to use cationic treatment chemicals by your applicable EPA Regional Office in advance of filing your NOI*? ☐ Yes ☐ No

If you have been authorized to use cationic treatment chemicals by your applicable EPA Regional Office, attach a copy of your authorization letter and include documentation of the appropriate controls and implementation procedures designed to ensure that your use of cationic treatment chemicals will not lead to a violation of water quality standards.

Please indicate the treatment chemicals that you will use:

* Note: You are ineligible for coverage under this permit unless you notify your applicable EPA Regional Office in advance and the EPA office authorizes coverage under this permit after you have included appropriate controls and implementation procedures designed to ensure that your use of cationic treatment chemicals will not lead to a violation of water quality standards.

## SECTION VII. STORMWATER POLLUTION PREVENTION PLAN (SWPPP) AND PERSONNEL TRAINING INFORMATION

**SWPPP**

Has the SWPPP been prepared in advance of filing this NOI, as required? ☐ Yes ☐ No

By indicating "Yes," I confirm that all required personnel, including those conducting inspections at your site, will meet the training requirements in Part 6 of this permit. ☐ Yes

**SWPPP Contact Information**

| First Name | Middle Initial | Last Name |
|---|---|---|
| | | |

Professional Title

| Phone number | Email address |
|---|---|
| | |

## SECTION VIII. ENDANGERED SPECIES PROTECTION

**Endangered Species Protection**

In accordance with Part 1.1.5, if the EPA Regional Office grants you a waiver from electronic reporting, you must complete the worksheet in Appendix D to select your eligibility criteria with respect to the protection of Federally listed threatened or endangered species and Federally designated "critical habitat" under the Endangered Species Act (ESA) [hereinafter "ESA-listed species and designated critical habitat(s)"] from discharges and discharge-related activities authorized under this permit.

**You must submit the ESA worksheet and all required supporting documentation with this NOI. If you do not submit the worksheet and the required supporting documentation with your NOI, your NOI will be considered incomplete.** After you submit your NOI and before your NOI is authorized, EPA may notify you if any additional controls are necessary to ensure your discharges are not likely to result in any short- or long-term adverse effects on ESA-listed species and critical habitat.

By indicating "Yes," I confirm that you have included the completed ESA worksheet from Appendix D and all required supporting information for your criterion selection with the submission of this NOI. ☐ Yes

## SECTION IX. HISTORIC PRESERVATION

**Historic Preservation**

Are you installing any stormwater controls as described in Appendix E that require subsurface earth disturbance? (Appendix E, Step 1) ☐ Yes ☐ No

If yes, have prior surveys or evaluations conducted on the site have already determined historic properties do not exist, or that prior disturbances have precluded the existence of historic properties? (Appendix E, Step 2) ☐ Yes ☐ No

If no, have you determined that your installation of subsurface earth-disturbing stormwater controls will have no effect on historic properties? (Appendix E, Step 3) ☐ Yes ☐ No

If no, did the SHPO, THPO, or other Tribal representative (whichever applies) respond to you within the 15 calendar days to indicate whether the subsurface earth disturbances caused by the installation of stormwater controls affect historic properties? (Appendix E, Step 4) ☐ Yes ☐ No

If yes, describe the nature of their response:

- ☐ Written indication that no historic properties will be affected by the installation of stormwater controls.
- ☐ Written indication that adverse effects to historic properties from the installation of stormwater controls can be mitigated by agreed upon actions.
- ☐ No agreement has been reached regarding measures to mitigate effects to historic properties from the installation of stormwater controls.
- ☐ Other (Specify):

## SECTION X. CERTIFICATION INFORMATION

**Certification Information**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

| First Name | Middle Initial | Last Name |
|---|---|---|
| | | |

| Title |
|---|
| |

| Signature | Date (MM/DD/YYYY) |
|---|---|
| | |

| Email Address |
|---|
| |

## General Instructions

### Who Must File an NOI Form?

Under the provisions of the Clean Water Act, as amended (33 U.S.C. 1251 et. seq.; the Act), Federal law prohibits stormwater discharges from certain construction activities to waters of the U.S. unless that discharge is covered under a National Pollutant Discharge Elimination System (NPDES) permit. Operators of construction sites where one or more acres are disturbed, smaller sites that are part of a larger common plan of development or sale where there is a cumulative disturbance of at least one acre, or any other site specifically designated by the Director, must obtain coverage under an NPDES general permit. For coverage under the 2022 CGP, each person, firm, public organization, or any other entity that meets either of the following criteria must file a Notice of Intent form: (1) they have operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; or (2) they have day-to-day operational control of those activities at the project necessary to ensure compliance with the permit conditions. If you have questions about whether you need a NPDES stormwater permit, or if you need information to determine whether EPA or your State agency is the permitting authority, contact your EPA Regional Office.

### Completing the Form

Obtain and read a copy of the 2022 CGP, viewable at https://www.epa.gov/npdes/stormwater-discharges-construction-activities#cgp. To complete this form, type or print uppercase letters, in the appropriate areas only. Please place each character between the marks (abbreviate if necessary to stay within the number of characters allowed for each item). Use one space for breaks between words, but not for punctuation marks unless they are needed to clarify your response. If you have any questions on this form, telephone EPA's NOI Processing Center at (866) 352-7755. **Please submit the original document with signature in ink - do not send a photocopied signature.**

### Section I. Approval to Use Paper NOI Form

You must indicate whether you have been granted a waiver from electronic reporting from the EPA Regional Office. Note that you are not authorized to use this paper NOI form unless the EPA Regional Office has approved its use. Where you have obtained approval to use this form, indicate the waiver that you have been granted, the name of the EPA staff person who granted the waiver, and the date that approval was provided.

See https://www.epa.gov/npdes/contact-us-stormwater#regional for a list of EPA Regional Office contacts.

### Section II. Permit Information

Provide the master permit number of the permit under which you are applying for coverage (see Appendix B of the general permit for the list of eligible master permit numbers)

### Section III. Operator Information

Provide the legal name of the person, firm, public organization, or any other entity that operates the project described in this NOI. Refer to Appendix A of the permit for the definition of "operator".

Indicate whether you are seeking coverage under this permit as a "Federal Operator" or "Federal Facility" as defined in Appendix A.

Also provide a point of contact, the operator's mailing address, county, telephone number, and e-mail address (to be notified via e-mail of NOI approval when available). Correspondence for the NOI will be sent to this address.

If the NOI was prepared by someone other than the certifier (for example, if the NOI was prepared by the facility SWPPP contact or a consultant for the certifier's signature), include the full name, organization, phone number, and email address of the NOI preparer.

### Section IV. Project/Site Information

Enter the official or legal name and complete street address, including city, State, ZIP code, and county or similar government subdivision of the project or site. If the project or site lacks a street address, indicate the general location of the site (e.g., Intersection of State Highways 61 and 34). Complete site information must be provided for permit coverage to be granted.

Provide the latitude and longitude of your facility in decimal degrees format. The latitude and longitude of your facility can be determined in several different ways, including through the use of global positioning system (GPS) receivers, U.S. Geological Survey (U.S.G.S.) topographic or quadrangle maps, and web-based siting tools, among others. For consistency, EPA requests that measurements be taken from the approximate center of the construction site. For linear construction sites, the measurement should be taken midpoint of the site. If known, enter the horizontal reference datum for your latitude and longitude. The horizontal reference datum is shown on the bottom left corner of USGS topographic maps; it is also available for GPS receivers.

Indicate whether the project is in Indian country lands or located on a property of religious or cultural significance to an Indian Tribe, and if so, provide the name of the Indian Tribe associated with the area of Indian country (including name of Indian reservation, if applicable), or if not in Indian country, provide the name of the Indian Tribe associated with the property.

Enter the estimated construction start and completion dates using four digits for the year (i.e., 10/06/2012). Indicate to the nearest quarter acre the estimated area to be disturbed. Indicate the type of construction site.

Indicate whether the pre-development land use of the site was used for agriculture Appendix A defines "agricultural land" as cropland, grassland, rangeland, pasture, and other agricultural land, on which agricultural and forest-related products or livestock are produced and resource concerns may be addressed. Agricultural lands include cropped woodland, marshes, incidental areas included in the agricultural operation, and other types of agricultural land used for the production of livestock.

Indicate whether earth-disturbing activities have already commenced on your project/site. If earth-disturbing activities have commenced on your site because stormwater discharges from the site have been previously covered under a NPDES permit, you must provide the 2017 CGP NPDES ID or

the NPDES permit number if coverage was under an individual permit.

Indicate if demolition is occurring, and if so, if the structure has at least 10,000 square feet of floor space.

Indicate if there are other operators covered under this permit for the same project site. If there are multiple operators, provide the NPDES ID number for the other operators at the site who have coverage under this permit.

Indicate whether you will be discharging dewatering water, as defined in Appendix A, during the course of the project. If you will be discharging dewatering water, indicate whether the site from which you will be dewatering is located on a current or former Federal or State remediation site. Federal remediation sites include cleanups covered by Superfund (both National Priorities List (NPL) sites and non-NPL sites), Resource Conservation and Recovery Act (RCRA) corrective actions sites, cleanups at Federal Facilities, and Federal, State, or Tribal brownfields sites. State remediation sites could include, for instance, brownfield site cleanups funded by the State, State superfund sites, and petroleum tank release sites. Operators may use online mapping resources, such as EPA's Cleanups in My Community Map, to help determine if they are located on a remediation site. The Cleanups in My Community Map is viewable at:

https://ordspub.epa.gov/ords/cimc/f?p=cimc:map::::71

**Section V. Discharge Information**

You must confirm that you understand that the CGP only authorizes the allowable stormwater discharges listed in Part 1.2.1 and the allowable non-stormwater discharges listed in Part 1.2.2. Any discharges not expressly authorized under the CGP are not covered by the CGP or the permit shield provision of the CWA Section 402(k) and they cannot become authorized or shielded by disclosure to EPA, State, or local authorities via the NOI to be covered by the permit or by any other means (e.g., in the SWPPP or during an inspection). If any discharges requiring NPDES permit coverage other than the allowable stormwater and non-stormwater discharges listed in Parts 1.2.1 and 1.2.2 will be discharged, they must either be eliminated or covered under another NPDES permit.

Indicate whether discharges from the site will enter into a municipal separate storm sewer system (MS4), as defined in Appendix A.

Also, indicate whether any waters of the U.S. exist within 50 feet from your site. Note that if "yes", you are required to comply with the requirement in Part 2.2.1 of the permit to provide natural buffers or equivalent erosion and sediment controls.

For each unique point of discharge you list, you must specify the name of the first water of the U.S. that receives stormwater directly from the point of discharge and/or from the MS4 that the point of discharge discharges to. You must specify whether any waters of the U.S. that you discharge to are listed as "impaired" as defined in Appendix A, and the pollutants for which the water is impaired. You must identify any Total Maximum Daily Loads (TMDL) that have been completed for any of the waters of the U.S. that you discharge to. Operators may find it useful to use EPA's Discharge Mapping Tool to determine whether the water of the U.S. is impaired, the pollutant causing the impairment, and whether a TMDL exists for the water body. The Discharge Mapping Tool is viewable at https://www.epa.gov/npdes/epas-stormwater-discharge-mapping-tools.

Indicate whether discharges from the site will enter into a water of the U.S. that is designated as a Tier 2, Tier 2.5, or Tier 3 water. A list of Tier 2, 2.5, and 3 waters is provided at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates. If the answer is "yes", name all waters designated as Tier 2, Tier 2.5, or Tier 3 to which the site will discharge.

**Section VI. Chemical Treatment Information**

Indicate whether the site will use polymers, flocculants, or other treatment chemicals. Indicate whether the site will employ cationic treatment chemicals. If the answer is "yes" to either question, indicate which chemical(s) you will use. Note that you are not eligible for coverage under this permit to use cationic treatment chemicals unless you notify your applicable EPA Regional Office in advance and the EPA office authorizes coverage under this permit after you have included appropriate controls and implementation procedures designed to ensure that your use of cationic treatment chemicals will not lead to a violation of water quality standards. If you have been authorized to use cationic treatment chemicals by your applicable EPA Regional Office, attach a copy of your authorization letter and include documentation of the appropriate controls and implementation procedures designed to ensure that your use of cationic treatment chemicals will not lead to a violation of water quality standards. Examples of cationic treatment chemicals include, but are not limited to, cationic polyacrylamide (C-PAM), PolyDADMAC (POLY DIALLYL DIMETHYL AMMONIUM CHLORIDE), and chitosan.

**Section VII. Stormwater Pollution Prevention Plan (SWPPP) and Personnel Training Information**

All sites eligible for coverage under this permit are required to prepare a SWPPP in advance of filing the NOI, in accordance with Part 7. Indicate whether the SWPPP has been prepared in advance of filing the NOI.

Confirm that all required personnel, including those conducting inspections at your site, will meet the training requirements in Part 6 of this permit.

Indicate the street, city, State, and ZIP code where the SWPPP can be found. Indicate the contact information (name, organization, phone, and email) for the person who developed the SWPPP for this project.

**Section VIII. Endangered Species Information**

Confirm that you have included the completed ESA worksheet from Appendix D and all required supporting information for your criterion selection with the submission of this NOI.

**Section IX. Historic Preservation**

Use the instructions in Appendix E to complete the questions on the NOI form regarding historic preservation.

**Section X. Certification Information**

The NOI must be signed as follows:

*For a corporation:* By a responsible corporate officer. For the purpose of this Section, a responsible corporate officer means:

(i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making

major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

*For a partnership or sole proprietorship:* By a general partner or the proprietor, respectively; or

*For a municipality, State, Federal, or other public agency:* By either a principal executive officer or ranking elected official. For purposes of this Part, a principal executive officer of a Federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of EPA). Include the name and title of the person signing the form and the date of signing. An unsigned or undated NOI form will not be considered eligible for permit coverage.

**Modifying Your NOI**

If you have been granted a waiver from your Regional Office from electronic reporting, and if after submitting your NOI you need to correct or update any fields on this NOI form, you may do so by indicating changes on this same form.

**Paperwork Reduction Act Notice**

This collection of information is approved by OMB under the Paperwork Reduction Act, 44 U.S.C. 3501 et seq. (OMB Control No. 2040-0305). Responses to this collection of information are mandatory (40 CFR 122.26). An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. The public reporting and recordkeeping burden for this collection of information is estimated to be 3.3 hours per response. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates and any suggested methods for minimizing respondent burden to the Regulatory Support Division Director, U.S. Environmental Protection Agency (2821T), 1200 Pennsylvania Ave., NW, Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed form to this address.

**Submitting Your Form**

Submit your NOI form by mail to one of the following addresses:

**For Regular U.S. Mail Delivery:**
Stormwater Notice Processing Center
Mail Code 4203M, ATTN: 2022 CGP
U.S. EPA
1200 Pennsylvania Avenue, NW
Washington, DC 20460

**For Overnight/Express Mail Delivery:**
Stormwater Notice Processing Center
William Jefferson Clinton East Building - Room 7420
ATTN: 2022 CGP
U.S. EPA
1201 Constitution Avenue, NW
Washington, DC 20004

Visit this website for instructions on how to submit electronically:

https://www.epa.gov/npdes/stormwater-discharges-construction-activities#ereporting

## Appendix I - Notice of Termination (NOT) Form and Instructions

Part 8.3 requires you to use the NPDES eReporting Tool, or "NeT" system, to prepare and submit your NOT electronically. However, if the EPA Regional Office grants you a waiver to use a paper NOT form, and you elect to use it, you must complete and submit the following form.

| NPDES Form 3510-13 | EPA | U.S. Environmental Protection Agency<br>Washington, DC 20460<br>Notice of Termination for the 2022 NPDES Construction General Permit | OMB No. 2040-0305<br>Exp. Date 01/31/2025 |
|---|---|---|---|

Submission of this Notice of Termination constitutes notice that the operator identified in Section III of this form is no longer authorized discharge pursuant to the NPDES Construction General Permit (CGP) from the site identified in Section IV of this form. All necessary information must be included on this form. Refer to the instructions at the end of this form.

## SECTION I. APPROVAL TO USE PAPER NOI FORM

**Paper NOI Form**

Have you been granted a waiver from electronic reporting from the Regional Office*? ☐ Yes ☐ No

If yes, check which waiver you have been granted, the name of the EPA Regional Office staff person who granted the waiver, and the date of approval:

Waiver granted:

☐ The owner/operator's headquarters is physically located in a geographic area (i.e., ZIP code or census tract) that is identified as under-served for broadband Internet access in the most recent report from the Federal Communications Commission.

☐ The owner/operator has issues regarding available computer access or computer capability.

| Name of EPA staff person that granted the waiver | Date approval obtained (MM/DD/YYYY) |
|---|---|
| | |

*** Note: You are required to obtain approval from the applicable Regional Office prior to using this paper NOI form. If you have not obtained a waiver, you must file this form electronically using the NPDES eReporting Tool (NeT).**

## SECTION II. PERMIT INFORMATION

**Permit**

NPDES ID

Reason for Termination (Check only one):

☒ You have completed all construction activities at your site, and you have met all other requirements in Part 8.2.1.

Check this box to confirm that you have attached photographs as required by Part 8.2.1.a that document your compliance with the permit's final stabilization requirements.

Include the date each photograph was taken, and a brief description of the area of the site captured by the photograph (e.g., photo shows application of seed and erosion control mats to remaining exposed surfaces on northeast corner of site).

☐ If any portion of your site is covered by one of the Part 2.2.14c.iii exceptions to the final stabilization criteria, indicate which exception applies and include a supplementary explanation with your photographs that provides the necessary context for why this portion of the site is in compliance even though it appears to be unstabilized.

☒ Another operator has assumed control over all areas of the site and that operator has submitted an NOI and obtained coverage under the CGP.

☒ You have obtained coverage under an individual permit or another general NPDES permit addressing stormwater discharges from the construction site.

## SECTION III. OPERATOR INFORMATION

**Operator Information**

Operator Name

Mailing Address

Street

| City | State | ZIP Code |
|---|---|---|
| | | |

County or Similar Government Division

| Phone Number | Email Address |
|---|---|
| | |

## SECTION IV. PROJECT/SITE INFORMATION

**Project/Site Address**

| | | |
|---|---|---|
| Project/Site Name | | |
| Street/Location | | |
| City | State | ZIP Code |
| County or Similar Government Division: | | |

## SECTION V. CERTIFICATION INFORMATION

**Certification Information**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

| | | |
|---|---|---|
| First Name | Middle Initial | Last Name |
| Title | | |
| Signature | | Date (MM/DD/YYYY) |
| Email Address | | |

## General Instructions

### Who May File an NOT Form?

Permittees who are presently covered under the EPA-issued 2022 Construction General Permit (CGP) for Stormwater Discharges Associated with Construction Activity may submit an NOT form when: (1) earth-disturbing activities at the site are completed and the conditions in Parts 8.2.1.a through 8.2.1.b are met; or (2) the permittee has transferred all areas under its control to another operator, and that operator has submitted and obtained coverage under this permit; or (3) the permittee has obtained coverage under a different NPDES permit for the same discharges.

### Completing the Form

Type or print, using uppercase letters, in the appropriate areas only. Please place each character between the marks. Abbreviate if necessary to stay within the number of characters allowed for each item. Use only one space for breaks between words, but not for punctuation marks unless they are needed to clarify your response. If you have any questions about this form, refer to https://www.epa.gov/npdes/stormwater-discharges-construction-activities#cgp or telephone EPA's NOI Processing Center at (866) 352-7755. **Please submit original document with signature in ink - do not send a photocopied signature.**

### Section I. Approval to Use Paper NOI Form

You must indicate whether you have been granted a waiver from electronic reporting from the EPA Regional Office. Note that you are not authorized to use this paper NOT form unless the EPA Regional Office has approved its use. Where you have obtained approval to use this form, indicate the waiver that you have been granted, the name of the EPA staff person who granted the waiver, and the date that approval was provided.

See https://www.epa.gov/npdes/contact-us-stormwater#regional for a list of EPA Regional Office contacts.

### Section II. Permit Information

Enter the existing NPDES ID assigned to the project . If you do not know the NPDES ID number, or contact EPA's NOI Processing Center at (866) 352-7755.

Indicate your reason for submitting this Notice of Termination by checking the appropriate box. Check only one. If you selected the first box, confirm that you have attached photographs as required by Part 8.2.1.a. All submitted photographs must: (1) be taken both before and after the site has met the final stabilization criteria in Part 2.2.14.c; (2) be clear and in focus, and in the original format and resolution; and (3) include the date each photograph was taken, and a brief description of the area of the site captured by the photograph (e.g., photo shows application of seed and erosion control mats to remaining exposed surfaces on northeast corner of site).

If any portion of your site is covered by one of the Part 2.2.14c.iii final stabilization exceptions, indicate which exception applies and provide an explanation with your photographs that describes why this portion of the site is in compliance even though it may appear to be unstabilized.

### Section III. Operator Information

Provide the legal name of the person, firm, public organization, or any other entity that operates the project described in this NOT and is covered by the NPDES ID identified in Section II. Enter the complete mailing address, telephone number, and email address of the operator.

### Section IV. Project/Site Information

Enter the official or legal name and complete street address, including city, State, ZIP code, and county or similar government subdivision of the project or site. If the project or site lacks a street address, indicate the general location of the site (e.g., Intersection of State Highways 61 and 34). Complete site information must be provided for termination of permit coverage to be valid.

### Section V. Certification Information

The NOT, must be signed as follows:

*For a corporation:* By a responsible corporate officer. For the purpose of this Part, a responsible corporate officer means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy-or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

*For a partnership or sole proprietorship:* By a general partner or the proprietor, respectively; or

*For a municipality, State, Federal, or other public agency:* By either a principal executive officer or ranking elected official. For purposes of this Part, a principal executive officer of a Federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of EPA).

Include the name, title, and email address of the person signing the form and the date of signing. An unsigned or undated NOT form will not be considered valid termination of permit coverage.

### Paperwork Reduction Act Notice

This collection of information is approved by OMB under the Paperwork Reduction Act, 44 U.S.C. 3501 et seq. (OMB Control No. 2040-0305). Responses to this collection of information are mandatory (40 CFR 122.26). An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a

currently valid OMB control number. The public reporting and recordkeeping burden for this collection of information is estimated to be 1.2 hours per response. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates and any suggested methods for minimizing respondent burden to the Regulatory Support Division Director, U.S. Environmental Protection Agency (2821T), 1200 Pennsylvania Ave., NW, Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed form to this address.

**Submitting Your Form**

Submit your NOT form by mail to one of the following addresses:

For Regular U.S. Mail Delivery:
Stormwater Notice Processing Center
Mail Code 4203M, ATTN: 2022 CGP
U.S. EPA
1200 Pennsylvania Avenue, NW
Washington, DC 20460

For Overnight/Express Mail Delivery:
Stormwater Notice Processing Center
William Jefferson Clinton East Building - Room 7420
ATTN: 2022 CGP
U.S. EPA
1201 Constitution Avenue, NW
Washington, DC 20004

Visit this website for instructions on how to submit electronically:

https://www.epa.gov/npdes/stormwater-discharges-construction-activities#ereporting

## Appendix J - Suggested Format for Request for Chemical Treatment

If you plan to add "cationic treatment chemicals" (as defined in Appendix A) to stormwater and/or authorized non-stormwater prior to discharge, Part 1.1.9 requires you to notify your applicable EPA Regional Office in advance of submitting your NOI. The EPA Regional Office will authorize coverage under this permit after you have included appropriate controls and implementation procedures designed to ensure that your use of cationic treatment chemicals will result in discharges that meet applicable water quality standards. To notify your EPA Regional Office, you may use following form.

| NPDES Form 6100-066 | EPA | U.S. Environmental Protection Agency<br>Washington, DC 20460<br><br>Suggested Form for Notifying EPA about Proposed Use of Cationic Treatment Chemicals under the 2022 NPDES Construction General Permit | OMB No. 2040-0305<br>Exp. Date 01/31/2025 |
|---|---|---|---|

Under Part 1.1.9 of the 2022 CGP, if you plan to add "cationic treatment chemicals" (as defined in Appendix A) to stormwater and/or authorized non-stormwater prior to discharge, you may not submit your Notice of Intent (NOI) until you notify your applicable EPA Regional Office in advance and the EPA Regional Office authorizes coverage under this permit after you have included appropriate controls and implementation procedures designed to ensure that your use of cationic treatment chemicals will result in discharges that meet applicable water quality standards. You may use this suggested form to notify your EPA Regional Office about your proposed use of cationic treatment chemicals.

## SECTION I. OPERATOR INFORMATION

**Operator Information**

| | | |
|---|---|---|
| Operator Name | | |
| Mailing Address | | |
| Street | | |
| City | State | ZIP Code |
| County or Similar Government Division | | |
| Phone Number | Email Address | |

## SECTION II. PROJECT/SITE INFORMATION

**Project/Site Information**

| | | |
|---|---|---|
| Project/Site Name | | |
| Project/Site Address | | |
| Street/Location | | |
| City | State | ZIP Code |
| County or Similar Government Division | | |
| Site Contact Information (if different from operator) | | |
| First Name | Middle Initial | Last Name |
| Phone Number | | |
| Receiving Waterbodies | | |
| Name(s) of Receiving Waterbodies: | | |

## SECTION III. MAP

**Map**

Attach a map that illustrates the entire site including all of the below items. Include this map in your Stormwater Pollution Prevention Plan (SWPPP).
- All receiving waterbodies
- All proposed location(s) of chemical treatment system(s)
- All proposed point(s) of discharge to receiving waterbodies
- All soil types within areas to be disturbed
- All areas of earth disturbance
- Sufficient indication of topography to indicate where stormwater flows

Attach a schematic drawing of the proposed treatment system(s). Include all components of the treatment train, sample points, and pipe configurations. In addition to sufficient holding capacity upstream of treatment, the system must have the capacity to hold water for testing and to re-treat water that does not meet water quality standards.

## SECTION IV. RESPONSIBLE PERSONNEL

**Responsible Personnel**

| Treatment System Operator or Company Name (if subcontracted out): | | |
|---|---|---|
| Street/Location | | |
| City | State | ZIP Code |

| Responsible Personnel | |
|---|---|
| List personnel who will be responsible for operating the chemical treatment systems and application of the chemicals. | Cite the training that the personnel have received in operation and maintenance of the treatment system(s) and use of the specific chemical(s) proposed. |
| | |
| | |
| | |
| | |
| | |

## SECTION V. PROPOSED TREATMENT

**Proposed Treatment**

| | |
|---|---|
| Check proposed treatment system to be used: | ☐ Chitosan enhanced sand filtration with discharge to infiltration (ground water). |
| | ☐ Chitosan enhanced sand filtration with discharge to temporary holding ponds (batch). |
| | ☐ Chitosan enhanced sand filtration with discharge to surface waters (flow-through). |
| | ☐ Other (describe below and submit documentation that the proposed system and chemical(s) demonstrate the ability to remove turbidity and produce non-toxic effluent/discharge): |
| Check proposed cationic chemical(s) to be used: | ☐ FlocClear™ (2% chitosan acetate solution). |
| | ☐ StormKlear™ LiquiFloc™ (1% chitosan acetate solution). |
| | ☐ ChitoVan™ (1% chitosan acetate solution). |
| | ☐ StormKlear™ LiquiFloc™ (3% chitosan acetate solution). |
| | ☐ Other (Specify): |

| Estimated Treatment Period Start Date (MM/DD/YYYY) | Estimated Treatment Period End Date (MM/DD/YYYY) |
|---|---|

Describe sampling and recordkeeping schedule. Attach additional sheets as needed:

**Proposed Treatment**

Explain why you have selected this proposed treatment system and chemicals. Include an explanation of why the use of cationic treatment chemicals is necessary at the site. Reference how the soil types on your site influenced your choices. Describe or provide an illustration of how the site of the discharge will be stabilized and why the discharge location will not cause erosion of the discharge water's bank or bed (please note that a permit from the Corps and State agencies may be necessary to place rock in the water body for this stabilization). Attach as many additional sheets as needed for a full explanation. If you have a report from a chemical treatment contractor describing their recommended approach you may attach that.

## SECTION VI. CERTIFICATION INFORMATION

**Certification Information**

I have documented and hereby certify that the following information is correct and has been documented in the SWPPP for this project:

- The SWPPP includes a complete site-specific description of the chemical treatment system herein proposed for use, including specifications, design, and Material Safety Data Sheets for all chemicals to be used.
- The controls to be used on the site are compatible with the safe and effective use of cationic chemical treatment.
- I verified through jar tests that the site soil is conducive to chemical treatment.
- I verified that the chemical treatment system operators for this project received training.
- I read, understand, and will follow all conditions and design criteria in the applicable use designation(s).
- If the discharge is to Tribal waters, I notified the appropriate Tribal government of the intent to use chemical treatment on a site located within that jurisdiction.
- I will keep the use level designation, operation and maintenance manual, and training certificate on site prior to and during use of chemical treatment.
- A licensed engineer designed the system for this project including system sizing, pond sizing, and flow requirements.
- I verify that the discharge will not adversely affect downstream conveyance systems or stream channels (e.g., cause erosion).

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Authorized Official

| First Name | Middle Initial | Last Name |
|---|---|---|
| | | |

Title

| Signature | Date (MM/DD/YYYY) |
|---|---|
| | |

Email Address

**Section I. Operator Information**

Provide the legal name of the person, firm, public organization, or any other entity that operates the project. Refer to Appendix A of the permit for the definition of "operator." Provide the operator's mailing address, county, telephone number, and e-mail address.

**Section II. Project/Site Information**

Enter the official or legal name and complete street address, including city, State, ZIP code, and county or similar government subdivision of the project or site. If the project or site lacks a street address, indicate the general location of the site (e.g., Intersection of State Highways 61 and 34).

Provide site contact information, if different from the operator.

Provide the name of the receiving waterbodies to which your site/project will discharge.

**Section III. Map**

Attach a map of the entire site that includes the identified items. Attach a schematic of the proposed treatment system(s) that includes the identified items.

**Section IV. Responsible Personnel**

Provide the legal name of the treatment system operator or company and complete street address, including city, State, including city, State, and ZIP code.

List personnel who will be responsible for operating the chemical treatment systems and application of the chemicals. For each personnel listed, cite the training that the personnel have received in operation and maintenance of the treatment system(s) and use of the specific chemical(s) proposed.

**Section V. Proposed Treatment**

Indicate the proposed treatment system and proposed cationic chemicals to be used. Indicate the estimated treatment start and end dates. Describe the sampling and recordkeeping schedule. Explain why you have selected the proposed treatment system and chemicals.

**Section VI. Certification Information**

The form must be signed as follows:

For a corporation: By a responsible corporate officer. For the purpose of this Section, a responsible corporate officer means:

(i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

For a partnership or sole proprietorship: By a general partner or the proprietor, respectively; or

For a municipality, State, Federal, or other public agency: By either a principal executive officer or ranking elected official. For purposes of this Part, a principal executive officer of a Federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of EPA). Include the name and title of the person signing the form and the date of signing.

**Submitting Your Form**

Submit this form to your applicable EPA Regional Office. Contact information can be found at: https://www.epa.gov/npdes/contact-us-stormwater#regional

## Appendix K – Turbidity Monitoring Report Form and Instructions

Part 3.3 requires you to use the EPA NPDES eReporting Tool, or "NeT" system, to prepare and submit your report electronically. However, if the EPA Regional Office grants you a waiver to use a paper form, and you elect to use it, you must complete and submit the following form.

| NPDES Form 6100-065 | EPA | U.S. Environmental Protection Agency<br>Washington, DC 20460<br>Turbidity Monitoring Report Form for Dewatering Discharges to Sensitive Waters Under the 2022 NPDES Construction General Permit | OMB No. 2040-0305<br>Exp. Date 01/31/2025 |
|---|---|---|---|

## SECTION I. APPROVAL TO USE PAPER FORM

**Paper Form**

Have you been granted a waiver from electronic reporting from the Regional Office*? ☐ Yes ☐ No

If yes, check which waiver you have been granted, and provide the name of the EPA Regional Office staff person who granted the waiver, and the date of approval:

Waiver granted:

☐ The owner/operator's headquarters is physically located in a geographic area (i.e., ZIP code or census tract) that is identified as under-served for broadband Internet access in the most recent report from the Federal Communications Commission.

☐ The owner/operator has issues regarding available computer access or computer capability.

| Name of EPA staff person that granted the waiver | Date approval obtained (MM/DD/YYYY) |
|---|---|
| | |

*** Note: You are required to obtain approval from the applicable Regional Office prior to using this paper form. If you have not obtained a waiver, you must file this form electronically using the NPDES eReporting Tool (NeT).**

## SECTION II. PERMIT INFORMATION

**Permit**

**NPDES ID**

Does this report fulfill turbidity monitoring report obligations of other operators that are covered under this permit for the same project site? ☐ Yes ☐ No

If yes, provide the NPDES ID number(s) for all other such operators at the same project site: _____

## SECTION III. OPERATOR INFORMATION

**Operator Information**

Operator Name

Mailing Address

Street

| City | State | ZIP Code |
|---|---|---|
| | | |

County or Similar Government Division:

| Phone Number | Email Address |
|---|---|
| | |

**Preparer**

Complete if form was prepared by someone other than the certifier:

| First Name | Middle Initial | Last Name |
|---|---|---|
| | | |

Organization

| Phone Number | Email Address |
|---|---|
| | |

## SECTION IV. SITE INFORMATION

**Site Address**

Site Name

**Site Address**

Street/Location

| City | State | ZIP Code |
|---|---|---|
| | | |

County or Similar Government Division:

## SECTION IV. MONITORING QUARTER

**Monitoring Quarter**

Identify monitoring quarter (select only one):

- ☐ Quarter 1 (January 1 – March 31)
- ☐ Quarter 2 (April 1 – June 30)
- ☐ Quarter 3 (July 1 – September 30)
- ☐ Quarter 4 (October 1 – December 31)

## SECTION IVI. TURBIDITY MONITORING DATA

**Turbidity Monitoring Data**

Discharge Point Description/ Name:

Was dewatering water discharged during the monitoring quarter? ☐ Yes (Enter the data below) ☐ No (Skip to Section VII)

| Specific Week within Monitoring Quarter[1] | Weekly Average (NTU)[2] | Benchmark Threshold (NTU) | Alternate Benchmark Threshold (NTU)[3] | Average exceeds Benchmark?[4] |
|---|---|---|---|---|
| Week 1 | | 50 | | ☐ Yes ☐ No |
| Week 2 | | 50 | | ☐ Yes ☐ No |
| Week 3 | | 50 | | ☐ Yes ☐ No |
| Week 4 | | 50 | | ☐ Yes ☐ No |
| Week 5 | | 50 | | ☐ Yes ☐ No |
| Week 6 | | 50 | | ☐ Yes ☐ No |
| Week 7 | | 50 | | ☐ Yes ☐ No |
| Week 8 | | 50 | | ☐ Yes ☐ No |
| Week 9 | | 50 | | ☐ Yes ☐ No |
| Week 10 | | 50 | | ☐ Yes ☐ No |
| Week 11 | | 50 | | ☐ Yes ☐ No |
| Week 12 | | 50 | | ☐ Yes ☐ No |
| Week 13 | | 50 | | ☐ Yes ☐ No |
| Week 14 | | 50 | | ☐ Yes ☐ No |

[1] Refer to Table K-1 to determine the specific monitoring week number for which you are reporting turbidity data for this quarter.

[2] Report to the nearest whole number. Enter "N/A" if no dewatering discharge occurred during any particular week.

[3] Prior approval from the EPA Regional Office is required pursuant to Part 3.3.2.b. Unless and until EPA approves your request to use an alternate benchmark, you are required to use the standard benchmark of 50 NTU and take any required corrective actions if an exceedance occurs. Enter "N/A" if you have not received approval for an alternate benchmark threshold.

[4] If "Yes," the operator must conduct follow-up corrective action pursuant to Part 5.2.2 and document any corrective action taken in the corrective action log in accordance with Part 5.4.

## VII. CERTIFICATION INFORMATION

**Certification Information**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

| First Name | Middle Initial | Last Name |
|---|---|---|
| | | |

| Title |
|---|
| |

| Signature | Date (MM/DD/YYYY) |
|---|---|
| | |

| Phone Number | Email Address |
|---|---|
| | |

## General Instructions

### Who Must Submit A Turbidity Monitoring Report to EPA?

Sites covered under the Construction General Permit (CGP or permit) that are required to monitor pursuant to Part 3.3 of the permit must submit Turbidity Monitoring Reports consistent with the reporting requirements specified in Part 3.3.4 of the permit.

### When Must I Submit A Turbidity Monitoring Report to EPA?

You must submit your report to EPA no later than 30 days following the end of each monitoring quarter. Submit a form for every quarter the site is active.

| Monitoring Quarter # | Months | Reporting Deadline |
|---|---|---|
| 1 | January 1 – March 31 | April 30 |
| 2 | April 1 – June 30 | July 30 |
| 3 | July 1 – September 30 | October 30 |
| 4 | October 1 – December 31 | January 30 |

### Completing the Form

Obtain and read a copy of the 2022 CGP, viewable at https://www.epa.gov/npdes/stormwater-discharges-construction-activities#cgp. To complete this form, type or print, using uppercase letters, in the appropriate areas only. Please submit the original document with signature in ink - do not send a photocopied signature. **Photocopy your form for your records before you send the completed original form to the appropriate address.**

### Section I. Approval to Use Paper Form

You must indicate whether you have been granted a waiver from electronic reporting from the EPA Regional Office. Note that you are not authorized to use this paper form unless the EPA Regional Office has approved its use. Where you have obtained approval to use this form, indicate the waiver that you have been granted, the name of the EPA staff person who granted the waiver, and the date that approval was provided. See https://www.epa.gov/npdes/contact-us-stormwater for a list of EPA Regional Office contacts.

### Section II. Permit Information

Provide the NPDES ID (i.e., NOI tracking number) assigned to the site for which this form is being submitted. Submit the form only for sites discharging dewatering water to a sediment-impaired water or a water designated as a Tier 2, Tier 2.5, or Tier 3 water.

Indicate whether this report fulfills turbidity monitoring report obligations of other operators that are covered under this permit for the same project site. If the answer is yes, provide all relevant NPDES ID numbers.

### Section III. Operator Information

Provide the legal name of the person, firm, public organization, or any other entity that is considered the operator of the site. See Part 1.1.1 and Appendix A for the definition of "operator." Provide the operator's mailing address, phone number, and e-mail. The operator information in this Section should match the operator information provided on your NOI form.

If this form was prepared by someone other than the certifier, include the name, organization, phone number, and email address of the person who prepared this form.

### Section IV. Site Information

Enter the official or legal name and complete street address, including city, State, ZIP code, and county or similar government subdivision of the site. If the site lacks a street address, indicate the general location (e.g., Intersection of State Highways 61 and 34). The site information in this Section should match the site information provided on your NOI form.

### Section V. Monitoring Quarter

Indicate the appropriate monitoring quarter (Quarter 1, 2, 3, or 4). The monitoring quarters are specified in the table in the section titled "When Must I Submit A Turbidity Monitoring Report to EPA." Select only one quarter.

### Section VI. Turbidity Monitoring Data

Provide the discharge point description/name if you are discharging dewatering water from more than one point at the site. If you are discharging from only one point at the site, leave the spaces blank.

Submit Section VI data for each dewatering discharge point. For example, if you are discharging dewatering water from two points at the site, then submit two Section VIs (one for each discharge point).

Indicate whether dewatering occurred during the monitoring quarter. If "Yes" enter the data in the data table. If "No" skip to Section VII.

For averaging purposes, a monitoring week starts with a Monday and ends on Sunday. A numerical value is assigned for each week, which is called a Week Number (e.g., 1, 2, 3 etc.). The form includes a Week Number for each week of the year. Refer to Table K-1 for the dates that correspond with each Week Number.

Next, calculate the weekly average turbidity value for the corresponding monitoring week. The weekly average is calculated by adding all of the individual turbidity results for that monitoring week and dividing by the total number of samples. The calculation for the weekly average includes only those days when dewatering discharge occurred. Days when no dewatering discharge occurred, and therefore do not have turbidity data associated with them, are not included in the calculation of the weekly average. For example, if turbidity samples from your dewatering discharge in week 1 result in values of 30 NTU on Tuesday, 40 NTU on Wednesday, and 45 NTU on Thursday, your weekly average turbidity value would be 38 NTU ((30+40+45) ÷ 3 = 38 NTU). If in week 2, your turbidity samples resulted in values of 45 NTU on Monday, 30 NTU on Tuesday, 25 NTU on Wednesday, and 15 NTU on Thursday, you would calculate a new average for that week, which would yield an average turbidity value of 29 NTU ((45+30+25+15) ÷ 4 = 29 NTU). By comparison, if your samples on consecutive days from Friday to Monday were 60

NTU, 45 NTU, 40 NTU, and 43 NTU, respectively, and there are no other dewatering discharges for the remainder of the week, you would calculate one weekly average for the Friday to Sunday to be 48 NTU ((60+45+40) ÷ 3 = 48 NTU), and a separate weekly average for the one Monday to be 43 NTU (43 ÷ 1 = 43 NTU).

If you collect and analyze more than one turbidity sample per day from your dewatering discharge, you must include any additional results in the calculation of your weekly average. For example, if during a monitoring week you take two turbidity samples on Tuesday with a value of 30 NTU and 35 NTU, three samples on Wednesday with a value of 40 NTU, 45 NTU, and 48 NTU, and one sample on Thursday with a value of 45 NTU, your weekly average turbidity value for this week would be 41 NTU ((30+35+40+45+48+45) ÷ 6 = 41 NTU).

Enter the weekly average turbidity values for the corresponding week into the table. Enter "N/A" into the table for the turbidity weekly average if no dewatering discharge occurred during the week.

The benchmark threshold for turbidity for this permit is 50 NTUs unless EPA has authorized the use of an alternate benchmark in accordance with Part 3.3.2.b. If you are using an alternate benchmark threshold, enter the number into the table for the corresponding week. Unless and until EPA approves your request to use an alternate benchmark, you are required to use the standard benchmark of 50 NTU and take any required corrective actions if an exceedance occurs. Enter "N/A" if you have not received approval for an alternate benchmark threshold.

For each week with a value for the weekly average, select "Yes" or "No" in the table to indicate whether the weekly average value exceeds the 50 NTU benchmark or the alternate turbidity benchmark (whichever is applicable). If "Yes", the operator must conduct follow-up corrective action pursuant to Part 5.2.2 and document any corrective action taken in the corrective action log in accordance with Part 5.4.

**Section VII. Certification Information**

Forms must be signed by a person described below, or by a duly authorized representative of that person.

*For a corporation:* By a responsible corporate officer. For the purpose of this Section, a responsible corporate officer means:

(i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long-term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

*For a partnership or sole proprietorship:* By a general partner or the proprietor, respectively; or

*For a municipality, State, Federal, or other public agency:* By either a principal executive officer or ranking elected official. For purposes of this Part, a principal executive officer of a Federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of EPA). Include the name and title of the person signing the form and the date of signing.

A person is a duly authorized representative only if:

1. The authorization is made in writing by a person described above;

2. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the company, (A duly authorized representative may thus be either a named individual or any individual occupying a named position.) and

3. The written authorization is submitted to the Director.

An unsigned or undated form will be considered incomplete.

**Submitting Your Form**

If you have been granted a waiver from your Regional Office to submit a paper form, you must send your form by mail to one of the following addresses:

**For Regular U.S. Mail Delivery:**

Stormwater Notice Processing Center
Mail Code 4203M, ATTN: 2022 CGP Reports
U.S. EPA
1200 Pennsylvania Avenue, NW
Washington, DC 20460

**For Overnight/Express Mail Delivery:**

Stormwater Notice Processing Center
William Jefferson Clinton East Building - Room 7420
ATTN: 2022 CGP Reports
U.S. EPA
1201 Constitution Avenue, NW
Washington, DC 20004

Visit this website for instructions on how to submit electronically:

https://epanet.zendesk.com/hc/en-us/sections/115000949868-CGP-Training-Material

**Revisions to a Submitted Form**

If you have previously submitted a form with an error, submit a revised form with the correct information. After discovering the error, submit the revised form as soon as possible. Make a notation on the revised form where the correction was made.

**Paperwork Reduction Act Notice**

This collection of information is approved by OMB under the Paperwork Reduction Act, 44 U.S.C. 3501 et seq. (OMB Control No. 2040-0305). Responses to this collection of information are mandatory (40 CFR 122.26). An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. The public reporting and recordkeeping burden for this collection of information is

estimated to be 0.2 hours per response. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates and any suggested methods for minimizing respondent burden to the Regulatory Support Division Director, U.S. Environmental Protection Agency (2821T), 1200 Pennsylvania Ave., NW, Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed form to this address.

# Table K-1: 2022 CGP - Dates Corresponding to Monitoring Weeks for Each Monitoring Quarter

| 2022 | | | |
|---|---|---|---|
| Monitoring Quarter | Week # | *Monday* Start Date | *Sunday* End Date |
| 1 | 1 | 1/3/22 | 1/9/22 |
| | 2 | 1/10/22 | 1/16/22 |
| | 3 | 1/17/22 | 1/23/22 |
| | 4 | 1/24/22 | 1/30/22 |
| | 5 | 1/31/22 | 2/6/22 |
| | 6 | 2/7/22 | 2/13/22 |
| | 7 | 2/14/22 | 2/20/22 |
| | 8 | 2/21/22 | 2/27/22 |
| | 9 | 2/28/22 | 3/6/22 |
| | 10 | 3/7/22 | 3/13/22 |
| | 11 | 3/14/22 | 3/20/22 |
| | 12 | 3/21/22 | 3/27/22 |
| | 13 | 3/28/22 | 4/3/22 |
| 2 | 1 | 4/4/22 | 4/10/22 |
| | 2 | 4/11/22 | 4/17/22 |
| | 3 | 4/18/22 | 4/24/22 |
| | 4 | 4/25/22 | 5/1/22 |
| | 5 | 5/2/22 | 5/8/22 |
| | 6 | 5/9/22 | 5/15/22 |
| | 7 | 5/16/22 | 5/22/22 |
| | 8 | 5/23/22 | 5/29/22 |
| | 9 | 5/30/22 | 6/5/22 |
| | 10 | 6/6/22 | 6/12/22 |
| | 11 | 6/13/22 | 6/19/22 |
| | 12 | 6/20/22 | 6/26/22 |
| | 13 | 6/27/22 | 7/3/22 |
| 3 | 1 | 7/4/22 | 7/10/22 |
| | 2 | 7/11/22 | 7/17/22 |
| | 3 | 7/18/22 | 7/24/22 |
| | 4 | 7/25/22 | 7/31/22 |
| | 5 | 8/1/22 | 8/7/22 |
| | 6 | 8/8/22 | 8/14/22 |
| | 7 | 8/15/22 | 8/21/22 |
| | 8 | 8/22/22 | 8/28/22 |
| | 9 | 8/29/22 | 9/4/22 |
| | 10 | 9/5/22 | 9/11/22 |
| | 11 | 9/12/22 | 9/18/22 |
| | 12 | 9/19/22 | 9/25/22 |
| | 13 | 9/26/22 | 10/2/22 |
| 4 | 1 | 10/3/22 | 10/9/22 |
| | 2 | 10/10/22 | 10/16/22 |
| | 3 | 10/17/22 | 10/23/22 |
| | 4 | 10/24/22 | 10/30/22 |
| | 5 | 10/31/22 | 11/6/22 |
| | 6 | 11/7/22 | 11/13/22 |
| | 7 | 11/14/22 | 11/20/22 |
| | 8 | 11/21/22 | 11/27/22 |
| | 9 | 11/28/22 | 12/4/22 |
| | 10 | 12/5/22 | 12/11/22 |
| | 11 | 12/12/22 | 12/18/22 |
| | 12 | 12/19/22 | 12/25/22 |
| | 13 | 12/26/22 | 1/1/23 |

| 2023 | | | |
|---|---|---|---|
| Monitoring Quarter | Week # | *Monday* Start Date | *Sunday* End Date |
| 1 | 1 | 1/2/23 | 1/8/23 |
| | 2 | 1/9/23 | 1/15/23 |
| | 3 | 1/16/23 | 1/22/23 |
| | 4 | 1/23/23 | 1/29/23 |
| | 5 | 1/30/23 | 2/5/23 |
| | 6 | 2/6/23 | 2/12/23 |
| | 7 | 2/13/23 | 2/19/23 |
| | 8 | 2/20/23 | 2/26/23 |
| | 9 | 2/27/23 | 3/5/23 |
| | 10 | 3/6/23 | 3/12/23 |
| | 11 | 3/13/23 | 3/19/23 |
| | 12 | 3/20/23 | 3/26/23 |
| | 13 | 3/27/23 | 4/2/23 |
| 2 | 1 | 4/3/23 | 4/9/23 |
| | 2 | 4/10/23 | 4/16/23 |
| | 3 | 4/17/23 | 4/23/23 |
| | 4 | 4/24/23 | 4/30/23 |
| | 5 | 5/1/23 | 5/7/23 |
| | 6 | 5/8/23 | 5/14/23 |
| | 7 | 5/15/23 | 5/21/23 |
| | 8 | 5/22/23 | 5/28/23 |
| | 9 | 5/29/23 | 6/4/23 |
| | 10 | 6/5/23 | 6/11/23 |
| | 11 | 6/12/23 | 6/18/23 |
| | 12 | 6/19/23 | 6/25/23 |
| | 13 | 6/26/23 | 7/2/23 |
| 3 | 1 | 7/3/23 | 7/9/23 |
| | 2 | 7/10/23 | 7/16/23 |
| | 3 | 7/17/23 | 7/23/23 |
| | 4 | 7/24/23 | 7/30/23 |
| | 5 | 7/31/23 | 8/6/23 |
| | 6 | 8/7/23 | 8/13/23 |
| | 7 | 8/14/23 | 8/20/23 |
| | 8 | 8/21/23 | 8/27/23 |
| | 9 | 8/28/23 | 9/3/23 |
| | 10 | 9/4/23 | 9/10/23 |
| | 11 | 9/11/23 | 9/17/23 |
| | 12 | 9/18/23 | 9/24/23 |
| | 13 | 9/25/23 | 10/1/23 |
| 4 | 1 | 10/2/23 | 10/8/23 |
| | 2 | 10/9/23 | 10/15/23 |
| | 3 | 10/16/23 | 10/22/23 |
| | 4 | 10/23/23 | 10/29/23 |
| | 5 | 10/30/23 | 11/5/23 |
| | 6 | 11/6/23 | 11/12/23 |
| | 7 | 11/13/23 | 11/19/23 |
| | 8 | 11/20/23 | 11/26/23 |
| | 9 | 11/27/23 | 12/3/23 |
| | 10 | 12/4/23 | 12/10/23 |
| | 11 | 12/11/23 | 12/17/23 |
| | 12 | 12/18/23 | 12/24/23 |
| | 13 | 12/25/23 | 12/31/23 |

| 2024 | | | |
|---|---|---|---|
| Monitoring Quarter | Week # | *Monday* Start Date | *Sunday* End Date |
| 1 | 1 | 1/1/24 | 1/7/24 |
| | 2 | 1/8/24 | 1/14/24 |
| | 3 | 1/15/24 | 1/21/24 |
| | 4 | 1/22/24 | 1/28/24 |
| | 5 | 1/29/24 | 2/4/24 |
| | 6 | 2/5/24 | 2/11/24 |
| | 7 | 2/12/24 | 2/18/24 |
| | 8 | 2/19/24 | 2/25/24 |
| | 9 | 2/26/24 | 3/3/24 |
| | 10 | 3/4/24 | 3/10/24 |
| | 11 | 3/11/24 | 3/17/24 |
| | 12 | 3/18/24 | 3/24/24 |
| | 13 | 3/25/24 | 3/31/24 |
| 2 | 1 | 4/1/24 | 4/7/24 |
| | 2 | 4/8/24 | 4/14/24 |
| | 3 | 4/15/24 | 4/21/24 |
| | 4 | 4/22/24 | 4/28/24 |
| | 5 | 4/29/24 | 5/5/24 |
| | 6 | 5/6/24 | 5/12/24 |
| | 7 | 5/13/24 | 5/19/24 |
| | 8 | 5/20/24 | 5/26/24 |
| | 9 | 5/27/24 | 6/2/24 |
| | 10 | 6/3/24 | 6/9/24 |
| | 11 | 6/10/24 | 6/16/24 |
| | 12 | 6/17/24 | 6/23/24 |
| | 13 | 6/24/24 | 6/30/24 |
| 3 | 1 | 7/1/24 | 7/7/24 |
| | 2 | 7/8/24 | 7/14/24 |
| | 3 | 7/15/24 | 7/21/24 |
| | 4 | 7/22/24 | 7/28/24 |
| | 5 | 7/29/24 | 8/4/24 |
| | 6 | 8/5/24 | 8/11/24 |
| | 7 | 8/12/24 | 8/18/24 |
| | 8 | 8/19/24 | 8/25/24 |
| | 9 | 8/26/24 | 9/1/24 |
| | 10 | 9/2/24 | 9/8/24 |
| | 11 | 9/9/24 | 9/15/24 |
| | 12 | 9/16/24 | 9/22/24 |
| | 13 | 9/23/24 | 9/29/24 |
| | 14 | 9/30/24 | 10/6/24 |
| 4 | 1 | 10/7/24 | 10/13/24 |
| | 2 | 10/14/24 | 10/20/24 |
| | 3 | 10/21/24 | 10/27/24 |
| | 4 | 10/28/24 | 11/3/24 |
| | 5 | 11/4/24 | 11/10/24 |
| | 6 | 11/11/24 | 11/17/24 |
| | 7 | 11/18/24 | 11/24/24 |
| | 8 | 11/25/24 | 12/1/24 |
| | 9 | 12/2/24 | 12/8/24 |
| | 10 | 12/9/24 | 12/15/24 |
| | 11 | 12/16/24 | 12/22/24 |
| | 12 | 12/23/24 | 12/29/24 |
| | 13 | 12/30/24 | 1/5/25 |

| 2025 | | | |
|---|---|---|---|
| Monitoring Quarter | Week # | *Monday* Start Date | *Sunday* End Date |
| 1 | 1 | 1/6/25 | 1/12/25 |
| | 2 | 1/13/25 | 1/19/25 |
| | 3 | 1/20/25 | 1/26/25 |
| | 4 | 1/27/25 | 2/2/25 |
| | 5 | 2/3/25 | 2/9/25 |
| | 6 | 2/10/25 | 2/16/25 |
| | 7 | 2/17/25 | 2/23/25 |
| | 8 | 2/24/25 | 3/2/25 |
| | 9 | 3/3/25 | 3/9/25 |
| | 10 | 3/10/25 | 3/16/25 |
| | 11 | 3/17/25 | 3/23/25 |
| | 12 | 3/24/25 | 3/30/25 |
| | 13 | 3/31/25 | 4/6/25 |
| 2 | 1 | 4/7/25 | 4/13/25 |
| | 2 | 4/14/25 | 4/20/25 |
| | 3 | 4/21/25 | 4/27/25 |
| | 4 | 4/28/25 | 5/4/25 |
| | 5 | 5/5/25 | 5/11/25 |
| | 6 | 5/12/25 | 5/18/25 |
| | 7 | 5/19/25 | 5/25/25 |
| | 8 | 5/26/25 | 6/1/25 |
| | 9 | 6/2/25 | 6/8/25 |
| | 10 | 6/9/25 | 6/15/25 |
| | 11 | 6/16/25 | 6/22/25 |
| | 12 | 6/23/25 | 6/29/25 |
| | 13 | 6/30/25 | 7/6/25 |
| 3 | 1 | 7/7/25 | 7/13/25 |
| | 2 | 7/14/25 | 7/20/25 |
| | 3 | 7/21/25 | 7/27/25 |
| | 4 | 7/28/25 | 8/3/25 |
| | 5 | 8/4/25 | 8/10/25 |
| | 6 | 8/11/25 | 8/17/25 |
| | 7 | 8/18/25 | 8/24/25 |
| | 8 | 8/25/25 | 8/31/25 |
| | 9 | 9/1/25 | 9/7/25 |
| | 10 | 9/8/25 | 9/14/25 |
| | 11 | 9/15/25 | 9/21/25 |
| | 12 | 9/22/25 | 9/28/25 |
| | 13 | 9/29/25 | 10/5/25 |
| 4 | 1 | 10/6/25 | 10/12/25 |
| | 2 | 10/13/25 | 10/19/25 |
| | 3 | 10/20/25 | 10/26/25 |
| | 4 | 10/27/25 | 11/2/25 |
| | 5 | 11/3/25 | 11/9/25 |
| | 6 | 11/10/25 | 11/16/25 |
| | 7 | 11/17/25 | 11/23/25 |
| | 8 | 11/24/25 | 11/30/25 |
| | 9 | 12/1/25 | 12/7/25 |
| | 10 | 12/8/25 | 12/14/25 |
| | 11 | 12/15/25 | 12/21/25 |
| | 12 | 12/22/25 | 12/28/25 |
| | 13 | 12/29/25 | 1/4/26 |

| 2026 | | | |
|---|---|---|---|
| Monitoring Quarter | Week # | *Monday* Start Date | *Sunday* End Date |
| 1 | 1 | 1/5/26 | 1/11/26 |
| | 2 | 1/12/26 | 1/18/26 |
| | 3 | 1/19/26 | 1/25/26 |
| | 4 | 1/26/26 | 2/1/26 |
| | 5 | 2/2/26 | 2/8/26 |
| | 6 | 2/9/26 | 2/15/26 |
| | 7 | 2/16/26 | 2/22/26 |
| | 8 | 2/23/26 | 3/1/26 |
| | 9 | 3/2/26 | 3/8/26 |
| | 10 | 3/9/26 | 3/15/26 |
| | 11 | 3/16/26 | 3/22/26 |
| | 12 | 3/23/26 | 3/29/26 |
| | 13 | 3/30/26 | 4/5/26 |
| 2 | 1 | 4/6/26 | 4/12/26 |
| | 2 | 4/13/26 | 4/19/26 |
| | 3 | 4/20/26 | 4/26/26 |
| | 4 | 4/27/26 | 5/3/26 |
| | 5 | 5/4/26 | 5/10/26 |
| | 6 | 5/11/26 | 5/17/26 |
| | 7 | 5/18/26 | 5/24/26 |
| | 8 | 5/25/26 | 5/31/26 |
| | 9 | 6/1/26 | 6/7/26 |
| | 10 | 6/8/26 | 6/14/26 |
| | 11 | 6/15/26 | 6/21/26 |
| | 12 | 6/22/26 | 6/28/26 |
| | 13 | 6/29/26 | 7/5/26 |
| 3 | 1 | 7/6/26 | 7/12/26 |
| | 2 | 7/13/26 | 7/19/26 |
| | 3 | 7/20/26 | 7/26/26 |
| | 4 | 7/27/26 | 8/2/26 |
| | 5 | 8/3/26 | 8/9/26 |
| | 6 | 8/10/26 | 8/16/26 |
| | 7 | 8/17/26 | 8/23/26 |
| | 8 | 8/24/26 | 8/30/26 |
| | 9 | 8/31/26 | 9/6/26 |
| | 10 | 9/7/26 | 9/13/26 |
| | 11 | 9/14/26 | 9/20/26 |
| | 12 | 9/21/26 | 9/27/26 |
| | 13 | 9/28/26 | 10/4/26 |
| 4 | 1 | 10/5/26 | 10/11/26 |
| | 2 | 10/12/26 | 10/18/26 |
| | 3 | 10/19/26 | 10/25/26 |
| | 4 | 10/26/26 | 11/1/26 |
| | 5 | 11/2/26 | 11/8/26 |
| | 6 | 11/9/26 | 11/15/26 |
| | 7 | 11/16/26 | 11/22/26 |
| | 8 | 11/23/26 | 11/29/26 |
| | 9 | 11/30/26 | 12/6/26 |
| | 10 | 12/7/26 | 12/13/26 |
| | 11 | 12/14/26 | 12/20/26 |
| | 12 | 12/21/26 | 12/27/26 |
| | 13 | 12/28/26 | 1/3/27 |

| 2027 | | | |
|---|---|---|---|
| Monitoring Quarter | Week # | *Monday* Start Date | *Sunday* End Date |
| 1 | 1 | 1/4/27 | 1/10/27 |
| | 2 | 1/11/27 | 1/17/27 |
| | 3 | 1/18/27 | 1/24/27 |
| | 4 | 1/25/27 | 1/31/27 |
| | 5 | 2/1/27 | 2/7/27 |
| | 6 | 2/8/27 | 2/14/27 |
| | 7 | 2/15/27 | 2/21/27 |
| | 8 | 2/22/27 | 2/28/27 |
| | 9 | 3/1/27 | 3/7/27 |
| | 10 | 3/8/27 | 3/14/27 |
| | 11 | 3/15/27 | 3/21/27 |
| | 12 | 3/22/27 | 3/28/27 |
| | 13 | 3/29/27 | 4/4/27 |

**Attachment D – Site Inspection Form and Dewatering Inspection Form**

**Attachment E – Corrective Action Form**

**Project Name:** _____
**NPDES ID Number:** _____

| **Section A – General Information**<br>(If necessary, complete additional inspection reports for each separate inspection location.) | |
|---|---|
| **Inspector Information** | |
| **Inspector Name:** | **Title:** |
| **Company Name:** | **Email:** |
| **Address:** | **Phone Number:** |
| **Inspection Details** | |
| **Inspection Date:** | **Inspection Location:** |
| **Inspection Start Time:** | **Inspection End Time:** |
| **Current Phase of Construction:** | **Weather Conditions During Inspection:** |

**Did you determine that any portion of your site was unsafe for inspection per CGP Part 4.5?** ☐ Yes ☐ No

**If "Yes," provide the following information:**

Location of unsafe conditions:

The conditions that prevented you inspecting this location:

**Indicate the required inspection frequency:** (Check all that apply. You may be subject to different inspection frequencies in different areas of the site.)

**Standard Frequency (CGP Part 4.2)**:

☐ At least once every 7 calendar days; **OR**

☐ Once every 14 calendar days *and* within 24 hours of the occurrence of either:

- A storm event that produces 0.25 inches or more of rain within a 24-hour period, or
- A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period

**Increased Frequency (CGP Part 4.3.1)** (If site discharges to sediment or nutrient-impaired waters or to waters designated as Tier 2, Tier 2.5, or Tier 3):

☐ Once every 7 calendar days *and* within 24 hours of the occurrence of either:

- A storm event that produces 0.25 inches or more of rain within a 24-hour period, or
- A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period

**Reduced Frequency (CGP Part 4.4)**:

- ☐ For stabilized areas: Twice during first month, no more than 14 calendar days apart; then once per month after first month until permit coverage is terminated
- ☐ For stabilized areas on "linear construction sites": Twice during first month, no more than 14 calendar days apart; then once more within 24 hours of the occurrence of either:
  - A storm event that produces 0.25 inches or more of rain within a 24-hour period, or
  - A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period
- ☐ For arid, semi-arid, or drought-stricken areas during seasonally dry periods or during drought: Once per month and within 24 hours of the occurrence of either:
  - A storm event that produces 0.25 inches or more of rain within a 24-hour period, or
  - A snowmelt discharge from a storm event that produces 3.25 inches or more of snow within a 24-hour period
- ☐ For frozen conditions where construction activities are being conducted: Once per month

**Was this inspection triggered by a storm event producing 0.25 inches or more of rain within a 24-hour period?** ☐ Yes ☐ No

**If "Yes," how did you determine whether the storm produced 0.25 inches or more of rain?**

- ☐ On-site rain gauge
- ☐ Weather station representative of site.
  Weather station location:

**Total rainfall amount that triggered the inspection (inches):**

**Was this inspection triggered by a snowmelt discharge from a storm event producing 3.25 inches or more of snow within a 24-hour period?** ☐ Yes ☐ No

**If "Yes," how did you determine whether the storm produced 3.25 inches or more of snow?**

- ☐ On-site rain gauge
- ☐ Weather station representative of site.
  Weather station location:

**Total snowfall amount that triggered the inspection (inches):**

| **Section B – Condition and Effectiveness of Erosion and Sediment (E&S) Controls (CGP Part 2.2)** (Insert additional rows if needed) | | | | | |
|---|---|---|---|---|---|
| **Type and Location of E&S Control** | **Conditions Requiring Routine Maintenance?[1]** | **If "Yes," How Many Times (Including This Occurrence) Has This Condition Been Identified?** | **Conditions Requiring Corrective Action?[2, 3]** | **Date on Which Condition First Observed (If Applicable)?** | **Description of Conditions Observed** |
| **1.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **2.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **3.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **4.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **5.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **If the same routine maintenance was found to be necessary three or more times for the same control at the same location (including this occurrence), follow the corrective action requirements and record the required information in your corrective action log, or describe here why you believe the specific condition should still be addressed as routine maintenance:** | | | | | |

[1] Routine maintenance includes minor repairs or other upkeep performed to ensure that the site's stormwater controls remain in effective operating condition, not including significant repairs or the need to install a new or replacement control. Routine maintenance is also required for specific conditions: (1) for perimeter controls, whenever sediment has accumulated to half or more the above-ground height of the control (CGP Part 2.2.3.c.i); (2) where sediment has been tracked-out from the site onto paved roads, sidewalks, or other paved areas (CGP Part 2.2.4.d); (3) for inlet protection measures, when sediment accumulates, the filter becomes clogged, and/or performance is compromised (CGP Part 2.2.10.b); and (4) for sediment basins, as necessary to maintain at least half of the design capacity of the basin (CGP Part 2.2.12.f)

[2] Corrective actions are triggered only for specific conditions (CGP Part 5.1):

1. A stormwater control needs a significant repair or a new or replacement control is needed, or, in accordance with Part 2.1.4.c, you find it necessary to repeatedly (i.e., three (3) or more times) conduct the same routine maintenance fix to the same control at the same location (unless you document in your inspection report under Part 4.7.1.c that the specific reoccurrence of this same problem should still be addressed as a routine maintenance fix under 2.1.4); or
2. A stormwater control necessary to comply with the requirements of this permit was never installed, or was installed incorrectly; or
3. Your discharges are not meeting applicable water quality standards; or
4. A prohibited discharge has occurred (see CGP Part 1.3); or
5. During the discharge from site dewatering activities:
   a. The weekly average of your turbidity monitoring results exceeds the 50 NTU benchmark (or alternate benchmark if approved by EPA pursuant to Part 3.3.2.b); or
   b. You observe or you are informed by EPA, State, or local authorities of the presence of the conditions specified in Part 4.6.3.e.

[3] If a condition on your site requires a corrective action, you must also fill out a corrective action log found at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates. See CGP Part 5.4 for more information.

**Project Name:** _____
**NPDES ID Number:** _____

| Section C – Condition and Effectiveness of Pollution Prevention (P2) Practices and Controls (CGP Part 2.3) (Insert additional rows if needed) | | | | | |
|---|---|---|---|---|---|
| **Type and Location of P2 Practices and Controls** | **Conditions Requiring Routine Maintenance?[1]** | **If "Yes," How Many Times (Including This Occurrence) Has This Condition Been Identified?** | **Conditions Requiring Corrective Action?[2, 3]** | **Date on Which Condition First Observed (If Applicable)?** | **Description of Conditions Observed** |
| **1.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **2.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **3.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **4.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **5.** | ☐ Yes ☐ No | | ☐ Yes ☐ No | | |
| **If the same routine maintenance was found to be necessary three or more times for the same control at the same location (including this occurrence), follow the corrective action requirements and record the required information in your corrective action log, or describe here why you believe the specific condition should still be addressed as routine maintenance:** | | | | | |

| **Section D – Stabilization of Exposed Soil (CGP Part 2.2.14)** (Insert additional rows if needed) | | | | | |
|---|---|---|---|---|---|
| **Specific Location That Has Been or Will Be Stabilized** | **Stabilization Method and Applicable Deadline** | **Stabilization Initiated?** | **Final Stabilization Criteria Met?** | **Final Stabilization Photos Taken?** | **Notes** |
| **1.** | | ☐ Yes ☐ No<br>If "Yes," date initiated: | ☐ Yes ☐ No<br>If "Yes," date criteria met: | ☐ Yes ☐ No | |
| **2.** | | ☐ Yes ☐ No<br>If "Yes," date initiated: | ☐ Yes ☐ No<br>If "Yes," date criteria met: | ☐ Yes ☐ No | |
| **3.** | | ☐ Yes ☐ No<br>If "Yes," date initiated: | ☐ Yes ☐ No<br>If "Yes," date criteria met: | ☐ Yes ☐ No | |
| **4.** | | ☐ Yes ☐ No<br>If "Yes," date initiated: | ☐ Yes ☐ No<br>If "Yes," date criteria met: | ☐ Yes ☐ No | |
| **5.** | | ☐ Yes ☐ No<br>If "Yes," date initiated: | ☐ Yes ☐ No<br>If "Yes," date criteria met: | ☐ Yes ☐ No | |

| **Section E – Description of Discharges (CGP Part 4.6.2)**<br>(Insert additional rows if needed) | |
|---|---|
| **Was a discharge (not including dewatering) occurring from any part of your site at the time of the inspection?[4]** ☐ Yes ☐ No<br><br>**If "Yes," for each point of discharge, document the following:**<br>• The visual quality of the discharge.<br>• The characteristics of the discharge, including color; odor; floating, settled, or suspended solids; foam; oil sheen; and other indicators of stormwater pollutants.<br>• Signs of the above pollutant characteristics that are visible from your site and attributable to your discharge in receiving waters or in other constructed or natural site drainage features. | |
| **Discharge Location** | **Observations** |
| **1.** | |
| **2.** | |
| **3.** | |
| **4.** | |
| **5.** | |

[4] If a dewatering discharge was occurring, you must conduct a dewatering inspection pursuant to CGP Part 4.3.2 and complete a separate dewatering inspection report.

| **Section F – Signature and Certification (CGP Part 4.7.2)** | |
|---|---|
| "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information contained therein. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information contained is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations." | |
| **MANDATORY: Signature of Operator or "Duly Authorized Representative:"** | |
| **Signature:** | **Date:** |
| **Printed Name:** | **Affiliation:** |
| **OPTIONAL: Signature of Contractor or Subcontractor** | |
| **Signature:** | **Date:** |
| **Printed Name:** | **Affiliation:** |

## General Tips for Using This Template

This Site Inspection Report Template is provided to assist you in preparing site inspection reports for EPA's 2022 Construction General Permit (CGP). If you are covered under the 2022 CGP, you can use this template to create a site inspection report form that is customized to the specific circumstances of your site and that complies with the minimum reporting requirements of Part 4.7 of the permit. Note that the use of this form is optional; you may use your own site inspection report form provided it includes the minimum information required in Part 4.7 of the CGP.

This template does not address the CGP's inspection reporting requirements related to dewatering activities. A separate inspection template has been developed specifically for dewatering activities and is available at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates.

Keep in mind that this document is a template and not an "off-the-shelf" inspection report that is ready to use without some modification. You must first customize this form to include the specifics of your project in order for it to be useable for your inspection reports. Once you have entered all of your site-specific information into the blank fields, you may use this form to complete inspection reports.

The following tips for using this template will help you ensure that the minimum permit requirements are met:

- **Review the inspection requirements.** Before you start developing your inspection report form, read the CGP's Part 4 inspection requirements. This will ensure that you have a working understanding of the permit's underlying inspection requirements.
- **Complete all required blank fields.** Fill out all blank fields. Only by filling out all fields will the template be compliant with the requirements of the permit. (Note: Where you do not need the number of rows provided in the template form for your inspection, you may delete these or cross them off as you see fit. Or, if you need more space to document your findings, you may insert additional rows in the electronic version of this form or use the bottom of the page in the field version of this form.)
- **Use your site map to document inspection findings.** In several places in the template, you are directed to specify the location of certain features of your site, including where stormwater controls are installed and where you will be stabilizing exposed soil. You are also asked to fill in location information for unsafe conditions and the locations of any discharges occurring during your inspections. Where you are asked for location information, EPA encourages you to reference the point on your SWPPP site map that corresponds to the requested location on the inspection form. Using the site map as a tool in this way will help you conduct efficient inspections, will assist you in evaluating problems found, and will ensure proper documentation.
- **Complete the inspection report within 24 hours of completing a site inspection.** You must complete an inspection report in accordance with Part 4.7.1 of the CGP.
- **Include the inspection form with your SWPPP.** Once your form is complete, make sure to include a copy of the inspection form in your SWPPP in accordance with Part 7.2.7.e of the CGP.
- **Retain copies of all inspection reports with your records.** You must also retain in your records copies of all inspection reports in accordance with the requirements in Part 4.7.3 of the CGP. These reports must be retained for at least 3 years from the date your permit coverage expires or is terminated in accordance with the requirements in Part 4.7.4 of the CGP.

## Instructions for Section A

**Inspector Name**

Enter the name of the person that conducted the inspection. Include the person's contact information (title, affiliated company name, address, email, and phone number).

**Inspection Date and Time**

Enter the date you performed the inspection and the time you started and ended the inspection.

**Weather Conditions During Inspection**

Enter the weather conditions occurring during the inspection, e.g., sunny, overcast, light rain, heavy rain, snowing, icy, windy.

**Current Phase of Construction**
If this project is being completed in more than one phase, indicate which phase it is currently in.

**Inspection Location**
If your project has multiple locations where you conduct separate inspections, specify the location where this inspection is being conducted. If only one inspection is conducted for your entire project, enter "Entire Site." If necessary, complete additional inspection report forms for each separate inspection location.

**Unsafe Conditions for Inspection** (CGP Part 4.5.7)
Inspections are not required where a portion of the site or the entire site is subject to unsafe conditions. These conditions should not regularly occur and should not be consistently present on a site. Generally, unsafe conditions are those that render the site (or a portion of it) inaccessible or that would pose a significant probability of injury to applicable personnel. Examples could include severe storm or flood conditions, high winds, and downed electrical wires.

If your site, or a portion of it, is affected by unsafe conditions during the time of your inspection, provide a description of the conditions that prevented you from conducting the inspection and what parts of the site were affected. If the entire site was considered unsafe, specify the location as "Entire Site."

**Inspection Frequency**
Check all the inspection frequencies that apply to your project. Note that you may be subject to different inspection frequencies in different areas of your site.

**Inspection Triggered by a Storm Event**
If you were required to conduct this inspection because of a storm event that produced 0.25 inches or more of rain within a 24-hour period, indicate whether you relied on an on-site rain gauge or a nearby weather station (and where the weather station is located). Also, specify the total amount of rainfall for this specific storm event.

If you were required to conduct this inspection because of a snowmelt discharge from a storm event that produced 3.25 inches or more of snow within a 24-hour period, then indicate whether you relied on an on-site measurement or a nearby weather station (and where the weather station is located). Also, specify the total amount of snowfall for this specific storm event.

## Instructions for Section B

**Type and Location of Erosion and Sediment (E&S) Controls**
Provide a list of all erosion and sediment (E&S) controls that your SWPPP indicates will be installed and implemented at your site. This list must include at a minimum all E&S controls required by CGP Part 2.2. Include also any natural buffers established under CGP Part 2.2.1. Buffer requirements apply if your project's earth-disturbing activities will occur within 50 feet of a discharge to receiving water. You may group your E&S controls on your form if you have several of the same type of controls (e.g., you may group "Inlet Protection Measures," "Perimeter Controls," and "Stockpile Controls" together on one line), but if there are any problems with a specific control, you must separately identify the location of the control, whether routine maintenance or corrective action is necessary, and in the notes section you must describe the specifics about the problem you observed.

**Conditions Requiring Routine Maintenance?**
Answer "Yes" if the E&S control requires routine maintenance as defined in footnote 1 of this template. Note that in many cases, "Yes" answers are expected and indicate a project with an active operation and maintenance program. You should also answer "Yes" if work to fix the problem is still ongoing from the previous inspection, though necessary work must be initiated immediately and completed by the end of the next business day or within seven calendar days if documented in accordance with CGP Part 2.1.4.b.

**If "Yes," How Many Times (Including this Occurrence) Has this Condition Been Identified?**
Indicate how many times the routine maintenance has been required for the same control at the same location.

**Conditions Requiring Corrective Action?**
Answer "Yes" if you found any of the conditions listed in footnote 2 in this template to be present during your inspection (CGP Part 5.1). If you answer "Yes," you must take corrective action and complete a corrective action log, found at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates. You should also answer "Yes" if work to fix the problem from a previous inspection is still ongoing, though the operator must comply with the corrective action deadlines in CGP Part 5.2.

**Date on Which Condition First Observed (If Applicable)?**
Provide the date on which the condition that triggered the need for routine maintenance or corrective action was first identified. If the condition was just discovered during this inspection, enter the inspection date. If the condition is a carryover from a previous inspection, enter the original date of the condition's discovery.

**Description of Conditions Observed**
For each E&S control and the area immediately surrounding it, describe whether the control is properly installed and whether it appears to be working to minimize sediment discharge. Indicate also whether a new or modified control is necessary to comply with the permit. Describe any problem condition(s) you observed such as the following:

1. Failure to install or to properly install a required E&S control
2. Damage or destruction to an E&S control caused by vehicles, equipment, or personnel, a storm event, or other event
3. Mud or sediment deposits found downslope from E&S controls, including in receiving waters, or on nearby streets, curbs, or open conveyance channels
4. Sediment tracked out onto paved areas by vehicles leaving construction site
5. Noticeable erosion or sedimentation at discharge outlets or at adjacent streambanks or channels
6. Erosion of the site's sloped areas (e.g., formation of rills or gullies)
7. E&S control is no longer working due to lack of maintenance
8. Other incidents of noncompliance

Describe also why you think the problem condition(s) occurred as well as actions (e.g., routine maintenance or corrective action) you will take or have taken to fix the problem.

For buffer areas, make note of whether they are marked off as required, whether there are signs of construction disturbance within the buffer, which is prohibited under the CGP, and whether there are visible signs of erosion resulting from discharges through the area.

If routine maintenance or corrective action is required, briefly note the reason. If routine maintenance or corrective action has been completed, make a note of the date it was completed and what was done. *If corrective action is required, note that you will need to complete a separate corrective action log describing the condition and your work to fix the problem*.

**Routine Maintenance Need Has Been Found to be Necessary Three (3) or More Times for the Same Control at the Same Location (Including this Occurrence)**
If routine maintenance has been required three (3) or more times for the same control at the same location, the permit requires (CGP Part 2.1.4.c) you to fix the problem using the corrective action procedures in CGP Part 5 or to document why you believe the reoccurring problem can be addressed as a routine maintenance fix. If you believe the problem can continue to be fixed as routine maintenance, describe why you believe the specific condition should still be addressed as routine maintenance.

## Instructions for Section C

**Type and Location of Pollution Prevention (P2) Practices and Controls**
Provide a list of all pollution prevention (P2) practices and controls that are implemented at your site. This list must include all P2 practices and controls required by CGP Part 2.3 and those that are described in your SWPPP.

**Conditions Requiring Routine Maintenance?**
Answer "Yes" if the P2 practice or control requires routine maintenance as defined in footnote 1of this template. Note that in many cases, "Yes" answers are expected and indicate a project with an active operation and maintenance program. You should also answer "Yes" if work to fix the problem is still ongoing

from the previous inspection, though necessary work must be initiated immediately and completed by the end of the next business day or within seven calendar days if documented in accordance with CGP Part 2.1.4.b.

**If "Yes," How Many Times (Including this Occurrence) Has this Condition Been Identified?**
Indicate how many times the routine maintenance has been required for the same practice or control at the same location.

**Conditions Requiring Corrective Action?**
Answer "Yes" if you found any of the conditions listed in footnote 2 in this template to be present during your inspection (CGP Part 5.1). If you answer "Yes," you must take corrective action and complete a corrective action log, found at https://www.epa.gov/npdes/construction-general-permit-resources-tools-and-templates. You should also answer "Yes" if work to fix the problem from a previous inspection is still ongoing, though the operator must comply with the corrective action deadlines in CGP Part 5.2.

**Date on Which Condition First Observed (If Applicable)?**
Provide the date on which the condition that triggered the need for maintenance or corrective action was first identified. If the condition was just discovered during this inspection, enter the inspection date. If the condition is a carryover from a previous inspection, enter the original date of the condition's discovery.

**Description of Conditions Observed**
For each P2 control and the area immediately surrounding it, describe whether the control is properly installed, and whether it appears to be working to minimize or eliminate pollutant discharges. Indicate also whether a new or modified control is necessary to comply with the permit. Describe any problem condition(s) you observed such as the following:

1. Failure to install or to properly install a required P2 control
2. Damage or destruction to a P2 control caused by vehicles, equipment, or personnel, or a storm event
3. Evidence of a spill, leak, or other type of pollutant discharge, or failure to have properly cleaned up a previous spill, leak, or other type of pollutant discharge
4. Spill response supplies are absent, insufficient, or not where they are supposed to be located
5. Improper storage, handling, or disposal of chemicals, building materials or products, fuels, or wastes
6. P2 control is no longer working due to lack of maintenance
7. Other incidents of noncompliance

Describe also why you think the problem condition(s) occurred as well as actions (e.g., routine maintenance or corrective action) you will take or have taken to fix the problem.

If routine maintenance or corrective action is required, briefly note the reason. If routine maintenance or corrective action has been completed, make a note of the date it was completed and what was done. *If corrective action is required, note that you will need to complete a separate corrective action log describing the condition and your work to fix the problem*.

**Routine Maintenance Need Was Found to be Necessary Three (3) or More Times for the Same Control at the Same Location (Including this Occurrence)**
If routine maintenance has been required three (3) or more times for the same control at the same location, the permit requires (CGP Part 2.1.4.c) you to fix the problem using the corrective action procedures in CGP Part 5 or to document why you believe the reoccurring problem can be addressed as a routine maintenance fix. If you believe the problem can continue to be fixed as routine maintenance, describe why you believe the specific condition should still be addressed as routine maintenance.

## Instructions for Section D

**Specific Location That Has Been or Will Be Stabilized**
List all areas where soil stabilization is required to begin because construction work in that area has permanently stopped or temporarily stopped (i.e., work will stop for 14 or more days), and all areas where stabilization has been implemented (CGP Part 2.2.14).

**Stabilization Method and Applicable Deadline**
For each area, specify the method of stabilization (e.g., hydroseed, sod, planted vegetation, erosion control blanket, mulch, rock).

Specify also which of the following stabilization deadlines apply to this location:

1. 5 acres or less of land disturbance occurring at any one time at site: Complete no later than 14 calendar days after stabilization initiated.
2. More than 5 acres of land disturbance occurring at any one time at site: Complete no later than 7 calendar days after stabilization initiated.
3. Arid, semi-arid, and drought-stricken areas: See CGP Part 2.2.14.b.i.
4. Unforeseen circumstances: See CGP Part 2.2.14.b.ii.
5. Discharges to a sediment- or nutrient-impaired water or to a water identified as Tier 2, 2.5, or 3 for antidegradation purposes: Complete no later than 7 days after stabilization initiated.

**Stabilization Initiated?**
For each area, indicate whether stabilization has been initiated. If "Yes," then enter the date stabilization was initiated.

**Final Stabilization Criteria Met?**
For each area, indicate whether the final stabilization criteria in CGP Part 2.2.14.c have been met. If "Yes," then enter the date final stabilization criteria were met.

**Final Stabilization Photos Taken?**
Answer "Yes" if you have taken photos before and after meeting the stabilization criteria as required in CGP Part 8.2.1.a.

**Notes**
For each area where stabilization has been initiated, describe the progress that has been made and what additional actions are necessary to complete stabilization. Note the effectiveness of stabilization in preventing erosion. If stabilization has been initiated but not completed, make a note of the date it is to be completed. If stabilization has been completed, make a note of the date it was completed. If stabilization has not yet been initiated, make a note of the date it is to be initiated and the date it is to be completed.

## Instructions for Section E

You are only required to complete this section if a discharge is occurring at the time of the inspection (CGP Part 4.6.2).

**Was a discharge (not including dewatering) occurring from any part of your site at the time of the inspection?**
During your inspection, examine all points of discharge from your site, and determine whether a discharge is occurring. If a dewatering discharge was occurring, you must conduct a dewatering inspection pursuant to CGP Part 4.3.2. If there is a discharge, answer "Yes" and complete the questions below regarding the specific discharge. If there is not a discharge, answer "No" and skip to the next page.

**Discharge Location** (Repeat as necessary if there are multiple points of discharge.)
Specify the location on your site where the discharge is occurring. The location may be an outlet from a stormwater control or constructed stormwater channel, a discharge into a storm sewer inlet, or a specific point on the site. Be as specific as possible; it is recommended that you refer to a precise point on your site map.

**Observations**
Document the visual quality of the discharge and take note of the characteristics of the stormwater discharge, including color; odor; floating, settled, or suspended solids; foam; oily sheen; and other indicators of stormwater pollutants. Also, document signs of these same pollutant characteristics that are visible from your site and attributable to your discharge in receiving waters or in other constructed or natural site drainage features.

## Instructions for Section F

Each inspection report must be signed and certified to be considered complete (CGP Part 4.7.2).

**Operator or "Duly Authorized Representative" – MANDATORY** (CGP Appendix G Part G.11.2 and CGP Appendix H Section X)

At a minimum, the site inspection report must be signed by either (1) the person who signed the NOI, or (2) a duly authorized representative of that person. The following requirements apply:

If the signatory will be the person who signed the NOI for permit coverage, as a reminder, that person must be one of the following types of individuals:

- *For a corporation*: By a responsible corporate officer. For the purpose of this subsection, a responsible corporate officer means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
- *For a partnership or sole proprietorship*: By a general partner or the proprietor, respectively.
- *For a municipality, State, Federal, or other public agency*: By either a principal executive officer or ranking elected official. For purposes of this subsection, a principal executive officer of a Federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of EPA).

If the signatory will be a duly authorized representative, the following requirements must be met:

- The authorization is made in writing by the person who signed the NOI (see above);
- The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position); and
- The signed and dated written authorization is included in the SWPPP. A copy must be submitted to EPA, if requested.

Sign, date and print your name and affiliation.

**Contractor or Subcontractor - OPTIONAL**

Where you rely on a contractor or subcontractor to complete the site inspection report, you should consider requiring the individual(s) to sign and certify each report. Note that this does not relieve you, the permitted operator, of the requirement to sign and certify the site inspection report as well. If applicable, sign, date, and print your name and affiliation.

## Note

While EPA has made every effort to ensure the accuracy of all instructions contained in this template, it is the permit, not this template, that determines the actual obligations of regulated construction stormwater discharges. In the event of a conflict between this template and any corresponding provision of the CGP, you must abide by the requirements in the permit. EPA welcomes comments on this Site Inspection Report Template at any time and will consider those comments in any future revision. You may contact EPA for CGP-related inquiries at cgp@epa.gov

**Attachment F – SWPPP Amendment Log**

| No. | Description of the Amendment | Date of Amendment | Amendment Prepared by [Name(s) and Title] |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

# 2022 CGP Corrective Action Log
# Project Name: _____
# NPDES ID Number: _____

| Section A – Individual Completing this Log | |
|---|---|
| **Name:** | **Title:** |
| **Company Name:** | **Email:** |
| **Address:** | **Phone Number:** |
| **Section B – Details of the Problem (CGP Part 5.4.1.a)**<br>Complete this section within 24 hours of discovering the condition that triggered corrective action. | |
| **Date problem was first identified**: | **Time problem was first identified**: |
| **What site conditions triggered this corrective action?** *(Check the box that applies. See instructions for a description of each triggering condition (1 thru 6).)*<br>☐ 1 ☐ 2 ☐ 3 ☐ 4 ☐ 5a ☐ 5b ☐ 6 | |
| **Specific location where problem identified:** | |
| **Provide a description of the specific condition that triggered the need for corrective action and the cause (if identifiable):** | |
| **Section C – Corrective Action Completion (CGP Part 5.4.1.b)**<br>Complete this section within 24 hours after completing the corrective action. | |
| **For site condition # 1, 2, 3, 4, or 6 (those not related to a dewatering discharge) confirm that you met the following deadlines (CGP Part 5.2.1):** | |
| ☐ Immediately took all reasonable steps to address the condition, including cleaning up any contaminated surfaces so the material will not discharge in subsequent storm events. **AND** | |
| ☐ Completed corrective action by the close of the next business day, unless a new or replacement control, or significant repair, was required. **OR** | |
| ☐ Completed corrective action within seven (7) calendar days from the time of discovery because a new or replacement control, or significant repair, was necessary to complete the installation of the new or modified control or complete the repair. **OR** | |
| ☐ It was infeasible to complete the installation or repair within 7 calendar days from the time of discovery. Provide the following additional information:<br>Explain why 7 calendar days was infeasible to complete the installation or repair: | |

Provide your schedule for installing the stormwater control and making it operational as soon as feasible after the 7 calendar days:

**For site condition # 5a, 5b, or 6 (those related to a dewatering discharge), confirm that you met the following deadlines:**

- ☐ Immediately took all reasonable steps to minimize or prevent the discharge of pollutants until a solution could be implemented, including shutting off the dewatering discharge as soon as possible depending on the severity of the condition taking safety considerations into account.
- ☐ Determined whether the dewatering controls were operating effectively and whether they were causing the conditions.
- ☐ Made any necessary adjustments, repairs, or replacements to the dewatering controls to lower the turbidity levels below the benchmark or remove the visible plume or sheen.

| **Describe any modification(s) made as part of corrective action:** (Insert additional rows below if applicable) | **Date of completion:** | **SWPPP update necessary?** | **If yes, date SWPPP was updated:** |
|---|---|---|---|
| **1.** | | ☐ Yes ☐ No | |
| **2.** | | ☐ Yes ☐ No | |

## Section D - Signature and Certification (CGP Part 5.4.2)

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information contained therein. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information contained is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

| **MANDATORY: Signature of Operator or "Duly Authorized Representative:"** | |
|---|---|
| **Signature:** | **Date:** |
| **Printed Name:** | **Affiliation:** |
| **OPTIONAL: Signature of Contractor or Subcontractor** | |
| **Signature:** | **Date:** |
| **Printed Name:** | **Affiliation:** |

## General Instructions

This Corrective Action Log Template is provided to assist you creating a corrective action log that complies with the minimum reporting requirements of Part 5.4 of the EPA's Construction General Permit (CGP). For each triggering condition on your site, you will need to fill out a separate corrective action log.

The entire form must be completed to be compliant with the requirements of the permit. (Note: In Section C, if you do not need the number of rows provided in the corrective action log, you may delete these or cross them off. Alternatively, if you need more space to describe any modifications, you may insert additional rows in the electronic version of this form or use the bottom of the page in the field version of this form.)

If you are covered under a State CGP, this template may be helpful in developing a log that can be used for that permit; however, you will likely need to modify this form to meet the specific requirements of any State-issued permit. If your permitting authority requires you to use a specific corrective action log, you should not use this template.

## Instructions for Section A

**Individual completing this form** Enter the name of the person completing this log. Include the person's contact information (title, affiliated company name, address, email, and phone number).

## Instructions for Section B

You must complete Section B within 24 hours of discovering the condition that triggered corrective action. (CGP Part 5.4)

**When was the problem first discovered?**

Specify the date and time when the triggering condition was first discovered.

**What site conditions triggered this corrective action?** (CGP Parts 5.1 and 5.3)

Check the box corresponding to the numbered triggering condition below that applies to your site.

1. A stormwater control needs a significant repair or a new or replacement control is needed, or, in accordance with Part Error! Reference source not found., you find it necessary to repeatedly (i.e., 3 or more times) conduct the same routine maintenance fix to the same control at the same location (unless you document in your inspection report under Part Error! Reference source not found. that the specific reoccurrence of this same problem should still be addressed as a routine maintenance fix under Part Error! Reference source not found.);
2. A stormwater control necessary to comply with the requirements of this permit was never installed, or was installed incorrectly;
3. Your discharges are not meeting applicable water quality standards;
4. A prohibited discharge has occurred (see Part 1.3);
5. During discharge from site dewatering activities:
   a. The weekly average of your turbidity monitoring results exceeds the 50 NTU benchmark (or alternate benchmark if approved by EPA pursuant to Part **Error! Reference source not found.**); or
   b. You observe or you are informed by EPA, State, or local authorities of the presence of any of the following at the point of discharge to a receiving water flowing through or immediately adjacent to your site and/or to constructed or natural site drainage features or storm drain inlets:
      - sediment plume
      - suspended solids
      - unusual color
      - presence of odor
      - decreased clarity
      - presence of foam
      - visible sheen on the water surface or visible oily deposits on the bottom or shoreline of the receiving water
6. EPA requires corrective action as a result of permit violations found during an inspection carried out under Part 4.8.

**Provide a description of the problem** (CGP Part 5.4.1.a)
Provide a summary description of the condition you found that triggered corrective action, the cause of the problem (if identifiable), and the specific location where it was found. Be as specific as possible about the location; it is recommended that you refer to a precise point on your site map.

## Instructions for Section C

You must complete Section C within 24 hours after completing the correction action. (CGP Part 5.4)

**Deadlines for completing corrective action for condition # 1, 2, 3, 4, or 6 (if not relating to a dewatering discharge)** (CGP Part 5.2.1)
Check the box to confirm that you met the deadlines that apply to each triggering condition. You are always required to check the first box (i.e., Immediately took all reasonable steps to address the condition, including cleaning up any contaminated surfaces so the material will not discharge in subsequent storm events.). Only one of the next three boxes should be checked depending on the situation that applies to this corrective action.

Check the second box if the corrective action for this particular triggering condition does not require a new or replacement control, or a significant repair. These actions must be completed by the close of the next business day from the time of discovery of the condition.

Check the third box if the corrective action for this particular triggering condition requires a new or replacement control, or a significant repair. These actions must be completed by no later than seven calendar days from the time of discover of the condition.

Check the fourth box if the corrective action for this particular triggering condition requires a new or replacement control, or a significant repair, and if it is infeasible to complete the work within seven calendar days. Additionally, you will need to fill out the table below the checkbox that requires:

1. An explanation as to why it was infeasible to complete the installation or repair within seven calendar days of discovering the condition.
2. Provide the schedule you will adhere to for installing the stormwater control and making it operational as soon as feasible after the seventh day following discovery.

Note: Per Part 5.2.1.c, where these actions result in changes to any of the stormwater controls or procedures documented in your SWPPP, you must modify your SWPPP accordingly within seven calendar days of completing this work.

**Deadlines for completing corrective action for condition # 5a, 5b, or 6 related to a dewatering discharge** (CGP Part 5.2.2)
These deadlines apply to conditions relating to construction dewatering activities. Check the box to confirm that you met the deadlines that apply to each triggering condition. You are required to check all of the boxes in this section to indicate your compliance with the corrective action deadlines.

**List of modification(s) to correct problem**
Provide a list of modifications you completed to correct the problem.

**Date of completion**
Enter the date you completed the modification. The work must be completed by the deadline you indicated above.

**SWPPP update necessary?**
Check "Yes" or "No" to indicate if a SWPPP update is necessary consistent with Part 7.4.1.a in order to reflect changes implemented at your site. If "Yes," then enter the date you updated your SWPPP. The SWPPP updates must be made within seven calendar days of completing a corrective action. (CGP Part 5.2.1.c)

## Instructions for Section D

Each corrective action log entry must be signed and certified following completion of Section D to be considered complete. (CGP Part 5.4.2)

**Operator or "Duly Authorized Representative" – MANDATORY** (CGP Appendix G Part G.11.2 and CGP Appendix H Section X)

At a minimum, the corrective action log must be signed by either (1) the person who signed the NOI, or (2) a duly authorized representative of that person. The following requirements apply:

If the signatory will be the person who signed the NOI for permit coverage, as a reminder, that person must be one of the following types of individuals:

- *For a corporation*: By a responsible corporate officer. For the purpose of this subsection, a responsible corporate officer means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
- *For a partnership or sole proprietorship*: By a general partner or the proprietor, respectively.
- *For a municipality, State, Federal, or other public agency*: By either a principal executive officer or ranking elected official. For purposes of this subsection, a principal executive officer of a Federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of EPA).

If the signatory will be a duly authorized representative, the following requirements must be met:

- The authorization is made in writing by the person who signed the NOI (see above);
- The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position); and
- The signed and dated written authorization is included in the SWPPP. A copy must be submitted to EPA, if requested.

Sign, date and print your name and affiliation.

**Contractor or Subcontractor - OPTIONAL**

Where you rely on a contractor or subcontractor to complete this log and the associated corrective action, you should consider requiring the individual(s) to sign and certify each log entry. Note that this does not relieve you, the permitted operator, of the requirement to sign and certify the log as well. If applicable, sign, date, and print your name and affiliation.

## Recordkeeping

Logs must be retained for at least 3 years from the date your permit coverage expires or is terminated. (CGP Part 5.4.4)

Keep copies of your signed corrective action log entries at the site or at an easily accessible location so that it can be made immediately available at the time of an on-site inspection or upon request by EPA. (CGP Part 5.4.3) Include a copy of the corrective action log in your SWPPP. (CGP Part 7.2.7.e)

## Note

While EPA has made every effort to ensure the accuracy of all instructions contained in this template, it is the permit, not this template, that determines the actual obligations of regulated construction stormwater discharges. In the event of a conflict between this template and any corresponding provision of the CGP, you must abide by the requirements in the permit. EPA welcomes comments on this Corrective Action Log Template at any time and will consider those comments in any future revision. You may contact EPA for CGP-related inquiries at cgp@epa.gov

**Attachment G –Subcontractor Certifications/Agreements**

# SUBCONTRACTOR CERTIFICATION
# STORMWATER POLLUTION PREVENTION PLAN

Project Number: _____

Project Title: _____

Operator(s): _____

As a subcontractor, you are required to comply with the Stormwater Pollution Prevention Plan (SWPPP) for any work that you perform onsite. Any person or group who violates any condition of the SWPPP may be subject to substantial penalties or loss of contract. You are encouraged to advise each of your employees working on this project of the requirements of the SWPPP. A copy of the SWPPP is available for your review at the office trailer.

Each subcontractor engaged in activities at the construction site that could impact stormwater must be identified and sign the following certification statement:

**I certify under the penalty of law that I have read and understand the terms and conditions of the SWPPP for the above designated project and agree to follow the practices described in the SWPPP.**

This certification is hereby signed in reference to the above named project:

Company: _____

Address: _____

Telephone Number: _____

Type of construction service to be provided: _____

_____

_____

Signature: _____

Title: _____

Date: _____

**Attachment H – Grading and Stabilization Activities Log**

| **Date Grading Activity Initiated** | **Description of Grading Activity** | **Description of Stabilization Measure and Location** | **Date Grading Activity Ceased** (Indicate Temporary or Permanent) | **Date When Stabilization Measures Initiated** |
|---|---|---|---|---|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**Attachment I – SWPPP Training Documentation**

**Stormwater Pollution Prevention Training Documentation**

Project Name:

Project Location:

Instructor's Name(s):

Instructor's Title(s):

Course Location: _____ Date: _____

Course Length (hours): _____

Stormwater Training Topic: (*check as appropriate)*

- ❑ **Sediment and Erosion Controls**
- ❑ **Emergency Procedures**
- ❑ **Stabilization Controls**
- ❑ **Inspections/Corrective Actions**
- ❑ **Pollution Prevention Measures**

Specific Training Objective:_____

_____

Attendee Roster: (*attach additional pages as necessary)*

| No. | Name of Attendee | Company |
|---|---|---|
| 1 | | |
| 2 | | |
| 3 | | |
| 4 | | |
| 5 | | |
| 6 | | |
| 7 | | |
| 8 | | |

**Attachment J – Delegation of Authority Form**

Delegation of Authority

I, _____ (name), hereby designate the person or specifically described position below to be a duly authorized representative for the purpose of overseeing compliance with environmental requirements, including the Construction General Permit, at the _____ construction site. The designee is authorized to sign any reports, stormwater pollution prevention plans and all other documents required by the permit.

_____ (name of person or position)
_____ (company)
_____ (address)
_____ (city, state, zip)
_____ (phone)

By signing this authorization, I confirm that I meet the requirements to make such a designation as set forth in Appendix I of EPA's Construction General Permit (CGP), and that the designee above meets the definition of a "duly authorized representative" as set forth in Appendix I.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

**Name:** _____

**Company:** _____

**Title:** _____

**Signature:** _____

**Date:** _____

**Attachment K – Endangered Species Documentation**

**Attachment L – Historic Preservation Documentation**

**Attachment M – Rainfall and Snowfall Gauge Recording**

Use the table below to record the rainfall and snowfall gauge readings at the beginning and end of each work day. An example table follows.

| Month/Year | | | Month/Year | | | Month/Year | | |
|---|---|---|---|---|---|---|---|---|
| Day | Start time | End time | Day | Start time | End time | Day | Start time | End time |
| 1 | | | 1 | | | 1 | | |
| 2 | | | 2 | | | 2 | | |
| 3 | | | 3 | | | 3 | | |
| 4 | | | 4 | | | 4 | | |
| 5 | | | 5 | | | 5 | | |
| 6 | | | 6 | | | 6 | | |
| 7 | | | 7 | | | 7 | | |
| 8 | | | 8 | | | 8 | | |
| 9 | | | 9 | | | 9 | | |
| 10 | | | 10 | | | 10 | | |
| 11 | | | 11 | | | 11 | | |
| 12 | | | 12 | | | 12 | | |
| 13 | | | 13 | | | 13 | | |
| 14 | | | 14 | | | 14 | | |
| 15 | | | 15 | | | 15 | | |
| 16 | | | 16 | | | 16 | | |
| 17 | | | 17 | | | 17 | | |
| 18 | | | 18 | | | 18 | | |
| 19 | | | 19 | | | 19 | | |
| 20 | | | 20 | | | 20 | | |
| 21 | | | 21 | | | 21 | | |
| 22 | | | 22 | | | 22 | | |
| 23 | | | 23 | | | 23 | | |
| 24 | | | 24 | | | 24 | | |
| 25 | | | 25 | | | 25 | | |
| 26 | | | 26 | | | 26 | | |
| 27 | | | 27 | | | 27 | | |
| 28 | | | 28 | | | 28 | | |
| 29 | | | 29 | | | 29 | | |
| 30 | | | 30 | | | 30 | | |
| 31 | | | 31 | | | 31 | | |

**Attachment N – Turbidity Meter Manual and Manufacturer's Instructions**

## APPENDIX G

**Soil Investigations**

NRCS Soil Maps and Descriptions
Compiled Test Pit Information

Hydrologic Soil Group—Norfolk and Suffolk Counties, Massachusetts




Map Scale: 1:1,820 if printed on A portrait (8.5" x 11") sheet.

N

Meters: 0 25 50 100 150

Feet: 0 50 100 200 300

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84

## MAP LEGEND

**Area of Interest (AOI)**

- Area of Interest (AOI)

**Soils**

**Soil Rating Polygons**

- A
- A/D
- B
- B/D
- C
- C/D
- D
- Not rated or not available

**Soil Rating Lines**

- A
- A/D
- B
- B/D
- C
- C/D
- D
- Not rated or not available

**Soil Rating Points**

- A
- A/D
- B
- B/D
- C
- C/D
- D
- Not rated or not available

**Water Features**

- Streams and Canals

**Transportation**

- Rails
- Interstate Highways
- US Routes
- Major Roads
- Local Roads

**Background**

- Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:25,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Norfolk and Suffolk Counties, Massachusetts
Survey Area Data: Version 17, Sep 3, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 25, 2020—Oct 4, 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

# Hydrologic Soil Group

| Map unit symbol | Map unit name | Rating | Acres in AOI | Percent of AOI |
|---|---|---|---|---|
| 71B | Ridgebury fine sandy loam, 3 to 8 percent slopes, extremely stony | D | 1.6 | 31.6% |
| 422B | Canton fine sandy loam, 0 to 8 percent slopes, extremely stony | B | 0.2 | 3.3% |
| 424C | Canton fine sandy loam, 8 to 15 percent slopes, extremely bouldery | A | 1.4 | 28.4% |
| 654 | Udorthents, loamy | A | 1.8 | 36.6% |
| **Totals for Area of Interest** | | | **5.0** | **100.0%** |

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff: None Specified*

*Tie-break Rule:* Higher

**Commonwealth of Massachusetts**
**City/Town of**

# Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

## C. On-Site Review (*minimum of two holes required at every proposed primary and reserve disposal area)*

**Deep Observation Hole Number:** 2 (Hole #) | 09/16/2022 (Date) | 10:30 (Time) | 50's/sunny (Weather) | - (Latitude) | - (Longitude)

1. Land Use: Woods (e.g., woodland, agricultural field, vacant lot, etc.) | - (Vegetation) | Boulders/Ledge Outcrop (Surface Stones (e.g., cobbles, stones, boulders, etc.)) | 3% (Slope (%))

Description of Location: Woods behind building

2. Soil Parent Material: Glacial Till | - (Landform) | - (Position on Landscape (SU, SH, BS, FS, TS, Plain))

3. Distances from: Open Water Body _____ feet | Drainage Way _____ feet | Wetlands _____ feet | Property Line _____ feet | Drinking Water Well _____ feet | Other _____ feet

4. Unsuitable Materials Present: ■ Yes ☐ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ■ Bedrock

5. Groundwater Observed: ☐ Yes ■ No If yes: - Depth to Weeping in Hole | - Depth to Standing Water in Hole

**Soil Log**

| Depth (in) | Soil Horizon /Layer | Soil Texture (USDA | Soil Matrix: Color-Moist (Munsell) | Redoximorphic Features | | | Coarse Fragments % by Volume | | Soil Structure | Soil Consistence (Moist) | Other |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | Depth | Color | Percent | Gravel | Cobbles & Stones | | | |
| 0-7 | A | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| 7-24 | Bw | Loamy Sand | 10 YR 4/6 | - | Cnc : - / Dpl: - | - | 10 | 20 | Mass | Friable | |
| 24-96 | C1 | Sand | 10 YR 6/2 | - | Cnc : - / Dpl: - | - | 20 | 35 | Single | Loose | Very gravelly, medium sand |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |

Additional Notes:

- Test pit 1 and the original location of test pit 2 were surrounded by ledge outcropping, so the original location of test pit 2 was moved to the open area near the fire pit to avoid ledge. Only one test pit was performed in this area due to the ledge.
- Refusal at 8 feet

**Commonwealth of Massachusetts**
**City/Town of**

# Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

## C. On-Site Review (*minimum of two holes required at every proposed primary and reserve disposal area)*

**Deep Observation Hole Number:** 3 (Hole #) | 09/16/2022 (Date) | 9:37 (Time) | 50's/sunny (Weather) | - (Latitude) | - (Longitude)

1. Land Use: Woods (e.g., woodland, agricultural field, vacant lot, etc.) | - (Vegetation) | Boulders/Ledge Outcrop (Surface Stones (e.g., cobbles, stones, boulders, etc.)) | 5% (Slope (%))

Description of Location: Woods near front corner of building

2. Soil Parent Material: Glacial Till | - (Landform) | - (Position on Landscape (SU, SH, BS, FS, TS, Plain))

3. Distances from: Open Water Body _____ feet | Drainage Way _____ feet | Wetlands _____ feet | Property Line _____ feet | Drinking Water Well _____ feet | Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☒ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: - Depth to Weeping in Hole | - Depth to Standing Water in Hole

**Soil Log**

| Depth (in) | Soil Horizon /Layer | Soil Texture (USDA | Soil Matrix: Color-Moist (Munsell) | Redoximorphic Features | | | Coarse Fragments % by Volume | | Soil Structure | Soil Consistence (Moist) | Other |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | Depth | Color | Percent | Gravel | Cobbles & Stones | | | |
| 0-8 | A | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| 8-35 | Bw | Loamy Sand | 10 YR 4/6 | - | Cnc : - / Dpl: - | - | 5 | 5 | Mass | Friable | |
| 35-84 | C1 | Sand | 10 YR 7/1 | - | Cnc : - / Dpl: - | - | 10 | 10 | Single | Loose | Very Fine Sand |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |

Additional Notes: Ledge @ 7' - refusal

**Commonwealth of Massachusetts**
**City/Town of**

# Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

## C. On-Site Review (*minimum of two holes required at every proposed primary and reserve disposal area)*

**Deep Observation Hole Number:** 4 (Hole #) | 09/16/2022 (Date) | 10:12 (Time) | 50's/sunny (Weather) | - (Latitude) | - (Longitude)

1. Land Use: Woods (e.g., woodland, agricultural field, vacant lot, etc.) | - (Vegetation) | Boulders/Ledge Outcrop (Surface Stones (e.g., cobbles, stones, boulders, etc.)) | 5% (Slope (%))

Description of Location: Woods near front corner of building

2. Soil Parent Material: Glacial Till | - (Landform) | - (Position on Landscape (SU, SH, BS, FS, TS, Plain))

3. Distances from: Open Water Body _____ feet | Drainage Way _____ feet | Wetlands _____ feet | Property Line _____ feet | Drinking Water Well _____ feet | Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☒ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: - Depth to Weeping in Hole | - Depth to Standing Water in Hole

**Soil Log**

| Depth (in) | Soil Horizon /Layer | Soil Texture (USDA | Soil Matrix: Color-Moist (Munsell) | Redoximorphic Features | | | Coarse Fragments % by Volume | | Soil Structure | Soil Consistence (Moist) | Other |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | Depth | Color | Percent | Gravel | Cobbles & Stones | | | |
| 0-8 | A | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| 8-20 | Bw | Loamy Sand | 10 YR 3/6 | - | Cnc : - / Dpl: - | - | 15 | 30 | Mass | Friable | |
| 20-48 | C1 | Loamy Sand | 10 YR 4/3 | - | Cnc : - / Dpl: - | - | 15 | 30 | Mass | Friable | Very Fine Sand |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |
| - | - | - | - | - | Cnc : - / Dpl: - | - | - | - | - | - | - |

Additional Notes:

Ledge @ 4' - refusal

Large boulders encountered near top of pit were removed by excavator before reaching refusal

**Commonwealth of Massachusetts**
**City/Town of**

# Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

## C. On-Site Review (*minimum of two holes required at every proposed primary and reserve disposal area)*

**Deep Observation Hole Number:** 5 (Hole #) | 09/16/2022 (Date) | 8:40 (Time) | 50's/sunny (Weather) | ____ (Latitude) | ____ (Longitude)

1. Land Use: parking lot (e.g., woodland, agricultural field, vacant lot, etc.) | - (Vegetation) | - (Surface Stones (e.g., cobbles, stones, boulders, etc.)) | 1-3% (Slope (%))

Description of Location: parking lot next to existing building

2. Soil Parent Material: Glacial Till | - (Landform) | - (Position on Landscape (SU, SH, BS, FS, TS, Plain))

3. Distances from: Open Water Body _____ feet | Drainage Way _____ feet | Wetlands _____ feet | Property Line _____ feet | Drinking Water Well _____ feet | Other _____ feet

4. Unsuitable Materials Present: ■ Yes ☐ No If Yes: ■ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ■ No If yes: - Depth to Weeping in Hole | - Depth to Standing Water in Hole

**Soil Log**

| Depth (in) | Soil Horizon /Layer | Soil Texture (USDA | Soil Matrix: Color-Moist (Munsell) | Redoximorphic Features | | | Coarse Fragments % by Volume | | Soil Structure | Soil Consistence (Moist) | Other |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | Depth | Color | Percent | Gravel | Cobbles & Stones | | | |
| 0-16 | Fill | Sand | 10 YR 4/4 | - | Cnc :<br>Dpl: | - | 30 | 10 | Single | Loose | very gravelly |
| 16-20 | Ab | - | - | - | Cnc : -<br>Dpl: - | - | - | - | - | - | - |
| 20-38 | B | Loamy Sand | 10 YR 3/4 | - | Cnc : -<br>Dpl: - | - | 15 | 10 | Mass | Friable | - |
| 38-98 | C1 | Loamy Sand | 10 YR 4/4 | - | Cnc : -<br>Dpl: - | - | 15 | 25 | Mass | Friable | Big Boulders, tough digging |
| 98-113 | C2 | Loamy Sand | 10 YR 4/3 | - | Cnc : -<br>Dpl: - | - | 15 | 25 | Mass | Friable | Moist, but not wet |
| - | - | - | - | - | Cnc : -<br>Dpl: - | - | - | - | - | - | - |

Additional Notes:

## APPENDIX H

**Existing Culvert Sizing**

PCSWMM Modeling

EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.015)
---

**********
Element Count
**********
Number of rain gages ..... 4
Number of subcatchments ... 1
Number of nodes ..... 2
Number of links ..... 1
Number of pollutants ..... 0
Number of land uses ..... 0

**********
Raingage Summary
**********

| Name | Data Source | Data Type | Recording Interval |
|---|---|---|---|
| NOAA_Type_A_3.41in | NOAA_Type_A_3.41in | INTENSITY | 6 min. |
| NOAA_Type_A_5.21in | NOAA_Type_A_5.21in | INTENSITY | 6 min. |
| NOAA_Type_A_6.33in | NOAA_Type_A_6.33in | INTENSITY | 6 min. |
| NOAA_Type_A_8.06in | NOAA_Type_A_8.06in | INTENSITY | 6 min. |

**********
Subcatchment Summary
**********

| Name | Area | Width | %Imperv | %Slope | Rain Gage | Outlet |
|---|---|---|---|---|---|---|
| S1 | 38.00 | 827.64 | 10.00 | 5.0000 | NOAA_Type_A_6.33in | J1 |

**********
Node Summary
**********

| Name | Type | Invert Elev. | Max. Depth | Ponded Area | External Inflow |
|---|---|---|---|---|---|
| J1 | JUNCTION | 244.73 | 3.00 | 0.0 | |
| OF1 | OUTFALL | 243.86 | 3.00 | 0.0 | |

**********
Link Summary
**********

| Name | From Node | To Node | Type | Length | %Slope | Roughness |
|---|---|---|---|---|---|---|
| C1 | J1 | OF1 | CONDUIT | 78.0 | 1.1155 | 0.0100 |

**********
Cross Section Summary
**********

| Conduit | Shape | Full Depth | Full Area | Hyd. Rad. | Max. Width | No. of Barrels | Full Flow |
|---|---|---|---|---|---|---|---|
| C1 | CIRCULAR | 3.00 | 7.07 | 0.75 | 3.00 | 1 | 91.58 |

**********
NOTE: The summary statistics displayed in this report are
based on results found at every computational time step,
not just on results from each reporting time step.
**********

**********
Analysis Options
**********
Flow Units ..... CFS
Process Models:
  Rainfall/Runoff ..... YES
  RDII ..... NO
  Snowmelt ..... NO
  Groundwater ..... NO
  Flow Routing ..... YES
  Ponding Allowed ..... NO
  Water Quality ..... NO
Infiltration Method ..... HORTON
Flow Routing Method ..... DYNWAVE
Surcharge Method ..... EXTRAN
Starting Date ..... 09/21/2022 00:00:00
Ending Date ..... 09/22/2022 00:00:00
Antecedent Dry Days ..... 0.0
Report Time Step ..... 00:01:00
Wet Time Step ..... 00:05:00
Dry Time Step ..... 00:05:00
Routing Time Step ..... 5.00 sec

```
Variable Time Step ....... YES
Maximum Trials ........... 8
Number of Threads ........ 1
Head Tolerance ........... 0.005000 ft
```

| Runoff Quantity Continuity | Volume acre-feet | Depth inches |
|---|---|---|
| Total Precipitation ..... | 20.045 | 6.330 |
| Evaporation Loss ..... | 0.000 | 0.000 |
| Infiltration Loss ..... | 10.924 | 3.450 |
| Surface Runoff ..... | 9.121 | 2.880 |
| Final Storage ..... | 0.015 | 0.005 |
| Continuity Error (%) ..... | -0.073 | |

| Flow Routing Continuity | Volume acre-feet | Volume 10^6 gal |
|---|---|---|
| Dry Weather Inflow ..... | 0.000 | 0.000 |
| Wet Weather Inflow ..... | 9.128 | 2.975 |
| Groundwater Inflow ..... | 0.000 | 0.000 |
| RDII Inflow ..... | 0.000 | 0.000 |
| External Inflow ..... | 0.000 | 0.000 |
| External Outflow ..... | 8.603 | 2.803 |
| Flooding Loss ..... | 0.524 | 0.171 |
| Evaporation Loss ..... | 0.000 | 0.000 |
| Exfiltration Loss ..... | 0.000 | 0.000 |
| Initial Stored Volume .... | 0.000 | 0.000 |
| Final Stored Volume ..... | 0.000 | 0.000 |
| Continuity Error (%) ..... | 0.014 | |

```
**************************
Time-Step Critical Elements
**************************
Link C1 (11.42%)
```

```
******************************
Highest Flow Instability Indexes
******************************
All links are stable.
```

**********
Routing Time Step Summary
**********

| | | |
|---|---|---|
| Minimum Time Step | : | 1.27 sec |
| Average Time Step | : | 4.81 sec |
| Maximum Time Step | : | 5.00 sec |
| Percent in Steady State | : | -0.00 |
| Average Iterations per Step | : | 2.00 |
| Percent Not Converging | : | 0.00 |
| Time Step Frequencies | : | |
| 5.000 - 3.155 sec | : | 94.76 % |
| 3.155 - 1.991 sec | : | 4.33 % |
| 1.991 - 1.256 sec | : | 0.91 % |
| 1.256 - 0.792 sec | : | 0.00 % |
| 0.792 - 0.500 sec | : | 0.00 % |

**********
Subcatchment Runoff Summary
**********

| Subcatchment | Total Precip in | Total Runon in | Total Evap in | Total Infil in | Imperv Runoff in | Perv Runoff in | Total Runoff in | Total Runoff 10^6 gal | Peak Runoff CFS | Runoff Coeff |
|---|---|---|---|---|---|---|---|---|---|---|
| S1 | 6.33 | 0.00 | 0.00 | 3.45 | 0.63 | 2.25 | 2.88 | 2.97 | 147.30 | 0.455 |

**********
Node Depth Summary
**********

| Node | Type | Average Depth Feet | Maximum Depth Feet | Maximum HGL Feet | Time of Max Occurrence days hr:min | Reported Max Depth Feet |
|---|---|---|---|---|---|---|
| J1 | JUNCTION | 0.32 | 3.00 | 247.73 | 0 12:02 | 3.00 |
| OF1 | OUTFALL | 0.32 | 3.00 | 246.86 | 0 12:19 | 2.88 |

**********
Node Inflow Summary
**********

| Node | Type | Maximum Lateral Inflow CFS | Maximum Total Inflow CFS | Time of Max Occurrence days hr:min | Lateral Inflow Volume 10^6 gal | Total Inflow Volume 10^6 gal | Flow Balance Error Percent |
|---|---|---|---|---|---|---|---|
| J1 | JUNCTION | 147.30 | 147.30 | 0 12:06 | 2.97 | 2.97 | 0.015 |
| OF1 | OUTFALL | 0.00 | 96.59 | 0 12:19 | 0 | 2.8 | 0.000 |

**********
Node Surcharge Summary
**********

Surcharging occurs when water rises above the top of the highest conduit.

| Node | Type | Hours Surcharged | Max. Height Above Crown Feet | Min. Depth Below Rim Feet |
|---|---|---|---|---|
| J1 | JUNCTION | 0.29 | 0.000 | 0.000 |

**********
Node Flooding Summary
**********

Flooding refers to all water that overflows a node, whether it ponds or not.

| Node | Hours Flooded | Maximum Rate CFS | Time of Max Occurrence days hr:min | Total Flood Volume 10^6 gal | Maximum Ponded Depth Feet |
|---|---|---|---|---|---|
| J1 | 0.29 | 51.00 | 0 12:06 | 0.171 | 0.000 |

**********
Outfall Loading Summary
**********

| Outfall Node | Flow Freq Pcnt | Avg Flow CFS | Max Flow CFS | Total Volume 10^6 gal |
|---|---|---|---|---|

| | | | | |
|---|---|---|---|---|
| OF1 | 99.91 | 6.36 | 96.59 | 2.803 |
| System | 99.91 | 6.36 | 96.59 | 2.803 |

**********
Link Flow Summary
**********

| Link | Type | Maximum \|Flow\| CFS | Time of Max Occurrence days hr:min | Maximum \|Veloc\| ft/sec | Max/ Full Flow | Max/ Full Depth |
|---|---|---|---|---|---|---|
| C1 | CONDUIT | 96.59 | 0 12:19 | 14.77 | 1.05 | 1.00 |

**********
Flow Classification Summary
**********

| Conduit | Adjusted /Actual Length | Fraction of Time in Flow Class: Dry | Up Dry | Down Dry | Sub Crit | Sup Crit | Up Crit | Down Crit | Norm Ltd | Inlet Ctrl |
|---|---|---|---|---|---|---|---|---|---|---|
| C1 | 1.00 | 0.00 | 0.00 | 0.00 | 0.02 | 0.98 | 0.00 | 0.00 | 0.66 | 0.00 |

**********
Conduit Surcharge Summary
**********

| Conduit | Hours Full: Both Ends | Upstream | Dnstream | Hours Above Full Normal Flow | Hours Capacity Limited |
|---|---|---|---|---|---|
| C1 | 0.11 | 0.29 | 0.11 | 0.33 | 0.11 |

Analysis begun on: Fri Sep 23 10:41:22 2022
Analysis ended on: Fri Sep 23 10:41:23 2022
Total elapsed time: 00:00:01

CONCLUSION: WETLAND AREA WILL PROVIDE STORAGE FOR THE STORMWATER RUNOFF IN THE 100 YEAR STORM. THE ELEVATION WILL BE 149.0 PER THE MCGUIRE HYDROLOGICAL STUDY.